



Version 14

Using JMP

*"The real voyage of discovery consists not in seeking new
landscapes, but in having new eyes."*

Marcel Proust

JMP, A Business Unit of SAS
SAS Campus Drive
Cary, NC 27513

14.2

The correct bibliographic citation for this manual is as follows: SAS Institute Inc. 2018.
Using JMP® 14. Cary, NC: SAS Institute Inc.

Using JMP® 14

Copyright © 2018, SAS Institute Inc., Cary, NC, USA

ISBN 978-1-63526-541-5 (Hardcopy)

ISBN 978-1-63526-542-2 (EPUB)

ISBN 978-1-63526-543-9 (MOBI)

ISBN 978-1-63526-544-6 (Web PDF)

All rights reserved. Produced in the United States of America.

For a hard-copy book: No part of this publication may be reproduced, stored in a retrieval system, or transmitted, in any form or by any means, electronic, mechanical, photocopying, or otherwise, without the prior written permission of the publisher, SAS Institute Inc.

For a web download or e-book: Your use of this publication shall be governed by the terms established by the vendor at the time you acquire this publication.

The scanning, uploading, and distribution of this book via the Internet or any other means without the permission of the publisher is illegal and punishable by law. Please purchase only authorized electronic editions and do not participate in or encourage electronic piracy of copyrighted materials. Your support of others' rights is appreciated.

U.S. Government License Rights; Restricted Rights: The Software and its documentation is commercial computer software developed at private expense and is provided with RESTRICTED RIGHTS to the United States Government. Use, duplication or disclosure of the Software by the United States Government is subject to the license terms of this Agreement pursuant to, as applicable, FAR 12.212, DFAR 227.7202-1(a), DFAR 227.7202-3(a) and DFAR 227.7202-4 and, to the extent required under U.S. federal law, the minimum restricted rights as set out in FAR 52.227-19 (DEC 2007). If FAR 52.227-19 is applicable, this provision serves as notice under clause (c) thereof and no other notice is required to be affixed to the Software or documentation. The Government's rights in Software and documentation shall be only those set forth in this Agreement.

SAS Institute Inc., SAS Campus Drive, Cary, North Carolina 27513-2414.

March 2018

August 2018

December 2018

SAS® and all other SAS Institute Inc. product or service names are registered trademarks or trademarks of SAS Institute Inc. in the USA and other countries. ® indicates USA registration.

Other brand and product names are trademarks of their respective companies.

SAS software may be provided with certain third-party software, including but not limited to open-source software, which is licensed under its applicable third-party software license agreement. For license information about third-party software distributed with SAS software, refer to <http://support.sas.com/thirdpartylicenses>.

Technology License Notices

- Scintilla - Copyright © 1998-2017 by Neil Hodgson <neilh@scintilla.org>.

All Rights Reserved.

Permission to use, copy, modify, and distribute this software and its documentation for any purpose and without fee is hereby granted, provided that the above copyright notice appear in all copies and that both that copyright notice and this permission notice appear in supporting documentation.

NEIL HODGSON DISCLAIMS ALL WARRANTIES WITH REGARD TO THIS SOFTWARE, INCLUDING ALL IMPLIED WARRANTIES OF MERCHANTABILITY AND FITNESS, IN NO EVENT SHALL NEIL HODGSON BE LIABLE FOR ANY SPECIAL, INDIRECT OR CONSEQUENTIAL DAMAGES OR ANY DAMAGES WHATSOEVER RESULTING FROM LOSS OF USE, DATA OR PROFITS, WHETHER IN AN ACTION OF CONTRACT, NEGLIGENCE OR OTHER TORTIOUS ACTION, ARISING OUT OF OR IN CONNECTION WITH THE USE OR PERFORMANCE OF THIS SOFTWARE.

- Telerik RadControls: Copyright © 2002-2012, Telerik. Usage of the included Telerik RadControls outside of JMP is not permitted.
- ZLIB Compression Library - Copyright © 1995-2005, Jean-Loup Gailly and Mark Adler.
- Made with Natural Earth. Free vector and raster map data @ naturalearthdata.com.
- Packages - Copyright © 2009-2010, Stéphane Sudre (s.sudre.free.fr). All rights reserved.

Redistribution and use in source and binary forms, with or without modification, are permitted provided that the following conditions are met:

Redistributions of source code must retain the above copyright notice, this list of conditions and the following disclaimer.

Redistributions in binary form must reproduce the above copyright notice, this list of conditions and the following disclaimer in the documentation and/or other materials provided with the distribution.

Neither the name of the WhiteBox nor the names of its contributors may be used to endorse or promote products derived from this software without specific prior written permission.

THIS SOFTWARE IS PROVIDED BY THE COPYRIGHT HOLDERS AND CONTRIBUTORS "AS IS" AND ANY EXPRESS OR IMPLIED WARRANTIES, INCLUDING, BUT NOT LIMITED TO, THE IMPLIED WARRANTIES OF MERCHANTABILITY AND FITNESS FOR A PARTICULAR PURPOSE ARE DISCLAIMED. IN NO EVENT SHALL THE COPYRIGHT OWNER OR CONTRIBUTORS BE LIABLE FOR ANY DIRECT, INDIRECT, INCIDENTAL, SPECIAL, EXEMPLARY, OR CONSEQUENTIAL DAMAGES (INCLUDING, BUT NOT LIMITED TO, PROCUREMENT OF SUBSTITUTE GOODS OR SERVICES; LOSS OF USE, DATA, OR PROFITS; OR BUSINESS INTERRUPTION) HOWEVER CAUSED AND ON ANY THEORY OF LIABILITY, WHETHER IN CONTRACT, STRICT LIABILITY, OR TORT (INCLUDING NEGLIGENCE OR OTHERWISE) ARISING IN ANY WAY OUT OF THE USE OF THIS SOFTWARE, EVEN IF ADVISED OF THE POSSIBILITY OF SUCH DAMAGE.

- iODBC software - Copyright © 1995-2006, OpenLink Software Inc and Ke Jin (www.iodbc.org). All rights reserved.

Redistribution and use in source and binary forms, with or without modification, are permitted provided that the following conditions are met:

- Redistributions of source code must retain the above copyright notice, this list of conditions and the following disclaimer.
- Redistributions in binary form must reproduce the above copyright notice, this list of conditions and the following disclaimer in the documentation and/or other materials provided with the distribution.
- Neither the name of OpenLink Software Inc. nor the names of its contributors may be used to endorse or promote products derived from this software without specific prior written permission.

THIS SOFTWARE IS PROVIDED BY THE COPYRIGHT HOLDERS AND CONTRIBUTORS "AS IS" AND ANY EXPRESS OR IMPLIED WARRANTIES, INCLUDING, BUT NOT LIMITED TO, THE IMPLIED WARRANTIES OF MERCHANTABILITY AND FITNESS FOR A PARTICULAR PURPOSE ARE DISCLAIMED. IN NO EVENT SHALL OPENLINK OR CONTRIBUTORS BE LIABLE FOR ANY DIRECT, INDIRECT, INCIDENTAL, SPECIAL, EXEMPLARY, OR CONSEQUENTIAL DAMAGES (INCLUDING, BUT NOT LIMITED TO, PROCUREMENT OF SUBSTITUTE GOODS OR SERVICES; LOSS OF USE, DATA, OR PROFITS; OR BUSINESS INTERRUPTION) HOWEVER CAUSED AND ON ANY THEORY OF LIABILITY, WHETHER IN CONTRACT, STRICT LIABILITY, OR TORT (INCLUDING NEGLIGENCE OR OTHERWISE) ARISING IN ANY WAY OUT OF THE USE OF THIS SOFTWARE, EVEN IF ADVISED OF THE POSSIBILITY OF SUCH DAMAGE.

- bzip2, the associated library “libbzip2”, and all documentation, are Copyright © 1996-2010, Julian R Seward. All rights reserved.

Redistribution and use in source and binary forms, with or without modification, are permitted provided that the following conditions are met:

Redistributions of source code must retain the above copyright notice, this list of conditions and the following disclaimer.

The origin of this software must not be misrepresented; you must not claim that you wrote the original software. If you use this software in a product, an acknowledgment in the product documentation would be appreciated but is not required.

Altered source versions must be plainly marked as such, and must not be misrepresented as being the original software.

The name of the author may not be used to endorse or promote products derived from this software without specific prior written permission.

THIS SOFTWARE IS PROVIDED BY THE AUTHOR “AS IS” AND ANY EXPRESS OR IMPLIED WARRANTIES, INCLUDING, BUT NOT LIMITED TO, THE IMPLIED WARRANTIES OF MERCHANTABILITY AND FITNESS FOR A PARTICULAR PURPOSE ARE DISCLAIMED. IN NO EVENT SHALL THE AUTHOR BE LIABLE FOR ANY DIRECT, INDIRECT, INCIDENTAL, SPECIAL, EXEMPLARY, OR CONSEQUENTIAL DAMAGES (INCLUDING, BUT NOT LIMITED TO, PROCUREMENT OF SUBSTITUTE GOODS OR SERVICES; LOSS OF USE, DATA, OR PROFITS; OR BUSINESS INTERRUPTION) HOWEVER CAUSED AND ON ANY THEORY OF LIABILITY, WHETHER IN CONTRACT, STRICT LIABILITY, OR TORT (INCLUDING NEGLIGENCE OR OTHERWISE) ARISING IN ANY WAY OUT OF THE USE OF THIS SOFTWARE, EVEN IF ADVISED OF THE POSSIBILITY OF SUCH DAMAGE.

- R software is Copyright © 1999-2012, R Foundation for Statistical Computing.
- MATLAB software is Copyright © 1984-2012, The MathWorks, Inc. Protected by U.S. and international patents. See www.mathworks.com/patents. MATLAB and Simulink are registered trademarks of The MathWorks, Inc. See www.mathworks.com/trademarks for a list of additional trademarks. Other product or brand names may be trademarks or registered trademarks of their respective holders.
- libopc is Copyright © 2011, Florian Reuter. All rights reserved.

Redistribution and use in source and binary forms, with or without modification, are permitted provided that the following conditions are met:

- Redistributions of source code must retain the above copyright notice, this list of conditions and the following disclaimer.

- Redistributions in binary form must reproduce the above copyright notice, this list of conditions and the following disclaimer in the documentation and / or other materials provided with the distribution.
- Neither the name of Florian Reuter nor the names of its contributors may be used to endorse or promote products derived from this software without specific prior written permission.

THIS SOFTWARE IS PROVIDED BY THE COPYRIGHT HOLDERS AND CONTRIBUTORS “AS IS” AND ANY EXPRESS OR IMPLIED WARRANTIES, INCLUDING, BUT NOT LIMITED TO, THE IMPLIED WARRANTIES OF MERCHANTABILITY AND FITNESS FOR A PARTICULAR PURPOSE ARE DISCLAIMED. IN NO EVENT SHALL THE COPYRIGHT OWNER OR CONTRIBUTORS BE LIABLE FOR ANY DIRECT, INDIRECT, INCIDENTAL, SPECIAL, EXEMPLARY, OR CONSEQUENTIAL DAMAGES (INCLUDING, BUT NOT LIMITED TO, PROCUREMENT OF SUBSTITUTE GOODS OR SERVICES; LOSS OF USE, DATA, OR PROFITS; OR BUSINESS INTERRUPTION) HOWEVER CAUSED AND ON ANY THEORY OF LIABILITY, WHETHER IN CONTRACT, STRICT LIABILITY, OR TORT (INCLUDING NEGLIGENCE OR OTHERWISE) ARISING IN ANY WAY OUT OF THE USE OF THIS SOFTWARE, EVEN IF ADVISED OF THE POSSIBILITY OF SUCH DAMAGE.

- libxml2 - Except where otherwise noted in the source code (e.g. the files hash.c, list.c and the trio files, which are covered by a similar license but with different Copyright notices) all the files are:

Copyright © 1998 - 2003 Daniel Veillard. All Rights Reserved.

Permission is hereby granted, free of charge, to any person obtaining a copy of this software and associated documentation files (the “Software”), to deal in the Software without restriction, including without limitation the rights to use, copy, modify, merge, publish, distribute, sublicense, and/or sell copies of the Software, and to permit persons to whom the Software is furnished to do so, subject to the following conditions:

The above copyright notice and this permission notice shall be included in all copies or substantial portions of the Software.

THE SOFTWARE IS PROVIDED “AS IS”, WITHOUT WARRANTY OF ANY KIND, EXPRESS OR IMPLIED, INCLUDING BUT NOT LIMITED TO THE WARRANTIES OF MERCHANTABILITY, FITNESS FOR A PARTICULAR PURPOSE AND NONINFRINGEMENT. IN NO EVENT SHALL DANIEL VEILLARD BE LIABLE FOR ANY CLAIM, DAMAGES OR OTHER LIABILITY, WHETHER IN AN ACTION OF CONTRACT, TORT OR OTHERWISE, ARISING FROM, OUT OF OR IN CONNECTION WITH THE SOFTWARE OR THE USE OR OTHER DEALINGS IN THE SOFTWARE.

Except as contained in this notice, the name of Daniel Veillard shall not be used in advertising or otherwise to promote the sale, use or other dealings in this Software without prior written authorization from him.

- Regarding the decompression algorithm used for UNIX files:

Copyright © 1985, 1986, 1992, 1993

The Regents of the University of California. All rights reserved.

THIS SOFTWARE IS PROVIDED BY THE REGENTS AND CONTRIBUTORS "AS IS" AND ANY EXPRESS OR IMPLIED WARRANTIES, INCLUDING, BUT NOT LIMITED TO, THE IMPLIED WARRANTIES OF MERCHANTABILITY AND FITNESS FOR A PARTICULAR PURPOSE ARE DISCLAIMED. IN NO EVENT SHALL THE REGENTS OR CONTRIBUTORS BE LIABLE FOR ANY DIRECT, INDIRECT, INCIDENTAL, SPECIAL, EXEMPLARY, OR CONSEQUENTIAL DAMAGES (INCLUDING, BUT NOT LIMITED TO, PROCUREMENT OF SUBSTITUTE GOODS OR SERVICES; LOSS OF USE, DATA, OR PROFITS; OR BUSINESS INTERRUPTION) HOWEVER CAUSED AND ON ANY THEORY OF LIABILITY, WHETHER IN CONTRACT, STRICT LIABILITY, OR TORT (INCLUDING NEGLIGENCE OR OTHERWISE) ARISING IN ANY WAY OUT OF THE USE OF THIS SOFTWARE, EVEN IF ADVISED OF THE POSSIBILITY OF SUCH DAMAGE.

1. Redistributions of source code must retain the above copyright notice, this list of conditions and the following disclaimer.

2. Redistributions in binary form must reproduce the above copyright notice, this list of conditions and the following disclaimer in the documentation and/or other materials provided with the distribution.

3. Neither the name of the University nor the names of its contributors may be used to endorse or promote products derived from this software without specific prior written permission.

- Snowball - Copyright © 2001, Dr Martin Porter, Copyright © 2002, Richard Boulton.

All rights reserved.

Redistribution and use in source and binary forms, with or without modification, are permitted provided that the following conditions are met:

1. Redistributions of source code must retain the above copyright notice, this list of conditions and the following disclaimer.

2. Redistributions in binary form must reproduce the above copyright notice, this list of conditions and the following disclaimer in the documentation and/or other materials provided with the distribution.

3. Neither the name of the copyright holder nor the names of its contributors may be used to endorse or promote products derived from this software without specific prior written permission.

THIS SOFTWARE IS PROVIDED BY THE COPYRIGHT HOLDERS AND CONTRIBUTORS \“AS IS\” AND ANY EXPRESS OR IMPLIED WARRANTIES, INCLUDING, BUT NOT LIMITED TO, THE IMPLIED WARRANTIES OF MERCHANTABILITY AND FITNESS FOR A PARTICULAR PURPOSE ARE DISCLAIMED. IN NO EVENT SHALL THE COPYRIGHT HOLDER OR CONTRIBUTORS BE LIABLE FOR ANY DIRECT, INDIRECT, INCIDENTAL, SPECIAL, EXEMPLARY, OR CONSEQUENTIAL DAMAGES (INCLUDING, BUT NOT LIMITED TO, PROCUREMENT OF SUBSTITUTE GOODS OR SERVICES; LOSS OF USE, DATA, OR PROFITS; OR BUSINESS INTERRUPTION) HOWEVER CAUSED AND ON ANY THEORY OF LIABILITY, WHETHER IN CONTRACT, STRICT LIABILITY, OR TORT (INCLUDING NEGLIGENCE OR OTHERWISE) ARISING IN ANY WAY OUT OF THE USE OF THIS SOFTWARE, EVEN IF ADVISED OF THE POSSIBILITY OF SUCH DAMAGE.

- Pako - Copyright © 2014–2017 by Vitaly Puzrin and Andrei Tuputcyn.

Permission is hereby granted, free of charge, to any person obtaining a copy of this software and associated documentation files (the “Software”), to deal in the Software without restriction, including without limitation the rights to use, copy, modify, merge, publish, distribute, sublicense, and/or sell copies of the Software, and to permit persons to whom the Software is furnished to do so, subject to the following conditions:

The above copyright notice and this permission notice shall be included in all copies or substantial portions of the Software.

THE SOFTWARE IS PROVIDED “AS IS”, WITHOUT WARRANTY OF ANY KIND, EXPRESS OR IMPLIED, INCLUDING BUT NOT LIMITED TO THE WARRANTIES OF MERCHANTABILITY, FITNESS FOR A PARTICULAR PURPOSE AND NONINFRINGEMENT. IN NO EVENT SHALL THE AUTHORS OR COPYRIGHT HOLDERS BE LIABLE FOR ANY CLAIM, DAMAGES OR OTHER LIABILITY, WHETHER IN AN ACTION OF CONTRACT, TORT OR OTHERWISE, ARISING FROM, OUT OF OR IN CONNECTION WITH THE SOFTWARE OR THE USE OR OTHER DEALINGS IN THE SOFTWARE.

Get the Most from JMP[®]

Whether you are a first-time or a long-time user, there is always something to learn about JMP.

Visit JMP.com to find the following:

- live and recorded webcasts about how to get started with JMP
- video demos and webcasts of new features and advanced techniques
- details on registering for JMP training
- schedules for seminars being held in your area
- success stories showing how others use JMP
- a blog with tips, tricks, and stories from JMP staff
- a forum to discuss JMP with other users

<http://www.jmp.com/getstarted/>

Contents

Using JMP

1	Learn about JMP	23
	Documentation and Additional Resources	
	Formatting Conventions	25
	JMP Documentation	26
	JMP Documentation Library	26
	JMP Help	32
	Additional Resources for Learning JMP	32
	Tutorials	32
	Sample Data Tables	33
	Learn about Statistical and JSL Terms	33
	Learn JMP Tips and Tricks	33
	Tooltips	33
	JMP User Community	34
	JMP Books by Users	34
	The JMP Starter Window	34
	Technical Support	35
2	Get Started	37
	Introduction to Basic Features	
	Anatomy of a JMP Session	39
	Data Tables	40
	Data Table Panels	41
	Data Grid	48
	Open Data File Options	53
	Platforms	55
	Launch Windows	55
	Reports	58
	Manage JMP Files and Open Windows	59
	JMP Home Window on Macintosh	63
	Search for Recently Opened Files on Windows	65
	Close Multiple Files	65
	Display and Arrange Open Windows	65
	Preview JMP Files	67

Using the Reveal Feature	68
JMP Starter Window	68

3 Import Your Data	71
Create Data Tables	
About Importing Data to JMP	74
Import Microsoft Excel Files	75
Preview and Import the Microsoft Excel Data	76
Import a Microsoft Excel File Directly	87
Import Data from SAS	88
SAS Menu Options	88
Import SAS Data Sets	89
Create SAS Transport Files in SAS	91
Connect to SAS	92
Open SAS Data Sets with SAS Query Builder	97
Open SAS Data Sets through a SAS Server	98
Using SAS Extended Attributes to Import Metadata	106
Run Stored Processes	108
Submit SAS Code	108
Generate ODS Results	110
Retrieve Generated SAS Data Sets	111
Build SQL Queries in Query Builder	113
Connect to a SQL Database	114
Select Tables from a SQL Database	115
Build the SQL Query	119
Save and Run the Query	133
Open the Selected Data in JMP	134
Query Builder Red Triangle Options	134
Write SQL Statements in Query Builder	135
Import Data from a Database	136
Connect to a Database	136
Open Data from a Database	137
Write SQL Statements to Query a Database	139
Structured Query Language (SQL): A Reference	141
Import Text Files	147
Text Import Wizard Options	149
Open a Text File in a Text Editing Window	153
Import Text from the Script Editor	155
Import Multiple Files	156
Import Data from the Internet or a Remote Computer	161

Import SPSS Files	163
Import Triple-S Survey Data	164
Import HDF5 Data	165
Import JSON Files	165
Import Data from MATLAB	166
Import Data from R	166
Import Data Using the Excel Add-In	167
Transfer Excel Data to a JMP Data Table	167
About the JMP Add-In for Excel	168
Uninstall the Excel Add-In	169
Create New Data Tables	169
4 Enter and Edit Data	171
Perform Basic Data Table Tasks	
Enter Data	174
Copy and Paste Data	174
Add Rows	175
Add Columns	175
Fill Columns with Sequential Data	177
Replace Missing Values with Previous Values	178
Enter Cell Formulas	179
Select Rows	180
Locate Next and Previously Selected Rows	182
Select Columns	183
Select Columns in the Columns Viewer	185
Locate Next and Previously Selected Columns	190
Select Cells	190
Resize Rows and Columns	192
Organize Data	192
Delete Rows and Columns	193
Rearrange Columns	193
Group Columns	194
Move Values	195
Color Cells	196
Edit or Delete Cells	196
Edit Column Names	196
Hide and Exclude Rows	196
Exclude Rows	197
Hide Rows	198
Exclude Columns	199

Hide Columns	200
View Patterns of Missing Data	200
Find and Replace Cell Values	202
Use the Row Editor to Edit Cells in a Row	204
Pop-Up Menus for Rows and Columns	206
Compare Data Tables	206
Assign Characteristics to Rows and Columns	210
How to Find Rows and Columns Options	211
Label Rows and Columns	211
Assign Colors or Markers to Rows	212
Create Color Themes	214
Delete Custom Color Themes	219
Select Matching Row State Cells	219
Delete Row Characteristics	220
Lock Columns in Place	220
Restructure Data	220
Make a Column into Multiple Columns	220
Make Indicator Columns	221
Combine Columns	221
Compress Selected Columns	222
Make Binning Formula	224
Convert Labels to Codes and Codes to Labels	226
Make a New Formula Column	227
Transform Columns	227
Recode Data	237
Edit the Data Table	246
Change Table Names	246
Lock Tables	246
Compress Tables	247
Use Table Variables	248
Create and Save Scripts	249

5 The Column Info Window	255
Set Column Attributes and Properties	
About the Column Info Window	257
About Modeling Types	260
The Short-Integer Format	260
Numeric Formats	261
Row State Columns	265
Initialize Data	267

Column Properties	268
Basic Column Properties	269
Properties That Validate Column Values	270
Properties That Attach Information to Column Values	271
Properties That Control the Display of Columns	276
Properties Used in Modeling and DOE	277
Properties Associated with Control Charts and Capability	278
Properties That Control How Columns Are Used in Platforms	279
SAS Properties	287
Virtual Join Properties	288
Additional Properties	289
Properties Assigned and Controlled by JMP	292
Standardize Attributes and Properties Across Columns	294
Recode Values	294
Standardize Attributes	295
Standardize Properties	295
Delete Properties	295
Example of Standardizing a Formula	296
Assign a Preselected Analysis Role	297

6 Reshape Data

Create Subsets, Sort Data, and More

Create a Subset Data Table	301
Stratified Subsets	303
Create a Subset Data Table from a Report	303
Sort Data Tables	304
Stack Columns	306
Example of Stacking into One Column	308
Example of Stacking into More Than One Column	309
Split Columns	311
Examples of Splitting Columns	312
Transpose Rows and Columns	314
Examples of Transposing Rows and Columns	317
Concatenate Data Tables	318
Example of Concatenating Data Tables	319
Example of Concatenating Data Tables and Table Variables	320
Join Data Tables	321
Examples of Joining Data Tables	324
Query and Join Data Tables with JMP Query Builder	332
About Links to Data Tables in JMP Queries	335

Virtually Join Data Tables	335
Example of Virtually Joining Columns	337
Example of Virtually Joining Columns and Showing Row States	340
Example of Merging Referenced Data in Virtually Joined Data Tables	341
Update Data Tables	343
Example of Updating a Data Table	345
Anonymize Data	346
7 Formula Editor	349
Construct Formulas	
Formula Overview	352
Create a Formula	352
Refer to Values in Columns and Table Variables	354
Use Local Variables	357
Incorporate Parameters	358
Insert Constants	359
Add Operators	361
Keypad Reference	361
Use Functions in a Formula	362
Customize the Functions List	365
Copy a Formula to Columns on the Right	367
Order Expressions in Formulas	369
Build a Formula in Order of Precedence	370
Use Formula Editor Options	371
Calculate Derivatives	371
Simplify Complex Formulas	372
Evaluate Formulas	373
Ignore Errors	374
View Formula Values from the Formula Editor	374
View a Formula in JSL	374
Edit Formulas	375
Correct Mistakes	375
Select Expressions	375
Delete Functions	376
Cut, Copy, and Paste	376
Click and Drag	377
Customize Formulas	377
Hide and Show Boxing	377
Change the Font Size	378
Specify the Matrix Size	378

	Change the Orientation of a Formula	378
	Open and Close Arguments	378
	Examples and Tutorials	379
	Use Basic Formula Editor Features	379
	Use Local Variables in a Formula	380
	Use the Munger Function	381
	Use the Match Conditional Function	382
	Use the Delete Expression Button	383
	Keyboard Shortcuts	384
	Glossary of Terms	385
8	Summarize Data	389
	The Table Summary Command	
	Summarize Columns	391
	Launch Window Roles	391
	Create a Summary Table	391
	Add a Statistics Column to an Existing Summary Table	395
	Explanation of Statistics	396
	Example of Creating a Summary Table	398
9	JMP Reports	401
	Navigate and Customize Report Windows	
	Navigate Reports	404
	Use the Hand Tool	405
	Access Report Display Options	405
	Show and Hide Parts of a Report	407
	Combine Several Reports	408
	Rename a Title	408
	Increase Font Sizes	408
	Resize a Window	408
	Red Triangle Options in a Report	409
	Local Data Filter	409
	Redo Menus	412
	Save Script Menus	412
	The Data Filter	415
	Types of Filter Columns	416
	Filtering Modes	416
	The Data Filter Control Panel	417
	Red Triangle Options for the Data Filter	420
	Animation in Data Filters	423
	Red Triangle Options for Variables	426

Reformat Report Tables	428
Modify Display Box Properties in a Report	429
Turn a Report Table Into a Matrix	430
Use Conditional Formatting	430
Select Points in Graphs	436
Select Rows in Graphs	437
Select a Rectangular Area of Points	437
Select an Irregular-Shaped Area of Points	438
Use Markers	439
Change Marker Shape	440
Change Marker Colors	440
Change Marker Size	440
Work with Crowded Markers	441
Add Outlines Around Markers	441
Marker Selection Modes	442
Specify Marker Transparency	443
Exclude and Hide Markers	443
Add Labels to Markers	444
Use Images as Markers	445
Change Marker Shape or Colors Based On Values	446
Change the Appearance of Graphs	448
Resize Graphs	449
Zoom In and Out	450
Display Images on Hover Labels	450
Pin Hover Labels on a Graph	451
Change Line Widths	453
Change the Background Color in a Graph	453
Change the Color of Histogram Bars	453
Display Coordinates and Temporary Reference Lines	453
Scroll and Scale Axes	454
Customize Axes and Axis Labels in the Axis Settings Window	455
Customize Axes and Axis Labels Using the Pop-Up Menu	464
Change the Order of Values	466
Change the Pattern and Format of Selected Objects	467
Add a Graph to a Data Table	467
Customize Graphical Elements	468
Add Images to a Graph or Report	474
Paste a Background Image into a Graph	474
Paste an Image at the End of a Report	475
Drag and Drop an Image into a Graph	475

Add Geographical Images and Boundaries	477
Extract Data from an Image	477
Add Annotations and Shapes to a Report	478
10 Save and Share Data	483
Get Your Data Out of JMP	
Save and Share Data Tables	486
Save as a Microsoft Excel File	487
Save as a CSV File	488
Save as a Text File	489
Save as a SAS Transport File	490
Save as a SAS Data Set	491
Save Data Tables to a Database	492
Replace a Database with a Data Table	493
Email a Data Table	494
Save and Share Reports	494
Email a Report	496
Share Interactive JMP Reports on the Web	496
Save as PDF	506
Save as PowerPoint	507
Save as Flash	508
Setting the Graphic DPI	509
Save Your Analysis as a Script	509
Save Parts of a Report in a Graphic Format	509
Print Reports	511
Copy and Paste Reports	511
Create a Journal	512
Example of Making a Journal for a Presentation	513
Create a New Journal	515
Manage Links in Shared Journals	515
Add and Edit Outlines	517
Journal Right-Click Options	517
Control the Display of Outline Levels	518
Add a Graph or Graphic	518
Customize Journal Items	519
Prevent Modifications	519
Append Reports to a Journal	519
Save the Journal in Another Format	520
Delete Items from a Journal	520
Create a Project	521

Save Files in a Project	524
Move Files to a Project	526
Share the Project	527
Projects Compatibility	528
Save JMP Sessions	529
Save Sessions upon Exiting	529
Save Sessions Manually	530
Save a Log Window	530
11 Extend JMP	531
Create Dashboards	
Combine Reports by Creating a Dashboard	533
Example of Creating a Dashboard with Two Reports	533
Details about Using the Dashboard Builder	534
Dashboard Builder Red Triangle Options	535
Sample Dashboards	537
Edit a Dashboard	537
View a Running Dashboard	540
Example of Combining Windows to Create a Dashboard	543
Example of Adding Selection Filters to a Dashboard	544
Example of Creating a JMP Query Dashboard and Add-In	546
Example of Creating a Dashboard from Two Data Tables	548
12 Personalize JMP	551
Customize Menus and Toolbars	
Personalize Toolbars and Menus on Windows	553
Change Customization Sets	554
Create Toolbars	555
Create Main Menus	558
Create Menu Items and Toolbar Buttons	559
Rearrange Toolbars	563
Copy and Paste Menus, Menu Items, Toolbars, and Buttons	563
Rearrange Custom Menus, Menu Items, and Buttons	565
Delete Custom Items	566
Show and Hide Items	567
Import Customizations	568
Remove Customizations	568
Personalize Toolbars on Macintosh	570
Personalize Menu Items on Macintosh	571
Customize Menus and Toolbars for an Add-In	572

13	JMP Preferences	575
	The Preferences Window	
	Overview	577
	General	577
	Reports	583
	Graphs	587
	Styles	591
	Tables	593
	Platforms	598
	Print	600
	Text Data Files	601
	Windows Specific	606
	Macintosh OS Settings	609
	Fonts	610
	Communications	613
	File Locations	614
	Script Editor	617
	SAS Integration	620
	JMP Updates	623
	JSL Debugger	625
	Menu Preferences	626
	Query Builder	628
A	Formula Functions Reference	631
	Descriptions of Functions in the Formula Editor	
	Row Functions	633
	Numeric Functions	635
	Transcendental Functions	636
	Trigonometric Functions	639
	Character Functions	640
	Character Pattern Functions	646
	Comparison Functions	650
	Conditional Functions	651
	Probability Functions	656
	Discrete Probability Functions	669
	Statistical Functions	672
	Random Functions	676
	Date Time Functions	681
	Row State Functions	684
	Assignment Functions	690

	Parametric Model Functions	690
	Finance Functions	691
B	JMP Technical Details	693
	Features That Support Multithreading	695
	Conventions for Mapping JMP Attributes to SAS Extended Attributes	696
	Index	705
	Using JMP	

Chapter 1

Learn about JMP

Documentation and Additional Resources

This chapter includes details about JMP documentation, such as book conventions, descriptions of each JMP book, the Help system, and where to find other support.

Contents

Formatting Conventions	25
JMP Documentation	26
JMP Documentation Library	26
JMP Help	32
Additional Resources for Learning JMP	32
Tutorials	32
Sample Data Tables	33
Learn about Statistical and JSL Terms	33
Learn JMP Tips and Tricks	33
Tooltips	33
JMP User Community	34
JMP Books by Users	34
The JMP Starter Window	34
Technical Support	35

Formatting Conventions

The following conventions help you relate written material to information that you see on your screen:

- Sample data table names, column names, pathnames, filenames, file extensions, and folders appear in Helvetica font.
- Code appears in *Lucida Sans Typewriter* font.
- Code output appears in *Lucida Sans Typewriter* italic font and is indented farther than the preceding code.
- **Helvetica bold** formatting indicates items that you select to complete a task:
 - buttons
 - check boxes
 - commands
 - list names that are selectable
 - menus
 - options
 - tab names
 - text boxes
- The following items appear in italics:
 - words or phrases that are important or have definitions specific to JMP
 - book titles
 - variables
- Features that are for JMP Pro only are noted with the JMP Pro icon . For an overview of JMP Pro features, visit <https://www.jmp.com/software/pro/>.

Note: Special information and limitations appear within a Note.

Tip: Helpful information appears within a Tip.

JMP Documentation

JMP offers documentation in various formats, from print books and Portable Document Format (PDF) to electronic books (e-books).

- Open the PDF versions from the **Help > Books** menu.
- All books are also combined into one PDF file, called *JMP Documentation Library*, for convenient searching. Open the *JMP Documentation Library* PDF file from the **Help > Books** menu.
- You can also purchase printed documentation and e-books on the SAS website:
<https://www.sas.com/store/search.ep?keyWords=JMP>

JMP Documentation Library

The following table describes the purpose and content of each book in the JMP library.

Document Title	Document Purpose	Document Content
<i>Discovering JMP</i>	If you are not familiar with JMP, start here.	Introduces you to JMP and gets you started creating and analyzing data. Also learn how to share your results.
<i>Using JMP</i>	Learn about JMP data tables and how to perform basic operations.	Covers general JMP concepts and features that span across all of JMP, including importing data, modifying columns properties, sorting data, and connecting to SAS.

Document Title	Document Purpose	Document Content
<i>Basic Analysis</i>	Perform basic analysis using this document.	Describes these Analyze menu platforms: • Distribution • Fit Y by X • Tabulate • Text Explorer Covers how to perform bivariate, one-way ANOVA, and contingency analyses through Analyze > Fit Y by X. How to approximate sampling distributions using bootstrapping and how to perform parametric resampling with the Simulate platform are also included.
<i>Essential Graphing</i>	Find the ideal graph for your data.	Describes these Graph menu platforms: • Graph Builder • Scatterplot 3D • Contour Plot • Bubble Plot • Parallel Plot • Cell Plot • Scatterplot Matrix • Ternary Plot • Treemap • Chart • Overlay Plot The book also covers how to create background and custom maps.
<i>Profilers</i>	Learn how to use interactive profiling tools, which enable you to view cross-sections of any response surface.	Covers all profilers listed in the Graph menu. Analyzing noise factors is included along with running simulations using random inputs.

Document Title	Document Purpose	Document Content
<i>Design of Experiments Guide</i>	Learn how to design experiments and determine appropriate sample sizes.	Covers all topics in the DOE menu and the Specialized DOE Models menu item in the Analyze > Specialized Modeling menu.
<i>Fitting Linear Models</i>	Learn about Fit Model platform and many of its personalities.	Describes these personalities, all available within the Analyze menu Fit Model platform: • Standard Least Squares • Stepwise • Generalized Regression • Mixed Model • MANOVA • Loglinear Variance • Nominal Logistic • Ordinal Logistic • Generalized Linear Model

Document Title	Document Purpose	Document Content
<i>Predictive and Specialized Modeling</i>	Learn about additional modeling techniques.	Describes these Analyze > Predictive Modeling menu platforms: • Modeling Utilities • Neural • Partition • Bootstrap Forest • Boosted Tree • K Nearest Neighbors • Naive Bayes • Model Comparison • Formula Depot Describes these Analyze > Specialized Modeling menu platforms: • Fit Curve • Nonlinear • Functional Data Explorer • Gaussian Process • Time Series • Matched Pairs Describes these Analyze > Screening menu platforms: • Response Screening • Process Screening • Predictor Screening • Association Analysis • Process History Explorer The platforms in the Analyze > Specialized Modeling > Specialized DOE Models menu are described in <i>Design of Experiments Guide</i>.

Document Title	Document Purpose	Document Content
<i>Multivariate Methods</i>	Read about techniques for analyzing several variables simultaneously.	Describes these Analyze > Multivariate Methods menu platforms: • Multivariate • Principal Components • Discriminant • Partial Least Squares • Multiple Correspondence Analysis • Factor Analysis • Multidimensional Scaling • Item Analysis Describes these Analyze > Clustering menu platforms: • Hierarchical Cluster • K Means Cluster • Normal Mixtures • Latent Class Analysis • Cluster Variables
<i>Quality and Process Methods</i>	Read about tools for evaluating and improving processes.	Describes these Analyze > Quality and Process menu platforms: • Control Chart Builder and individual control charts • Measurement Systems Analysis • Variability / Attribute Gauge Charts • Process Capability • Pareto Plot • Diagram • Manage Spec Limits

Document Title	Document Purpose	Document Content
<i>Reliability and Survival Methods</i>	Learn to evaluate and improve reliability in a product or system and analyze survival data for people and products.	Describes these Analyze > Reliability and Survival menu platforms: • Life Distribution • Fit Life by X • Cumulative Damage • Recurrence Analysis • Degradation and Destructive Degradation • Reliability Forecast • Reliability Growth • Reliability Block Diagram • Repairable Systems Simulation • Survival • Fit Parametric Survival • Fit Proportional Hazards
<i>Consumer Research</i>	Learn about methods for studying consumer preferences and using that insight to create better products and services.	Describes these Analyze > Consumer Research menu platforms: • Categorical • Choice • MaxDiff • Uplift • Multiple Factor Analysis
<i>Scripting Guide</i>	Learn about taking advantage of the powerful JMP Scripting Language (JSL).	Covers a variety of topics, such as writing and debugging scripts, manipulating data tables, constructing display boxes, and creating JMP applications.
<i>JSL Syntax Reference</i>	Read about many JSL functions on functions and their arguments, and messages that you send to objects and display boxes.	Includes syntax, examples, and notes for JSL commands.

Note: The **Books** menu also contains two reference cards that can be printed: The *Menu Card* describes JMP menus, and the *Quick Reference* describes JMP keyboard shortcuts.

JMP Help

JMP Help is an abbreviated version of the documentation library that provides targeted information. You can open JMP Help in several ways:

- On Windows, press the F1 key to open the Help system window.
- Get help on a specific part of a data table or report window. Select the Help tool  from the **Tools** menu and then click anywhere in a data table or report window to see the Help for that area.
- Within a JMP window, click the **Help** button.
- Search and view JMP Help on Windows using the **Help > Help Contents**, **Search Help**, and **Help Index** options. On Mac, select **Help > JMP Help**.
- Search the Help at <https://jmp.com/support/help/> (English only).

Additional Resources for Learning JMP

In addition to JMP documentation and JMP Help, you can also learn about JMP using the following resources:

- [“Tutorials”](#)
- [“Sample Data Tables”](#)
- [“Learn about Statistical and JSL Terms”](#)
- [“Learn JMP Tips and Tricks”](#)
- [“Tooltips”](#)
- [“JMP User Community”](#)
- [“JMP Books by Users”](#)
- [“The JMP Starter Window”](#)

Tutorials

You can access JMP tutorials by selecting **Help > Tutorials**. The first item on the **Tutorials** menu is **Tutorials Directory**. This opens a new window with all the tutorials grouped by category.

If you are not familiar with JMP, then start with the **Beginners Tutorial**. It steps you through the JMP interface and explains the basics of using JMP.

The rest of the tutorials help you with specific aspects of JMP, such as designing an experiment and comparing a sample mean to a constant.

Sample Data Tables

All of the examples in the JMP documentation suite use sample data. Select **Help > Sample Data Library** to open the sample data directory.

To view an alphabetized list of sample data tables or view sample data within categories, select **Help > Sample Data**.

Sample data tables are installed in the following directory:

On Windows: C:\Program Files\SAS\JMP\14\Samples\Data

On Macintosh: \Library\Application Support\JMP\14\Samples\Data

In JMP Pro, sample data is installed in the JMPPRO (rather than JMP) directory. In JMP Shrinkwrap, sample data is installed in the JMPSW directory.

To view examples using sample data, select **Help > Sample Data** and navigate to the Teaching Resources section. To learn more about the teaching resources, visit <https://jmp.com/tools>.

Learn about Statistical and JSL Terms

The **Help** menu contains the following indexes:

Statistics Index Provides definitions of statistical terms.

Scripting Index Lets you search for information about JSL functions, objects, and display boxes. You can also edit and run sample scripts from the Scripting Index.

Learn JMP Tips and Tricks

When you first start JMP, you see the Tip of the Day window. This window provides tips for using JMP.

To turn off the Tip of the Day, clear the **Show tips at startup** check box. To view it again, select **Help > Tip of the Day**. Or, you can turn it off using the Preferences window.

Tooltips

JMP provides descriptive tooltips when you place your cursor over items, such as the following:

- Menu or toolbar options

- Labels in graphs
- Text results in the report window (move your cursor in a circle to reveal)
- Files or windows in the Home Window
- Code in the Script Editor

Tip: On Windows, you can hide tooltips in the JMP Preferences. Select **File > Preferences > General** and then deselect **Show menu tips**. This option is not available on Macintosh.

JMP User Community

The JMP User Community provides a range of options to help you learn more about JMP and connect with other JMP users. The learning library of one-page guides, tutorials, and demos is a good place to start. And you can continue your education by registering for a variety of JMP training courses.

Other resources include a discussion forum, sample data and script file exchange, webcasts, and social networking groups.

To access JMP resources on the website, select **Help > JMP User Community** or visit <https://community.jmp.com/>.

JMP Books by Users

Additional books about using JMP that are written by JMP users are available on the JMP website:

https://www.jmp.com/en_us/software/books.html

The JMP Starter Window

The JMP Starter window is a good place to begin if you are not familiar with JMP or data analysis. Options are categorized and described, and you launch them by clicking a button. The JMP Starter window covers many of the options found in the Analyze, Graph, Tables, and File menus. The window also lists JMP Pro features and platforms.

- To open the JMP Starter window, select **View (Window on the Macintosh) > JMP Starter**.
- To display the JMP Starter automatically when you open JMP on Windows, select **File > Preferences > General**, and then select **JMP Starter** from the Initial JMP Window list. On Macintosh, select **JMP > Preferences > Initial JMP Starter Window**.

Technical Support

JMP technical support is provided by statisticians and engineers educated in SAS and JMP, many of whom have graduate degrees in statistics or other technical disciplines.

Many technical support options are provided at <https://www.jmp.com/support>, including the technical support phone number.

Chapter 2


Get Started

Introduction to Basic Features

To get you started with JMP, this chapter covers the following topics:

- learn about the initial windows that appear when you start JMP
- understand data tables
- open data files
- manage open windows
- learn about the anatomy of a typical JMP user session

Figure 2.1 The JMP Home Window on Windows



Contents


Anatomy of a JMP Session.....	39
Data Tables.....	40
Data Table Panels.....	41
Data Grid.....	48
Open Data File Options.....	53
Platforms.....	55
Launch Windows.....	55
Reports.....	58
Manage JMP Files and Open Windows.....	59
JMP Home Window on Windows.....	59
JMP Home Window on Macintosh.....	63
Search for Recently Opened Files on Windows.....	65
Close Multiple Files.....	65
Display and Arrange Open Windows.....	65
Preview JMP Files.....	67
Using the Reveal Feature.....	68
JMP Starter Window.....	68

Anatomy of a JMP Session

JMP consists of platforms that are organized by the type of statistical analysis. For example, the Distribution platform produces a univariate analysis using histograms, additional graphs, and reports. You might analyze data in the Distribution platform and then choose another platform to examine the data more thoroughly. As a result, several windows are open at once: at a minimum, the data table, platform launch windows, and the results of the analyses.

Figure 2.2 shows a typical JMP session. Note that the windows are not maximized so that you can quickly switch from one window to another.

Figure 2.2 Anatomy of a Typical JMP Session on Windows




The following sections describe the windows that you typically work with.

Data Tables

In JMP, data points are organized into rows and columns referred to as the *data table*. A data table has two parts: the *data table panels* on the left and the *data grid* on the right.

You can enter, view, edit, and manipulate data using data tables. In a data table, each variable is a column, and each observation is a row.

Figure 2.3 Data Table Features



The data table has the following characteristics:

- Column names can contain any keyboard character, including spaces, and can be up to 255 characters long.
- The maximum length of the data table's name depends on your computer's operating system.
- Consider setting the Autosave Timeout value in the General preferences to automatically save data tables at the specified number of minutes. This autosave value also applies to journals, scripts, projects, and reports.
- Change the default size and font for names and values selecting **File > Preferences > Fonts**. (On the Macintosh, select **JMP > Preferences > Fonts**.)
- Column names automatically wrap in the column name area to accommodate the column width that you specify.
- Move column boundaries and enlarge the column to view long values. Adjust widths of all selected columns at once by pressing the Alt key as you drag the double arrow cursor on any of the selected column boundaries.
- The number of rows and columns in a data table is limited only by your computer's memory.
- Resize rows by dragging one of the row borders. All rows are resized to the same height. Graphics that display inside each cell shrink based on the row height.

To resize columns to the same width, select the columns and press Control (Windows) or Option (Macintosh); drag one of the column borders. All columns are resized to the same width.

Tip: To close a report thumbnail in the data table on Windows, press the middle-click button on your mouse.

Data Table Panels

Data tables contain three panels:

- Table panel
- Columns panel
- Rows panel

These panels are located on the left of the data grid. They contain information about the table and its contents. Each panel has interactive areas. See Figure 2.4.


Figure 2.4 Interacting with the Data Table Panels

Table Panel

The Table panel contains the following elements:

- Name of the data table
- Icons indicating the table state
- Red triangle menus containing table and script options
- (Optional) Table variables
- (Optional) Table scripts


Figure 2.5 Example of a Table Panel

Table Options

Clicking on the red triangle menu next to the data table name shows these options:

Tables Contains the same options as the Tables menu. See [“Reshape Data”](#) chapter on page 299.

New Table Variable Creates a new table variable, which can be text or any other constant character value that you always want to be available in the data table. Table variables are

normally used to document tables. See [“Use Table Variables”](#) on page 248 in the “Enter and Edit Data” chapter for more information.

Note: To rename a table variable, double-click on it and enter a new name in the Name field.

New Script Creates a JSL script to save with the data table. After selecting this command, name the script and type in the value (the JSL commands). After you click **OK**, the new script is listed in the Table panel and you can click its green triangle to run, edit, or delete it. See [“Create and Save Scripts”](#) on page 249 in the “Enter and Edit Data” chapter.

Suppress Formula Eval Turns off the feature that automatically evaluates formulas. You can turn off evaluation and build sections of a formula. To then test the formula, deselect Suppress Formula Eval.

Lock Data Table Locks the data table so that data and column properties cannot be edited or added. You can still run analyses and assign characteristics. See [“Lock Tables”](#) on page 246 in the “Enter and Edit Data” chapter.

Compress file when saved Compresses the data table when it is saved. After the data table is saved, a compressed file icon  appears next to the data table name in the table panel. See [“Compress Tables”](#) on page 247 in the “Enter and Edit Data” chapter.

The **Compress file when saved** option only decreases the file size. This command does not affect the memory required to analyze the data. To reduce both the file size and memory required for analyzing, use **Cols > Utilities > Compress Selected Columns**. See [“Compress Selected Columns”](#) on page 222 in the “Enter and Edit Data” chapter.

Tip: You can also configure JMP to always use GZ compression when saving tables by selecting **Preferences > General > Save Data Table Columns GZ Compressed**.

Disable Undo Removes all actions from the undo history and does not record future actions. Undos are disabled only while the data table is open; the setting is not saved with the data table. This option saves memory, especially when you delete many rows or perform other tasks on the data table that require a large amount of memory to record the data.

Copy Table Script Copies the script that re-creates the table. To re-create the table, put the copied script in a new script and run it. Note that referenced columns in virtually joined tables are not included in the script.

Rerun Formulas Re-evaluates all columns containing formulas within the data table.

Script Options

To run a script from the data table panel, click the green triangle  next to the script name. Right-clicking the script name or green triangle shows these options:

Run Script Runs the script.

Tip: Run multiple table scripts at once by holding down the Control key, while selecting the table scripts you want to run. Then, right-click inside the empty area under the list of table scripts, and select **Run Script**.

Edit Opens most scripts in the script editor so that you can edit it. Opens a JMP application script in Application Builder.

Delete Deletes the script.

Group Scripts Moves the selected scripts into a group. Click the group name to rename it. Helpful when you want to organize scripts or minimize a long list of scripts.

Ungroup Scripts Ungroups scripts in the selected group to return them to the top level.

Copy Copies the script. You can then paste it into the Table panel of another data table.

Debug Script Opens the script in the JSL Debugger. See the Scripting Tools chapter in the *Scripting Guide*.

Paste Pastes the script from another data table.

Additional Options

In the Table panel, you can also perform the following tasks:

- Double-click a table variable or script name to edit the name and content.
- Drag a table variable or script to rearrange it.


Columns Panel

The Columns panel provides a way to view and move columns. The panel contains the following information:

- Column options (contains some of the same options as the Cols menu)
- Total number of columns and number of columns selected in the data table
- A list of columns found in the data table
- Icons indicating each column's modeling type (see [“About Modeling Types”](#) on page 260 in the “The Column Info Window” chapter)

- Icons representing characteristics and properties assigned to the columns (not shown, see Figure 2.7)


Figure 2.6 Example of a Columns Panel



Icons Representing Column Characteristics and Properties

Icons to the right of each column name indicate characteristics and properties the columns contain.

Figure 2.7 Icons Indicating Column Characteristics and Properties



Note: Italics indicate that the column is locked into place. When you scroll horizontally, the column remains visible.

Icons that can appear in the Columns panel are described as follows:

 Indicates that points on plots corresponding to the column are labeled by the value instead of the row number. See [“Label Rows and Columns”](#) on page 211 in the “Enter and Edit Data” chapter.

 Indicates that the column is excluded from the calculations. See [“Exclude Rows”](#) on page 197 in the “Enter and Edit Data” chapter.

 Indicates that the column is not included in graphs. See [“Hide Rows”](#) on page 198 in the “Enter and Edit Data” chapter.

 Can be X or Y. Indicates that the column has been assigned the preselected role of *x* or *y*. See [“Assign a Preselected Analysis Role”](#) on page 297 in the “The Column Info Window” chapter.

 Indicates that the column contains one or more properties. Click to reveal a list of properties the column contains.

 Indicates that the values in the column result from a formula. When formula evaluation is suppressed, the icon appears gray. Double-click to view and edit the formula. See [“Use Formula Editor Options”](#) on page 371 in the “Formula Editor” chapter.

 Indicates that the range check or the list check option is turned on. Click to view and edit the range or list. See [“Range Check”](#) on page 270 in the “The Column Info Window” chapter and [“List Check”](#) on page 270 in the “The Column Info Window” chapter.

 Indicates that the column has been assigned the preselected role of *weight*. See [“Assign a Preselected Analysis Role”](#) on page 297 in the “The Column Info Window” chapter.

 Indicates that the column has been assigned the preselected role of *frequency*. See [“Assign a Preselected Analysis Role”](#) on page 297 in the “The Column Info Window” chapter.

 Indicates that the column values cannot be edited. See [“About the Column Info Window”](#) on page 257 in the “The Column Info Window” chapter.

 Indicates that the expression column contains images that can be used as markers. See [“Use Images as Markers”](#) on page 445 in the “JMP Reports” chapter for details.

Virtual Join Icons



Indicates that the column has a Link Reference column property. This property links a column in the current data table to the ID column in the referenced data table. Blue indicates that the referenced data table is linked.



Indicates that the column has a Link Reference column property. Gray indicates that the referenced data table is not open or not linked properly.



Indicates that the column has a Link ID column property, which marks a column in the data table as the ID column. That is, the rows of the data table are uniquely identified by the values of the ID column.



Indicates that the column is linked from the referenced data table.

For details about virtual join, see [“Virtually Join Data Tables”](#) on page 335 in the “Reshape Data” chapter.

Rows Panel

The Rows panel contains the following information:

- Row options (same options as the **Rows** menu)
- Total number of rows
- Number of selected (highlighted), excluded, hidden, and labeled rows

Figure 2.8 Example of a Rows Panel


row options —

Rows	
All rows	233
Selected	0
Excluded	0
Hidden	0
Labelled	0

Right-click the categories in the Rows panel to select rows, clear the selection, or to create a *data view*.

A data view creates a linked subset of the main data table. For example, if several rows are marked hidden, you might want to open a window that shows you only the hidden rows. Right-click **Hidden** in the Rows panel and select **Data View**.

Figure 2.9 Creating a Data View from the Rows Panel




When using a data view, continue to do most of your editing in the main data table. When you make changes in either the main data table or in the data view, the changes are reflected in both. You can make minor changes (such as changing some data or adding a column) in the data view. However, if you want to make major changes (like adding a formula) you must make those changes in the main data table.

Data Grid

The data grid is the main part of the data table that contains your data. Figure 2.10 illustrates how to interact with the data grid. See also “[Select Rows](#)” on page 180 in the “Enter and Edit Data” chapter.

Figure 2.10 Interacting with the Data Grid



No.	Description
1	Hides or shows the data table panels.
2	Click to deselect any selected columns. To select all columns, hold down the Shift key and click. Double-click to add multiple columns.
3	Shows the columns menu.
4	Click to select the column. Double-click to view the Column Info window. See “About the Column Info Window” on page 257. Right-click for column options. See “Pop-Up Menu for Columns” on page 49.
5	Double-click the column name to edit it in the Column Info window, or select the column name and press Enter.
6	Click and drag to change a column width. To change several column widths, select the columns, press Alt, then click and drag.
7	Click to select the row. Double-click to open the Row Editor. See “Use the Row Editor to Edit Cells in a Row” on page 204 in the “Enter and Edit Data” chapter. Right-click for row options. See “Pop-Up Menu for Rows” on page 51.
8	Shows the rows menu.
9	Click to deselect all selected rows. To select all rows, hold down the Shift key and click. Double-click to add rows.

Pop-Up Menu for Columns

Right-clicking in a column heading shows these options:

Column Info Opens the Column Info window. See [“About the Column Info Window”](#) on page 257.

Standardize Attributes Copies attributes (data types, modeling types, numeric formats, and so on) or properties (formulas, notes, list and range checks, and so on) from one column to other columns. Also deletes selected attributes or properties from columns. See [“Standardize Attributes and Properties Across Columns”](#) on page 294 in the “The Column Info Window” chapter.

Column Properties Contains a list of column properties. Select one to open the Column Info window and apply it to the column. This list is also available from the Column Info window. See [“Column Properties”](#) on page 268 in the “The Column Info Window” chapter.

Formula Opens the Formula Editor. See the [“Formula Editor”](#) chapter on page 349.

New Formula Column Creates a formula column. See [“Make a New Formula Column”](#) on page 227 in the “Enter and Edit Data” chapter for details.

Insert Columns Inserts one or more columns before the selected column or columns.

Delete Columns Deletes all selected columns.

Label/Unlabel Labels or unlabels selected columns in all plots. See [“Label Rows and Columns”](#) on page 211 in the “Enter and Edit Data” chapter.

Link ID Used in virtually joined data tables to mark a column in the auxiliary data table as the ID column. That is, the rows of the data table are uniquely identified by the values of the ID column. The Link ID column property checkbox is selected if the column is the ID column for the data table. See [“Virtual Join Properties”](#) on page 288 in the “The Column Info Window” chapter for details.

Link Reference Used in virtually joined data tables to map a column in the main data table to the ID column in the auxiliary data table. The Link Reference column property specifies the path name of the auxiliary data table. See [“Virtual Join Properties”](#) on page 288 in the “The Column Info Window” chapter for details.

Sort Sorts all of the rows in the table by the values in the selected column. You can choose to sort the rows in ascending or descending order. See [“Sort Data Tables”](#) on page 304 in the “Reshape Data” chapter.

Copy Column Properties Copies all of the column properties for the selected column. Note that if you copy column properties for more than one column and then paste into a single column, all column properties are pasted into that single column.

Paste Column Properties Pastes all of the copied column properties into the selected column or columns.

Copy Multi Columns Properties Copies all of the column properties for the selected columns. Supports adjacent and non-adjacent columns.

Paste Multi Columns Properties Pastes all of the copied column properties into the selected adjacent or non-adjacent columns. For example, select column one and column two and then select **Copy Multi Column Properties**. Select column three and column five

and then select **Paste Multi Column Properties**. Column one properties are pasted into column three. Column two properties are pasted into column five.

Pop-Up Menu for Rows

Right-clicking in a row heading shows these options:

Hide and Exclude Hides the selected rows in all plots and graphs and excludes them from analyses. See [“Hide and Exclude Rows”](#) on page 196 in the “Enter and Edit Data” chapter.

Exclude/Unexclude Excludes or includes selected rows from analyses. See [“Exclude Rows”](#) on page 197 in the “Enter and Edit Data” chapter.

Hide/Unhide Hides or shows selected rows in all plots and graphs. See [“Hide Rows”](#) on page 198 in the “Enter and Edit Data” chapter.

Label/Unlabel Labels or unlabels selected rows in all plots. See [“Label Rows and Columns”](#) on page 211 in the “Enter and Edit Data” chapter.

Colors Provides a color palette. Select a color to apply it to the selected rows. The color is used in plots and graphs. See [“Assign a Color to Rows”](#) on page 212 in the “Enter and Edit Data” chapter.

Markers Provides a palette of markers or symbols. Select a marker to apply it to the selected rows. The marker is used in plots and graphs instead of points. See [“Add Markers to Rows”](#) on page 212 in the “Enter and Edit Data” chapter.

Color Rows by Row State Colors the row the same as the current row state color. For more details, see [“Assign Colors or Markers to Rows Based on Column Values”](#) on page 213 in the “Enter and Edit Data” chapter.

Select Matching Cells Selects rows in the active data table with values that match the selected row(s). See [“Select Cells”](#) on page 190 in the “Enter and Edit Data” chapter

Invert Selection Selects all previously deselected rows, and deselects all currently selected rows.

Clear Row States Clears all active row states in the data table. All rows become included, visible, unlabeled, and show in plots as black dots. It does not affect row states saved in row state columns. See [“Delete Row Characteristics”](#) on page 220 in the “Enter and Edit Data” chapter.

Add Rows Adds the specified number of rows to the data table. See [“Add Rows”](#) on page 175 in the “Enter and Edit Data” chapter.

Delete Rows Removes all selected rows from the data table. Use the **Undo** command on the **Edit** menu to undo an accidental deletion. See “Delete Rows and Columns” on page 193 in the “Enter and Edit Data” chapter.

Cursor Forms

The cursor takes different forms, depending on its location in the data grid.

Arrow Cursor  The standard arrow cursor appears in the following locations:

- In the panels area to the left of the data table
- In the triangular rows and columns area, located in the upper left corner of the data grid

You can perform the following actions with the arrow cursor:

- To select a column using the arrow cursor, click its name in the Columns panel.
- Double-click a column name in the Columns panel to edit it.
- Click the triangular areas in the upper left corner of the data grid to deselect rows and columns.

Selection (Large Plus) Cursor  When the cursor is at the top of a column heading, or in a row number area, it becomes a large plus, indicating that you can select rows or columns. When you click, that row or column is selected and highlighted. Click and drag to select multiple rows or columns, and hold down the Control key and click to select discontinuous rows or columns.

- Double-click a column heading area to see the Column Info window for that column.
- Select a column to change the column name. The column highlights. Begin typing (if it is not in a locked column or locked data table).
- Double-click the row number area to edit the rows using the Row Editor.

I-beam Cursor  When you select editable text, the cursor becomes a standard I-beam. To edit text, position the I-beam within highlighted text. Click to mark an insertion point, or drag to select text for replacement.

Double Arrow Cursor  The cursor changes to a double arrow when it is on a column or a panel boundary. Drag this cursor left or right to change the width of a column or panel. Changing the width of a column does not affect the column field width specified in the Column Info window (accessed by double-clicking a column name).

Tip: You can adjust widths of all selected columns at once by pressing the Alt key as you drag the double arrow cursor on any of the selected column boundaries.

List Check Cursor  The cursor changes form when you move the mouse over values in columns that have data validation in effect. It becomes a small, downward-pointing arrow on a column with list checking. When you click, the value is highlighted and the cursor becomes the I-beam. Enter or edit data as usual with any values defined as valid text or valid numbers. See “[List Check](#)” on page 270 in the “The Column Info Window” chapter, for details.

Pointer Cursor  The cursor changes to a pointer over these objects:

- Red triangle menus for options
- Triangular disclosure icons  that open or close panels
- Table script titles for opening
- Modeling type icons for changing

Open Data File Options

Note: For more details about opening files, see the “[Import Your Data](#)” chapter on page 71.

To open a data file, select **File > Open** and select the file type. Some file types have additional features and options that appear in the Open Data File window. See Table 2.1.

Tips:

- Windows only: To open the same file type every time, select the **Select this filter the next time this window is invoked** check box.
- Open a file by dragging it onto the JMP Home Window.
- To change which directory the **File > Open** command looks in, see “[File Locations](#)” on page 614 in the “JMP Preferences” chapter.

Table 2.1 File > Open Options by File Type

File Type	Additional Features and Options
JMP Data Tables	Table notes, the number of columns (Cols), and the number of rows appear. Use the Select Columns option to select which columns are imported into the data table. On Windows, click the arrow next to Open and then use the Select Columns option to specify which columns are imported into the data table. On Macintosh, you can select which columns to import after you click Open.

Table 2.1 File > Open Options by File Type *(Continued)*

File Type	Additional Features and Options
Excel Files	• Import the file in the Excel Import Wizard by default to customize the layout and preview the data before you import it. • Click the arrow next to Open and then select one of the options. Convert the first spreadsheet row into column headings.
Text Files	• To automatically determine data arrangement, select one of the following options: – Open as data using preferences – Open as data using a best guess – Open as plain text into a script window • To manually specify data arrangement, select the Data with preview option. See “Text Import Wizard Options” on page 149 in the “Import Your Data” chapter.
SAS Data Sets	• Use SAS variables for column names • (Windows only) Enter a password when you open a password-protected data set. • (SAS Transport files only) Select columns before opening
SPSS Data Files	Use SPSS variable or label names for column names.
All Files	• To automatically determine data arrangement, select one of the following options: – Open as data using preferences – Open as data using a best guess – Open as plain text into a script window • To manually specify data arrangement, select the Data with preview option. • (Windows only) To open text files using your computer’s default text editor, select Use default program to open.

Platforms

JMP consists of platforms that are organized by the type of statistical analysis. For example, the Distribution platform produces a univariate analysis (the distribution of a single variable) using histograms, additional graphs, and reports. You might analyze data in the Distribution platform and then choose another platform to examine the data more thoroughly.

Platforms and reports work together as follows:


1. The data table is the input for a platform. See [“Data Tables”](#) on page 40.
2. The platform analysis starts in a launch window. See [“Launch Windows”](#) on page 55.
3. The platform results appear in a report window. See [“Reports”](#) on page 58.

[Figure 2.2 “Anatomy of a Typical JMP Session on Windows”](#) on page 39 shows how a platform interacts with the data table and then displays the results in a report window. Information about using platforms is available in the JMP documentation library.

Launch Windows

The launch window is your point of entry into a platform, where you specify the columns to analyze. Figure 2.11 shows the Distribution launch window.

Figure 2.11 Launch Window Features



All launch windows have in common provide the following options:

Select Columns Lists all of the variables in your current data table. Note the following:

- Right-click the modeling type icon next to a column name to change the modeling type.
- Right-click the column name to create a transform column. See [“Transform Columns”](#) on page 227 in the “Enter and Edit Data” chapter.
- Filter and sort the columns using the options in the red triangle menu. See [“Column Filter Menu”](#) on page 57.

Cast Selected Columns into Roles Moves selected columns into roles (such as Y, X, and so on.) You cast a column into the role of a variable (like an actor is cast into a role). See [“Cast Selected Columns into Roles Buttons”](#) on page 56.

In the Graph Builder window, click the **Dialog** button on the left or select **Redo > Relaunch Analysis** to show this panel.

Action The following options are available:

OK performs the analysis.

Cancel stops the analysis and quits the launch window.

Remove deletes any selected variables from a role.

Recall populates the launch window with the last analysis that you performed.

Help takes you to the Help for the launch window.

Cast Selected Columns into Roles Buttons

The following buttons frequently appear throughout launch windows. Buttons that are specific to certain platforms are described in the chapter for the specific platform.

Y Identifies a column as a response or dependent variable whose distribution is to be studied.

X Identifies a column as an independent, classification, or explanatory variable that predicts the distribution of the Y variable.

Weight Identifies the data table column whose variables assign weight (such as importance or influence) to the data.

Freq Identifies the data table column whose values assign a frequency to each row. This option is useful when a frequency is assigned to each row in summarized data. If the value is 0 or a positive integer, then the value represents the frequencies or counts of observations for each row when there are multiple units recorded.

JMP PRO Validation Identifies the data table column whose values assign rows to training, validation, and test sets for crossvalidation in fitting models.

Notes:


- For some platforms, KFold validation is available if you specify more than three levels in the Validation column.
- If you click the Validation button with no columns selected in the Select Columns list, you have the option to create a Validation column. For more information about the Make Validation Column utility, see the Modeling Utilities chapter in the *Predictive and Specialized Modeling* book.

By Identifies a column that creates a report consisting of separate analyses for each level of the variable.

Column Filter Menu

A Column Filter menu appears in most of the launch windows. The Column Filter menu is found by clicking the red triangle in the Select Columns panel. Use these options to sort columns, show or hide columns, or search columns.

Figure 2.12 The Column Filter Menu



Reset Resets the columns to its original list.

Sort by Name Sorts the columns in alphabetical order by name.

Modeling Type Provides options for showing or hiding columns with specific modeling types.

Numeric Shows or hides columns whose data type is Numeric.

Character Shows or hides columns whose data type is Character.

Expression Shows or hides columns whose data type is Expression.

Match case (Only applicable to the Name options below) Makes your search case-sensitive.

Name Contains Searches for column names containing specified text. To remove the text box, select **Reset**.

Name Does Not Contain Searches for column names that do not contain specified text. To remove the text box, select **Reset**.

Name Starts With Searches for column names that begin with specified text. To remove the text box, select **Reset**.

Name Ends With Searches for column names that end with specified text. To remove the text box, select **Reset**.

Exclude Formats Excludes columns with specific formats from the column selection list. Select from the following formats: date, time, duration, geographic, or all numeric formats.


Column Groups Shows or hides groups of columns. See [“Group Columns”](#) on page 194 in the “Enter and Edit Data” chapter.

Ungrouped Columns Shows or hides columns that have not been grouped.

Reports

After you launch your analysis, the report window appears. The report window shows the output of your analysis using interactive graphs and text reports. For details, see the [“JMP Reports”](#) chapter on page 401.

Figure 2.13 Report Window Features



Manage JMP Files and Open Windows


The JMP Home Window provides instant access to open window and files. Opening recently opened files, closing windows, and pinning frequently used files are a few of the options.

JMP Home Window on Windows

On Windows, the JMP Home Window appears when you open JMP.

- Open recent files in the Recent Files list or pin a frequently used file.
- Right-click files in the Recent Files list to perform common tasks.
- Open or close active JMP windows in the Window List.
- Set an open data table as the current data table by selecting it from the data table list at the top.

Figure 2.14 JMP Home Window Actions



JMP Home Window Buttons

On Windows, the JMP Home Window panels can contain the following buttons:

-  The Open Selected button opens the selected files in the Recent Files list.
-  The Sort By Name button sorts recent files alphabetically.
-  The Filter button filters the types of files that appear in the Recent Files and Window List panels.
-  Enlarges the font size and icon size of items in the Recent Files list.
-  The Close button closes the panel.

Recent Files

On Windows, the Recent Files list provides quick access to files that you recently opened.

Keep your favorite files at the top of the list for quick access. Place your cursor over the filename and click the pin icon . To unpin a file, click the pin icon .

You can drag files from the Recent Files list as follows:

- into the JMP Window List to open the file
- into a Windows folder or on to your desktop to create a copy of the file
- into applications such as Microsoft Notepad or Microsoft Word to edit the file

Right-click files to access the following options:

- Open a file
- Copy the location path to a file
- Open a file within the folder that contains it
- Sort files alphabetically by name or by most recent
- Remove a selected file or files from the list
- Remove a file or files that are no longer in the same location (Alternatively, you can select the files and press the DELETE key.)
- (JSL scripts) Edit, run, or debug a script
- (Text files) Change the import method or open as plain text
- (SQL queries) Run an SQL query that you saved in Query Builder. You can also create a new query using an existing query as a template.
- Run or edit a JMP application

When you open a non JMP file from the Recent Files list, JMP applies your import preferences to arrange the data. You can right-click on a text file to change the import method or to open the file in a text editing window. Your import preference is bolded in the pop-up menu.

Tip: To prevent files that were opened by a script from appearing in the Recent Files window, select **File > Preferences > General** and de-select **Add files opened by scripts to the Recent Files list**.

Search the Recent Files List for JMP Files

To find a recently opened file in a long list of files, enter part of the file name in the Recent Files Filter box.

The following options are provided:

- Enter part of the file name in the Filter box above the list of files.
- Place your cursor over the Filter box to view search tips.
- As the files are filtered, the Up and Down arrow keys change the selected file. Press Enter to open the selected file, or select the file with your cursor.
- If a file is selected in the Recent Files list, press Ctrl and then F to activate the Filter box.
- Press Esc or click the X button to exit the filtering mode after you typed a search term.

Window List

On Windows, the Window List shows open JMP windows, such as data tables, reports, and scripts. You can open, close, rearrange, and hide JMP windows.

- If you place your mouse pointer over a file in the Window List, a thumbnail appears.
- To open the Window List in its own window, select **View > Window List**.
- To display windows side-by-side, right-click the selected windows and select **Arrange**.
- To always automatically display the Window List inside maximized windows, select **File > Preferences > Windows Specific** and select **Dock the Window List in maximized windows**.

Right-click files to access the following options:

- View a window
- Close a window (Alternatively, you can select files and press the DELETE key.)
- Close all windows except the currently selected window (if the selected window is a report window, the dependent data table also remains open)
- Move a window to the back
- Hide a window from the Windows taskbar or unhide a window
- Select all windows, or clear all selections

Rearrange Panels in the Home Window

To rearrange the panels in the Home Window on Windows, click and drag the title bar of the panel. Drop the title bar onto a top, bottom, left, or right arrow to position the panel. A blue box indicates where the panel will be placed. To turn the panels into tabs, drag and drop any panel into the middle of the Home Window.

Tips:

- To put the Home Window back into its original order, select **View > Home Window Panes > Revert to Factory Layout**.
- If you close a panel and want to reopen it, select **View > Home Window Panes** and select the panel that you want to open.


- Open the JMP Home Window by selecting **View > Home Window** or clicking the **JMP Home Window**  button in the lower right corner of most JMP windows. If you cannot see the **JMP Home Window** button, select **View > Status Bars**.
- If you prefer to see the JMP Starter or the Window List upon start-up, you can specify that in the Preferences (Windows only). Select **File > Preferences > General** and select an option from the Initial JMP Window list.

JMP Home Window on Macintosh

Use the JMP Home window on Macintosh to quickly access JMP files and open windows.

- Open recent files in the Recent Files list.
- Press Control and select a file in the Recent Files list to perform common tasks, such as adding or removing a favorite.
- Open or close active JMP windows in the Windows list.
- Set an open data table as the current data table by selecting it from the Active Table list. Press the Option key while selecting the data table from the list to activate the data table without bringing it to the front.
- Open the log.
- Find a file in the Recent Files list or an open window in the Windows list by entering a search term in the Search box.
- Click **Toggle Layout** to display the Recent Files and Windows lists horizontally instead of vertically.

Open the JMP Home window on Macintosh by selecting **Window > JMP Home** (Figure 2.15). To view the window each time you open JMP, select **JMP > Preferences > General > Home Window**.

Figure 2.15 Example of the JMP Home Window (Macintosh)

Tips:

- The Status bar area shows the path for the currently selected file. You can click on a folder to open the folder to view its contents.
- To be able to quickly view the JMP Home window from any JMP window, right-click the window, select **Customize Toolbar**, and drag the JMP Home icon to the toolbar.
- To copy a file from Recent Files to another document or into the Finder, select the file and then select **Edit > Copy**.

Recent Files

On Macintosh, the Recent Files list provides quick access to files that you recently opened.

You can also click the star that appears when you place your cursor over the file name to add it to your favorites.

Press the Control key and select a file to access other options. For example, you can run or debug a JSL script by holding down the Control key and selecting Run Script or Debug Script.

Tip: To prevent files that were opened by scripts from appearing in the Recent Files window, select **File > Preferences > General** and de-select **Add files opened by scripts to the Recent Files list**.

Windows List

On Macintosh, the Windows list shows open JMP windows, such as data tables, reports, and scripts.

To close a window, click the **x** button that appears when you place your cursor over the window in the Windows list.

If the window that you are closing is a parent to one or more children, you are prompted to **Hide Data Table**, **Cancel**, or **Close All** windows. Select **Close All** to close the parent and all its children windows.

Search for Recently Opened Files on Windows

Recently opened files are listed in the Home Window. You can also search for recently opened files from any JMP window.

Select **File > Quick Open** or press Alt, Shift, and then O to open the Filter box and enter your search term. This option also lets you view the path of the file. Press Esc or click the X button to close the window after you type a search term.

Close Multiple Files

On Windows, close several files at once from the JMP Home Window. Select the files in the Window List, right-click, and select **Close**. To leave a single file opened and close the rest, select the single file and then select **Close All But This**.

On Macintosh, select **File > Close Multiple** and then select the files that you want to close.

Display and Arrange Open Windows

In JMP, typically you have several windows open at once (for example, data tables, reports, and the JMP Home Window). JMP provides several ways to arrange and display these open windows.


On Windows:

- Press the Control and Tab keys to switch between windows.
- Use the Reveal feature (F9 or Window > Reveal). See [“Using the Reveal Feature”](#) on page 68.
- Use the options in the Window menu. Note that Arrange options are also available using the Arrange Menu  option in the bottom right corner of most windows. If you cannot see Arrange Menu, JMP Home Window, and View Associated Data buttons, select **View > Status Bars**.

Tip: From the Arrange Menu option on Windows, you can merge open windows by selecting Combine Windows. See [“Example of Combining Windows to Create a Dashboard”](#) on page 543 in the “Extend JMP” chapter for details.

- To display the JMP Home Window, click the **JMP Home Window**  button in the lower right corner of most windows, or hold down Control and press 1.
- To show the data table for a report, click **View Associated Data**  button in the bottom right corner of the report.
- To open an associated report when you are viewing a data table, double-click the thumbnail preview of the report in the bottom pane. To enlarge the preview, place your cursor over the thumbnail. See Figure 2.16.
- Middle-click the thumbnail preview to close the associated report.

Figure 2.16 Thumbnail Previews of Open Reports



On Macintosh:

- Use the options in the Window menu.
- Use the Expose feature (F9 or F3).

Preview JMP Files

For some JMP file types, you can use Windows Explorer or the Macintosh Finder to view a portion of the selected file. Windows supports a preview of JMP data tables, journals, and scripts. Macintosh supports a preview of data tables and scripts.


To preview a JMP file

1. In Windows Explorer or the Macintosh Finder, select the file that you want to preview.
2. In Windows Explorer, select the **Show the preview pane**  button in the upper right corner. Support in e-mail programs varies.

In the Macintosh Finder, select the file and press the spacebar, or select the **Quick Look** option on the pop-up menu or File menu. In Mail, select the **Quick Look Attachment** option on the pop-up menu or File menu.

The preview pane shows a portion of the selected file.

Figure 2.17 Data Table Preview Pane (Windows)



Name	Date modified		Country	Year	Birth	Death
BabySleep.jmp	4/8/2013 12:46 AM					
Bacteria.jmp	4/8/2013 12:46 AM					
Baltic.jmp	4/8/2013 12:46 AM					
Bands Data.jmp	4/8/2013 12:46 AM					
Bank Loan.jmp	4/8/2013 12:46 AM					
Baseball.jmp	4/8/2013 12:46 AM					
Basketball.jmp	4/8/2013 12:46 AM					
Batch.jmp	4/8/2013 12:46 AM					
Bicycle.jmp	4/8/2013 12:46 AM					
Big Class.jmp	4/8/2013 12:46 AM					
Birth Death Subset.jmp	4/8/2013 12:46 AM					
Birth Death.jmp	4/8/2013 12:46 AM					
BirthDeathYear.jmp	4/8/2013 12:46 AM	1	Australia	1975	16.90	7.90
Blood Pressure by Time.jmp	4/8/2013 12:46 AM	2	Australia	1980	15.30	7.40
Blood Pressure.jmp	4/8/2013 12:46 AM	3	Australia	1985	15.70	7.50
blsPriceData.jmp	4/8/2013 12:46 AM	4	Australia	1990	15.40	7.00
Body Fat.jmp	4/8/2013 12:46 AM	5	Australia	2004	12.40	7.40
Body Measurements.jmp	4/8/2013 12:46 AM	6	Australia	2005	12.30	7.40
Boston Housing.jmp	4/8/2013 12:46 AM	7	Australia	2006	12.10	7.50
BoxCox.jmp	4/8/2013 12:46 AM	8	Austria	1975	12.50	12.80
Cancer1.jmp	4/8/2013 12:46 AM	9	Austria	1980	12.00	12.20
Cancer2.jmp	4/8/2013 12:46 AM	10	Austria	1985	11.60	11.90
Candy Bars.jmp	4/8/2013 12:46 AM	11	Austria	1990	11.60	10.60
Candy.jmp	4/8/2013 12:46 AM	12	Austria	2004	8.90	9.60
		13	Austria	2005	8.80	9.70
		14	Austria	2006	8.70	9.80
		15	Belgium	1975	12.20	12.20
		16	Belgium	1980	12.70	11.60
		17	Belgium	1985	11.50	11.20
		18	Belgium	1990	12.60	10.60
		19	Belgium	2004	10.60	10.20
		20	Belgium	2005	10.50	10.20

Using the Reveal Feature

On Windows, press F9 to use the Reveal feature. The Reveal feature shows a top-level window with thumbnails of all open JMP windows.

- Click on a window to activate it.
- Press the spacebar to turn on Preview mode, where a full-sized view of the thumbnail under the cursor appears in the center of the screen.
- By default, the windows are ordered to match the original ordering on the screen in a top-down, left-to-right order. Press S to sort the thumbnails by name.

To exit the Reveal feature, press F9, Esc, or Alt and Tab and then select another application.


JMP Starter Window

The JMP Starter window is a good place to begin if you are not familiar with JMP or data analysis. Options are categorized and described, and you launch them by clicking a button. The JMP Starter window covers many of the options found in the Analyze, Graph, Tables, and File menus.

- To open the JMP Starter window, select **View (Window on the Macintosh) > JMP Starter**.
- To display the JMP Starter automatically when you open JMP on Windows, select **File > Preferences > General**, and then select **JMP Starter** from the Initial JMP Window list. On Macintosh, select this option on the **JMP > Preferences > General** page.

Figure 2.18 shows the JMP Starter window for Windows. The Macintosh JMP Starter window is identical.

Figure 2.18 The JMP Starter Window (Windows)




Chapter 3

Import Your Data Create Data Tables

This chapter covers the following topics:

- How to import data into JMP, such as text files, SPSS files, and SAS data
- How to transfer Excel data into a JMP data table
- How to read in real-time data
- How to create a new data table

Figure 3.1 Importing a Text File



Contents

About Importing Data to JMP	74
Import Microsoft Excel Files	75
Preview and Import the Microsoft Excel Data	76
Import a Microsoft Excel File Directly	87
Import Data from SAS	88
Java Runtime Environment (JRE) Requirements	88
SAS Menu Options	88
Import SAS Data Sets	89
Create SAS Transport Files in SAS	91
Connect to SAS	92
Open SAS Data Sets with SAS Query Builder	97
Open SAS Data Sets through a SAS Server	98
Using SAS Extended Attributes to Import Metadata	106
Run Stored Processes	108
Submit SAS Code	108
Generate ODS Results	110
Retrieve Generated SAS Data Sets	111
Build SQL Queries in Query Builder	113
Connect to a SQL Database	114
Select Tables from a SQL Database	115
Build the SQL Query	119
Save and Run the Query	133
Open the Selected Data in JMP	134
Query Builder Red Triangle Options	134
Write SQL Statements in Query Builder	135
Import Data from a Database	136
Connect to a Database	136
Open Data from a Database	137
Write SQL Statements to Query a Database	139
Structured Query Language (SQL): A Reference	141
Import Text Files	147
Text Import Wizard Options	149
Open a Text File in a Text Editing Window	153
Import Text from the Script Editor	155
Import Multiple Files	156
Import Data from the Internet or a Remote Computer	161
Import SPSS Files	163
Import Triple-S Survey Data	164
Import HDF5 Data	165

Import JSON Files	165
Import Data from MATLAB	166
Import Data from R	166
Import Data Using the Excel Add-In	167
Transfer Excel Data to a JMP Data Table	167
About the JMP Add-In for Excel	168
Uninstall the Excel Add-In	169
Create New Data Tables	169

About Importing Data to JMP

You can import many file formats into JMP and save them as data tables. JMP opens many files by default. The file formats which JMP does not support by default require specific Open Database Connectivity (ODBC) drivers.

The Following File Formats Are Supported by Default:

- Comma-separated (.csv)
- .dat files that consist of text
- ESRI shapefiles (.shp)
- Flow Cytometry versions 2.0 and 3.0 (.fcs)
- Hierarchical Data Format, Version 5 (.h5)
- HTML (.htm, .html)
- JSON (.json)
- MATLAB (.m, .M)
- Microsoft Excel 1997 through 2016 (.xls, .xlsx on Macintosh)
- Microsoft Excel 2010 through 2016 (*.xlsx, *.xlsm on Windows)
- Minitab Portable Worksheet (.mtp)
- Plain text (.txt)
- R (.r)
- SAS transport (.xpt, .stx)
- SAS versions 7 through 9 on Macintosh (.sas7bdat)
- SAS versions 7 through 9 on Windows (.sas7bdat, .sas7bxat)
- SPSS (.sav)
- SQLite 3.0 or higher (.sqlite, .db, .sqlite3, .db3)
- Tab-separated (.tsv)
- Teradata database (.trd)
- Triple-S (.sss, .xml)
- xBase data files (.dbf)

Notes on SAS Support:

On both Windows and Macintosh, you can open SAS data sets directly through the **File > Open** command. See [“Import SAS Data Sets”](#) on page 89 for details.

Another option is connecting to a SAS server by selecting **File > SAS > Browse Data**. See [“Open SAS Data Sets through a SAS Server”](#) on page 98 for details.

The Following Files Require ODBC Drivers:

- Database (dBASE) (.ndx, .mdx) is supported with a V3+ compliant ODBC driver. .dbf files do not require an ODBC driver.
- Microsoft Access Database (.mdb) is supported with a V3+ compliant ODBC driver.

See [“Import Data from a Database”](#) on page 136 for details for working with databases.

Your computer’s available memory affects data import. Very large files might load slowly or not at all. Consider splitting up large files before importing them. In JMP, you can then join or concatenate the tables. For more information, see [“Concatenate Data Tables”](#) on page 318 in the “Reshape Data” chapter and [“Join Data Tables”](#) on page 321 in the “Reshape Data” chapter.

Note: You can open R code (.R) and SAS program files (.sas) in JMP, but the text opens in a Script window, not in a data table.

Import Microsoft Excel Files

Microsoft Excel files open in the Excel Import Wizard by default. The wizard shows a preview of the data. You can then modify the settings before importing the data. For example, you might indicate which row the data begin on and whether the worksheet contains column headers or hidden rows or columns. Microsoft Excel .xls, .xlsm, and .xlsx file formats are supported.

For information about opening a Microsoft Excel file outside the wizard, see [“Import a Microsoft Excel File Directly”](#) on page 87.

Notes:

- Password-protected Microsoft Excel files cannot be opened in JMP.
- Between Windows and Macintosh, the number of digits after a decimal point and the date format of imported data might differ. For example, “10/25/2012” might be formatted as “25Oct2012” on Macintosh. Columns might be imported as character columns on Macintosh but not on Windows.
- Consider setting the Autosave Timeout value in the General preferences to automatically save open data tables. This autosave value also applies to other JMP document types.

Preview and Import the Microsoft Excel Data

Before you import a worksheet, open the spreadsheet in Excel and decide how you want the data to be structured in the final data table. For example, you need to know whether the worksheet includes hidden or merged cells. In the wizard, you can then exclude hidden columns or rows.

To import a Microsoft Excel file that contains several worksheets, follow these steps:

1. Open the worksheet in Microsoft Excel.

For the figures in this example, we used the *Team Results.xlsx* file located in the JMP Samples/Import Data folder. The file has the following characteristics:

- the data begin on row 4, column 2 and end on row 9, column 5
- two worksheets
- the second worksheet has two sets of merged cells
- no hidden rows or columns

Figure 3.2 Team Results.xlsx Worksheet

	A	B	C	D	E	F
1		Here are the team results for this year's game.				
2						
3		Team	Member Name	Age	Winnings	
4		1	Joe	21	\$50.22	
5		1	Mary	22	\$24.34	
6		1	Cindy	23	\$25.54	
7		2	Mark	22	\$52.11	
8		2	Bill	23	\$43.32	
9		2	Jennifer	24	\$11.23	


2. To open an Excel file in JMP, select **File > Open**.

The Open Data File window appears.

3. Select the Excel file.

The worksheet opens in the Excel Import Wizard, where a preview of the data appears along with import options (Figure 3.3).

Figure 3.3 Example Initial Data Preview



Note the following characteristics in the Data Preview:

- Both worksheets are selected for import in the upper right corner.
- The first column has been automatically been removed.
- Text from the first row of the worksheet appears as the column headings. However, you want the text in row 3 of the worksheet to be used as the column headings.
- The first data row is empty.


Note: JMP remembers your previous changes each time you import a worksheet, even after closing and reopening JMP. This feature is helpful when you want to reimport the same worksheet several times and experiment with options. To clear those changes when you import a different worksheet, click **Restore Default Settings**.

4. Type 3 for **Column headers start on row**
5. Type 4 for **Data starts on row**.
6. Select **Ungrouped Team Results** in the Worksheets pane.
Only this worksheet will be imported.
7. Deselect **Use for all worksheets**.

These settings apply only to Ungrouped Team Results.

Figure 3.4 shows your changes.

Figure 3.4 Selecting the Column Header Row



- See [“Individual Worksheet Settings”](#) on page 79 for details about all options.
- Click **Next** to configure other import settings.
- The window displays additional import settings.
- For **Data ends with row**, type 9.
 - For **Data ends with column**, type 5.
- Figure 3.5 shows your changes.

Figure 3.5 Specifying the Last Column

Data Preview

	Team	Member Name	Age	Winnings
1	1	Joe	21	\$50.22
2	1	Mary	22	\$24.34
3	1	Cindy	23	\$25.54
4	2	Mark	22	\$52.11
5	2	Bill	23	\$43.32
6	2	Jennifer	24	\$11.23

Rows Shown: 6 / 6

Individual Worksheet Settings

- ☐ Treat multiple column header lines as hierarchies
- ☒ Replicate data in spanned rows
- ☒ Suppress hidden rows
- ☒ Suppress hidden columns
- ☒ Suppress empty columns

Data ends with row 9

Data ends with column 5

☐ Use for all worksheets

Preview Pane Refresh

- ☒ Update settings on any change

Advanced Options

Worksheets

Select sheets to open

	Custom setting
Ungrouped Team Results	
Grouped Team Results	

Select all

Buttons: Restore Default Settings, Back, Next, Import, Cancel, Help

Custom setting is automatically selected when you modify the import options.

See [“Additional Individual Worksheet Settings”](#) on page 80 for details about all options.

11. Click **Import** to convert the worksheet as you specified (Figure 3.6).

Figure 3.6 Final Data Table

Ungrouped Team Results

	Team	Member Name	Age	Winnings
1	1	Joe	21	\$50.22
2	1	Mary	22	\$24.34
3	1	Cindy	23	\$25.54
4	2	Mark	22	\$52.11
5	2	Bill	23	\$43.32
6	2	Jennifer	24	\$11.23

Columns (4/0)

- Team
- Member Name
- Age
- Winnings

Rows

All rows	6
Selected	0
Excluded	0
Hidden	0
Labelled	0

The following sections describe options in the Excel Import Wizard.

Individual Worksheet Settings

Worksheet contains column headers Select if the worksheet contains rows with column headers.

Column headers start on row Indicates which row the column headers begin on in the worksheet. Click the up arrow  until the headers begin on the correct row, or enter the row number and press Enter.

Number of rows with column headers Indicates whether the worksheet has multiple rows as column headers. Click the up arrow  until the header rows appear correctly, or enter the number of rows and press Enter.

Data starts on row Indicates which row the data start on in the worksheet.

Data starts on column Indicates which column the data start on in the worksheet.

Concatenate worksheets and try to match columns Merges all worksheets into one data table. JMP matches columns that have the same header.

Create column with worksheet name when concatenating Adds a new Source Table column that lists the worksheet name for each imported table. This option is available after you select the preceding concatenate option.

Use for all worksheets Applies the current import settings to all worksheets that are selected in the upper right corner.

Additional Individual Worksheet Settings

Treat multiple column header lines as hierarchies Indicates that the worksheet contains multiple rows as column headers and you want these headers to be hierarchies. This option is only for stackable data.

Replicate data in spanned rows Indicates cells are merged in the worksheet across rows. JMP unspan the cells and copy the cell contents into all of the resulting cells. The option is selected by default.

If you deselect **Replicate data in spanned rows**, JMP unspans the cells and copies the cell contents into the topmost cell. The remaining unspanned cells are left empty.

Suppress hidden rows Prevents hidden rows from appearing in the data table.

Suppress hidden columns Prevents hidden columns from appearing in the data table.

Suppress empty columns Indicates whether an empty column that has a column header is imported. Deselect the option to import the column.

Data ends with row Indicates the last row in the worksheet that contains data.

Data ends with column Indicates the last column in the worksheet that contains data.

Advanced Options

Column Name Separator String Indicates the separator between each word in a column heading if the headings were originally in different rows. Specify the number of rows with column headers on the first Excel Import Wizard window. Then enter a character or space in the Column Name Separator String box. The default string, a hyphen, results in a column heading such as “First-Second-Third”.

Multiple Series Stack Divides subcategories into separate columns in a worksheet with hierarchical headings. You must also select **Treat multiple column header lines as hierarchies**. The main category is imported as the Label column.

Replicate headers in spanned rows Repeats the header text in each cell for rows that are spanned in the worksheet. For example, the State column heading shown in Figure 3.7 was in a merged cell in the worksheet. On the left, the heading is replicated. Deselect the option to avoid repeating the heading as shown on the right.

Figure 3.7 Replicated Headers in a Microsoft Excel File

Replicated headers Unreplicated headers

	State-State
1	TX
2	TX
3	TX
4	TX

	State
1	TX
2	TX
3	TX
4	TX

Import cell colors Applies the cell coloring from the worksheet to the data table. On the Mac, only primary and secondary colors can be reliably imported.

Limit column type detection Scans a maximum of 100 rows to determine the column type. Select this option to speed up the import of large worksheets.

Tips:

- JMP remembers your previous changes each time you import a worksheet, even after closing and reopening JMP. This feature is very helpful when you want to reimport the same worksheet several times and experiment with options. To clear those changes when you import a different worksheet, click **Restore Default Settings**.
- Your import settings are saved in a data table script named Source. To reimport the worksheet using the same settings, run the script. The script includes the path to the worksheet, so make sure that other users have access to that location.
- To speed up the data preview in large worksheets, deselect **Update settings on any change** on the first wizard window. Modify the settings and then click **Update now** to refresh the data preview.

- To view all rows in the Data Preview pane, select **Show all rows**. The preview might be slightly delayed depending on the size of the spreadsheet.
- You can combine two worksheets from the same workbook into one data table. The column names are matched on import, so the order of the columns is irrelevant.

Importing a Microsoft Excel File with Hierarchical Headings

In an Excel worksheet, multiple header rows can have an implied hierarchy; the second header row contains data that are categories of the first header row. Figure 3.8 shows an example. In the worksheet at the top, the seasons “Winter” and “Spring” are in spanned cells above the months within those seasons. In the JMP data table, you want the seasons in one column and their corresponding months in another column.

Figure 3.8 The Original Data in Excel and Final Data in JMP

Figure 3.8: The Original Data in Excel and Final Data in JMP

The top part of the figure shows an Excel spreadsheet with columns A through I and rows 1 through 17. The data is organized as follows:

State	County	City	Winter		Spring			
			Jan	Feb	Mar	Apr	May	Jun
TX	Bexar	San Antonio	0.42	0.2	1.82	0.83	0.66	0.01
	Travis	Austin	0.4	0.94	3.21	3.74	1.73	1.03
	Dallas	Dallas	0.82	0.72	5.56	3.54	4.36	3.98
	Harris	Houston	0.49	1.52	4.08	10.38	0.38	0.27

*Data are from the U.S. National Weather Service.

The bottom part of the figure shows the JMP interface. The main window displays a table with the following columns: State, County, City, Column, Column 2, and Data. The data is organized as follows:

State	County	City	Column	Column 2	Data
1 TX	Bexar	San Antonio	Winter	Jan	0.42
2 TX	Bexar	San Antonio	Winter	Feb	0.2
3 TX	Bexar	San Antonio	Winter	Mar	1.82
4 TX	Bexar	San Antonio	Spring	Apr	0.83
5 TX	Bexar	San Antonio	Spring	May	0.66
6 TX	Bexar	San Antonio	Spring	Jun	0.01
7 TX	Bexar	San Antonio	Summer	Jul	3.86
8 TX	Bexar	San Antonio	Summer	Aug	4.98
9 TX	Bexar	San Antonio	Summer	Sep	0.46
10 TX	Bexar	San Antonio	Fall	Oct	0.26
11 TX	Bexar	San Antonio	Fall	Nov	0.01
12 TX	Bexar	San Antonio	Fall	Dec	0.25
13 TX	Travis	Austin	Winter	Jan	0.4
14 TX	Travis	Austin	Winter	Feb	0.94
15 TX	Travis	Austin	Winter	Mar	3.21
16 TX	Travis	Austin	Spring	Apr	3.74
17 TX	Travis	Austin	Spring	May	1.73

The left sidebar shows the project structure, including the data table and the list of columns (State, County, City, Column, Column 2, Data). The bottom of the sidebar shows the number of rows (All rows: 192, Selected: 0, Excluded: 0, Hidden: 0, Labelled: 0).

To import the worksheets and maintain multiple column hierarchies, follow these steps.

1. In JMP, select **File > Open**.
2. In the Open Data File window, select **Texas Precipitation.xlsx**, located in the JMP Samples/Import Data folder, and then click **Open**.

The worksheet opens in the Excel Import Wizard, where a preview of the data appears along with import options.

Figure 3.9 Excel Import Wizard Preview




Figure 3.9 shows the default settings for this worksheet:

1	All worksheets are selected for import.
2	Each season is split over several columns.
3	Data from the second heading row of the worksheet appear in the first row.
4	The empty rows at the top have been removed.
-
3.	Under Preview Pane Refresh, make sure that Update settings on any change is selected. This means that the Data Preview automatically refreshes when you make changes.
4.	Next to Number of rows with column headers , click the up arrow once. Notice that Data starts on row automatically updates to 3. Figure 3.10 shows the updated settings.

Figure 3.10 Updated Settings on Page One

Data Preview

	State	County	City	Winter-Jan	Winter-Feb	Winter-Mar
1	TX	Bexar	San Antonio	0.42	0.2	
2	TX	Travis	Austin	0.4	0.94	
3	TX	Dallas	Dallas	0.82	0.72	
4	TX	Harris	Houston	0.49	1.52	
5				.	.	.
6				.	.	.
7				.	.	.

Rows Shown: 9 / 9

Worksheets

Select sheets to open	Custom setting
2009	
2010	
2011	
2012	

Select all

Individual Worksheet Settings

- ☒ Worksheet contains column headers
- 1 Column headers start on row
- 2 Number of rows with column headers
- 3 Data starts on row
- 1 Data starts on column
- ☐ Concatenate worksheets and try to match columns
 - ☐ Create column with worksheet name when concatenating
- ☒ Use for all worksheets

Restore Default Settings

Preview Pane Refresh

- ☒ Update settings on any change
- Update now
- ☐ Show all rows

Back Next Import Cancel Help

5. Click **Next**.
6. Select **Treat multiple column header lines as hierarchies**.

Each season and month in the header rows of the worksheet will become categories in the data table.

7. Next to **Data ends with row**, type 6 and press Enter.

After the first three empty rows are removed from the worksheet, the data end with row 6.

Tip: Instead of you typing the end row number, JMP can calculate the row for you. In the Data Preview pane, select row 4. Click the plus sign  next to **Data ends with row**.

Figure 3.11 shows the updated settings.

Figure 3.11 Updated Settings on Page Two

The screenshot shows the JMP Import dialog box, Page Two. It is divided into several sections:

- Data Preview:** A table showing the first 7 rows of data. The columns are State, County, City, Column, and Column 2. The data is as follows:

	State	County	City	Column	Column 2
1	TX	Bexar	San Antonio	Winter	Jan
2	TX	Bexar	San Antonio	Winter	Feb
3	TX	Bexar	San Antonio	Winter	Mar
4	TX	Bexar	San Antonio	Spring	Apr
5	TX	Bexar	San Antonio	Spring	May
6	TX	Bexar	San Antonio	Spring	Jun
7	TX	Bexar	San Antonio	Summer	Jul
- Worksheets:** A table with two columns: Select sheets to open and Custom setting. The rows are 2009, 2010, 2011, and 2012. A 'Select all' button is below the table.

Select sheets to open	Custom setting
2009	
2010	
2011	
2012	
- Individual Worksheet Settings:**
 - ☒ Treat multiple column header lines as hierarchies
 - ☒ Replicate data in spanned rows
 - ☒ Suppress hidden rows
 - ☒ Suppress hidden columns
 - ☒ Suppress empty columns
 - 6 Data ends with row (+)
 - . Data ends with column (+)
- Preview Pane Refresh:**
 - ☒ Update settings on any change (with 'Update now' button)
 - ☐ Show all rows
 - Advanced Options (dropdown)
- Use for all worksheets:** ☒
- Buttons:** Restore Default Settings, Back, Next, Import, Cancel, Help.

Notice that **Replicate data in spanned rows** is selected by default. JMP unmerges data that were merged in the worksheet and copies the cell contents as separate categories. "TX" was originally in a merged cell. In JMP, it will be copied into separate cells.

8. Click **Import**.

The four worksheets open as separate data tables. The data tables contain a Source script, which you can run to import the data into new data tables using the same import settings (Figure 3.12). Your import settings are also saved the next time you open the worksheet in the Excel Wizard in any JMP session.

Figure 3.12 The Final Data

	State	County	City	Column	Column 2	Data
1	TX	Bexar	San Antonio	Winter	Jan	0.42
2	TX	Bexar	San Antonio	Winter	Feb	0.2
3	TX	Bexar	San Antonio	Winter	Mar	1.82
4	TX	Bexar	San Antonio	Spring	Apr	0.83
5	TX	Bexar	San Antonio	Spring	May	0.66
6	TX	Bexar	San Antonio	Spring	Jun	0.01
7	TX	Bexar	San Antonio	Summer	Jul	3.86
8	TX	Bexar	San Antonio	Summer	Aug	4.98
9	TX	Bexar	San Antonio	Summer	Sep	0.46
10	TX	Bexar	San Antonio	Fall	Oct	0.26
11	TX	Bexar	San Antonio	Fall	Nov	0.01
12	TX	Bexar	San Antonio	Fall	Dec	0.25
13	TX	Travis	Austin	Winter	Jan	0.4
14	TX	Travis	Austin	Winter	Feb	0.94
15	TX	Travis	Austin	Winter	Mar	3.21
16	TX	Travis	Austin	Spring	Apr	3.74
17	TX	Travis	Austin	Spring	May	1.73

Import a Microsoft Excel File Directly

Microsoft Excel files open in the Excel Import Wizard by default. This option is helpful when the structure of data in the worksheet is irregular. For example, you might want to exclude hidden columns or convert text in the third row to column headings.

Instead of opening spreadsheets in the Excel Import Wizard, you can select **File > Open** to open the file. By default, JMP detects whether the first row contains labels and converts them to column headings. You can change this setting in the General preferences. The Excel Open Method preferences are in **File > Preferences > General (Windows)** and **JMP > Preferences > General (Macintosh)**. From the Use Excel Labels for Headings list, select **Always** or **Never**.

To set the Excel Open Method preference

To always open Microsoft Excel files outside the wizard, change the Excel Open Method preference. Choose to open all worksheets at once or select them from a list.

To open a Microsoft Excel file (Windows)

1. After you set the Excel Open Method as described above, select **File > Open**.
2. To convert text in the first row to column headings, select **Always** next to **Always enforce Excel Row 1 as labels**.
3. Select the **Excel Files** file type, select the file, or enter the URL.
4. To import all worksheets, click **Open**.

or

To select the worksheets that you want to open, click the **Open** button arrow, and then select **Open Selected Worksheets**. Select one or more worksheets and click **OK**.

To open a Microsoft Excel file (Macintosh)

1. Select **File > Open** and select the file.
2. (.xls only) To convert text in the first row to column headings, select **Use Excel Labels as Headings**.
3. (.xls only) To open specific worksheets, select **Select Individual Excel Worksheets**.
4. Click **Open**.

If you chose to open specific worksheets, select those worksheets from the list, and then click **OK**. You can also click **Select All** if you change your mind and want to import all worksheets.

If you chose to open specific worksheets, select those worksheets from the list, and then click **OK**. You can also click **Select All** if you change your mind and want to import all worksheets.

If you selected an .xlsx file, a preview of the data appears in the Excel Wizard. See [“Preview and Import the Microsoft Excel Data”](#) on page 76 for details.

Import Data from SAS

You can connect to a SAS server and work directly with SAS data sets.

Java Runtime Environment (JRE) Requirements

- On Windows, Java Runtime Environment (JRE) 7 or later must be installed on your computer to access SAS. However, JRE 7 does not need to be specified as the current version.
- On Macintosh, JRE 7 or later must be installed for SAS integration.

Note: On Windows, the bitness of the JRE must match that of JMP. For example, 64-bit JMP communicates with both 32-bit and 64-bit SAS if the 64-bit JRE is installed. 32-bit JMP communicates with both 32-bit and 64-bit SAS if the 32-JRE is installed.

SAS Menu Options

Browse Data Browse and import data residing on a SAS Server.

SAS Query Builder Select and import data on a SAS server without writing SQL statements. See [“Build SQL Queries in Query Builder”](#) on page 113 for details.

Export Data to SAS Export JMP data tables to a SAS Server.

Browse SAS Folders Browse and run SAS stored processes or open Metadata-defined data tables.

New SAS Program Opens a script window for writing and submitting SAS code.

Submit to SAS Sends SAS code directly from JMP to the currently active SAS server.

Open SAS Log Window Opens a SAS log window for the active SAS server.

Open SAS Output Window Opens a SAS output window for the active SAS server. This window shows recent SAS output.

Server Connections Administer connections to SAS servers.

You can also find shortcuts for SAS options on the SAS page of the JMP Starter, and there is a SAS toolbar. You can save certain settings pertaining to SAS Integration on the SAS Integration page of the Preferences window (**File > Preferences**). For more information about setting your SAS Integration preferences, see [“SAS Integration”](#) on page 620 in the “JMP Preferences” chapter.

Import SAS Data Sets

SAS data sets are saved in one of many SAS formats:

- Windows supported formats are .sas7bdat and .sas7bxat.
- Macintosh supports reading and writing .sas7bdat files.
- Windows and Macintosh support reading and writing .xpt files

When you open a data set in JMP, the file opens as a data table. JMP uses SAS variable names as column names by default. To use variable labels in a specific file on Windows, select the option when you open the file (see step 5 below).


The following ISO date formats are supported: B8601DA, B8601DN, B8601DT, B8601DZ, B8601LZ, B8601TM, B8601TZ, E8601DA, E8601DN, E8601DT, E8601DZ, E8601LZ, E8601TM, E8601TZ. If the date format is not supported, the data is imported with the Scientific Notation format.

To open a SAS data set:

1. Select **File > Open**.
2. (Windows only) Select **SAS Data Sets** from the list next to **File name** as shown in Figure 3.13.

Note: SAS variable names and formats are preserved and can be saved after changes are made to the SAS data set. See [“Save as a SAS Data Set”](#) on page 491 in the “Save and Share Data” chapter.

3. Select the file.

Figure 3.13 Open SAS Data Set


Note: To select the columns to import, click the arrow on the Open button and select **Select columns**.

4. (Optional) Select any of the following options:

SAS variable labels Uses the SAS variable labels (instead of variable names) as the column names in the JMP data table.

SAS variable names Uses the SAS variable names (instead of the labels) as the column names in the JMP data table.

5. (Optional on Windows) Select any of the following options:

Apply table and column properties from SAS 9.4 extended attributes If the SAS server supports extended attributes (SAS 9.4), includes the extended attributes when storing JMP metadata. This setting overrides the SAS 9.4 Extended Attributes preference on the SAS Integration page.

Select this filter the next time this dialog is invoked Sets the default file type choice to the option that you select next to the **File name** list. If selected, the default file type will be **SAS Data Sets** the next time you reach this window.

6. (Optional) Select any of the following for a SAS Transport (.xpt) file:

Select member Lets you enter the name of a specific member, or table, for JMP to open. On Macintosh, select **Member Tables > Specified** and then enter the name.

Open all members Opens all members, or tables, in the transport file. On Macintosh, select **Member Tables > All**.

Save all members Saves the file as a JMP file as soon as you open it. The file is saved to the same directory where the SAS transport file was opened. On Macintosh, the option is **Save all**.

Select columns Tells JMP to open only certain columns from the transport file. Select the columns that you want to import from the list that appears. On Macintosh, the option is **Select columns before opening**.

7. Click **Open**.

Note: If you are importing date variables from a SAS file, JMP looks for a SAS date format and translates it to a JMP date column.

Create SAS Transport Files in SAS

JMP can open SAS transport files that were saved using the SAS XPORT engine. For example, below is sample SAS code that creates a transport file called test.

Note: misc and work are SAS libref names.

```
data test;
input name $ age weight;
cards;
Susan 12 72
Melanie 10 68
Jonathan 11 77
Sheila 13 67
;
```

```
libname misc xport 'C:/test.xpt';
proc copy in=work out=misc;
run;
```


Connect to SAS

You can either connect to a SAS Metadata Server or directly to a SAS Workspace Server. Once connected to a SAS Metadata Server, you can browse through SAS servers, libraries, and data sets.

Note: SAS Server version 9.4 is the default setting in the JMP SAS Integration preferences. The earliest supported release of the SAS Metadata Server is version 9.1.3 SP4. Connections to earlier releases of the SAS Metadata Server are experimental and are not supported.

To begin, select **File > SAS > Server Connections**. The SAS Server Connections window shown in Figure 3.14 appears. All connections are made in this window.

Figure 3.14 SAS Server Connections



The following sections describe how to connect to a SAS server.

- “[Connect to a SAS Metadata Server](#)” on page 93
- “[Connect to a Remote SAS Workspace Server](#)” on page 95
- “[Connect to a SAS Environment \(Windows Only\)](#)” on page 96
- “[Connect to SAS on Your Local Machine \(Windows Only\)](#)” on page 97

Connect to a SAS Metadata Server

Note: You can be connected to only one Metadata Server at a time. If you make a second connection, your first one is disconnected.

To connect to a Metadata Server

1. Select **File > SAS > Server Connections**. The SAS Server Connections window shown in [Figure 3.14](#) on page 92 appears.
2. Select the version for the SAS Server. Your SAS Metadata Server administrator should have this information.

SAS Server version 9.4 is selected by default based on the JMP SAS Integration preferences.

3. Select the profile that you want to use.

If you do not have a profile set up, see [“To create or modify a SAS Metadata Server profile”](#) on page 94.

4. Click **Connect**.

If JMP is unable to establish a connection, an error message appears. Common reasons are invalid user names or passwords. If you need to update the information for the profile, see [“To create or modify a SAS Metadata Server profile”](#) on page 94.


5. Click **Close**.

Once you are connected to a SAS Metadata Server, you can connect to any SAS Workspace Servers that the Metadata Server offers.

To connect to a SAS Workspace Server (Windows only)

1. Select **File > SAS > Server Connections**. The SAS Server Connections window shown in [Figure 3.14](#) on page 92 appears.
2. Select the Workspace Server to connect to (Figure 3.15).


Figure 3.15 Open a Connection to a Workspace Server



3. Click **Connect**.

Under Open Workspace Server Connections, the Workspace Server is shown as the current active connection. See Figure 3.16.

Figure 3.16 Current Active Connection



4. Click **Close**.

To change the active connection

Note: The active connection is what is used to submit SAS code or handle SAS script commands.

To change the active connection, you first need to be connected to more than one server. Follow the instructions in [“To connect to a SAS Workspace Server \(Windows only\)”](#) on page 93 to add two or more server connections.

1. In the Open Workspace Server Connections section, click the drop-down menu and select the desired server.
2. Click **Set as Active**.
3. Click **Close**.

Tip: You can change the active server at any time.

To disconnect from a SAS Workspace Server

1. In the SAS Server Connections window, select the Workspace Server to disconnect under Open Workspace Server Connections.
2. Click **Disconnect**.

To disconnect from a SAS Metadata Server

1. In the SAS Server Connections window, select the Metadata Server to disconnect.
2. Click **Disconnect**.


To create or modify a SAS Metadata Server profile

1. In the SAS Server Connections window, select the **SAS Server Version**.

2. Click **Manage Profiles**.
3. Click **Add** to add a new profile, or click **Modify** to change a profile's settings.

The Create Profile or Modify Profile window appears. If you are adding a new profile, all fields are empty except the Authentication domain field, which contains DefaultAuth, and the Port field. If you are modifying a profile, the fields contain the current information.

Figure 3.17 Create or Modify a Metadata Server Profile



Profile name:

Description:

Machine:

Port:

☐ Use Integrated Windows Authentication

User name: Password:

Authentication domain:

4. Fill in the information needed to connect to a SAS Metadata Server. Your SAS Metadata Server administrator should have this information.

Profile name Select a name for this profile. This name is shown in the list of profiles.

Description (Optional) You can enter a short description of this profile.

Machine The name of the machine that hosts the Metadata Server. (Example: myserver.mycompany.com)

Port The port through which you should connect to the machine. (Example: 8561)

Use Integrated Windows Authentication Select this option to use your Windows log in ID and password to access the server. When enabled, the User name and password fields are disabled. This option is disabled by default.

User name Your user name for the Metadata Server.

Password Your password. This is always displayed as asterisks.

Authentication domain The domain you, as a user, belong to.

5. Click **Save**.


Connect to a Remote SAS Workspace Server

You can also connect directly to a SAS Workspace Server, instead of going through a Metadata Server.

To connect to a Remote SAS Workspace Server

1. Select **File > SAS > Server Connections**. The SAS Server Connections window shown in [Figure 3.14](#) on page 92 appears.
2. Under Establish New Workspace Server Connection, select **Connect to remote SAS server on**. See [Figure 3.18](#).

Figure 3.18 Open a Connection to a Remote SAS Server



3. Enter the machine name and the port number. Your SAS server administrator has this information.
4. Click **Connect**.
5. Enter your user name and password in the window that appears.
6. Click **OK**.
7. Click **Close** in the SAS Server Connections window.

To disconnect from a Remote SAS Workspace Server

1. In the SAS Server Connections window, select the server to disconnect under Open Workspace Server Connections.
2. Click **Disconnect**.

Connect to a SAS Environment (Windows Only)

On Windows, you can connect to a SAS mid-tier (or *SAS environment*) if SAS Server version 9.3 or 9.4 is selected in JMP's preferences and your computer or JMP has been configured correctly. (SAS Server version 9.4 is the default setting in the JMP SAS Integration preferences.)

The SAS installer should have set up your computer to find the SAS environment definition file. If not, you can enter the path to the file in the JMP preferences.

To configure your JMP preferences

1. Select **File > Preferences > SAS Integration**.

2. Select **I want to connect to a SAS Environment** and then click **Configure**.
3. To connect to an environment that JMP has already detected, click **Automatic discovery**, and then select the URL from the list if necessary.
4. To enter the path to the SAS environment definition file, click **Manual configuration** and enter the URL.
5. Click **OK**.

To connect to a SAS Environment

1. Select **File > SAS > Server Connections** to open the SAS Server Connections window.
2. In the Metadata Server Connection area, select **Connect to a SAS Environment**.
If this option is not available, either your computer or JMP is not configured to find the environment. See [“To configure your JMP preferences”](#) on page 96 for details.
3. Select the name of the environment from the Environment list if necessary.
4. Click **Connect**.
5. Enter your user name and password if prompted.

Connect to SAS on Your Local Machine (Windows Only)

You can also connect directly to SAS on your local machine.

To connect to SAS on your computer

1. Select **File > SAS > Server Connections** to open the SAS Server Connections window.
2. Under Establish New Connection, select **Connect to SAS on this machine**.
This option is disabled if SAS is not installed on the computer.
3. Click **Connect**.
4. Click **Close** in the SAS Server Connections window.

To disconnect from SAS on your computer

1. In the SAS Server Connections window, select **Local** under Open Connections.
2. Click **Disconnect**.

Open SAS Data Sets with SAS Query Builder

SAS Query Builder is the preferred method for selecting and importing data from a SAS server. You can preview the data before importing it into a data table. You can also save the queries to modify and run later or to reference in a JSL script.

SAS Query Builder provides an alternative to opening SAS data sets with the File > SAS > Browse Data feature.

To open a SAS data set with SAS Query Builder, follow these steps:

1. Select **File > SAS > SAS Query Builder**.
2. In the Connect to SAS Server window, select a Metadata server or a remote server.
 - To connect to a Metadata server that you have already set up in JMP, select the server from the **Connect to metadata-defined SAS server** list.

Connect to all available libraries is selected by default based on the SAS Integration preferences. This option connects metadata-defined SAS libraries automatically across all JMP sessions. When the Workspace Server contains a large number of metadata-defined SAS libraries, consider deselecting this option to speed up your connection to the server.
 - To add or configure a Metadata server, click **Manage Profiles** and follow steps in [“To create or modify a SAS Metadata Server profile”](#) on page 94.
 - To connect to a remote server, enter the machine name and the port number. Your SAS Metadata Server administrator should have this information.
3. Click **OK**.

The SAS Query Builder window appears.

For details about using Query Builder, see [“Build SQL Queries in Query Builder”](#) on page 113.


Notes:

- All Query Builder queries run in the foreground.
- Extended attributes are not imported by default. To import them, modify the JMP SAS Integration preferences. Select **File > Preferences** (Windows) or **JMP > Preferences** (Macintosh). Select **SAS Integration** and then select **On import, apply table and column properties from extended attributes**.
- SAS Query Builder does not support local server connections.

Open SAS Data Sets through a SAS Server

Once you connect to a SAS Workspace Server, you can browse through the SAS libraries on that server and import data into JMP.

To browse the data sets on the SAS server, select **File > SAS > Browse Data**. The Browse SAS Data window appears. See Figure 3.19.

Figure 3.19 Browse SAS Data

The window is initially populated with a list of servers the SAS Metadata Server provides (if connected). Any physical and local connections are also shown (as listed in [Figure 3.18](#) on page 96).

- Select a server to see a list of libraries that server contains.
- Select a library to see a list of data sets within that library.
- Select a data set to see a list of columns within that data set.

When you close and reopen the Browse SAS Data window, the previously viewed library and data set appear in the window. However, at any time, you can select a different server from the SAS Server list and then select a library and data set.

Tip: If a server is unavailable, or if the connections failed, the server's name is shown in light, italic text. Click it to try to re-establish the connection.


Browse SAS Data Information

You can select a SAS data set and see information about its contents before opening it using the Get Details, Column Details, and Data Preview options.

Data Preview

When you select a data set, the Data Preview outline shows you the first ten rows and columns in the data set. See [Figure 3.20](#).

Figure 3.20 Data Preview




Data Set Details

Click **Get Details** in the Browse SAS Data window to see the size and last modification date for each data set in the library. This option helps you estimate whether your computer can process the entire data set.

Column Details

To see information about a particular column in the data set, select it. The Column Details outline shows you some basic information about the data column. See Figure 3.21.

Figure 3.21 Column Details



Name Column name from the SAS data set.

Label Descriptive column label. The label can be longer than the name, and is often helpful to determine what the column name means.

Type Specifies whether the column has a character or numeric data type.

Length The length in bytes of data in the column.

Sort Order How the column is sorted in SAS.

Format The format for the SAS column, such as DOLLAR. This format field also contains information about the width of formatted values and the number of decimal places.

Open a SAS Data Set in JMP

You can import SAS data sets directly into JMP.

1. From the Browse SAS Data window, select a data set.
By default, JMP specifies **All rows** for import.
2. Click **Import**.


The entire SAS data set is imported into a JMP data table. When SAS data is imported, JMP attempts to make the best match to the SAS format.

Import a Sample of a SAS Data Set

You can import a sample of a SAS data set directly into JMP.

1. From the Browse SAS Data window, select a data set.
2. Open the Import Options outline. See Figure 3.22.

Figure 3.22 Import Options



3. If you want to import only a portion of a data set, you can do any of the following:
 - Select the first x number of rows only. See [“To import the first \$x\$ number of rows only”](#) on page 103.
 - Select to auto-sample a specified file size. See [“To import an auto-sample file of a specified size”](#) on page 103.
 - Select a subset of the columns. See [“To select a subset of columns”](#) on page 103.
 - Construct a WHERE clause to filter the data. See [“To import using a WHERE clause”](#) on page 103.
 - Take a custom sample of the data. See [“Importing a Random Sample of the Data”](#) on page 104.

The following options are also available:

Use labels for imported column names Converts SAS labels to column names.

Add SQL table variable to imported table Saves the SQL table variable as a data table variable.

Restore JMP metadata from SAS extended attributes Includes JMP metadata (table and column properties) that were saved in the SAS data set as extended attributes.

To import the first x number of rows only

1. In the Import Options section, select **First x rows only** and specify the number of rows to import.
2. In the Browse SAS Data window, click **Import**.

JMP imports the specified number of rows.

To import an auto-sample file of a specified size


1. In the Import Options section, select **Auto-sample** and specify the number of MB to import.
2. In the Browse SAS Data window, click **Import**.

JMP imports the specified number of MB.

To select a subset of columns

1. In the Import Options section, click **Select Columns**.
The Select Columns window appears. See Figure 3.23.

Figure 3.23 Select Columns



2. Select the columns that you want to import.
To select more than one column at a time, press CTRL and click each column.
3. Click **Add**.
4. When you have added all the columns that you want, click **OK**.
5. In the Browse SAS Data window, click **Import**.

Only the columns that you selected from the SAS data set are imported into a JMP data table.

To import using a WHERE clause

1. Click **Where**.
2. Use the WHERE clause editor to construct your WHERE clause.
3. Click **OK** to return to the Browse SAS Data window.
4. Click **Import**.

Only the data that matches your WHERE clause are imported into a JMP data table.

For information about constructing WHERE clauses and using the WHERE clause editor, see [“Use the WHERE Clause Editor”](#) on page 145.

Note: If you import data using both a WHERE clause and sampling, the WHERE clause is applied first, and then a sample of the filtered data is taken.

You can also write your own SQL statements.

To import using a custom SQL statement

You can also open a SAS data set using a custom SQL statement.

1. Open the Custom SQL outline under the Import Options outline. See Figure 3.22.

Figure 3.24 Custom SQL



2. Enter your SQL statement in the window.
3. Click **Execute Custom SQL**.

Note: Your SQL is run on the selected server but is not restricted to any selected library or data set.

Importing a Random Sample of the Data

You can also import a random sample of the rows of the SAS data set.

Note: The sampling feature requires that the SAS server has the SAS/STAT product licensed and installed. If SAS/STAT is not present, sampling is disabled.

In the Sample Imported Data area of the Import Options outline, select the **Custom random sample** check box. By default, 5% of the rows are imported. To change the random sample import settings, click the **Settings** button.

Figure 3.25 Sampling Settings

In this window, you specify any of the following:

Sample Size You can set the sample size be percentage or by number of rows. To ensure that each row is sampled only once, de-select the **With replacement** option. To ensure that any row can be sampled and appear more than once in the imported data, select the option.

Selecting by Column You can select strata by moving columns into the Strata list.

Handling Multiple Row Sampling If **With replacement** is selected, you can specify to either add each duplicated row as a separate row or combine all duplicated rows into one row. If the second option is selected, a column is added to the table that contains a count of how many times each row was sampled.

Setting minimum and maximum numbers of items selected Select the option and enter a number.

Setting the random number seed Select the option and enter a seed. Specifying the seed lets you reproduce the exact same sample multiple times.

Note: If you import data using both a WHERE clause and sampling, the WHERE clause is applied first, and then a sample of the filtered data is taken.

Import Options

There are additional options that you can use to specify how SAS data is imported into JMP.

Use labels for imported column names When selected, this option switches the column name, which has a limited length and might be difficult to decipher, with the column label.

This option is turned off by default. To use the SAS data column names as column names in JMP, deselect this box.

Add SQL table variable to imported table When selected, this option adds SQL queries to the data table panel as a variable. This option is turned on by default. If you turn off this option, only two variables are added when you import the data table: the SAS server and the data set.

Restore JMP metadata from SAS extended attributes

Tip: If your data is password-protected, you might want to turn this option off, because your password might be shown in the SQL.

Table Variables

After you import the JMP data table, table variables appear in the upper left panel of the data table. These variables show the SAS server, data set, and the SQL query and sampling settings if applicable. There is also a source script added that lets you re-do the import at any time.

Open Password-Protected Data Sets

JMP can open SAS version 7 or higher data sets that are password protected. The passwords are not case sensitive.

To open password-protected data sets

1. Select **File > Open**.
2. Select **SAS Data Sets** from the **Files of type** list.
3. Select the file.
4. Click **Open**.
5. Enter the password and then click **OK**.

When the password is incorrect, you are prompted to enter it again until you get it right.

Using SAS Extended Attributes to Import Metadata

SAS extended attributes are metadata that you define in SAS code to import information such as table scripts, labels, length, and type. You associate the extended attributes with a data set or variable and define them in name-value pairs, such as `_JMP_TABLESCRIPTNAME_2="OnOpen"`. For more information, see the SAS documentation on extended attributes at <https://sas.com/>.

On export from JMP to SAS, items such as column properties and table scripts are preserved automatically. You map SAS extended attributes to JMP attributes only when importing SAS code into JMP.

Here is an example of defining extended attributes in SAS code. The attributes define a table script name and the table script itself.

```
/* specify two table scripts. */
%LET _DS_ATTRIBUTES=_JMP_TABLESCRIPTCOUNT=2
/* define the table script names */
_JMP_TABLESCRIPTNAME_1="Favorite Movie By State"
_JMP_TABLESCRIPTNAME_2="OnOpen"
_JMP_TABLESCRIPTVALUE_2="CurrentDataTable() << RunScript("""Favorite Movie By
    State""");"
/* define the OnOpen table script */
_JMP_TABLESCRIPTVALUE_1=
/* a portion of the OnOpen table script */
"
    Current Data Table();
    New Column("""max_name""",
        Character,
        Width(128)
    );
```

The following example shows how to combine PROC DATASETS with extended attributes:

```
%LET _DS_ATTRIBUTES = attr-name=attr-value...attr-name=attr-value;
%LET _VAR_ATTRIBUTES= var-name (attr-name=attr-value...)...var-name
    (attr-name=attr-value...);

PROC DATASETS NOLIST LIB=WORK;
    MODIFY AttributeReferenceTable;
    XATTR OPTIONS MAXCHUNK=100;
    XATTR SET DS &_DS_ATTRIBUTES;
    XATTR SET VAR &_VAR_ATTRIBUTES;
RUN;
QUIT;
```

See [“Conventions for Mapping JMP Attributes to SAS Extended Attributes”](#) on page 696 for details about SAS extended attributes and their corresponding JMP attributes.

Two SAS Integration preferences determine whether extended attributes are imported or exported. Select **On export, store table and column properties in extended attributes to export extended attributes**. Select **On import, apply table and column properties from extended attributes**. The options are deselected by default.

To see an example of exporting extended attributes, run the following script:

```
dt = Open( "$SAMPLE_DATA/Big Class.jmp" );
sd = dt << Make SAS Data Step Window( SaveJMPMetadata( 1 ) );
```

Run Stored Processes

Stored processes are SAS DATA step code saved on the SAS server that you are connected to. You can run them from JMP and see the results of the script in JMP.

Note: Depending on the preferences that you have set for SAS, error messages are sent either to the JMP log or to a separate SAS log window.

You must be connected to a Metadata Server to view and run stored processes. If you select **File > SAS > Browse SAS Folders** without such a connection, you are prompted to either make a connection or cancel your action.

To select and run a stored process

1. Select **File > SAS > Browse SAS Folders**.

The Browse SAS Folders window appears.

2. Browse through the stored processes to find the one that you want to run.
3. Select it and click **Run**.

The data opens as a JMP data table.

On Windows, you can also right-click a stored process and select **Copy Metadata Path**. This option copies the path to the clipboard. You can then paste it into a script window to include it as a parameter for the JSL operator `Meta Get Stored Process()`. For more information, see the JSL Functions chapter in the *JSL Syntax Reference*.

Note: Static graphs might not appear in the results returned from a SAS stored process when streaming output is selected.

Stored processes send reports to HTML by default, but you can select RTF or PDF instead on the SAS Integration page of the JMP preferences. Select **File > Preferences** (Windows) or **JMP > Preferences** (Macintosh) to view the JMP preferences.

Submit SAS Code

You can submit SAS code directly from JMP to the currently active SAS server. If the submitted SAS code generates SAS Listing output, that output is automatically retrieved from the SAS server and displayed in JMP. Also, the generated SAS Log is retrieved, and, if there are any errors in the submitted code, the SAS Log is automatically displayed in the SAS Log window.

All analyses in JMP are run natively within JMP without any dependency on the SAS System. The SAS code that JMP generates is intended to enable you to perform a separate but similar

analysis in the SAS System after the initial JMP analysis, or to score new observations in the SAS System using a model that was fit within JMP.

Figure 3.26 SAS Code Submission Example

SAS Code	JMP Code to Submit SAS Code
data a;	SAS Connect("sasmain");
x=1;	SAS Submit("data a; x=1; proc print; run;");
proc print;	
run;	

The following JMP platforms generate SAS code:

- Standard Least Squares - PROC GLM
- REML - PROC MIXED
- Stepwise - PROC GLM
- Nominal and Ordinal Logistic - PROC LOGISTIC
- GLM - PROC GENMOD
- Time Series (ARIMA and TFM) - PROC ARIMA
- Neural - SAS Data Step scoring code
- Partition (Decision Tree, Bootstrap Forest, Boosted Tree) - SAS Data Step scoring code

Note: Use the JSL function `As SAS Expr( formula );` to turn any prediction formula into an expression that can be used in a SAS Data Step. See the JSL Functions chapter in the *JSL Syntax Reference*.

To run SAS code directly from JMP

1. Either open an existing SAS program using **File > Open**, or create a new SAS program. (Create a new SAS program by selecting **File > SAS > New SAS Program** and typing in the SAS code.)
2. Click the **Submit to SAS** icon .

You can also right-click in the Program Editor window and select **Submit to SAS**. The menu item also includes the name of the active SAS server that the SAS code will be submitted to.

You can also press the F8 key (press COMMAND-Shift-R on Macintosh).

To run SAS code using a JSL script

Write and run a JSL script that uses either the `SAS Submit` or `SAS Submit File` JSL functions. For more information about writing JSL scripts that submit SAS code, see the Extending JMP chapter in the *Scripting Guide*.

To view the SAS Listing output

If the submitted SAS code generates SAS Listing (textual) output, that output is automatically displayed in a SAS Output window when the job is completed. If you need to view the SAS Listing output again later in the JMP session, select **File > SAS > Open SAS Output Window**. The SAS Output Window retains the listing output from the previous 25 submits to the active SAS server.

To view the SAS log

If the submitted SAS code contained errors, the SAS Log window for the active SAS server is automatically opened, displaying the SAS Log for the job. However, you can view the SAS Log for the most recent 25 submits to the active server at any time by selecting **File > SAS > Open SAS Log Window**.

If you prefer that SAS Log information is appended to the JMP log after a submit completes:

1. Select **File > Preferences** (Windows) or **JMP > Preferences** (Macintosh).
2. Open the SAS Integration category.
3. In the Show SAS Log section, select **JMP Log** rather than **Separate Window**.

Also, in the Show SAS Log section, you can set whether the SAS Log should be displayed **Always**, **Never**, or **On Error** (the default).


Generate ODS Results

The SAS Output Delivery System (ODS) is a powerful mechanism for generating reports in HTML, RTF, PDF, and other formats. ODS output is generally much more attractive and customizable than plain-text SAS Listing output. You can set your submitted SAS code generate ODS results rather than SAS Listing output using Preferences.

To generate ODS results from your submitted SAS code

1. Select **File > Preferences** (Windows) or **JMP > Preferences** (Macintosh).
2. Open the SAS Integration category and find the large SAS Submit Options group, as shown in Figure 3.27.

Figure 3.27 SAS Submit Options in Preferences



3. Select the **Automatically generate ODS results** option.
4. From the **ODS Result Format** list, select the format in which to generate the ODS results: HTML, PDF, RTF, or a JMP report.
5. (Optional) You can use other options to specify a style or style sheet to format the results or set the format for generated graphics. For more details, see [“SAS Integration”](#) on page 620 in the “JMP Preferences” chapter.

Performing the previous steps causes JMP to generate additional SAS code, including an ODS statement, that is wrapped around the SAS code that you submit. The SAS code that you submit then automatically generates ODS results in the specified format. Those results are downloaded to your computer and displayed either within JMP, when possible, or in an appropriate external application.

Retrieve Generated SAS Data Sets

SAS code that you submit might generate SAS data sets. You can have them automatically imported into JMP for further analysis.

1. Select **File > Preferences** (Windows) or **JMP > Preferences** (Macintosh).
2. Open the SAS Integration category.
3. Select the **Import generated SAS data sets into JMP** option.

Export JMP Data Tables to SAS


You can export JMP data tables to a SAS Workspace Server.

1. Connect to the SAS Workspace Server.
2. Open the file that you want to export.
3. Select **File > SAS > Export Data to SAS**.

If necessary, you are connected automatically using your profile's user name and password.

4. Select the data table that you want to export to SAS from the list of open data tables under Select Data to Export.

Figure 3.28 Export Data to SAS



5. (Optional) To export only some of the columns in the data table, click **Select Columns**. See [“To select columns to export”](#) on page 112 for details.
6. Select the Destination Server.
7. Select the Library.

Tip: If your libraries do not appear, see [“Show Libraries in the Export Data to SAS Window”](#) on page 113.

A list of the data sets in the library appears.

8. Enter the name as you want it to appear in the SAS library.
9. (Optional) Set the export options that you want to use. See [“Export Options”](#) on page 113 for details.
10. Click **Export**.

To select columns to export

1. To export only some of the columns in the data table, click **Select Columns**.

2. In the window that appears, select the columns to export and click **Add**.
3. When all the columns have been added to the Selected Columns list, click **OK**.

Export Options

The available export options are as follows:

Ignore 'excluded' row state (export all rows) Select this option to export all rows in the data table. Deselect this option to export only those rows that are not excluded. This option is on by default.

Preserve SAS variable names This option is useful for data tables that were imported originally from SAS. When importing a SAS data set, the original SAS variable name is saved in a column property for each column. Select this option to use the SAS variable name for each column when exporting to SAS. Deselect this option to export the JMP variable names. This option is off by default.

Preserve SAS formats This option is useful for data tables that were imported originally from SAS. When importing a SAS data set, the original SAS format and informat is saved in a column property for each column. Select this option to use the SAS format and informat for each column when exporting to SAS. Deselect this option to export the JMP formats instead. This option is on by default.

Show Libraries in the Export Data to SAS Window

If your libraries do not appear in the Export Data to SAS window, define the library in one of the following ways:

- Using JSL, submit code to the SAS server. The code defines a library using a `libname` command.
- Define an `autoexec.sas` file that runs a snippet of SAS code every time SAS is invoked. This creates the same `librefs` every time you connect to SAS. For details about `autoexec.sas` files, see the SAS documentation.

Libraries that are defined in metadata (such as libraries defined in the SAS Management Console under the Data Library Manager) cannot be accessed from the Export Data to SAS window.

Build SQL Queries in Query Builder

Query Builder is the preferred method for selecting and importing data from a SQL database without writing SQL statements. You can preview the data before importing it into a data table. Share your queries so that other users can customize and run the queries.

Query Builder provides an alternative to writing your own queries using the File > Database > Open Table feature. However, you can also start building a query in Query Builder and then add your own SQL statements.

SAS Query Builder is also available for querying SAS data sets on SAS servers. See [“Open SAS Data Sets with SAS Query Builder”](#) on page 97 for details.

Notes:

- Database table names that contain the characters \$# -+/%()&| ;? are not supported.
- The Value Ordering column property is not supported. Consider writing a script in the Post-Query Script window to sort the rows.


Connect to a SQL Database

Set up the ODBC connection through the Windows Control Panel or inside JMP.

1. Select **File > Database > Query Builder** to display the Select Database Connection window. The Connections box lists data sources that you connected to in the current JMP session.
2. If the desired data source is *not* listed in the Connections box, click **New Connection** to choose a data source. The method of choosing a data source depends on your operating system and the ODBC driver. See [“Connect to a Database”](#) on page 136 for details.
3. Select a table or schema from the Schemas - Tables box and click **Next**.

Query Builder examples are based on a table named SQBTest, which contains movie rental data.

Figure 3.29 Select the Database Schema



Tip: To find the table in a long list, enter the name in the search box above the schemas. You can also search for tables above the list of tables. The red triangle menu provides options for matching case and searching with regular expressions.

Select Tables from a SQL Database

After connecting to the SQL database, select the tables that you want to query. Either select a primary table or join several tables to query them all.

By default, JMP attempts to join tables based on key relationships that are assigned in the tables.

- A primary key identifies a column that uniquely describes the data (for example, a customer ID number). All rows from the primary table are included in your query.
- A foreign key in a secondary table matches the primary key in one of the joined tables. Only matching rows from the secondary table are included in your query.

If there are no keys, data are matched by column name, which joins the two tables. By default, only matching rows from the secondary tables are included in the query.

This example shows how to join multiple tables. However, you can also build a query using a single table. In this case, joining is not necessary.


Note: The Query Builder examples are based on a database that is not installed with JMP.

1. Select **File > New > Database Query**, connect to the database, and select the **SQBTest** schema. (See [“Connect to a Database”](#) on page 136 for details.)
2. Select the schema from the Schemas - Tables list.
If you also select a table, that table will be the primary table after you click Next.
3. In the Select Tables for Query window, select **g6_Customers** from the Available Tables list, and then click **Primary**.
The Columns tab shows that CustID is the primary key. The data is indexed, which speeds up the query.
4. Select **g6_Movies** and **g6_Rentals** from the Available Tables list, and then click **Secondary**.
The Left Join icon  indicates that the tables were automatically joined (Figure 3.30). CustID is the primary key in g6_Customers and matches a foreign key in one of the other tables.

Tip: After you add a primary or secondary table, click **Add Related Tables** to add tables that have matching columns. The button is unavailable when no related tables are found or when a primary or secondary table is not selected.

Figure 3.30 shows the completed window.


Figure 3.30 Selecting Primary and Secondary Tables



Tip: To find the schema in a long list, enter the name in the search box above the schemas. You can also search for tables above the list of tables. The red triangle menu provides options for matching case and searching with regular expressions.

5. Click the **Table Snapshot** tab for each table to preview the data (Figure 3.31).

Figure 3.31 Table Snapshot Tab



- Below the primary and secondary tables, click **Preview Join** to see a preview of the table that was created from the specified joins.

Tips:

- The icon next to a secondary table indicates that the table is not joined in the query. Click the **Edit Join** button to specify the columns to join. If you cannot find columns to join, click the **Remove** button to remove the table. See [“Edit the Conditions for Joining Tables”](#) for details.
- On the Columns tab, the Key column might show multiple keys; some columns can be both primary and foreign keys. A unique key icon does not appear next to primary keys, because all primary keys are unique.
- On the Columns tab, the Reference is specified for foreign keys that match primary keys in another schema. The reference is the name of the schema and column.
- Click **Change Data Source** to query a different schema or database.
- To join data from different sources (for example, a database and Microsoft Excel), use Query Builder to import the database data into a data table; import the Excel data into a data table; use JMP Query Builder in the Tables menu to query and join the tables.
- When you import a table that contains a primary key, the Link ID column property is added to the column in the data table. The column property enables you to virtually join data tables. See [“Virtually Join Data Tables”](#) on page 335 in the “Reshape Data” chapter.
- If you try to query a Microsoft Excel file that has more than 255 columns, only 255 columns are imported. Instead, select **File > Open** to open the Excel file in the Excel Import Wizard, and save the file as a data table.

Edit the Conditions for Joining Tables

In the Select Tables for Query red triangle menu, Auto join Database Tables is initially selected. JMP automatically joins database tables based on key relationships or matching column names.

If there are no keys, or when column names do not match, click **Edit Join**  to specify the columns to join.

Note: The Query Builder examples are based on a database that is not installed with JMP.

To edit the conditions for joining tables

1. Select **File > New > Database Query**, connect to the database, and select the **SQBTest** schema. (See [“Connect to a Database”](#) on page 136 for details.)
2. In the Select Tables for Query window, select **g1_books** as the Primary table and **g1_charges** as the Secondary table.


The  icon next to the secondary table indicates that the table is not joined in the query.

3. Select **g1_charges** in the Secondary table pane and click **Edit Join** .

The Add Condition window appears.

4. In the Left Column list, select **g1_books**.
5. Select **Book ID** from the Left Column box.
6. Select **ID** from the Right Column box.
7. Make sure that the equal sign is selected between the two boxes.

Figure 3.32 The Edit Condition Window



8. Click **Next**.

The Edit Join window shows that non-matching rows from **g1_books** will be included in the data table. Rows that are only in **g1_charges** will be omitted.

To do a full join and import all rows, you would select **Include non-matching rows from g1_charges**. If only one of the non-matching options is available, the database does not support full joins.

9. Click **OK**.

Note: The **OK** button is unavailable until all of the secondary tables are joined.

To prevent tables from joining automatically

- Deselect **Auto join Database Tables** from the Select Tables for Query red triangle menu above the primary table.
- If you frequently query large databases, deselect **Automatically join tables added to a query** in **Preferences > Query Builder** to prevent memory issues.

Build the SQL Query

After selecting database tables, you either import the data or build a query. Query Builder enables you to interactively create the database query rather than write SQL expressions.

After selecting database tables (and joining them if necessary), click **Build Query** to open the Query Builder window. You can continue to refine the query by selecting which columns to include and specifying criteria for sampling and filtering. You can also save the query to edit and run again later.

The columns from all database tables appear in the Available Columns list. Prefixes such as t1 and t2 (also called *aliases*) associate each column with the corresponding database table.

To skip the Query Builder step and import all data, click **Import Now** instead.


Note: The JMP Query Builder in the Tables menu provides many of the same options but lets you query and join JMP data tables. See [“Query and Join Data Tables with JMP Query Builder”](#) on page 332 in the “Reshape Data” chapter for details.

Select Columns from the Database Table

Suppose that you want to view movie rentals by movie genre, rating, and demographic data such as marital status and age.

Note: The Query Builder examples are based on a database that is not installed with JMP.

1. Select **File > New > Database Query**, connect to the database, and select the **SQBTest** schema. (See [“Connect to a Database”](#) on page 136 for details.)
2. In the Select Tables for Query window, select **g6_Customers** and click **Primary**.
3. Select **g6_Movies** and **g6_Rentals** and click **Secondary**.
4. Click **Build Query** to show the Query Builder window.
5. In the Available Columns box, select t1.Gender, t1.Age, t1.Married, t1.KidsUnder12, t2.Rating, and t2.Genre.
6. Click **Add** on the Included Columns tab.

Figure 3.33 Selected Columns

Notes:

- When a query contains eight tables or more, a search box appears above the table names near the upper left corner. To find a column in a long list, enter the name in the search box below Available Columns. The red triangle menu provides options for matching case and searching with regular expressions. To hide the search box, deselect **Show Search Box** from the Available Columns red triangle menu.
 - Reference columns no longer appear in the Available Columns list because they are not supported in queries.
 - You can change the width of the column by selecting an option from the Format list in the Included Columns list.
- Select the **SQL** tab below the columns to view the SQL statements for your query. This code is saved as a data table property after you run the query.
 - Click **Save** in the lower right corner.
Your work is saved as g6_Customers.jmpquery, which you can open later to return to this point or to run the query.
 - Click **Run Query** to import the data.
The data table includes the following scripts:
 - Run the Source script to reconnect to the database and import the data.
 - Run the Modify Query script to open the query in Query Builder.

- Run the Update From Database script to re-import and refresh the data.

Tips:

- To rename a column, double-click the JMP Name in the Included Columns tab and enter a new name.
- To rename an alias, right-click the table in the Select Tables for Query window and select **Change Alias**. Aliases are not case sensitive.
- The query runs in the background unless you deselect **Run queries in the background when possible** from the Query Builder ODBC preferences. You can also check the progress of all ODBC queries by selecting **View > Running Queries**.

Note: For SAS Query Builder, all queries run in the foreground.

- Deselect **Update preview automatically** if the preview loads too slowly. Click **Update** below the Query Preview tab to update the data view. Consider changing the Preview options in the JMP Query Builder preferences if you frequently work with large databases. Consider limiting the maximum number of rows that can be previewed. In the JMP Query Builder preferences, change the value of **Maximum number of rows for previews**.
- To omit duplicate rows from the database, select **Distinct rows only** on the Included Columns tab.

Maintain Compatibility with JMP 12

If you add a JMP 13 feature to a query, that query will no longer load in JMP 12. If you are using JMP 13, but you need to create queries that will still run in JMP 12, select **Keep this query compatible with JMP 12** in the Query Builder Preferences. After you select the option, features that create compatibility problems are hidden in Query Builder.

When you are ready to move JMP 12 queries to JMP 13 or 14, deselect this preference.

Create a Computed Column


You can create a new column from existing columns. You might calculate the mean for two columns and store the mean in a new column. Date-time values might be in the wrong format. From the Available Columns red triangle menu, select **Add Computed Column**, and create the new column in the formula editor.

Suppose that you want to calculate the maximum number of times you can watch a movie during the rental period. You are querying a database that contains the length of each movie and number of days the movie was checked out. This example shows how to create a new computed column from these data.

Note: The Query Builder examples are based on a database that is not installed with JMP.

1. Select **File > New > Database Query**, connect to the database, and select the **SQBTest** schema. (See [“Connect to a Database”](#) on page 136 for details.)
2. In the Select Tables for Query window, select **g6_Rentals** as the Primary table and **g6_Movies** as the Secondary table.
3. Click **Build Query** to show the Query Builder window.
4. From the Available Columns red triangle menu, select **Add Computed Column**.
The Computed Column window appears (Figure 3.34). The window contains the JMP Formula Editor.

Figure 3.34 Computed Column Window with Formula Editor




Notes:

- Operators and functions are provided in the list on the left side of the Formula Editor (Figure 3.34). In some instances, you might need to change the server type based on your database.
 - The Operators list does not provide a Concatenate (||) operator. You must type the formula in the Formula Editor box.
5. From the g6_Rentals list on the left, select **Days Out** and click the multiplication  button.


Figure 3.35 Computed Column

6. Select the blank box, type $24 * 60$, and press Enter.

This formula multiplies the number of hours in a day by the number of minutes in day.
Notice that when you type the first parenthesis, then second one is automatically inserted.

Figure 3.36 First Portion of the Formula

7. Click the outer box to select the entire equation and click the division $\div$ button.
8. Select **g6_Movies** from the list on the left and then select **LengthMins**.

Figure 3.37 Second Portion of the Formula

9. Click **OK**.
A new column named Calc1 is created.
10. Right-click the column and select **Rename Column**.
11. Type MaximumTimesWatched and click **OK**.
12. In the Available Columns list, select MaximumTimesWatched and click **Add**.
13. Select t2.Name and click **Add**.

On the Query Preview tab, notice that Nanny McPhee can be watched 160 times while the movie is rented.

Group the Common Values

You can combine (or group) common values in a column before importing the data into JMP. To group common values, select an Aggregation function to determine how the common values are calculated.

Note: Aggregation support is based on your database. See the database documentation for more information.


Suppose that you are interested in the number of times a specific movie was rented. In this example, the count for each item number is calculated, and common movie values are grouped into single rows.

Note: The Query Builder examples are based on a database that is not installed with JMP.

1. Select **File > New > Database Query**, connect to the database, and select the **SQBTest** schema. (See “[Connect to a Database](#)” on page 136 for details.)
2. In the Select Tables for Query window, select **g6_Movies** as the Primary table and **g6_Rentals** as the Secondary table.
3. Click **Build Query** to show the Query Builder window.
4. In the Available Columns box, select **t1.Name** and **t2.ItemNo** and click **Add**.
5. Select **t2.ItemNo** and select **Count** from the Aggregation list.

The Group By check box is selected for **t1.Name** (Figure 3.38). All instances of a specific movie name will be grouped into one row.

Figure 3.38 Grouped Columns



6. Click **Run Query** to import the data.
7. In the data table, right-click the **Count-ItemNo** column and select **Sort > Descending**. Scarface was rented most frequently (Figure 3.39).

Figure 3.39 Sorted Count-ItemNo Column

	Name	Count-ItemNo
1	Scarface	15991
2	Rambo	15643
3	Nanny McPhee	15289
4	Marmaduke	15255
5	A Bug's Life	15128
6	Diary of a Wimpy Kid	14989
7	Cars	14905

Tips:

- To clear the grouped rows, select **None** from the column's Aggregation list.
- The DISTINCT Aggregation functions show only rows that contain distinct values. Rows with duplicate values are omitted. These functions are useful when a database contains many duplicate values.

Import a Sample of the Data

With large databases, consider sampling the data. Sampling returns a subset of rows and decreases the query time. The database query runs, and a smaller portion of data are imported based on options that you select on the Sample tab.

Sampling methods differ based on the database vendor.

- SQL Server supports block sampling by default. A block sample takes an entire page of rows (such as all rows on pages 1 and 5). If you select 1,000 rows, approximately 1,000 rows are imported.
- Oracle and other databases support row sampling. If you select 5,000 rows, between 4,800 and 5,200 rows per sample are typically imported, based on how Oracle cycles through the data.

For major database vendors, JMP detects the capabilities and provides vendor-specific options when possible. Features that are unsupported by the vendor are unavailable on the Sample tab.

Suppose that you want to import a sample of the data. In this example, you select 5,000 random rows.

Note: The Query Builder examples are based on a database that is not installed with JMP.

1. Select **File > New > Database Query**, connect to the database, and select the **SQBTTest** schema. (See [“Connect to a Database”](#) on page 136 for details.)
2. In the Select Tables for Query window, select **g6_Rentals** as the Primary table and **g6_Movies** as the Secondary table.
3. Click **Build Query** to show the Query Builder window.

4. Click the **Add All** button on the Included Columns tab.
5. Click the **Sample** tab and select **Sample this result set**.
6. Select **Random N Rows** and type 5,000.

In the Sample By area, Blocks or Pages is the only option based on which type of sampling the database supports.

7. Click **Run Query** to import the data.

The new data table consists of approximately 5,000 rows. With block or page sampling, you might get a sample of 4,900 rows one time and 5,600 rows the next time.

Tips:

- To re-create the same sample set each time you run a query, set the Seed value to any positive integer up to 64,000. Suppose that you want to query movie rentals by gender. Type 1 as the Seed value and run the query. The distribution of male customers in the results is low. Type 2 as the Seed value and run the query again. Repeat this process to find the Seed value that results in a similar distribution of males and females.
- To add individual columns to the Included Columns tab, right-click the column and select **Include Column** or click the **Add** button.

Select Filters to Import a Subset of the Data

Add filters to import a subset of values from the selected filters into the data table. Some filters are not available if the query is compatible with JMP 12. See [“Maintain Compatibility with JMP 12”](#) on page 121 for details.

Filters for Both Continuous and Categorical Columns

Simple Comparison Matches values using the specified operator.

Age > 14 matches ages that are greater than 14.

Range Matches a range of values using the specified operator.

12 ≤ Age ≤ 17 matches ages that are between 12 and 17.

Is NULL or Is Not NULL Matches missing values.

Either **NULL** or **not NULL** matches missing values and non-missing values.

Custom Expression Enables you to write your own SQL expression.

```
( ( ( t2.Gender IN ( 'F' ) ) AND ( t2.Age >= 20 ) AND ( t2.Age <= 50 ) ) ) )
```

matches the F Gender. It also matches Age between 20 and 50.

Filters that are Only for Categorical Columns

List Box Displays a list box from which you select one or more values. List Box is the default filter for categorical columns based on the Query Builder preferences.

Manual List Enables you to enter the column values.

Check Box List Displays a check box list.

Note: List Box, Manual List, and Check Box List include a **Not in list** option that enables you to retrieve rows that do not match the selected values.

Contains Matches a string that contains or does not contain the specified value. **Contains Comedy OR Romance** matches Comedy and Romance.

For most categorical columns, the filter is a Check Box List by default. For columns that contain over 1,000 levels, the Contains filter is automatically selected. You can change the number of levels in the Query Builder preferences.

Like or Not Like Matches a string that is similar to or not similar to the specified value. Supports the % wildcard (zero or more characters) and _ wildcard (exactly one character).

Genre Like %com matches any number of characters before “com”, as in “RomCom”. To also match “Comedy”, use %com% or **Contains com**.

Match Column Values Matches the specified column value. Select the table and then select the columns. The **Select non-matching** option enables you to filter all rows except for the selected rows. See [“Import Matching Data from an Existing Data Table”](#) on page 129 for an example.

This example shows how to import data for age 30 and over customers, and movies in the RomCom and Comedy genres.

Note: The Query Builder examples are based on a database that is not installed with JMP.

1. Select **File > New > Database Query**, connect to the database, and select the **SQBTest** schema. (See [“Connect to a Database”](#) on page 136 for details.)
2. In the Select Tables for Query window, select **g6_Rentals** from the Available Tables list, and then click **Primary**.
3. Select **g6_Customers** and **g6_Movies** and then click **Secondary**.
4. Click **Build Query** to show the Query Builder window.
5. In the Available Columns box, select t2.Gender, t2.Age, and t3.Genre, and then click **Add** on the Included Columns tab.

6. Select all columns on the Included Columns tab and click **Add Selected Items to Filters**



Filters for the columns appear in the Filters outline.

7. Set the t2.Age filter to ≥ 30 .
8. From the t3.Genre red triangle menu, select **Like**, type %com%, and press **Enter**.

The % wildcards match any number of characters before and after “com”. On the Query Preview tab, notice that movies in both the RomCom and Comedy genres are shown (Figure 3.40).

Figure 3.40 Selecting Filters

The screenshot displays the JMP Query Builder interface. The 'Included Columns' panel on the left lists three variables: t2.Age (Age, Best format, None aggregation), t3.Genre (Genre, None aggregation), and t2.Gender (Gender, None aggregation). The 'Filters' panel on the right shows filters for t2.Age (≥ 30) and t3.Genre (Like %com%). The 'Query Preview' panel at the bottom shows a table of results with columns Age, Genre, and Gender. The table contains 8 rows of data, showing movies in both the RomCom and Comedy genres.

	Age	Genre	Gender
1	64	RomCom	F
2	66	Comedy	F
3	45	Comedy	M
4	50	Comedy	M
5	36	Comedy	M
6	49	Comedy	F
7	63	RomCom	F
8	31	RomCom	F

9. In the Filters red triangle menu, select **All Prompt on Run**.
Users who run the query can customize the filters.
10. Click **Run Query**.
11. In the Query Prompts window, click **OK** to apply the preselected filters and import the data.

Notes:

- For most categorical columns, the filter is a list box by default. For columns that contain over 1,000 levels, the Contains filter is automatically selected. You can change the number of levels in the Query Builder preferences.
- The Conditional option in a filter's red triangle menu enables you to filter data within hierarchical categories. For example, suppose that you have a State filter and a City filter. To select a state and then display only cities that are in that state, select Conditional from the City red triangle menu.
- The Inverse option at the top of the Filters list enables you to select all but the specified rows for all filters. The option is unavailable for filters that select all rows.
- "<Blank>" in the filter list indicates that the database contains a missing value for that column.
- To create a filter for large columns of categorical data, JMP attempts to determine the number of rows in the table.
 - The Query Builder preference called **Retrieve category levels for tables whose size cannot be determined** is selected by default so that JMP automatically retrieves the levels. If you deselect the preference, the Contains fallback filter type in the Query Builder preferences is selected.
 - If the categorical column has more than 1 million rows, JMP does not automatically retrieve the unique category levels for the filtered column. The Query Builder preference called **Maximum rows in table for which category levels will be automatically retrieved** supports a minimum of -1 (no limit) and a maximum value of 1 billion rows.
- The default filter for categorical columns is a list box unless the **Keep this query compatible with JMP 12** Query Builder preference is selected.

Import Matching Data from an Existing Data Table

You can also select rows from an open data table that match a column in your query. Consider a database of airline data. The database includes data such as flight duration and tail number. You also have a data table that includes tail number data. Use the Match Column Values filter to import only data for matching tail numbers.

Note: The Query Builder examples are based on a database that is not installed with JMP.

1. Select **Help > Sample Data Library** and open `Air Traffic.jmp`.
2. Select **File > New > Database Query**, connect to the database, and select the `SQBTest` schema. (See ["Connect to a Database"](#) on page 136 for details.)
3. In the Select Tables for Query window, select `g5_AIRLINE_ONTIMEPERF` from the Available Tables list, and then click **Primary**.

4. Click **Build Query** to show the Query Builder window.
5. Click **Add All** on the Included Columns tab.
6. Select t1.TailNum on the Included Columns tab and click **Add Selected Items to Filters** .
7. From the t1.TailNum red triangle menu in the Filters column, select **Filter Type**, and then select **Match Column Values**.
8. Select **Air Traffic** below **Match values from table**.
9. Select the Tail Number column and then select **All rows (38,118)** from the list.
The data view on the Query Preview tab updates to show the filtered values.
10. Click **Run Query** to import the data.
The data table includes only data for rows that are in the Tail Number column.


Write a Custom Expression to Import a Subset of the Data

In addition to selecting filters to subset the data, you can write custom SQL expressions if you do not want to use the filters that are provided.

Note: The Query Builder examples are based on a database that is not installed with JMP.

1. Select the columns that you want to filter (described in [“Select Filters to Import a Subset of the Data”](#) on page 126).
2. From the Filters red triangle menu, select **Add Custom Expression**.
3. Type the following text in the Custom Expression box:

```
( ( ( t2.Gender IN ( 'F' ) ) AND ( t2.Age >= 20 ) AND ( t2.Age <= 50 ) ) )
```
4. Click outside the Custom Expression box to update the Query Preview tab (Figure 3.41).
This expression matches the F Gender. It also matches Age between 20 and 50.

Figure 3.41 Writing a Custom Filter Expression

Sort the Selected Data

You can sort the rows in specific columns by values to control how the data appear in the data table. In this example, you sort the Married column in descending order and sort the data by age and then height.


Note: The Query Builder examples are based on a database that is not installed with JMP.

1. Select **File > New > Database Query**, connect to the database, and select the **SQBTest** schema. (See [“Connect to a Database”](#) on page 136 for details.)
2. In the Select Tables for Query window, select **g4_bigclass** as the Primary table.
3. Click **Build Query** to show the Query Builder window.
4. On the Included Columns tab, click **Add All**.
5. Select t1.age and t1.height and click **Order by the Selected Items** .

The columns appear in the Order By outline in the right column.

The columns are sorted by age first (youngest to oldest) and then height (shortest to tallest).

Figure 3.42 Selecting the Order By Columns




6. In the Order By outline, select t1.height and then click **Sort the values in descending order**  below the columns.

The height column is sorted from tallest to shortest.

7. Select t1.height and click **Move the Selected Items Up in the List** .

The height column is sorted first. Values in the age column are sorted within each level of height. For a height of 68, age is sorted from 14 to 17.

Figure 3.43 Result of Reordering Columns



View the Query Status

On the Query Status tab, view the status of a query as it runs in the background. The query name, SQL statements, and number of processed records appear. You can stop a query at any time and view only the processed records. To view background queries from other JMP windows, select **View > Running Queries**. The status details are unavailable if you deselect **Run queries in the background when possible** from the Query Builder preferences.

Note: For SAS connections in Query Builder, all queries and query previews run in the foreground.

Write a Post-Query Script

On the Post-Query Script tab, write a JSL script that runs after you run the query. For example, you might want to import the data and then create a distribution.

```
Distribution( Column( :age, :gender ) );
```

This script is part of the Source script in the final data table.

Save and Run the Query

Save your query as a .jmpquery file to modify or run the query later. You are prompted to enter the password if the server connection string does not specify it. The .jmpquery file can also be opened and run by a JSL script.

After you build a query, click **Save** in the lower right corner to save the settings as a .jmpquery file. Clicking **Save** again overwrites the file with your latest changes. Clicking **Save As** saves the query in a new .jmpquery file.

Run the Query

A query file opens in Query Builder by default, where you modify the query and then run it as needed to import the data. After you are satisfied with the query, you can configure it to run when opened instead of opening in Query Builder.

When you are building the query, select **Run on Open** from the red triangle menu next to the Query Name box in the upper left corner.

To override the Run on Open setting, press the Control key (Windows) or Command key (Macintosh) before opening the file from the file system. On Windows, you can also right-click the query in the JMP Home Window and select **Edit Query**.

Using the Saved Query as a Template

You can also use the .jmpquery file as a starting point for a new query. This option prevents you from overwriting your original query if you accidentally click **Save**. It works the same as clicking **Save As** after you modify the query.

1. Right-click the .jmpquery file in the JMP Home Window's Recent Files list.
2. Select **Open as Template**.
3. Modify the query and click **Save** to create a new .jmpquery file.

Note: The .jmpquery file contains database login information. You must have set up the database connection before running the query. See [“Connect to a Database”](#) on page 136 for details.

Open the Selected Data in JMP

After you specify the columns and data to import, click **Run Query** to open the data in a data table. The SQL statements are saved as a table variable. The following scripts are available:

Source Runs the query.

Modify Query Opens the query in Query Builder, where you can change which columns and data are imported and further customize the query.

Update From Database Connects to the database to refresh the data and then run the query. If the data table and database table contain the same number of columns, values in the existing data table are updated when the database is refreshed.

The existing data table is also updated when only formula columns follow the last column that is refreshed.

Otherwise, the updated data appears in a new data table.

Query Builder Red Triangle Options

The Query Builder red triangle menu provides scripting and custom SQL options. The modify and run scripts are always automatically saved in the final data table.

Copy Modify Script Copies a script to the computer's clipboard that lets you modify the query.

Copy Run Script Copies a script to the computer's clipboard that lets you refresh the data and run the query.

Save Modify Script to Script Window Saves the Modify Query script to the script window.

Save Run Script to Script Window Saves the Update From Database script to the script window.

Convert to Custom SQL Shows the query statements in a new script editor window. You must remove prompting filters before selecting this option.

When you save the query from the Custom SQL window, the custom SQL is saved. Interactive components that were present before you customized the query are not saved. Revert to Interactive is also unavailable on the red triangle menu.

Keep this query compatible with JMP 12 Makes subsequent changes to the query compatible with JMP 12. Features that cause compatibility issues with JMP 12 are hidden while you edit the query. After you deselect this option and make a change that is supported only in JMP 13 and later, this option is no longer available.

The JMP Query Builder preferences include the same option, which is deselected by default. When you open a query in JMP 14 that is marked as JMP 12 compatible, features that create compatibility problems are hidden regardless of how the preference is set.

Revert to Interactive Displays the interactive query in the Query Builder window. Changes that you made on the Custom SQL tab are not saved when you revert.

Write SQL Statements in Query Builder

Query Builder enables you to interactively create SQL queries without writing SQL statements. You can also build a query in Query Builder and then add custom statements to the query.

Note: The Query Builder examples are based on a database that is not installed with JMP.

1. Select **File > New > Database Query**, connect to the database, and select the **SQBTtest** schema. (See [“Connect to a Database”](#) on page 136 for details.)
2. In the Select Tables for Query window, select **g6_Rentals** as the Primary table.
3. Select **g6_Movies** and **g6_Customers** as the Secondary tables.
4. Click **Build Query** to show the Query Builder window.
5. Click the **Add All** button on the Included Columns tab.
6. From the Query Builder red triangle menu, select **Convert to Custom SQL** and click **OK**.
The SQL that Query Builder generated appears on the Custom SQL tab.
7. Click before the semicolon and type the following SQL statement:

```
WHERE ( ( ( t2.Gender IN ( 'F' ) ) AND ( t2.Age >= 20) AND (t2.Age
      <= 50) ) ) )
```
8. Click **Run Query** to import the data into JMP.

The data table scripts include the custom query.

Note: If you select **Revert to Interactive** from the red triangle menu, the changes that you made on the Custom SQL tab are not saved. If you save the custom query and reopen it, Revert to Interactive is not available.

See [“Structured Query Language \(SQL\): A Reference”](#) on page 141 for a brief primer of SQL statements.

Import Data from a Database

You can import data from a database if you have an ODBC (Open Database Connectivity) driver for the database and then save the data back to the database.

You can use Structured Query Language (SQL) statements to control what you import from an external database. When you open a database file in JMP, you are actually sending a SQL statement to the database. By default, this statement gets all columns and records in the database table. See [“Build SQL Queries in Query Builder”](#) on page 113 for details about interactively building queries. See [“Write SQL Statements to Query a Database”](#) on page 139 for details about writing queries yourself.

This section describes how to connect to a database and import the data.

Notes:

- Database table names that contain the characters \$# -+/%()&| ; ? are not supported.
- Multiple connections to a datasource are not permitted.
- The bitness of the ODBC driver must match the bitness of JMP. If you are running 32-bit JMP you would need a 32-bit ODBC Driver for that kind of data. If you are using a 64-bit version of JMP, then you will need to utilize a 64-bit version of the ODBC driver for that kind of data.


Connect to a Database

Your operating system provides an interface for JMP to communicate with databases using ODBC data sources. Create and configure data sources with operating system software. For example, on Windows 7, use **Control Panel > System and Security > Administrative Tools > Data Sources (ODBC)**; on the Macintosh, use **Applications > Utilities > ODBC Manager**.

After you create the data source in the operating system software, follow these steps to connect to the database in JMP.

1. Select **File > Database > Open Table**. The Connections box lists data sources that you have connected to in the current JMP session.
2. Click **New Connection**.
3. (Windows) In the Select Data Source window (Figure 3.44), click the Machine Data Source tab, select the data source, click **OK**, enter the user name and password, and then click **OK**.
(Macintosh) In the Choose DSN window, select the data source, enter the user name and password, and then click **Choose DSN**.

Figure 3.44 Select a Data Source (Windows)



The new connection is shown in the Database Open Table window.

Open Data from a Database

After you connect to the ODBC database and select a table to import, the data is opened in a data table. Several table scripts are included in the data table.

- Run the Source script to reconnect to the database.
- Run the Update from DB script to re-import and refresh the data. If the database table has the same number of columns as the original JMP table, the values in that existing JMP table are updated in place. However, if the number of columns is not the same, then a new data table opens where the updated data is stored.
- Run the Save to DB script to save the data table to the database. The existing data in the database is replaced. This script might contain the user name and password. There is a JSL-only preference called ODBC Hide Connection String that can be set to prevent including this possibly sensitive information. See the Extending JMP chapter in the *Scripting Guide* for more details.

To import data from a database

1. Select **File > Database > Open Table**.


The Database Open Table window appears (Figure 3.45).

2. If you are already connected to the database, select it in the Connections box. Follow the steps in [“Connect to a Database”](#) on page 136.

The Connections box lists data sources to which JMP is connected. The Schemas - Tables box lists schemas for those databases that support them.

Figure 3.45 Database Open Table Window

When one or more database connections are made, the list of connections shows in the Connections list.



If your database supports schemas (for example, Oracle), this field shows the schema list. It disappears if you select a database that does not support schemas.

If there are tables in the selected database file or directory, they appear in the Tables list.

Note: The **Fetch Procedures** check box is disabled if the ODBC driver does not support fetching procedures.

3. If the desired data source is *not* listed in the Connections box, click **Connect** to choose a data source. The method of choosing a data source depends on your operating system. Select a data source and click **OK**.
4. Select the desired data source in the Connections box. The tables list in the Tables box updates accordingly. The update might take a several seconds, depending on the number of tables and the speed of the connection to the database. If your database supports

schemas, tables are loaded for the first schema in the list, and on other schemas as you click on them.

5. Control which tables are listed by choosing the options in the **Include in Table List** group of check boxes. Different drivers interpret these labels differently. Your options are as follows:

User Tables When clicked, displays all available user tables in the **Tables** list. User tables are specific to which user is logged on to the computer.

Views When clicked, displays “views” in the **Tables** list along with all other file types that can be opened. “Views” are virtual tables that are query result sets updated each time you open them. They are used to extract and combine information from one or more tables.

System Tables When clicked, displays all available system tables in the **Tables** list. System tables are tables that can be used by all users or by a system-wide service.

Synonyms When clicked, displays all available ORACLE synonyms in the **Tables** list.

Sampling Enter the percentage of rows that you want to appear in the list of tables. Selecting this option speeds up queries in large databases. JMP uses the sampling method supported by the database. The check box is unavailable when the database does not support sampling.

6. Select the desired table from the Tables list.

Note: If you are connected to a dBase database, select the database *folder* to which you would like to connect. Individual files are grayed out and cannot be selected.

7. Click **Open Table** to import all the data in the selected table, or click **Advanced** to specify a subset of the table to be imported. Some databases require that you enter the user ID and password to access the data.

You might see a short delay when opening large tables. To see the status of all active ODBC queries, select **View > Running Queries**.

Note: If the data were previously exported to a database in JMP and contained an Expression column, the column will be imported as a Character column. Select **Cols > Column Info** and change the Data Type to Expression.

Write SQL Statements to Query a Database

You can use Structured Query Language (SQL) statements to control what you import from a database. When you open a database file in JMP, you are actually sending a SQL statement to the database. By default, this statement gets all columns and records in the database table. In some cases, this is too much data. When you are interested only in a subset of the table’s data,

you can customize the SQL request to only request the data that you want. After you execute a SQL query, the code for the query is stored in the data table in the SQL table variable.

This section describes how to write SQL statements to retrieve data. To interactively query data without writing SQL statements, use Query Builder. You can also start creating a query in Query Builder and then add your own SQL. See [“Write SQL Statements in Query Builder”](#) on page 135 for details.

1. Select **File > Database > Open Table**.

The Database Open Table window appears (Figure 3.45).

2. Connect to the database if necessary or select an existing database connection. Follow the steps in [“Connect to a Database”](#) on page 136.

The Connections box lists data sources to which JMP is connected. The Schemas - Tables box lists schemas for those databases that support them.

Note: The SQL Query that you run in this window operates only on the tables and procedures that are displayed in the left panes of the window. Running unrelated SQL here has no results.


3. From the Database Open Table window, click the **Advanced** button to open specific subsets of a table.
4. Either type in a valid SQL statement, or modify the default statement. Figure shows a default SQL `Select` statement appropriate for the selected file. See [“Structured Query Language \(SQL\): A Reference”](#) on page 141, for a description of SQL statements that you can use.

Instead, you can add expressions by clicking the **Where** button and using the WHERE Clause editor to create expressions. See [“Use the WHERE Clause Editor”](#) on page 145, for details.

Figure 3.46 Reading All Variables from the Solubility Table Stored in an Excel File

List of tables that are accessible in the current database

List of columns that appear in the table.
Highlight another table name in the list on left to view its columns



5. Click **Execute SQL**. A JMP data table appears with the columns that you selected. (For details, see [“Use Table Variables”](#) on page 248 in the “Enter and Edit Data” chapter.)
6. To see the status of all running queries, select **View > Running Queries**.

Note that you can enter any valid SQL statement and click **Execute SQL** to execute the command. Valid SQL varies with the data source and ODBC driver.

Structured Query Language (SQL): A Reference

The following sections are a brief introduction to SQL. They give you insight to the power of queries, and they are not meant to be a comprehensive reference.

Use the SELECT Statement

The fundamental SQL statement in JMP is the SELECT statement. It tells the database which rows to fetch from the data source. When you completed the process in [“Write SQL Statements to Query a Database”](#) on page 139 with the Solubility.jmp sample data table, you were actually sending the following SQL statement to your data source:

```
SELECT * FROM "Solubility"
```

The * operator is an abbreviation for “all columns.” So, this statement sends a request to the database to return all columns from the specified data table.

Rather than returning all rows, you can replace the * with specific column names from the data table. In the case of the Solubility data table example, you could select the ETHER, OCTANOL, and CHLOROFORM columns only by submitting this statement:

```
SELECT ETHER, OCTANOL, CHLOROFORM FROM "Solubility"
```

Note: JMP does not require you to end SQL statements with a semicolon.

JMP provides a graphical way of constructing simple SELECT statements without typing actual SQL. To select certain columns from a data source, highlight them in the list of columns.

To highlight several rows

- Shift-click to select a range of column names
- Ctrl-click (Windows) or Command-click (Macintosh) to select individual column names.

Note that the SQL statement changes appropriately with your selections.

Sometimes, you are interested in fetching only unique records from the data source. That is, you want to eliminate duplicate records. To enable this, use the DISTINCT keyword.

```
SELECT DISTINCT ETHER, OCTANOL, CHLOROFORM FROM "Solubility"
```

Sort Results

You can have the results sorted by one or more fields of the database. Specify the variables to sort by using the ORDER BY command.

```
SELECT * FROM "Solubility" ORDER BY LABELS
```

selects all fields, with the resulting data table sorted by the LABELS variable. If you want to specify further variables to sort by, add them in a comma-separated list.

```
SELECT * FROM "Solubility" ORDER BY LABELS, ETHER, OCTANOL
```

Use the WHERE Statement

With the WHERE statement, you can fetch certain rows of a data table based on conditions. For example, you might want to select all rows where the column ETHER has values greater than 1.

```
SELECT * FROM "Solubility" WHERE ETHER > 1
```

The WHERE statement is placed after the FROM statement and can use any of the following logical operators.

Table 3.1 WHERE Operators

Operator	Meaning
=	Equal to
!= or <>	Not equal to
>	Greater than
<	Less Than
>=	Greater than or equal to
<=	Less than or equal to
NOT	Logical NOT
AND	Logical AND
OR	Logical OR

When evaluating conditions, NOT statements are processed for the entire statement first, followed by AND statements, and then OR statements. Therefore

```
SELECT * FROM "Solubility" WHERE ETHER > -2 OR OCTANOL < 1 AND CHLOROFORM > 0
```

is equivalent to

```
SELECT * FROM "Solubility" WHERE ETHER > -2 OR (OCTANOL < 1 AND CHLOROFORM > 0)
```

Use the IN and BETWEEN Statements

To specify a range of values to fetch, use the IN and BETWEEN statements in conjunction with WHERE. IN statements specify a list of values and BETWEEN lets you specify a range of values. For example,

```
SELECT * FROM "Solubility" WHERE LABELS IN ('Methanol', 'Ethanol', 'Propanol')
```

fetches all rows that have values of the LABELS column Methanol, Ethanol, or Propanol.

```
SELECT * FROM "Solubility" WHERE ETHER BETWEEN 0 AND 2
```

fetches all rows that have ETHER values between 0 and 2.

Use the LIKE Statement

With the LIKE statement, you can select values similar to a given string. Use % to represent a string of characters that can take on any value. For example, you might want to select

chemicals out of the Solubility data that are alcohols, that is, have the OL ending. The following SQL statement accomplishes this task.

```
SELECT * FROM "Solubility" WHERE LABELS LIKE '%OL'
```

The % operator can be placed anywhere in the LIKE statement. The following example extracts all rows that have labels starting with M and ending in OL:

```
SELECT * FROM "Solubility" WHERE LABELS LIKE 'M%OL'
```

Use Aggregate Functions

Aggregate functions are used to fetch summaries of data rather than the data itself. Use any of the following aggregate functions in a SELECT statement.

Table 3.2 SELECT Statement Functions

Function	Meaning
SUM()	Sum of the column
AVG()	Average of the column
MAX()	Maximum of the column
MIN()	Minimum of the column
COUNT()	Number of rows in the column

Some examples include:

- The following statement requests the sum of the ETHER and OCTANOL columns:
SELECT SUM(ETHER), SUM(OCTANOL) FROM "Solubility"
- This statement returns the number of rows that have ETHER values greater than one:
SELECT COUNT(*) FROM "Solubility" WHERE ETHER > 1
- The following statement lets you know the average OCTANOL value for the data that are alcohols:
SELECT AVG(OCTANOL) FROM "Solubility" WHERE LABELS LIKE '%OL'

Note: When using aggregate functions, the column names in the resulting JMP data table are Expr1000, Expr1001, and so on. You probably want to rename them after the fetch is completed.

The GROUP BY and HAVING Commands

The GROUP BY and HAVING commands are especially useful with the aggregate functions. They enable you to execute the aggregate function multiple times based on the value of a field in the data set.

For example, you might want to count the number of records in the data table that have ETHER=0, ETHER=1, and so on, for each value of ETHER.

- `SELECT COUNT(ETHER) FROM "Solubility" GROUP BY (ETHER)` returns a single column of data, with each entry corresponding to one level of ETHER.
- `SELECT COUNT(ETHER) FROM "Solubility" WHERE OCTANOL > 0 GROUP BY (ETHER)` does the same thing as the above statement, but only for rows where OCTANOL > 0.

When using GROUP BY with an aggregate function of a column, include the column itself in the SELECT statement. For example,

```
SELECT ETHER, COUNT(ETHER) FROM "Solubility" GROUP BY (ETHER)
```

returns a column containing the levels of ETHER in addition to the counts.

Use Subqueries

Aggregate functions are also useful for computing values to use in a WHERE statement. For example, you might want to fetch all values that have greater-than-average values of ETHER. In other words, you want to find the average value of ETHER, and then select only those records that have values greater than this average. Remember that `SELECT AVG(ETHER) FROM "Solubility"` fetches the average that you are interested in. So, the appropriate SQL command uses this statement in the WHERE conditional:

```
SELECT * FROM "Solubility" WHERE ETHER > (SELECT AVG(ETHER) FROM "Solubility")
```

Save and Load SQL Queries

After constructing a query, you might want to repeat the query at a later time. You do not have to hand-type the query each time you want to use it. Instead, you can export the query to an external file. To do this, click the **Export SQL** button in the window shown in Figure 3.46. This brings up a window that lets you save your SQL query as a text file.

To load a saved query, click the **Import SQL** button in the window shown in Figure 3.46. This brings up a window that lets you navigate to your saved query. When you open the query, it is loaded into the window.

Use the WHERE Clause Editor

JMP provides help building WHERE clauses for SQL queries during ODBC import. It provides a WHERE clause editor that helps you build basic expressions using common SQL features,

allowing vendor-specific functions. For example, you do not need to know whether SQL uses '=' or '==' for comparison, or avg() or average() for averaging.

In addition, string literals should be enclosed by single quotes ('string') rather than double quotes ("string").

To open the WHERE clause editor

1. Connect to a database by following the steps in [“Connect to a Database”](#) on page 136.
2. From the **Database Open Table** window, click the **Advanced** button.
3. Click the **Where** button.

USE the WHERE Clause Editor to add any of the following from the work panel: expressions, functions, and terms. They are applied to the highlighted blue box.

1. Click the Table Name Browser to select a table. The columns in that table appear in the list.
2. Click the SQL Vendor Name Browser to select the type of SQL that you want to use: GenericSQL, Access, DB2, MySQL, Oracle, SQL Server, or all of the above. Perform an action by clicking a function or operator in the list and selecting an operator from the list that appears.

Note: The following SQL Server data types are not supported: Binary, Geography, and Geometry.

3. Select an empty formula element in the formula editing area by clicking it. It is selected when there is a red outline around it. All terms within the smallest nesting box relative to the place that you clicked become selected. The subsequent actions apply to those combined elements.
4. Add operators to an expression by clicking buttons on the keypad.
5. (Optional) To customize your WHERE clause, select one of the options from the red triangle menu in the formula editor:

Show Boxing Show or hide boxes around the WHERE clause terms.


Larger Font Increase the font size of the formula.

Smaller Font Decrease the font size of the formula.

Simplify Simply the WHERE clause statement as much as possible.

Reset panel layout Display the panels as shown in Figure 3.47.

The WHERE clause editor works similarly to the Formula Editor, which is described in the [“Formula Editor”](#) chapter on page 349.

Figure 3.47 The WHERE Clause Editor

Import Text Files

You can open text files with the extensions .txt, .csv, and .tsv, and the text is converted to a data table. Files with the .dat extension that consist of text are also supported. Text files can be delimited using almost any character, or they can be fixed-width files.

Trailing whitespace is removed when you import text files into JMP.

When JMP finds an integer in the text file that is greater than 9,007,199,254,740,991, the column is considered character data. You can set the column to numeric using the Text Import Wizard window or an import script.

Tip: You can import more than one text file at a time using the Multiple File Import option. See [“Import Multiple Files”](#) on page 156 for details.

To adjust import settings, choose from one of the following options

- Select **File > Preferences > Text Data Files** to change the import settings so that JMP determines the best way to structure and format the data table.
- Manually select the import settings as you open the file (described in this section).
- Open the file in the Script Editor, edit the content, and then import the content. This option is helpful when you need to add text delimiters or modify the text.

To import a text file

- 1. Select **File > Open**.
- 2. On Windows, you can set the file type to **Text Files**.
- 3. Select the text file that you want to open.
For information about the options, see Table 3.3 and Table 3.4.

Table 3.3 Opening Text Files on Windows

Automatically Determining Data Arrangement	Manually Specifying Data Arrangement
1. Select File > Open. 2. From the list next to File name, select Text Files. 3. To use the import rules from the preferences, select Data, using Text Import preferences. (See “Text Data Files” on page 601 in the “JMP Preferences” chapter.) To have text import use its best guess to arrange the data, select the Data, using best guess option. (Optional) Select the Select this filter the next time this dialog is invoked option to apply the filter that you chose by default. 4. Select the file that you want to open. 5. Click Open. Tip: The JMP Home window provides a shortcut to the above steps if you recently opened the file. Right-click the file in the Recent Files list and select Import (Preferences) or Import (Best Guess). (Your import preference is bolded in the right-click menu.)	1. Select File > Open. 2. From the list next to File name, select Text Files. 3. Select Data with Preview next to Open at the bottom of the window. 4. Select the file that you want to open. 5. Click Open. 6. Complete the Text Import window. See “Text Import Wizard Options” on page 149, for details. 7. Click Import. Tip: The JMP Home window provides a shortcut to the above steps if you recently opened the file. Right-click the file in the Recent Files list and select Import (Preview).

Table 3.4 Opening Text Files on Macintosh

Automatically Determining Data Arrangement	Manually Specifying Data Arrangement
1. Select File > Open. 2. Select the file that you want to open. 3. From the Open As field, select Data (Best Guess) or Data (Using Preferences). 4. Click Open.	1. Select File > Open. 2. Select the file that you want to open. From the Open As field, select Data (Using Preview). 3. Click Open. 4. Complete the Text Import Wizard window. See “Text Import Wizard Options” on page 149, for details. 5. Click Import.

Notes:

- On Windows, JMP can open text files in your computer’s default text editor. Select **File > Open**, and then select **All Files (*.*)** from the **File name** list. Select the text file, and then select **Use default program to open. Uncheck to open as text**.
- If you cancel the import while JMP is scanning the data, data is imported based on what JMP detected. The data might not appear as you expect. For example, you might see missing values in a column that was incorrectly detected as numeric. If you cancel the import *after* the data is scanned, only the data read up to that point is imported.

For details about importing text from a Script window, see [“Import Text from the Script Editor”](#) on page 155.

Text Import Wizard Options

When you open a text file that JMP supports, JMP can show a preview of the text before opening the file as a data table. This option lets you manually arrange and format the data. For example, you can specify the end-of-line character or strip quotation marks.

JMP detects the file’s structure and shows options for importing text with either delimiters or fixed width fields. If JMP chooses the wrong file structure, click the **Delimited fields** or **Fixed width fields** radio button to import the data as the correct format. (For example, the fixed width window might appear when your file is actually delimited.)

The text import wizard options are shown in Figure 3.48 and Figure 3.49.

Figure 3.48 Text Import Wizard for Fixed Width Files

1 139

```
FOX 1 0 fall
FOX 1 0 winter
FOX 1 5 spring
FOX 1 3 summer
FOX 2 3 fall
FOX 2 1 winter
FOX 2 5 spring
FOX 2 4 summer
FOX 3 4 fall
FOX 3 3 winter
```

☐ Delimited fields
☒ Fixed width fields

Charset
Best Guess

Fixed data format: click to create additional column dividers. Drag the dividers to the proper position. Drag a divider on top of another divider to delete it. The numbers at the top are the column positions and the column widths. The next step sets the column names and types.

☐ File contains column names on line: 1

Data starts on line: 1

Subset

☒ All
☐ lines from start of file
☐ lines from end of file
☐ random lines in file
☐ probability per line (0.0 to 1.0)

Compatibility

☐ Strip enclosing quotation marks Two-digit year rule: 2000-2099

☐ Recognize apostrophe as quotation mark (not recommended)

☐ Use Regional Settings

Back Next Import Cancel Help

Figure 3.49 Text Import Wizard for Delimited Files

Name	Age	Sex	Height	Weight
KATIE	12	F	59	95
LOUISE	12	F	61	123
JANE	12	F	55	74
JACLYN	12	F	66	145
LILLIE	12	F	52	64
TIM	12	M	60	84
JAMES	12	M	61	128
ROBERT	12	M	51	79
BARBARA	13	F	60	112
ALICE	13	F	61	107

☒ Delimited fields
☐ Fixed width fields

Charset: Best Guess

End Of Field:
☒ Tab
☐ Space
☐ Spaces
☐ Comma
☐ Other

End Of Line:
☒ <CR> + <LF>
☒ <CR>
☒ <LF>
☐ Semicolon
☐ Other

☐ File contains column names on line: 1
Data starts on line: 1

Subset
☒ All
☐ lines from start of file
☐ lines from end of file
☐ random lines in file
☐ probability per line (0.0 to 1.0)

Compatibility
☒ Strip enclosing quotation marks
Two-digit year rule: 2000-2099
☒ Recognize apostrophe as quotation mark (not recommended)
☒ Use Regional Settings

Back Next Import Cancel Help

Charset Select the character set used in the imported file, or let JMP detect the character set. If incorrect characters are displayed in the imported file, open the file again and select another character set.

End of Field (Available only in the Delimited Import window) Select the check boxes beside the character that marks the end of a field. Alternatively, select the check box beside **Other** and enter a character if the appropriate character is not listed.

End of Line (Available only in the Delimited Import window) Select the check boxes beside the character that marks the end of a line (row). Alternatively, select the check box beside **Other** and enter a character if the appropriate character is not listed. Note that when JMP finds double quotation marks, the delimiter rules change to look for an end double quotation mark. Other text delimiters, including spaces embedded within the quotes, are ignored and treated as part of the text string.

File contains column names on line Tell JMP where to find data to use as column names. For example, if the column names in your text file are on line (row) 3, select this option and type 3 in the check box. Otherwise, JMP uses the data in the first line of the imported file as the column name in the JMP data table or takes the first line as data.

Data starts on line Specify the number of the first line that contains data.

Number of Lines Specify the number of lines (rows) that you want to import.

Strip enclosing quotation marks Available only on fixed-width imports. Select this check box when you want JMP to remove quotation marks that enclose data in the text file.

Two-digit year rule Specify how to display dates that have two-digit years. Select the 100-year range in which your dates fall. For example, if the earliest date is 2/2/79, and the year is 1979, select **1970-2069**. If the earliest date is 2/2/12, and the year is 2012, select **2000-2099**. If dates span centuries, you must recode the dates with four-digit years before importing the data.

Recognize apostrophe as quotation mark (not recommended) (Available only in the Delimited Import window). Use this option only if your data comes from a nonstandard source that places apostrophes around data fields rather than quotation marks.


Use Regional Settings Specifies whether the operating system's regional settings are used when importing a text file. If the option is deselected (the default setting), files that use a period for a decimal point and a comma for the value separator import correctly. You must specify the value separator in the Text Data Files import preferences.

If the file uses a comma for a decimal point, you must also set the following options: the OS regional settings must use a comma for a decimal point (Windows and Macintosh), or the Windows Specific Display Language preference must be set to a language that uses commas for decimal points.

When you are finished selecting the settings, click **Next**. The next window shows each column's modeling type. To change the default modeling types, do one of the following:

- Click on the data type icon to change the data type from numeric () to character (). Clicking the icon cycles between the modeling type and exclude (). Exclude means that the column is not imported.
- To change a numeric column's data format, select the format from the red triangle menu.
- Click on the column heading to modify the text.

The top of the text import window shows a preview of the text file as it appears when imported into a JMP data file. Click the **Import** button to import the data.

Figure 3.50 Text Import Wizard Window with Column Options

6. When you are finished, click **Import** to complete the text import.

Tip: To automatically import numeric data into numeric columns, use the Multiple File Import option. Select **File > Multiple File Import**, click **CSV Settings**, and make sure that Make Numeric Columns from Numeric Data is selected. See [“Import Multiple Files”](#) on page 156 for details.

Open a Text File in a Text Editing Window

You can open a text file in a Script window, where you edit the text. Then you can import the text as a data table. This feature is helpful when you want to reformat the text before importing it as a data table. For example, you might need to insert the correct delimiters or modify the text.

Another option is opening a JMP add-in definition (.def) file as text and then editing it in a Script window.


To open a text file in a text editing window (Windows)

Files that you recently opened are listed in the JMP Home window. For most files, right-click the text file and select **Open as Plain Text** to open the file in a text editing window. JMP add-in definition files cannot be opened as plain text from the JMP Home window.

When you are opening the file for the first time, follow these steps:

1. Select **File > Open**.
2. Do one of the following:

- To open a JMP add-in definition file as text, select **All JMP Files** or **JMP Add-In Files** from the list next to **File name**. Click the **Open** button arrow, and then select **Open as Plain Text**. The file opens in a Script window. Skip the remaining steps.
- To open other text files, select **Text Files** from the list next to **File name**.

Figure 3.51 Select Text Files



3. (Optional) To set the default option file type to **Text Files**, select the check box beside **Select this filter the next time this dialog is invoked**.
4. Select the file.
5. Select **Plain text into Script window** next to **Open as**.
6. Click **Open**.

The text appears in a Script window.

To open a text file in a text editing window (Macintosh)

1. Select **File > Open**.

Figure 3.52 Opening a Text Document on the Macintosh



2. Select the file.
3. Click **Options**.
4. Select **Text** from the **Open As** list.
5. Click **Open**.

The text appears in a Script window.

For details about converting the text to a data table, follow step 3 in [“Import Text from the Script Editor”](#) on page 155.

Import Text from the Script Editor

You can import text from the Script Editor as a data table. The text can be in a table format (for example, from a Microsoft Word document or Web page) or in plain text format. This feature is helpful when you want to reformat the text before importing it as a data table. For example, you might need to insert the correct delimiters or modify the text.

JMP uses the import settings in the preferences to determine how to structure and format the text. Some options include removing quotation marks around text and specifying the rows

that contain column headings and data. See [“Text Data Files”](#) on page 601 in the “JMP Preferences” chapter for details.

Note: You can also import an entire web page as a data table. See [“Import Data from the Internet or a Remote Computer”](#) on page 161 for details.

This section describes how to import text that you paste into the Script Editor. For details about opening a text file in the Script Editor, see [“Open a Text File in a Text Editing Window”](#) on page 153.

To import text from the Script window

1. Open a new Script window in JMP by selecting **File > New > Script** (Windows) or **File > New > New Script** (Macintosh).
2. Copy and paste the text into the Script Editor.
3. Do one of the following:
 - To import all text from the Script Editor, select **File > Import as Data** (Windows) or **Edit > Import as Data** (Macintosh).
 - To import specific text, select the text, and then select **File > Import as Data** (Windows) or **Edit > Import as Data** (Macintosh).

The text is imported into a JMP data table.

Note: To preview text that you import from the Script Editor, hold down the Shift key before you select File > Import as Data.

Import Multiple Files

Multiple File Import (MFI) is designed to import CSV data and unstructured text files from one directory and stack them in a data table (or to import them in separate data tables). You can save the import settings as a script and then run the script when the data is updated in the future.

Multiple File Import supports the following file types:

- XLSX
- CSV
- TSV
- DAT
- TXT

- SAS7BDAT
- JMP
- JSON
- PNG
- JPG
- GIF

Multiple File Import can also import only one file. Table 3.5 can help you decide whether to use the standard Text Import, Multiple File Import, or JSL.

Table 3.5 Importing One File or Multiple Files

Import Characteristics	One File	Multiple Files
CSV, TSV, DAT	Text Import has a preview wizard to help name the columns, pick date formats, and subset the data.	MFI can stack similar files automatically. You can change formatting later.
Unstructured text	MFI, possibly in JSL with <code>Load Text File()</code> .	MFI
Large files over 100MB	You can use the Source script from a previous Text Import to speed up the next import.	MFI imports in parallel and might be much faster than Text Import.
Unsure about format	Text Import might be able to guess. The preview wizard lets you see the results before the text is imported.	MFI does not guess. You specify the tab delimiters. There is no preview, but select Keep dialog open , and it is easy to try different import settings.
Pictures	Try the JSL <code>Open()</code> function.	MFI understands PNG, JPG, and GIF files. You'll get a table with a picture column.

Table 3.5 Importing One File or Multiple Files *(Continued)*

Import Characteristics	One File	Multiple Files
JMP, XLSX, and JSON	Try the JSL <code>Open()</code> function.	MFI opens JMP, XLSX, and JSON files using JSL <code>Open()</code> and will stack them if requested. MFI does not keep the table and column scripts when it opens JMP tables, so you might need to use <code>Files In Directory()</code> and <code>Open()</code> if you need all of those scripts.

To import multiple files, follow these steps:


1. Place the files that you want to import in the same directory.
This example uses import data found in the JMP Samples/Import Data folder.
2. Select **File > Import Multiple Files** (Windows) or **File > Open Multiple** (Macintosh).
3. Browse to select the JMP Samples/Import Data folder.
4. In the **Select Files by name or extension** box, type `UN*.csv` and press Enter.

In this example, the files have the UN prefix and are CSV files.

The Files list updates to show which files have been selected.

Specify multiple file names and extensions by separating them with semicolons, or click **Add Extension** and select an extension.

Figure 3.53 Selected CSV Files



Notice that the Refresh button  flashes if the files have changed in the directory since the last refresh.

- (Optional) In the **Select files by size** box, type the lower and upper file size limits. Consider specifying the limits if you don't want to import large files over a certain limit.

Note: Specify file sizes in kB (or kilobits). One kB equals 1,000 bytes.

- (Optional) In the **Select files by date and time** box, click the calendar button  to specify the date and time range of the files that you want to import.
- Specify the columns that you want added to the data table.

By default, no extra columns are added. You might like a File Name column to show the names of the imported files.

8. (Unstructured text files) Select **Text, Whole File on One Row** or **Text, One Line Per Row** based on how the file is structured.

Notes:

- These two options are not supported for XLSX, JSON, and JMP files.
 - When you select Text, Whole File on One Row, the import includes the whole file and does not skip lines before the first data line.
9. (CSV files) Select **Data, Using CSV Settings** to import a comma-delimited file.

Note: The Text Data Files preferences do not determine which options are selected in the CSV settings, although the settings are similar.

10. Keep **Stack Similar Files** selected because these CSV files have the same columns.
11. Click **Import**.

JMP applies the file name, file size, and file date and time filters to stack the files. Data with columns that contain the same column headings are imported in the same data table. If the columns do not match, the mismatched columns are imported into a separate data table.

Figure 3.54 Imported CSV Data

UN Malaria 2009_UN ...		Country or Area	Year	Number of Incidents	File Name
		1 Afghanistan	2009	64880	UN Malaria 2009.csv
		2 Algeria	2009	4	UN Malaria 2009.csv
		3 Angola	2009	1573422	UN Malaria 2009.csv
		4 Argentina	2009	86	UN Malaria 2009.csv
		5 Azerbaijan	2009	78	UN Malaria 2009.csv
		6 Bangladesh	2009	63873	UN Malaria 2009.csv
		7 Belize	2009	256	UN Malaria 2009.csv
		8 Benin	2009	889597	UN Malaria 2009.csv
		9 Bhutan	2009	972	UN Malaria 2009.csv
		10 Bolivia ...	2009	9743	UN Malaria 2009.csv
		11 Botswana	2009	1024	UN Malaria 2009.csv
		12 Brazil	2009	309316	UN Malaria 2009.csv
		13 Burkina ...	2009	182527	UN Malaria 2009.csv
		14 Burundi	2009	1185622	UN Malaria 2009.csv
		15 Cabo Verde	2009	65	UN Malaria 2009.csv
		16 Cambodia	2009	64595	UN Malaria 2009.csv
		17 Cameroon	2009	0	UN Malaria 2009.csv
		18 China	2009	9287	UN Malaria 2009.csv

Columns (4/0)	
Country or Area	
Year	
Number of Incidents	
File Name	

Rows	
All rows	374
Selected	0
Excluded	0
Hidden	0
Labelled	0

Note: JMP creates a data table that lists the files that could not be imported (for example, SAS datasets).

Importing Structured Data with Different Quoting

Sometimes export filters place something other than quotation marks around fields. You specify the delimiter in the CSV settings.

Text in a CSV file might contain escape sequences such as a backlash instead of doubling the quotation mark. You also specify the delimiter in the CSV settings.

Tips:

- **Keep dialog open** is off by default, but you might turn it on while testing. This enables you to import files to see what the data looks like, edit the source files if necessary, and reimport them with the same settings.
- When you import files that are not supported, a data table called “@ Unused Files” is created. The file names are listed in the Files table script. Right-click the script and select Edit. To output the file names of unsupported files in this data table, select **Add file name column** on the Multiple File Import window.
- Right-click the Files list and select Sort by Column to change the way the Files list is sorted.
- The Import button is unavailable if no files match the filters that you selected.
- JMP automatically changes the CSV settings when you select either of the two options for Text Explorer-style data (the bottom center radio buttons). A delimiter is not specified, which loads all data in one column. JMP also changes the CSV settings to not use an end-of-line character, which loads the entire file in one row. You can also change the CSV settings. If you try the manual approach, be sure to set No Headers and First Data Line to 1.

Import Data from the Internet or a Remote Computer

Import data from the Internet, FTP sites, or other computers by selecting **File > Internet Open**. A file path can start with *http*, *ftp*, or *file*; a drive letter; or, the path to a network drive (relative or absolute).

Using Internet Open, you can import data and images from the Internet or a remote computer and save it as a data table, web page, or text. You can also open a SAS stored process report using this option.

Suppose that you want to import data (with images) from a table on a web page and save it as a data table. The specific web page lists countries by population.

1. Select **File > Internet Open**.
2. Enter the following URL:
https://en.wikipedia.org/wiki/List_of_countries_and_dependencies_by_population.
3. Click **OK**.

4. Keep **Open As** set to **Data**, and click **OK** again.
JMP finds several tables on the specified page.
5. Click **Rank country (or dependent territory)...** and click **OK**.
JMP opens a data table that contains the information from the web page table.
6. (Optional) To add the images to the data table, run the *Load pictures* script.

Notes:

- You can open a remote file as one of the following formats:

Data Opens the file as a data table.

Web page Opens the web page in the JMP browser (Windows) or the default browser (Macintosh).

From the File menu on Windows, you can then choose to save the file or import the data as a data table. Select this option to import data that is generated by web page scripts and server-side requests.

Text Opens the file in the script editor. If you imported an HTML file, the HTML tags of a web page are displayed.

- When you open a file from an FTP server, an FTP login window appears. For an anonymous account, click **OK**. For an authenticated login, enter your user ID and password. The file then opens as you specified.

Note: Some anonymous FTP servers require a user ID. If the data table does not open, try typing either 'ftp' or 'anonymous' in the User ID text box. Leave the Password text box empty and click **OK**.

- JMP waits 60 seconds before stopping the import due to an error. You can change the Internet Time Out setting on the General preferences page.
- If the table that you are importing contains images, the images are first imported as text. To display the images in your data table, run the automatically generated table script named *Load pictures*. A new expression column that contains the images is added to the data table.
- Running the Source script in a data table enables you to re-import and refresh the data.

To open a SAS stored process report as a data table (Windows only)

1. Select **File > Internet Open** and select the file.
The file opens in the JMP browser.
2. In the JMP browser, select **File > Import Table as Data Table**.
A window appears that lists the tables found in the web page.

3. Select the table or tables that you want to import.
4. Click **OK**.

Each table is opened as a new data table.

See [“Run Stored Processes”](#) on page 108 for more information about stored process reports.

Import SPSS Files

JMP opens SPSS files as data tables and maintains several SPSS features:

- General numeric and character data with minimal formatting are supported.
- SPSS date, datetime, and time formats are supported.
- By default, labels are converted to column headings. When you select this option, and the data contains no labels, the columns are named *Column 1*, *Column 2*, and so on.

You also have the option of selecting the conversion method for column headings when opening an SPSS file. The method that you select then overrides the preferences.

To change the default conversion method, select **File > Preferences** (or **JMP > Preferences** on Macintosh). On the General page, deselect **Use SPSS labels for column names during import**. Variable names are then imported automatically as column headings.

- The value labels that you defined in the SPSS file are saved as Value Labels column properties. The value label then appears in each data table cell instead of the original value. For details about Value Label properties, see [“Value Labels”](#) on page 272 in the “The Column Info Window” chapter.
- SPSS can assign certain values in a variable to be treated as missing for analyses. For example, the value 64 could be regarded as missing for a Height variable. Then, the calculation of the distribution of height would ignore values of 64. When you import SPSS into JMP, these values are included in the Missing Value Codes column property for the appropriate variable.

Missing value ranges of up to 20 numbers are supported. If the range begins with a negative number, the numbers count down to the maximum value (for example, -10 through -5). If the range begins with a positive number, the numbers count up from the minimum value (for example, 1 through 12).

Custom currency formats selected in an SPSS file are not maintained on import. In addition, JMP does not read SPSS data that contains double-byte characters, such as non-Unicode Japanese characters.

Note: As with importing other files, you might experience a delay when opening and saving large SPSS files.

To open an SPSS file (Windows)

1. Select **File > Open**.
2. From the list next to **File name**, select **SPSS Data Files (*.sav)**.
3. Select the SPSS file.
4. (Optional) To specify the column headings, select one of the following **Set JMP column names from** options:
 - **SPSS Labels** creates column headings from SPSS labels.
 - **SPSS Variable Names** creates column headings from variable names.
5. Click **Open**.

JMP opens the file as a data table.

To open an SPSS file (Macintosh)

1. Select **File > Open**.
2. Select the SPSS file.
3. (Optional) To specify the column headings, do one of the following
 - Deselect **Use SPSS Labels as Headings** to convert variable names to column headings.
 - Select **Use SPSS Labels as Headings** to convert labels to column headings.
4. Click **Open**.

JMP opens the file as a data table.

Import Triple-S Survey Data

Triple-S (SSS) is a specification for survey data. The survey data is stored in a pair of files: .xml or .sss, and a .csv, .dat, or .asc file. The .xml or .sss file defines the variables and describes the survey. The accompanying .csv, .dat, or .asc file contains the data gathered from each respondent.

Variable labels are converted to column headings by default. To convert variable names to column headings, deselect **Use Triple-S Labels as Headings** in the JMP General preferences.

To import a Triple-S file, follow these steps:

1. Place the pair of Triple-S files in the same folder and use the same root name for both files.
2. Select **File > Open**.
3. On Windows, select **Triple-S Survey Files** from the File name list.
4. Select the SPSS file.

5. (Optional on Windows) To override the Triple-S column heading preference, select Variable Labels or Variable Names next to **Set JMP column names from:**.
6. Click **Open**.
JMP opens the file as a data table.

Import HDF5 Data

Hierarchical Data Format, Version 5 (HDF5) is a portable file format for storing data. An HDF5 file consists of groups and datasets. When you import the file, JMP opens a group to present the names of the inner datasets. For example, if the file contains data for a group of musical recordings with songs and artists tables, JMP prompts you to open either “songs” or “artists”. If the file does not contain a group, JMP prompts you to open a single table.

JMP handles only tables with numeric (integer, float, double) and string types, and compound files with three or fewer dimensions that contain only simple types. If a data set does not appear in the import window, the file is most likely unsupported.

You can import up to 1,000,000 columns and an unbounded number of rows.

Note: Only ASCII characters are supported in HDF5 files. Non-ASCII characters such as French and Chinese characters are not supported.

To import an HDF5 file, follow these steps:

1. Select **File > Open**.
2. On Windows, make sure that **All JMP Files** or **HDF5 Data File** is selected from the File name list.
3. Select the HDF5 file.
A list of groups or datasets in the file appears.
4. Select the data set that you want to import and click **Import**.
The data are opened as data tables.

Import JSON Files

A JSON file consists of name and value pairs that are imported as column headings and data. In the following example, the first name in each string is appended to “Grocery Store Purchases” and turned into column headings, as in “Grocery Store Purchases.Item”. “avocado” is the value in the first cell of the table. The next column is named “Grocery Store Purchases.Category”, and “Produce” is the value in the first cell of the second column.

```
{"Grocery Store Purchases":[  
  {"Item":"avocado", "Category":"Produce"},  
  {"Item":"bread", "Category":"Bakery"},  
  {"Item":"chocolate", "Category":"candy"}  
]}
```

To open a JSON file in JMP, select **File > Open**, select the file, and then click **Open**. On Windows, make sure that JSON Data File is selected in the Filename list on the Open Data File window.

Notes:

- The JSON file does not contain date, time, currency, geographic, percent, and scientific information to determine the column format. After you import the file into JMP, right-click the numeric column, select **Column Properties**, and change the Format.
- The available memory on your computer determines the maximum number of columns rows that can be imported. The limit also depends on the other programs that are running at the time of import.
- Member names in name-value pairs are case insensitive.
- For nested items, JMP repeats the outer item for each row.
- The file cannot have an empty array element. The name must be quoted before the colon in the name-value pair.
- The locale is ignored when you export data to JSON format. The JSON standard accepts decimal numbers with decimal points.

Import Data from MATLAB

JMP provides a scripting interface to MATLAB. See the Extending JMP chapter in the *Scripting Guide* and the Functions chapter in the *JSL Syntax Reference*.

Import Data from R

JMP provides a scripting interface to R. See the Extending JMP chapter in the *Scripting Guide* and the Functions chapter in the *JSL Syntax Reference* for details.

Import Data Using the Excel Add-In

The add-in for Excel provides new capabilities to JMP and Excel users on Windows:

- Transfer selected cells in Excel to JMP data tables. See [“Transfer Excel Data to a JMP Data Table”](#) on page 167.
- Use the JMP Profiler with calculation models in Excel workbooks. The profiler tool is designed to bring the power of the JMP profiler to models residing in Excel worksheets. You do not have to recreate your Excel models in JMP, verify that they are correct, and maintain the model in both JMP and Excel. For more information, see the Excel Profiler chapter in the *Profilers* book.

Note: During the JMP installation, select the Excel Add-In. This installs the add-in for your version of Microsoft Excel.

- Microsoft Excel 2010, Microsoft Excel 2013, and Microsoft 2016 are supported.

Transfer Excel Data to a JMP Data Table

You can use the JMP Add In for Excel to transfer a worksheet from Excel to the following JMP destinations:

- a data table
- Graph Builder
- Distribution platform
- Fit Y by X platform
- Fit Model platform
- Time Series platform
- Control Chart platform

You can also create models for profiling in JMP. See the Excel Profiler chapter in the *Profilers* book.

To transfer data from Excel to a JMP data table and platform

1. In your Excel worksheet, show the **JMP** add-in on the ribbon.
2. Click the **Preferences** button.
3. Accept the default **Data Table Name** (File name_Worksheet name) or type a name.
4. Select **Use the first rows as column names** if the first row in the worksheet contains column headers.
5. If you selected to use the first rows a column headers, type the number of rows used.

6. Select **Transfer Hidden Rows** if the worksheet contains hidden rows to be included in the JMP data table.
7. Select **Transfer Hidden Columns** if the worksheet contains hidden columns to be included in the JMP data table.
8. Click **OK** to save your preferences.
9. Select the cells to transfer into JMP, including any cells that you want to use as column names.

If you are using cells as column names, they need to be the first rows in your selection.

If only one cell (or no cell) is selected, the entire Excel worksheet is transferred to JMP.

10. Select the JMP destination from the toolbar:

- Data Table
- Graph Builder
- Distribution platform
- Fit Y by X platform
- Fit Model platform
- Time Series platform
- Control Chart platform

JMP opens, and the selected data is placed in a new JMP data table and the selected launch window appears.

Note: Empty cells are imported as missing data, and dates, numbers, and strings are recognized correctly.

Note: Your JMP windows might be hidden behind your Excel window, especially if you maximize Excel.

For more information about using the various JMP platforms refer to the proper book.

About the JMP Add-In for Excel

The JMP add-in commands are in two groups:

Transfer to JMP

Preferences Set preferences for transferring data from Excel to JMP.

Data Table Transfer the selected data in your Excel file to a JMP data table.

Graph Builder Transfer the selected data in your Excel file to a JMP data table and launch the Graph Builder platform.

Distribution Transfer the selected data in your Excel file to a JMP data table and launch the Distribution platform.

Fit Y By X Transfer the selected data in your Excel file to a JMP data table and launch the Fit Y by X platform.

Fit Model Transfer the selected data in your Excel file to a JMP data table and launch the Fit Model platform.

Time Series Transfer the selected data in your Excel file to a JMP data table and launch the Time Series platform.

Control Chart Transfer the selected data in your Excel file to a JMP data table and launch the Control Chart platform.

Profile in JMP

Create/Edit Model Set up preferences for using the JMP profiler with Excel data.

Run Model Run the JMP profiler.

Uninstall the Excel Add-In

To uninstall the Excel Add-in, double-click the JMP installer, click **Modify**, and deselect **Excel Add-In**.

Create New Data Tables

To create a new data table by entering data manually, follow these steps:

1. Select **File > New > Data Table**. This shows an empty data table with no rows and one numeric column, labeled Column 1.
2. Move the cursor onto a cell.
3. Click in the cell. The cursor appears as a line in the cell, as shown in Figure 3.55.

Chapter 4

Enter and Edit Data Perform Basic Data Table Tasks


After you import data into JMP or create a new data table, you can format your data to prepare it for analysis.

This chapter contains the following information:

- Change formatting for numeric values
- Add, delete, and select rows and columns
- Use the Row Editor to navigate within rows and edit rows
- Create scripts that are saved to the data table

Figure 4.1 The Rows and Cols Menus

Enter and edit data using the options in the Rows and Cols menus.



Contents

Enter Data.....	174
Copy and Paste Data.....	174
Add Rows.....	175
Add Columns.....	175
Fill Columns with Sequential Data.....	177
Replace Missing Values with Previous Values.....	178
Enter Cell Formulas.....	179
Select Rows.....	180
Locate Next and Previously Selected Rows.....	182
Select Columns.....	183
Select Columns in a Data Table.....	184
Select Columns in the Columns Viewer.....	185
Locate Next and Previously Selected Columns.....	190
Select Cells.....	190
Resize Rows and Columns.....	192
Organize Data.....	192
Delete Rows and Columns.....	193
Rearrange Columns.....	193
Group Columns.....	194
Move Values.....	195
Color Cells.....	196
Edit or Delete Cells.....	196
Edit Column Names.....	196
Hide and Exclude Rows.....	196
Exclude Rows.....	197
Hide Rows.....	198
Exclude Columns.....	199
Hide Columns.....	200
View Patterns of Missing Data.....	200
Find and Replace Cell Values.....	202
Use the Row Editor to Edit Cells in a Row.....	204
Pop-Up Menus for Rows and Columns.....	206
Compare Data Tables.....	206
Assign Characteristics to Rows and Columns.....	210
How to Find Rows and Columns Options.....	211
Label Rows and Columns.....	211
Assign Colors or Markers to Rows.....	212
Create Color Themes.....	214
Delete Custom Color Themes.....	219

Select Matching Row State Cells	219
Delete Row Characteristics	220
Lock Columns in Place	220
Restructure Data	220
Make a Column into Multiple Columns	220
Make Indicator Columns	221
Combine Columns	221
Compress Selected Columns	222
Make Binning Formula	224
Convert Labels to Codes and Codes to Labels	226
Make a New Formula Column	227
Transform Columns	227
Recode Data	237
Edit the Data Table	246
Change Table Names	246
Lock Tables	246
Compress Tables	247
Use Table Variables	248
Create and Save Scripts	249

Enter Data

This section describes how to add rows and columns, fill columns with sequential data, and enter cell formulas.

- [“Copy and Paste Data”](#)
- [“Add Rows”](#)
- [“Add Columns”](#)
- [“Fill Columns with Sequential Data”](#)
- [“Replace Missing Values with Previous Values”](#)
- [“Enter Cell Formulas”](#)

Tip: Consider setting the Autosave Timeout value in the General preferences to automatically save open data tables at the specified number of minutes. This autosave value also applies to journals, scripts, projects, and reports.

Copy and Paste Data

When you paste data from another document into a data table, JMP adds rows and columns as needed. Click on a cell and paste the data.

Multiple Lines of Data

When you select one data table cell and paste several lines of data, each line is pasted into its own cell.

To paste all lines into one cell, do one of the following:

- Double-click an existing cell first and then paste.
- Right-click an existing cell and select **Paste into Cell**. The Paste into Cell option is available only on character and expression columns.

Note: If you try to paste into a cell that does not exist, the text will paste into separate cells.

The data type of the copied content needs to match the data type of the cells you’re pasting into. You can add new columns and paste the data, paste the data into cells of the correct data type, or change the data type of the cells if necessary.

Add Rows

To add any number of rows to the table

1. Select **Rows > Add Rows**.
2. Enter the number of rows to add.
3. Specify where to add the new rows (at the start or end of the data table, or after a specific row).
4. Click **OK**.

To add a single row to the end of the table

- Below the last row, click anywhere in a cell and begin typing.
- Below the last row, double-click in the empty row number area.

Add Columns

There are several ways to add new columns:

- Double-click the empty space to the right of the last data table column to add one column. See [“About the Column Info Window”](#) on page 257 for details about changing attributes after you add the column.
- Select **Cols > New Columns**. Use this option to add one or more columns and change their attributes.
- Double-click the upper triangle in the data grid above the row numbers. The Add Multiple Columns window appears.

Notes:

- When you initially create a column, you can choose to fill it with initial data values. See [“Initialize Data”](#) on page 267 in the “The Column Info Window” chapter. However, after you modify the cells, this option no longer appears.
- If any rows are selected in the data table, double-clicking to create a new column will deselect the rows. Using Cols > New Columns to create a new column will not change the row selection.
- When you create a new data table, do not edit the first empty column, and then add columns, the first column is counted as a newly added column. For example, if you add three columns, the first empty column is counted as the first column and then two columns are added.

To add one or more columns using New Columns

1. (Optional) Select the column before or after which the new column or columns will be added.
2. Select **Cols > New Columns**.
3. Change the column name.
By default, the new column names are Column 1, Column 2, and so on.
4. Select the data type, modeling type, and format for all of the columns. See [“About the Column Info Window”](#) on page 257.
5. (Optional) Select initial data values for all of the columns. See [“Initialize Data”](#) on page 267 in the [“The Column Info Window”](#) chapter.
6. Specify where you want to put the new columns. If you do not select an option, the column is added after the last column.
7. (Optional) For multiple columns, specify whether the columns should be grouped. See [“Group Columns”](#) on page 194.
8. To add more columns, follow these steps:
 - a. Click **Apply** to add the new column.
 - b. Click **Next**, change the column properties, and then click **Apply**.
 - c. Click **Next** to add another column.
9. Click **OK** to save your changes.

Figure 4.2 The New Column Window

Add columns to 'Big Class'

Column Name: Column 6

☐ Lock

Data Type: Numeric

Modeling Type: Continuous

Format: Best Width: 12

☐ Use thousands separator (,)

Initialize Data: Missing/Empty

Number of columns to add: 1

Before first column

Column Properties

OK, Cancel, Apply, Next, Help


Tip: To change the modeling type after the columns are created, click on the modeling type icon in the Columns panel and select a different type.

To add one or more columns using *Add Multiple Columns*

1. Double-click the upper triangular area in the data grid. The Add Multiple Columns window appears.

Figure 4.3 Adding Multiple Columns

double-click



2. Change the prefix for each column.
By default, the new column names are Column 1, Column 2, and so on.
3. Enter the number of columns to add.
4. Specify whether the columns should be grouped. See [“Group Columns”](#) on page 194.
5. Select the data type for all of the columns. See [“About the Column Info Window”](#) on page 257.
6. Specify where you want to put the new columns.
7. (Optional) Select initial data values for all of the columns. See [“Initialize Data”](#) on page 267 in the [“The Column Info Window”](#) chapter.
8. Click **OK** to save your changes.

Fill Columns with Sequential Data

To fill columns with a repeating sequence of data or with a continuation of values, follow these steps:

Figure 4.5 Missing Values

X
4
.
.
.
.
6
.
.
7
.

2. Right-click and select **Fill > Replace Missing with Previous Value**.

Figure 4.6 Replaced Values

X
4
4
4
4
4
6
6
6
7
7

Enter Cell Formulas

In numeric columns, you can enter cell expressions preceded by an equal sign (=). JMP evaluates the expression and stores the new number as the cell's value. Unlike column formulas, a cell expression is not stored. Cell expressions can contain operators, constants, and global and column variables.

To enter an expression

1. Click the cell where you want to enter the expression.
2. Type an equal sign (=), and then type the expression. See Table 4.1.
3. Press the ENTER key.

Table 4.1 Examples of Expressions in Table Cells

Example expression	Cell value
=sqrt(2)	1.41
=456+890	1346
=height+weight	Sums the values of cells in columns height and weight located in the same row as the cell that you entered the expression.
=height[1]	Displays the value found in row 1 of the height column

Select Rows

To select one entire row

- Click in the empty space that contains the row number.

To select a specific row number

- Select **Rows > Row Selection > Go to Row** and type in the desired row number.


To select multiple rows

- For continuous selection:
 - Click and drag the cursor over the row numbers.
 - Hold down the Shift key and click the first and last rows of the desired range.
 - Hold down the Shift key and press the up or down arrow key.
- For discontinuous selection:
 - Hold down the Ctrl key and click on each row.

To select or deselect all rows

- To select all rows, select **Rows > Row Selection > Select All Rows**.
- To deselect all rows, select **Rows > Clear Row States**.
or
- Hold down the Shift key and click the lower triangular area in the upper left corner of the data grid to select. Click again in the same area to deselect all rows. See Figure 4.7.
- To clear all highlighted areas in the data table, press the Esc key.

Figure 4.7 Lower Triangular Area



	name	age
1	KATIE	12
2	LOUISE	12
3	JANE	12
4	JACLYN	12
5	LILLIE	12
6	TIM	12

To select random rows

1. Select **Rows > Row Selection > Select Randomly**.
2. You can randomly select either a specific number of rows, or a proportion of the total number of rows:
 - Enter a whole number to select that number of rows.
 - Enter a value between 0 and 1 to select that proportion of rows.

For example, enter 10 to select 10 rows. Enter 0.1 to select 10% of the rows.

To invert the row selection

- Select **Rows > Row Selection > Invert Row Selection**.

To select dominant rows

1. Select **Rows > Row Selection > Select Dominant**.
2. Choose the column(s) whose values you want to use to determine dominance.
3. Select the high or low values to dominate by for each column.
4. Click **OK**.

Note the following about dominant values and rows:

- A value is dominant over another value if it is higher or lower (based on your specification).
- The Select Dominant option selects each row that is not dominated by any other row. A row dominates another row only if *all* of its values are dominating the other row's values.
- The resultant set of rows is called the Pareto Frontier.

To save the current row selection in a new column

1. Select **Rows > Row Selection > Name Selection in Column**.
2. Type a column name.
3. Label the selected and deselected rows.
4. Click **OK**.

Tip: If you repeat this process after creating the new column and indicate the same column name, the original column is overwritten. Changes that you made in the data table to Selected or Unselected values are lost. Avoid overwriting those values by clearing the corresponding box in the Name Selection in Column window. For example, to avoid overwriting the Unselected values, clear the Unselected box.

To select excluded, hidden, or labeled rows

1. Select **Rows > Row Selection**.
2. Select from the following options:
 - Select Excluded
 - Select Hidden
 - Select Labeled

Note: For details about excluded, hidden, or labeled rows, see [“Assign Characteristics to Rows and Columns”](#) on page 210.

To select rows that contain duplicate values

1. Select **Rows > Row Selection > Select Duplicate Rows**.

All duplicate rows except for the first are selected. If no columns are selected, duplicate rows will be selected using all the columns.

If columns are selected, duplicate values are found in the rows of those columns.

The match is case sensitive.

Locate Next and Previously Selected Rows

You can locate the next selected row after the current row and cause it to flash by selecting **Rows > Next Selected**.

Each time you select **Rows > Next Selected**, the next selected row is found and flashes. A beep signals when the last selected row is located.

You might want to use this feature when you have selected rows intermittently in a large data set and want to look through the selected rows in the data table.

Example of Locating Next Selected Rows

1. Select **Help > Sample Data Library** and open Diamonds Data.jmp.
2. Select **Analyze > Fit Y by X**.
3. Select Carat Weight and click **Y, Response**.


4. Select Price and click **X, Factor**.
5. Click **OK**.
6. Select **Tools > Lasso**.

If you cannot see the menu bar, place your mouse pointer over the blue bar below the title bar to reveal it.

7. Lasso some of the points near the 10,000 dollar price at the bottom of the plot. See Figure 4.8.
8. In the data table, select **Rows > Next Selected** (or you can press the F7 key).

You can easily navigate through the selected rows to see the data for each.

Figure 4.8 Points Selected



Select Columns

There are several ways to select columns:

- Select columns in the data table itself. See [“Select Columns in a Data Table”](#) on page 184.
- In a data table that has many columns, select columns by attributes, properties, and statistics in the Columns Viewer. See [“Select Columns in the Columns Viewer”](#) on page 185.
- Find the next or previously selected column. See [“Locate Next and Previously Selected Columns”](#) on page 190.

Select Columns in a Data Table

To select one entire column

- In the data grid, click in the empty space around the column name.
- or
- In the Columns panel, click the column name.

To select a specific column number

1. Select **Cols > Column Selection > Go to**.
2. Enter the column number or name and click **OK**.


To select multiple columns

- For continuous selection:
 - Click and drag the cursor over the column name.
 - Hold down the Shift key and click the first and last columns of the desired range.
 - Hold down the Shift key and press the left or right arrow key.
- For columns that are not next to each other:
 - Hold down the Ctrl key and click on each column.

To select or deselect all columns

- Hold down the Shift key and click the upper triangular area in the upper left corner of the data grid to select. Click again in the same area to deselect all columns. See Figure 4.9.

Figure 4.9 Upper Triangular Area



Tip: To clear all highlighted areas in the data table, press the Esc key.


To invert the column selection

Select **Cols > Column Selection > Invert Column Selection**. Selects any column that is currently deselected and deselects any column that is currently selected.

Select Columns in the Columns Viewer


The Columns Viewer helps you quickly select columns by attributes, properties, and statistics, particularly in a data table that has many columns. You can view summary statistics and properties for those columns, view quartiles in the summary statistics, subset the data, and more. And columns in the Columns Viewer window are also linked to the data table columns (Figure 4.10).

Figure 4.10 Linked Columns in the Column Viewer



The Columns Viewer gives you a quick view of data table characteristics. For example, the Summary Statistics report shows which columns contain missing values (Figure 4.11). You can select those columns in the report and then exclude them in the data table.

Figure 4.11 Identify Missing Values



39 Columns Clear Select Distribution			
Columns	N	N Missing	N Categories
I come from a large family	448	0	2
Brush	448	0	4
Floss	448	0	4
Brush After Waking Up	448	0	2
Brush After Meal	448	0	2
Brush Before Sleep	448	0	2
Brush Another Time	448	0	.
Brush Other	8	440	7
Brush Delimited	448	0	12
Floss After Waking Up	448	0	.
Floss After Meal	448	0	.
Floss Before Sleep	448	0	.
Floss Another Time	448	0	.
Floss Other	27	421	24
Floss Delimited	431	17	10
Frequency of Teeth Cleaning	448	0	4
Number of Fillings	448	0	4
Toothpaste Cost	448	0	.

The Summary Statistics report shows the following information:

- the total number of rows (N)
- the number of rows with missing values (N Missing)
- the number of categories (N Categories)
- for continuous data, the Min, Max, Mean, and Std Dev

Other options include the following:

Clear Select Deselects columns in the data table and in the Columns Viewer. This option ensures that no columns are selected before you begin selecting columns.

Subset Creates a linked subset data table from the selected columns.

Show Summary Creates a linked Summary Statistics report for the selected columns. Right-click to select options such as sorting by column or creating a data table. Select **Show Quartiles** to include lower quartiles, upper quartiles, and interquartile ranges. And to create a linked data table from all columns in the report, select Data Table View from the Summary Statistics red triangle menu.

Find Columns with Properties Shows a list of column properties in the Columns with Properties report. Select the properties that you want to find and then click **OK** to create a linked report from all columns. Or you can select columns first in the Select Columns list and then show the list of properties just for those columns.

Tip: Each time you click the **Show Summary** or **Find Columns with Properties** buttons, a new report is added to the window. To delete a report, select **Remove** from the report's red triangle menu.


Example of Finding Columns with a Specific Property

This example shows how to find columns that have a Formula property and then view all formulas at once.

1. Select **Help > Sample Data Library** and open **Consumer Preferences.jmp**.
2. Select **Cols > Columns Viewer** to open the Data Table Columns Viewer window.
3. Select **Find Columns with Properties**, select **Formula**, and click **OK**.


The Columns with Properties report appears. Several columns include the Formula property (Figure 4.12). Because the list is so long, you want to view all formula columns together.

Figure 4.12 Select the Formula Column Property



4. Right-click the report, select **Sort by Column, Formula**, and then click **OK**.
- Columns that have a Formula property appear at the top of the report (Figure 4.13).

Figure 4.13 Sort by Column




5. Select the Employee Tenure, Position Tenure, and Salary Group columns and select **Column Info**.

Formulas for the selected columns appear in the data table's Column Settings window.

Example of Showing Summary Statistics

This example shows how to find columns with a low standard deviation. This can be helpful if you want to delete or exclude that data from an analysis.

1. Select **Help** > **Sample Data Library** and open Semiconductor Capability.jmp.
2. Select **Cols** > **Columns Viewer** to open the Data Table Columns Viewer window.
3. In the Select Columns red triangle menu, select **Name Starts With**.
4. Type PNP and press **Enter** to select the PNP columns (Figure 4.14).

Figure 4.14 Filter Columns by Name

- Click **Show Summary** to add the Summary Statistics report (Figure 4.15).
The rows show the minimum, maximum, mean, and standard deviation for each column.

Figure 4.15 Summary Statistics for Selected Columns

Columns	Min	Max	Mean	Std Dev
PNP1	116.29903	527.676177	313.069716	58.3535251
PNP2	128.160882	728.924323	456.615693	79.82589
PNP3	120.896887	158.498912	137.614574	6.06076156
PNP4	149.453273	373.172883	256.375597	32.6073816
PNP5	-55.762191	-40.722372	-47.178172	2.047573
PNP6	0	0	0	0
PNP7	-16.888557	-14.961357	-15.89982	0.28816317
PNP8	-44.913142	-34.771668	-39.21972	1.49081788
PNP9	-79.665058	-66.929598	-73.35004	1.94997812
PNP10	-0.6442798	-0.623852	-0.6335016	0.00299937

- Right-click in the report and select **Sort by Column**.
- Select **Std Dev** and **Ascending**, and then click **OK**.

Notice that PNP6 has no standard deviation, because the minimum, maximum, and mean values are 0.

Figure 4.16 Sorted Std Dev Column

Columns	Min	Max	Mean	Std Dev ^
PNP6	0	0	0	0
PNP10	-0.6442798	-0.623852	-0.6335016	0.00299937
PNP7	-16.888557	-14.961357	-15.89982	0.28816317
PNP8	-44.913142	-34.771668	-39.21972	1.49081788
PNP9	-79.665058	-66.929598	-73.35004	1.94997812
PNP5	-55.762191	-40.722372	-47.178172	2.047573
PNP3	120.896887	158.498912	137.614574	6.06076156
PNP4	149.453273	373.172883	256.375597	32.6073816
PNP1	116.29903	527.676177	313.069716	58.3535251
PNP2	128.160882	728.924323	456.615693	79.82589

8. In the Summary Statistics report, select the row for PNP6 and then display the data table.
9. View the data table and press **Delete** to remove the selected column.
The column is instantly removed from the data table.
10. To close the Columns Viewer, click the **X** button in the upper right corner (Windows) or upper left corner (Macintosh) of the window.

Locate Next and Previously Selected Columns

You can find the next selected column after the current column by selecting **Cols > Column Selection > Next Selected Column**. Similarly, you can find the previously selected column before the current column by selecting **Cols > Column Selection > Previous Selected Column**.

Each time you select one of these options, the next or previously selected column appears and flashes. The options are available only when columns are selected.

You might want to use this feature to look at intermittently selected columns in a large data table.

Select Cells

To select a block of cells

- Drag the arrow cursor diagonally across the cells.

JMP can find all cells whose values are the same as the ones you currently have highlighted. You can do this within one data table or throughout all open data tables. Highlight the cells that contain the values that you want to locate.

To find all matching cells within the active data table

- Select **Rows > Row Selection > Select Matching Cells**

or

- Right-click one of the highlighted row numbers and select **Select Matching Cells**.

To find all matching cells across all open data tables


- Select **Rows > Row Selection > Select All Matching Cells**. The rows that contain the same values as the selected ones are highlighted.

To select cells that contain specific values

JMP can search for a specific value (or text string) and highlight all of the cells in the data table that contain the specific value.

1. Select **Rows > Row Selection > Select Where**.

Figure 4.17 Specify Criteria for Selecting Rows



2. From the column list, highlight the name of the column whose rows you want to select.
3. Use the drop-down menu to select a condition from the list (equals, does not equal, and so on). See Figure 4.17.
4. Type the search value. To search for missing values, leave the box empty.
5. Click **OK**.

You can also specify the following optional features:

- To compare the values of two columns, click the **Compare column** check box. Select from the list of columns for comparison.
- To make the search case-sensitive, click the box beside **Match Case**.

If you currently have rows selected in the data table, you can specify the following optional features:

- Click an option under **Current Selection** to tell JMP how to handle that current selection:
 - **Clear** removes the highlight from currently selected rows and selects all rows that contain the specified value.
 - **Extend** keeps the currently selected rows selected and also selects the rows in which the specified value has been found.
 - **Restrict** selects the rows in the currently selected array that contain the specified values.
- Click **Add Condition** to add a condition to the list.
- To add more conditions to the search, repeat the previous steps. Click the appropriate item in the **Select Rows** area to specify if you would like JMP to select rows conditionally: if *all* conditions are met, or if *any* of the conditions are met.
- To keep the window open after you click **OK**, select **Keep dialog open**.

Resize Rows and Columns

To resize rows

Resize rows by dragging one of the row borders. All rows are resized to the same height. Graphics that display inside each cell shrink based on the row height.

To resize columns

To resize a column, drag the column border to the right or left.

To resize several columns to the same width, follow these steps:

1. Select the columns that you want to resize.
2. Press the Alt key (Windows) or Option key (Macintosh) and drag one of the column borders. All columns are resized to the same width.

Organize Data

- [“Delete Rows and Columns”](#)
- [“Rearrange Columns”](#)
- [“Group Columns”](#)
- [“Move Values”](#)

- “Color Cells”
- “Edit or Delete Cells”
- “Edit Column Names”
- “Hide and Exclude Rows”
- “Exclude Rows”
- “Hide Rows”
- “Exclude Columns”
- “Hide Columns”
- “View Patterns of Missing Data”
- “Find and Replace Cell Values”
- “Use the Row Editor to Edit Cells in a Row”
- “Pop-Up Menus for Rows and Columns”
- “Compare Data Tables”

Delete Rows and Columns

To delete rows

1. Highlight the rows that you want to delete.
2. Press the Delete key, or right-click on the row numbers and select **Delete Rows**.

Caution: When you try to delete thousands of rows, an alert might appear if your computer has insufficient memory to save data for undo. Either select fewer rows to delete or select **Disable Undo** from the Table panel red triangle menu. This option removes all actions from the undo history and does not record future actions. When the **Disable Undo** option is selected, it is in effect only while the data table is open; the setting is not saved with the data table.

To delete columns

1. Highlight the columns to delete.
2. Press the Delete key, or right-click and select **Delete Columns**.

Rearrange Columns

You can rearrange or sort data table columns by their name, data type, or modeling type, or reverse the current order. To reorder columns, select **Cols > Reorder Columns** and select from one of the following options:

Move Selected Columns moves the selected columns to a particular place in the data table. Specify where to place the selected columns in the Move Selected Columns window:

- **To first:** moves the selected columns so that they are in the left-most position in the data table.
- **To last:** moves the selected columns so that they are in the right-most position in the data table.
- **After:** moves the selected columns so that they are after a column that you identify.

Original Order returns the columns to the order they were in when data table was last saved.

Reorder by Name arranges the columns from left to right in alphabetical order by column name.

Reorder By Data Type arranges the columns from left to right in alphabetic order by data type (expression, row state, character, numeric).

Reorder By Modeling Type arranges the columns from left to right in alphabetic order by modeling type (none, continuous, ordinal, nominal, multiple response, unstructured text, vector). Row state columns have no modeling type, and are shown last.

Reverse Order reverses the order of the data table columns.

Group Columns

Group columns within a single heading to manage large numbers of columns and facilitate analysis role assignment. Grouped columns appear in an outline format within the Columns panel.

To group or ungroup columns

1. Within the data grid, select the columns that you want to group.
 2. From the main menu, select **Cols > Group Columns** or **Cols > Ungroup Columns**.
- or
1. From the Columns panel, select the columns that you want to group.
 2. Right-click on the selected columns and select **Group Columns** or **Ungroup Columns**.

Note: Grouped columns are automatically retained for data tables generated from the following commands: **Subset**, **Sort**, **Summary**, **Join**, **Stack**, and **Split**. For the **Stack** command, if all the columns in the stack group belong to the same columns group, then the group's name is used for the column name.

Move Values

To move values in a data table, select the values, click and pause, and then drag and drop the values into the new location.

Tip: Clicking and dragging on a selection without pausing extends the selection.

When dragging and dropping values, note the following:

- Cells retain all of their characteristics and column properties.
- After you move cells, missing values appear in the cells that you initially selected.
- The selected cells and the destination cells must have the same data type.
- If you drag a set of cells to an empty area of the table, new columns are automatically created.
- New columns have the original columns' display format and modeling types.

To specify where to move rows

1. Highlight the rows that you want to move.
2. Select **Rows > Move Rows**.
3. Specify where you would like to move the rows in the Move Rows window:
 - To the beginning of the table (**At start**)
 - To the end of the table (**At end**)
 - After a specific row number (**After row:**)

Move Content into Another Window

On Windows, you can drag selected content over a minimized window. The minimized window moves to the front and you can paste your content into it. You can do the same thing in JMP. For example, you can drag selected content over the Home Window button  (located in the bottom right corner of most windows). Then in the Window List, drag the content over the window that you want to move the content into. That window moves to the front and you can drop in the content.

Tip: If you cannot see the JMP Home Window button, select **View > Status Bars**.

For example, you can drag a selected column, row, or cell from one data table into another; drag selected text from one script window into another; or drag selected content from a report into a journal.

Color Cells

You can select one or more data table cells and change the color to highlight a specific value. Right-click the cell or cells, select **Color Cells**, and select a color. If a color is assigned to a cell, right-click and select **Clear Color** to remove the color. You can also select the color black to remove the color.

Edit or Delete Cells

To edit or delete the contents of a cell, follow these steps:

1. Click the cell containing the value that you want to edit or delete.
2. Press the Delete key.
3. To edit the value, click the cell a second time, and then edit the cell's value.

Edit Column Names

To edit a column name, select the column and begin typing. You can also edit the column name in the Column Info window, or select the header and press Enter.

Hide and Exclude Rows

Apply Hidden and Excluded row states to rows that you do not want to include in analysis or plot calculations and that you do not want to display in plots. These rows are not included in subsequent analyses.

Notes:

- Plots found under the Graph menu, with the exception of Profilers, are immediately recalculated to reflect hidden and excluded rows.
- For many platforms, reports and plots are not updated immediately to reflect excluded and hidden observations. You need to rerun the analysis to recalculate analysis results and the related plots. For exceptions, see [“Platforms that Update Immediately for Hide and Exclude”](#) on page 197.
- When you Exclude and Hide rows, they are excluded and hidden in all open reports and plots that update automatically.
- When you Exclude and Hide rows, a circle with a strikethrough (, for Exclude) and a mask icon (, for Hide) appear beside the row number.
- Rows remain hidden and excluded until you highlight the rows and select **Hide and Exclude** again

To hide and exclude one or more rows

1. Select the rows that you want to hide and exclude.
2. Do one of the following:
 - Right-click on the highlighted area next to the row numbers and select **Hide and Exclude**.
 - From the **Rows** menu, select **Hide and Exclude**.

Platforms that Update Immediately for Hide and Exclude

When you apply Hide and Exclude to rows, for most platforms under the Analyze menu, points or plot elements that correspond directly to rows are usually hidden immediately in plots. However, calculations shown in accompanying reports usually are *not* updated. For the following platforms, applying Hide and Exclude results in immediate updates to plots *and* calculations:

- Tabulate
- Control Chart Builder

Exclude Rows

Apply the Excluded row state to rows that you do not want to include in subsequent calculations. Statistics are recalculated without the excluded rows.

To exclude one or more rows, follow these steps:

1. Select rows that you want to exclude.
2. Do one of the following:
 - Right-click on the highlighted area next to the row numbers and select **Exclude/Unexclude**.
 - From the **Rows** menu, select **Exclude/Unexclude**.

Notes:

- In most cases, when a row is represented by a point or an individual plot element, excluding the row does *not* hide it in plots.
- In Graph Builder, when a plot element is represented by a group of rows, the plot is reconstructed using only the unexcluded rows and does not display plot elements corresponding to the excluded rows. Excluded rows are treated as if they are both hidden *and* excluded.
- Plots found under the Graph menu (with the exception of Profilers, Parallel Plot, and Scatterplot Matrix) are immediately recalculated to reflect excluded rows.

- For many platforms, reports and plots are not updated immediately to reflect excluded observations. You need to rerun the analysis to recalculate plots and analysis results.
- When you Exclude rows, they are excluded in all open plots and reports that are updated immediately.
- A circle with a strikethrough () appears beside the row number of an excluded row.
- Rows remain excluded until you highlight the rows and select **Exclude/Unexclude** again.

Hide Rows

Apply the Hidden row state to rows that you do not want to include in plots.

Note: Not all plots hide the elements that correspond to hidden rows. This is often the case when the calculations used to construct the plot elements use the data from the hidden rows. As a general rule, if there is a one-to-one correspondence between rows and plot elements, the points or elements corresponding to the hidden rows are hidden.

To hide one or more rows, follow these steps:

1. Select rows that you want to hide.
2. Do one of the following:
 - Right-click on the selected area next to the row numbers and select **Hide/Unhide**.
 - From the **Rows** menu, select **Hide/Unhide**.

Notes:

- When you Hide rows, they are hidden in all open plots that are updated immediately.
- Hiding rows does *not* exclude them from calculations and analyses.
- When each hidden row corresponds to a point or an individual plot element, plots are updated immediately when you apply the Hidden row state to rows.
- Depending on the platform, plot elements are calculated using multiple observations, but they do not correspond directly to a row. In these cases, the plot elements generally are not updated to reflect hidden observations unless those rows are also excluded.
- For some plots where plot elements correspond to groups of rows, when you Hide rows, the plot is updated to hide plot elements corresponding to hidden rows. See [“Plots Where Grouping Elements are Updated for Hide”](#) on page 199.
- A mask icon () appears beside the row number of a hidden row.
- Rows remain hidden until you select the rows and select **Hide/Unhide** again.

Plots Where Grouping Elements are Updated for Hide

When you apply Hide to rows, in plots with a one-to-one correspondence between rows and plot elements, the points or plot elements are usually hidden immediately. However, for the following platforms and options, applying Hide results in immediate updates to plot elements that correspond to groups of rows:

- Control Chart Builder. See the Control Chart Builder chapter in the *Quality and Process Methods* book for details.
- Graph Builder. The Bar chart, Heat Map, and Pie chart are updated to reflect hidden rows. See the Graph Builder chapter in the *Essential Graphing* book for details.
- Bubble Plot. See the Bubble Plots chapter in the *Essential Graphing* book for details.

Exclude Columns

When your data table contains columns that you do not want to consider for analysis, you can exclude those columns so that they do not appear in selection lists in launch windows. Note the following:

- Excluded columns remain visible in the data grid.
- A circle with a strikethrough () appears to the right of the column name in the Columns panel.

To exclude columns from launch windows

1. Select one or more columns that you want to exclude.
2. Do one of the following:
 - Right-click on the highlighted column name in the Columns panel and select **Exclude/Unexclude**.
 - From the **Cols** menu, select **Exclude/Unexclude**.

To unexclude columns

1. Select the columns in the Columns panel.
2. Do one of the following:
 - Right-click on the highlighted column name in the Columns panel and select **Exclude/Unexclude**.
 - From the **Cols** menu, select **Exclude/Unexclude**.

Hide Columns

When your data table contains columns that you do not want to see in the data grid, you can hide those columns. Note the following:

- Hidden columns appear in launch windows and are available for analyses.
- A mask icon () appears to the right of the column name in the Columns panel.

To hide columns

1. Select one or more columns that you want to hide.
2. Do one of the following:
 - Right-click on the highlighted column name in the Columns panel and select **Hide/Unhide**.
 - From the **Cols** menu, select **Hide/Unhide**.

To unhide columns

1. Select the columns in the Columns panel.
2. Do one of the following:
 - Right-click on the highlighted column name in the Columns panel and select **Hide/Unhide**.
 - From the **Cols** menu, select **Hide/Unhide**.

View Patterns of Missing Data

If your data table contains missing data, you might want to determine whether there is a pattern to the missing data. The pattern might help you make discoveries about your data.

To view patterns of missing data, follow these steps:

1. With your data table open, select **Tables > Missing Data Pattern**.
2. Select the columns for which you would like to find patterns of missing data.
3. Click **Add Columns**.
4. Select **Count Missing Value Codes** to count missing value codes as missing values.
5. Select **Add Value Colors Property** to consistently color columns that contain 0 or 1 (missing value indicators).


For example, non-missing is always colored blue, missing is always colored red. This is especially helpful for data tables that might have similar values across columns.

6. Click **OK**.

Example of Viewing Patterns of Missing Data

1. Select **Help > Sample Data Library** and open Missing Data Pattern.jmp.
2. Select **Tables > Missing Data Pattern**.

Figure 4.18 The Missing Data Pattern Window



3. Highlight all of the columns.

Note: For details about the options in the red triangle menu, see [“Column Filter Menu”](#) on page 57 in the “Get Started” chapter.

4. Click **Add Columns**.
5. Click **OK**.

Figure 4.19 A Missing Data Pattern Table

	Count	Number of columns missing	Patterns	Trial 1	Trial 2	Trial 3	Trial 4
1	2	0	0000	0	0	0	0
2	2	1	0001	0	0	0	1
3	2	2	0011	0	0	1	1
4	1	3	0111	0	1	1	1

Tip: To quickly create a Treemap or Cell Plot of the data, click the green triangle next to the Treemap or Cell Plot script in the table panel.

Figure 4.19 shows the following patterns:

- Row 1 shows that there are two instances where all rows in Trial 1, Trial 2, Trial 3, and Trial 4 have no missing values.
- Row 2 shows that there are two rows in the source table whose one missing value is in the Trial 4 column.


- Row 3 shows that there are two rows in the source table whose missing values are in the Trial 3 and Trial 4 columns.
- Row 4 shows that there is one row in the source table whose three missing values are in the Trial 2, Trial 3, and Trial 4 columns.

The Count column is assigned the frequency role. If you now use the Missing Data Pattern data table to run an analysis, JMP automatically uses Count as a frequency. For details, see [“Assign a Preselected Analysis Role”](#) on page 297 in the “The Column Info Window” chapter.

Find and Replace Cell Values

You can find and replace cell values by selecting the **Edit > Search > Find** options.

Figure 4.20 The Find Window



The following rules apply to searching for values:

- To find values in hidden columns, unhide the column.
- Values found in locked columns cannot be modified.
- The **Undo** command works only with **Replace**. You cannot undo **Replace All**.
- If your data table contains value labels, using the **Search** commands searches for actual values, but does not search for labels. See [“Value Labels”](#) on page 272 in the “The Column Info Window” chapter.
- If your data table contains formatted values (such as dates, times, or durations) using the Search command searches for the formatted values, not the actual values.

Find Window Options

Refine your search with the following options:

Match Case Performs a case sensitive search, which can be useful for locating proper nouns or other capitalized words.

Match entire cell value Detects empty spaces, which lets you search for a series of words in a character column, or locate strings with unwanted leading or trailing empty spaces.

Tip: To find missing character values, leave the **Find what** box empty and check **Match entire cell value**. To find missing numeric values, insert a period into the **Find** box and check **Match entire cell value**.

Use regular expressions Assumes the find string to be a regular expression instead of the literal string that you enter in the **Find what** box. The regular expressions follow standard semantics.

Restrict to selected rows Restricts the search to selected rows.

Restrict to selected columns Restricts the search to selected columns.

Search data Searches only data cells (omitting column names).

Search column names Searches only column names (omitting data cells).

By column Searches the table column by column, from top to bottom, until it reaches the last cell in the rightmost column, or until you stop the search.

By row Searches the data table row by row from left to right, to the rightmost cell in the last row or until you stop the search.

Multiple lines Increases the Find and Replace boxes to 3 lines long instead of 1. The Enter key inserts a return into the field.

Tip: You can alternatively click and drag on the Find and Replace boxes to make them larger. If you copy and paste, the boxes resize to 1 line long, but all of your text is still there.

Keep dialog open Keeps the Find window open during your search.

Search Actions

This section describes some common searches that you might perform.

Begin by searching for a value in the data table. The search begins with the first cell in the first column and searches every cell until it locates the value or reaches the end of the table.

To replace the currently highlighted cell value

Enter a value in the Replace with box and click **Replace**. Or, if the Search window is closed, select **Edit > Search > Replace**. If the replace value is a missing value, the currently highlighted cell content becomes a missing value.

To replace all occurrences of the specified value

Enter a value in the Replace with box and click **Replace All**. Or, if the Search window is closed, select **Edit > Search > Replace All**.

To replace the value and search for the next value

Enter a value in the Replace with box and click **Replace**. Or, if the Search window is closed, select **Edit > Search > Replace and Find Next**. Or, press CTRL-L.

To use a selected value as the Find what value

In the data table, select a value. Select **Edit > Search > Use Selection for Find**. Next, select **Edit > Search > Find**. The value that you selected in the data table is already entered in the **Find what** field.

To use a selected value as the Replace with value

In the data table, select a value. Select **Edit > Search > Use Selection for Replace** to populate the **Replace with** field.

To find the next value when the Search window is closed

Select **Edit > Search > Find Next**. Or, press CTRL-G, or F3 on Windows.

To find a missing value:

- To find missing character values, leave the Find what field empty and select **Match entire cell value**.
- To find missing numeric values, type a period into the Find what text box.

Use the Row Editor to Edit Cells in a Row

Use the Row Editor to browse or edit cells one row at a time. Open the Row Editor in one of the following ways:

- Select **Rows > Row Editor**.
- In a data table, double-click in the row number area. The row that you use is the row that first appears in the Row Editor.
- In a report window, right-click in a plot or graph and select **Row Editor**.

Figure 4.21 Row Editor



Note the following:

- If you have a report window open, and you want edited data to be automatically reflected there, make sure that Automatic Recalc is turned on. See [“Automatic Recalc”](#) on page 413 in the “JMP Reports” chapter.
- If your data table contains value labels, the Row Editor displays the label, and when the cell is highlighted for editing, it shows the actual value. See [“Value Labels”](#) on page 272 in the “The Column Info Window” chapter.

Row Editor Buttons

Click the arrow buttons to browse through selected rows or the entire data set if no rows are selected. Row Editor buttons are described as follows:

- Shows the previous row.
- Shows the previously selected row.
- Makes the row blink in graphs.
- Shows the next selected row.
- Shows the next row.
- Searches for a row. See [“Select Cells”](#) on page 190.
- Creates a new row at the end of the data table.

Note: Changes made to a row using the Row Editor are written to the data table when you change fields in the Row Editor. You still need to save the changes to the data table.

Row Editor Options

The red triangle menu in the Row Editor contains the following options:

Next Selected displays information for the selected row that is located after the current one.

Prev Selected displays information for the selected row that is located before the current one.

Next displays information for the row that is located after the current one, regardless of whether the row is selected.

Prev displays information for the row that is located before the current one, regardless of whether the row is selected.

Save saves the data table and any changes that you have made to it via the Row Editor.

New Row creates a new row in the data table.

Find displays the same window as if you had selected **Rows > Row Selection > Select Where**. Select one of the options from the **Current Selection** menu, and then highlight the column whose rows you want to select. Type in the value for which you want JMP to search. See [“Select Cells”](#) on page 190.

Blink causes the current row’s highlight to flash at a rapid rate.

Note: Text in a locked column or a locked data table cannot be edited. For details, see [“Lock”](#) on page 257 in the “The Column Info Window” chapter and [“Lock Tables”](#) on page 246.

Pop-Up Menus for Rows and Columns

When you right-click in the row number area, or at the top of a column in the column name area, pop-up menus appear. These menus provide quick access to selected commands in the Rows and Columns menus. For details about these options, see [“Pop-Up Menu for Columns”](#) on page 49 in the “Get Started” chapter and [“Pop-Up Menu for Rows”](#) on page 51 in the “Get Started” chapter.

Compare Data Tables

JMP can compare two open data tables and report the differences between data, scripts, table variables, column names, column properties, and column attributes. Character values that do not match exactly appear in the report. For numeric data, you can select a relative (or *fuzzy*) comparison. The numeric values are considered equal if they are within the relative error rate that you specify. The smaller the relative error, the more precise the comparison.

To compare two data tables

1. Open the data tables.
2. In one of the tables, select **Tables > Compare Data Tables**.


3. If necessary, select the data table that you want to compare from the list.
4. (Optional) Select **Fuzzy Compare** and enter the relative error to see numeric differences within the specified rate.
5. Click on the red triangle menu and select the following options:
 - which items you want to compare
 - how to show the differences
6. Click **Compare**.

The Difference Summary and Difference Plot are shown by default. The red triangle options that you selected also appear.

Basic Table Information

The Tables Info report shows the data table names and locations along with the numbers of columns and rows in each table. In Figure 4.22, you see that Big Class1.jmp contains one more row than Big Class2.jmp.

Figure 4.22 Basic Information



Tables Info	
Big Class1	T:\BookMaster\V10\UG\Images\EnterEdit\ManageData\Big Class1.jmp (5 columns, 40 rows)
Big Class2	T:\BookMaster\V10\UG\Images\EnterEdit\ManageData\Big Class2.jmp (5 columns, 39 rows)


Compare Data

The interactive Difference Summary report and Different Plot indicate how rows differ between reports. Each entry in the Difference Summary report shows which action occurred, how many rows are affected, and the first row in which the change occurs.

In Figure 4.23, Big Class1.jmp (left) and Big Class2.jmp (right) are compared.


- The first entry in Figure 4.23 indicates that one row (N) has changed (or been replaced) in the first row of Big Class2.jmp. When you select the entry in the Difference Summary report on the left, the entry is highlighted in yellow, and the row flashes in the data table. For a graphical view of the comparison, place your cursor over a colored cell in the Difference Plot. Figure 4.23 shows that the name KATIE in Big Class1.jmp was changed to KIM in Big Class2.jmp. The entire first row is highlighted in the Difference Plot, which tells you that all values in that row are different.

Figure 4.23 Modified Data




- In Figure 4.24, the second entry indicates that two rows were deleted beginning at row four. The deleted rows are highlighted in Big Class1.jmp on the left. And the Difference Plot specifies the different values. The name in row four of Big Class1.jmp was JACLYN and TIM in Big Class2.jmp.

Figure 4.24 Deleted Rows



- In Figure 4.25, the third entry tells you that one row was added before what was originally row eight. The name in row eight of Big Class1.jmp was ROBERT. PETER is the name in row six of Big Class2.jmp.

Figure 4.25 Identify New Rows




Click the **Previous difference** and **Next difference** buttons above the Difference Summary to navigate from row to row.

Tip: Save the Difference Summary report to a data table by selecting **Save Difference Summary** from the red triangle menu.

Compare Table Properties

Select **Compare Table Properties** from the red triangle menu to see differences in table scripts and variables. For example, Figure 4.26 shows that the Distribution script in Big Class2.jmp refers to the height column rather than the weight column.

Figure 4.26 Modified Table Script



Compare Column Attributes and Properties

Select **Compare Column Attributes and Properties** from the red triangle menu to see differences in column notes, cell colors, and the like. For example, Figure 4.27 shows that column notes and value colors differ in Big Class2.jmp.

Figure 4.27 Modified Column Attributes and Properties

5/1 Cols
39/0 Rows

	name	age	sex	height	weight
1	KIM	13	F	62	99
2	LOUISE	12	F	61	123
3	JANE	12	F	55	74
4	TIM	12	M	60	84
5	JAMES	12	M	61	128
6	PETER	14	M	64	100
7	ROBERT	12	M	51	79
8	BARBARA	13	F	60	112
9	ALICE	13	F	61	107
10	SUSAN	13	F	56	67

evaluations done

Column Attributes and Properties

	sex	sex
Value Colors	-----	{F" = -15113984, "M" = -5882409}
Color Cell by Value	No	Yes
	height	height
Notes	"Explore data adventurously"	"The unit of measure is inches."
	weight	weight
Notes	"Explore data adventurously"	"The unit of measure is pounds."

original values new values

Assign Characteristics to Rows and Columns

This section describes how to exclude, hide, label, color, or mark rows and columns in order to customize the appearance of points in scatterplots and graphs.

- [“How to Find Rows and Columns Options”](#)
- [“Label Rows and Columns”](#)
- [“Assign Colors or Markers to Rows”](#)
- [“Create Color Themes”](#)
- [“Delete Custom Color Themes”](#)
- [“Select Matching Row State Cells”](#)
- [“Delete Row Characteristics”](#)
- [“Lock Columns in Place”](#)

How to Find Rows and Columns Options

The menu for row actions can be accessed from the following places:

- the **Rows** menu in the main menu
- right-click on a row
- the red triangle in the Rows panel
- the left red triangle in the upper left corner of the data grid

Similarly, the menu for columns actions can be accessed from the following places:

- the **Cols** menu in the main menu
- right-click on a column
- the red triangle in the Columns panel
- the right red triangle in the upper left corner of the data grid

Label Rows and Columns

When you position the arrow cursor over a point in a plot, the point's label appears. By default, row numbers are used as labels. You can customize the labels as follows:

- You can change the label to display column values instead of the row number.
- You can enable the label to always appear, not only when you position the cursor over points.
- A label or yellow tag icon (🏷️) appears beside the column name in the Columns panel, indicating that points on plots are identified by the column value. If there are multiple columns that are labeled, their values appear on plots separated by a comma.
- Data remain labeled until you select **Label/Unlabel** again.

To change the label to display column values

1. Highlight one or more columns whose values you want to appear as the label in plots.
2. Select **Cols > Label/Unlabel** from the menu or right-click and select **Label/Unlabel**.

To enable the label to always appear (not just when you position the cursor over points)

1. Highlight one or more rows whose label you want to always appear in plots.
2. Select **Rows > Label/Unlabel** from the menu.

To turn off labeling for rows or columns

1. Highlight the labeled rows or columns that you no longer want labeled.

2. Select **Label/Unlabel** from the **Rows** menu or **Cols** menu. You can also right-click columns or rows and select **Label/Unlabel**.

Tip: A photo can be displayed in the label when you place your cursor over data. For example, the SAS Offices.jmp sample data table contains an Expression column that is labeled. A photo of each office is stored in the column. When you place your cursor over a data point on the map, the photo for that row appears. See “[Expression Role](#)” on page 289 in the “The Column Info Window” chapter for details.

Assign Colors or Markers to Rows

- If you assign a color to a row, the points representing the values in that row are colored in the plot.
- If you assign a marker to a row, the point is replaced with the marker in the plot.
- You can also assign colors or markers based on column values.

Assign a Color to Rows

Assigning a color to selected rows means that the points in plots appear in the color that you select. In the data grid, the active color assigned to a row appears next to the row number.

To assign rows a color

1. Highlight one or more rows that you want to assign a color to.
2. Right-click on the highlighted rows and select **Rows > Colors**.
3. Select one of the available colors.

Tip: To clear an assigned color from the selected rows, assign the color black.

Add Markers to Rows

To replace the standard points in plots with a marker, use the JMP markers palette. In the data table, these markers also appear next to row numbers.

1. Highlight one or more rows that you want to apply the marker to.
2. Right-click on the selected rows and select **Markers**, and then select the marker shape.
Select **Other** to create custom markers. You can type alphabetic characters, numerals, and other keyboard symbols.

Tip: To return to the default marker, select the initial dot marker.


Assign Colors or Markers to Rows Based on Column Values

You can assign colors or markers to your data table rows based on the values found in a particular column. For example, in a column called **Sex**, you could assign all rows whose value is **F** a red circle marker. All rows whose value is **M** could have a green plus marker. These colors and markers replace the default black dot in plots and appear next to its row number in the data table.

To assign colors or markers to rows based on column values

1. Select **Rows > Color or Mark by Column**.
2. Select the column to color and or mark. See Figure 4.28.

Figure 4.28 Color or Mark by Column



3. Select the **Colors** and **Markers** schemes to apply.
A preview of your selection appears under Row States.
4. (Optional) Select any additional options. See [“Color or Mark by Column Options”](#) on page 213.
5. Click **OK**.
6. (Optional) To shade all rows according to their row state, right-click in the row numbers area within the data grid and select **Color Rows by Row State**.

From then on, the rows are shaded with the color that you assign to the rows.

Color or Mark by Column Options

Colors select a color theme to assign different colors to the rows in your data table. Color assignment is based on the values of the selected column.

Continuous Scale assigns colors in a chromatic sequence based on the values in the highlighted column.

Reverse Scale assigns colors in a reversed chromatic sequence based on the values in the highlighted column.

Markers assigns a different marker to each row in your data table based on the values found in the column that you highlighted.

Make Window with Legend Includes a legend with your new characteristics so that you can easily identify which colors and markers correspond with which row.

Save To Column Property saves the color and marker information as a column property. The rows in the selected column of the data table are colored, based on the color theme.

Save To Table Property saves the color and marker information as a table property.

Excluded Rows assigns colors or markers to rows that are excluded.

Create Color Themes

JMP includes several color themes that can distinguish a range of values in a graph. You can also create your own color themes based on an existing color theme or create custom themes.


Note: When you select a default color theme, the colors are not applied to reports that are open. You need to rerun the existing reports to format them with the default color theme.

See [“Delete Custom Color Themes”](#) on page 219 for details about deleting custom color themes.

To create a color theme


1. Select **File > Preferences > Graphs**.
2. To either create a new Continuous Color Theme or Categorical Color Theme, click the appropriate color theme.
If you are creating a new continuous color theme, the Continuous Color Themes window appears.

Figure 4.29 Continuous Color Themes Window




If you selected to create a new categorical color theme, the Categorical Color Themes window appears.

Figure 4.30 Categorical Color Themes Window



3. (Optional) To base the theme on an existing theme, select a color themes from the available themes.
4. Click the Custom Color Theme disclosure icon to show the Custom Color Theme panel.
Figure 4.31 shows the color theme panels for both continuous and categorical themes (respectively).

Figure 4.31 Custom Color Theme Panel


5. Click **New** to create a new theme.

A new color theme is created based on the selected color theme. A temporary name is assigned to the theme.

6. Type a new name in place of the temporary label. On Windows, do not press Enter. The window closes if you do so.
7. To modify the color theme, do any of the following:
 - To modify the gradient of continuous color, move the sliders left or right.
 - To add more colors to the gradient, click the color bar to choose a color. A new slider is displayed under the color bar.
 - To change the color of a slider, click on the slider to display the Color window and choose another color.
 - To reverse the order of the colors on the gradient, click **Reverse**.
 - To distribute the colors evenly on the gradient, click **Space Evenly**.
 - To list the custom theme in the Sequential pane, select **Sequential** from the list.
 - To list the custom theme in the Diverging pane, select **Diverging** from the list.
 - To list the custom theme in the Chromatic pane, select **Chromatic** from the list.
 - To prevent a theme from appearing in lists of color themes, select **Hidden**.
 - To remove a color from the color theme, click the color's slider and drag the slider above or below the color bar.
 - To discard your changes, click **Cancel**.
8. Click **Save** to save the custom color theme.


The new custom color theme is appended to the contents of the selected pane.
9. Click **OK** to close the color theme window.

Continuous and Categorical Color Themes

The following figure shows examples of the two types of color themes in JMP, continuous and categorical. When a color theme is selected for continuous data, the colors are graduated (as

shown on the left). When the same color theme is selected for categorical data, the color consists of distinct blocks of color. (as shown on the right).

Figure 4.32 Examples of Continuous and Categorical Color Themes



Custom Color Themes

Custom color themes can be applied in the same way as built-in color themes:

- You can select custom color themes as defaults from the **Continuous Color Theme** and **Categorical Color Theme** drop-down menus in the Graphs preferences. Only continuous color themes are available for continuous data. All color themes are available for categorical data.
- You can apply the custom color themes to components such as markers and data table rows. See [“Assign Colors or Markers to Rows Based on Column Values”](#) on page 213 for details.
- In certain reports, such as treemaps and surface plots, you can select specific custom color themes. See the *Essential Graphing* book for details.

Use Custom Color Themes on Multiple Computers

In Windows, the color themes that you create are defined in the JMP preferences file called JMP.PFS. If you use JMP on more than one computer (for example, at home and at work), you can copy the color theme definitions from one JMP preferences file to another. Custom colors are then available on both computers.

In the preferences file, the code for a custom color theme looks like this:

```
Add Color Theme(
```

```

{"Pink to Blue", {{255, 168, 255}, {255, 0, 255}, {0, 128, 255}}}
),

```

In this example, the name of the color theme is “Pink to Blue.” The Red/Green/Blue (RGB) values for each color slider are located in brackets. The first slider defines the RGB values 255, 168, and 255. The second and third groups of brackets define colors for the second and third sliders.

In a text editor (such as Microsoft Notepad) add this color theme to the preferences file on your other computer. The preferences file is located in your Users folder within the JMP or JMPPro folder.

C:/Users/<user_name>/AppData/Roaming/SAS/JMP/14

C:/Users/<user_name>/AppData/Roaming/SAS/JMPPro/14

C:/Users/<user_name>/AppData/Roaming/SAS/JMP/14

Note: To see the preceding folders, you must configure Windows Explorer to show hidden files and folders. For details, refer to the Windows help.

To transfer color themes to another Windows computer

1. On the computer that contains the customized JMP preferences, select **File > New > Script**. The Script window appears.
2. Type the following JSL function:

```
Show Preferences()
```
3. Click **Run Script** .
Your customized preferences are written to the log.
4. Select **View > Log** (or display the open log).
The custom color theme that you created appears, for example:

```
Add Color Theme(
{"Pink to Blue", {{255, 168, 255}, {255, 0, 255}, {0, 128, 255}}}
),
```

This definition might be in the middle of other customized preferences that appear in the log.
5. Save the log as Log.jsl and open the file on the computer whose preferences you are updating.
6. On the computer whose preferences you are updating, close JMP.
7. Make a backup of JMP.PFS, and then open the original JMP.PFS in a text editor.
8. Copy and paste the custom color definition from Log.jsl to JMP.PFS. The definition goes after Preferences(as shown in the following example:

```
Preferences(  
  Add Color Theme(  
    {"Pink to Blue", {{255, 168, 255}, {255, 0, 255}, {0, 128, 255}}}  
  ),  
);
```

Note: Be sure to include the closing parenthesis and comma. The code does not need to be indented. You can put the code in any valid location. Pasting it after `Preferences(` helps ensure that you do not delete any necessary parentheses or commas.

9. Save the file.

If you open JMP and the new color definition is not displayed in the preferences, delete the updated preferences file and add the definition to the original preferences file. Make sure that you copy and paste the definition in the correct location.

Delete Custom Color Themes

1. Select **File > Preferences > Graphs**.
2. To either delete a color theme, select either the Continuous or Categorical Color Theme. The relevant Color Themes window appears.
3. Click the Custom Color Theme disclosure icon to show the Custom Color Theme panel.
4. From the appropriate pane, select the custom color to delete.

Note: You can delete only custom color themes.

5. Click **Delete**.
6. Click **OK** to save your changes and close the Color Themes window.

Select Matching Row State Cells

You can select a cell in a row state column and then select all cells that contain the selected cell's attributes. This option enables you to select cells with any combination of row state attributes, such as Exclude, Hide, color, or marker. For example, if a cell has a red marker and is excluded, and you select matching cells, all cells in excluded rows with red markers are selected.

1. Right-click the cell whose row state you want to select.
2. Select **Select Matching Cells**.

The cells with matching row states are selected.

Delete Row Characteristics

To clear all row states in the data table, select **Rows > Clear Row States**. To clear row states only in selected rows, select **Rows > Clear Selected Row States**.

All rows become included, visible, unlabeled, and show in plots as black dots. The **Clear Row States** command does not affect row states saved in row state columns.

Lock Columns in Place

You can lock a column in place so that when you scroll horizontally, the column remains visible. Highlight the columns and select **Cols > Scroll Lock/Unlock**. Note the following:

- Hidden columns cannot be scroll locked.
- The name of a locked column appears in italics in the Columns panel.
- Scroll locked columns are moved to the left in the data grid. Once you unlock them, they are not moved back to their original locations in the data table, but remain on the left.
- Columns remain scroll locked until you highlight the columns and select **Scroll Lock/Unlock** again.

Restructure Data

- [“Make a Column into Multiple Columns”](#)
- [“Make Indicator Columns”](#)
- [“Combine Columns”](#)
- [“Compress Selected Columns”](#)
- [“Make Binning Formula”](#)
- [“Convert Labels to Codes and Codes to Labels”](#)
- [“Make a New Formula Column”](#)
- [“Transform Columns”](#)
- [“Recode Data”](#)

Make a Column into Multiple Columns

Use the **Text to Columns** option to make a character column with delimited fields into multiple columns. Highlight a column from a data table and select **Cols > Utilities > Text to Columns**. The maximum number of delimited fields across all rows determines the number of new columns created.

Note: **Text to Columns** is case-sensitive.

The **Text to Columns** window has the following options:

Delimiter Specify text, such as a comma, to indicate how the data in the source column is organized into new columns. For example, if the original cell reads “NY, NJ, PA,” and the delimiter is a comma, three new columns are created that contain “NY”, “NJ”, and “PA”.

TAB Specifies tabs as delimiters.

NEWLINE Specifies newline characters (\r, \n, and \r\n) as delimiters.

Make Indicator Columns Makes new columns that are named after the distinct fields in the source column with cell values of either 0 or 1.

Include Missing Allows any empty rows to be counted as a category. An additional column named Missing is added to the data table. A value of 1 indicates an empty row.

Make Indicator Columns

Convert a categorical column into multiple indicator columns based on each distinct category. The columns are named after each level in the column. For example, when you make an indicator column from sex in Big Class.jmp, the indicator columns are named F and M.

Highlight a column in a data table and select **Cols > Utilities > Make Indicator Columns**. You can then indicate whether you want to prepend the original column name to the indicator column names (as in sex_F and sex_M) and include missing values.

Multiple columns with values of either 0 or 1 are created. A value of 1 indicates that the original column contains that specific category.

If the given column has the Multiple Response modeling type or Multiple Response column property, the categories are determined from the set of responses.

Combine Columns

The **Combine Columns** option is the opposite of **Text to Columns**. Instead of making multiple columns, you can combine a set of columns into one character column with delimited fields.

To combine indicator columns, follow these steps:

1. Select **Help > Sample Data Library** and open Consumer Preferences.jmp.
2. Select the columns, Floss After Waking Up, Floss After Meal, and Floss Before Sleep.
3. Select **Cols > Utilities > Combine Columns**.
4. Type “Combined Floss” for the column name, and keep the default delimiter as a comma.

5. Select **Selected Columns are Indicator Columns** and click **OK**.

Figure 4.33 Combined Floss Column

Combined Floss	Floss After Waking Up	Floss After Meal	Floss Before Sleep
Floss After Waking Up	1	0	0
Floss After Meal	0	1	0
Floss After Meal	0	1	0
Floss After Meal	0	1	0
Floss After Meal	0	1	0
Floss Before Sleep	0	0	1
Floss After Meal	0	1	0
Floss Before Sleep	0	0	1
	0	0	0
Floss After Meal	0	1	0
Floss Before Sleep	0	0	1
Floss After Meal, Floss Before Sleep	0	1	1
Floss After Waking Up, Floss Before Sleep	1	0	1
Floss After Waking Up, Floss After Meal, Floss Before Sleep	1	1	1
Floss After Waking Up, Floss Before Sleep	1	0	1
Floss After Waking Up, Floss After Meal	1	1	0

The selected columns are represented in the Combined Floss column with each field separated by a comma. Only the columns that have a value of 1 are represented in the combined column for each given row.

Note: Value labels show a label in the data table instead of a value. A label appears for each instance of the value in the combined column. You can show the original values by double-clicking a label within a cell. To avoid using value labels, select **No Value Labels** when you combine the columns.

Compress Selected Columns

JMP lets you compress columns in a data table to minimize the size of the file and reduce the amount of memory required to analyze data. This feature is helpful when numeric columns contain many small integers or when any column contains fewer than 255 unique values. For example, compressing columns in a data table with 389 columns and 85,000 rows might decrease the file size from 250MB to 33MB, depending on the type of data.

When you compress columns, JMP verifies whether the data can be stored in a more compact form based on the data type:

- In character columns with fewer than 255 unique values, the List Check property is added to the column where appropriate (shown in Figure 4.34).

The List Check property restricts the values in the selected column to valid values. The List Check property is not applied when the number of values in the selected column is too

great. For example, if the number of values is almost the same as the number of rows, the data table does not add the List Check property to the column.

- For numeric columns, only those with the Best, Fixed Dec, or Data format are compressed. Data is compressed to 1-byte, 2-byte, or 4-byte integers when possible (shown in Figure 4.35). For details about short integers, see [“The Short-Integer Format”](#) on page 260 in the [“The Column Info Window”](#) chapter.

A numeric column with non-integer values can also be compressed if there are fewer than 255 unique values. In this case, the List Check property is added to the column.

Caution: In a column with the List Check property, you can enter only a value that is in the list. Otherwise, JMP warns that the cell contains invalid data when you try to enter the new value. For details, see [“List Check”](#) on page 270.

Figure 4.34 List Check Property Added to a Compressed Character Column




Figure 4.35 Column Info Window Showing Numeric Column before and after Compression



To compress columns, select one or more columns and select **Cols > Utilities > Compress Selected Columns**. (Select all columns if you do not know which columns can be compressed.)

The column or columns are compressed if possible. The log shows which columns were compressed and how they were compressed. (Select **View > Log** to show the log.)

Note: To compress a numeric column manually, set your Tables preferences to allow short numeric data and then change the column's data type to **1-byte integer**, **2-byte integer**, or **4-byte integer**. For details about this preference, see [“Tables”](#) on page 593 in the “JMP Preferences” chapter.

Make Binning Formula

You can distribute your data into equal width bins using the **Make Binning Formula** option. Select the column or columns that you want to divide into bins, and select **Cols > Utilities > Make Binning Formula**. New formula columns are added to the data table.

The Make Binning Formula window contains the following options:

Format Select a format for displaying the range of values in the bin. You can see a preview by moving the cursor over the graph.

Bin Shape: Offset Select an offset value for the lower edge of the bins.

Note: Bins are identified by their lower edge. The lower edge is in the bin. The upper edge is in the next bin because it is the next bin's lower edge.

Bin Shape: Width Select the width of values for the bins.

Note: The colored bands reflect the offset and the width of the bins with respect to the data.

Labels Specify whether value labels are shown instead of the data values.

- Select **Use Value Labels** to show a label instead of the value.
- Select **Use Range Values** to include the lower and upper values for each range in the label.
- Select **No Labels** to use the lower edge value as the label.

For more information, see [“Value Labels”](#) on page 272 in the “The Column Info Window” chapter.

Tip: Value Labels are recommended in most platforms, many of which do not support range labels. In the Categorical platform, you must use value labels. On some axes, you might find that range labels more clearly identify the values, or you can try adjusting the offset and width for the axis.

Make All Like X (Appears only if multiple columns are selected) Applies the choices made for the first column (X) to the remaining columns.

Make Formula Columns Creates the formula columns and closes the window.

Example of Making a Binning Formula

1. Select **Help > Sample Data Library** and open Big Class.jmp.
2. Select the height column.
3. Select **Cols > Utilities > Make Binning Formula**.


You want the range of values to appear as X-X, so keep the range set to **Low - High**.

4. Change the **offset** to -0.5.

Tip: For integer data, setting the offset to -0.5 helps disambiguate values on the edge. In this example, one of the bins covers 59.5 to 64.5, so it is clear that 59 and 65 are not included in this bin.

5. Keep the **width** set to 5.
6. For the labels, keep it set to **Use Value Labels**, so that you can see the range of values for the bin.

Figure 4.36 Completed Binning Window



7. Click **Make Formula Columns**.
A column called height Binned is added to the Big Class.jmp data table.
8. To see how the formula is calculated, right-click on the height Binned column and select **Formula**.

Figure 4.37 Formula

$$-0.5 + 5 * \text{Floor} \left(\frac{\text{height} - (-0.5)}{5} \right)$$

Convert Labels to Codes and Codes to Labels


Suppose that you have a column of strings such as “dissatisfied”, “somewhat dissatisfied”, and “somewhat satisfied”, and “satisfied”. You can recode the values to “1”, “2”, “3”, and “4”. The original strings are placed in the Value Labels column property for that column. If the column has a List Check property, the property is removed. The column data type is changed to 1-byte Integer. Converting a column of strings to short numeric codes saves memory and can speed up processing.

You can also convert a numeric column of codes to labels. The column must have value labels. The column data type is changed to Character, and the Value Label column property is removed. This is, in effect, the opposite of converting labels to codes.

Convert Labels to Codes

1. Select the character column and select **Cols > Utilities > Labels to Codes**.

Figure 4.38 Converting Labels to Codes



Default codes are assigned to the values.

2. Change the codes if desired and click **OK**.

The column is recoded, and value labels are added to the column.

Convert Codes to Labels

1. Select the numeric column that contains value labels and select **Cols > Utilities > Codes to Labels**.

2. Change the codes if desired and click **OK**.

The column is recoded with the original value labels.

Make a New Formula Column

To perform further analyses on your data, use the New Formula Column menu options from your existing data table. Formula columns use formulas or calculations to define column values.

Right-click a column heading in your data table and select **New Formula Column**. Choose from Transform, Character, Combine, Pairwise, Aggregate, Distributional, Date Time, Random, Row, Vector, or Formula to calculate column values. A new formula column is added to the data table. See [“Transform Columns”](#) on page 227 for a description of these options.

Note: The same options exist in both the New Formula Column menu, and the right-click column menu in the launch window. However, performing these tasks in a launch window results in a temporary column, and New Formula Column adds a new column to the original data table.

Right-click options depend on the selected column’s data type and the number of columns selected. If the selected column is a Character column, Character and Row options appear. See [“Character Menu”](#) on page 234 and [“Row Menu”](#) on page 235 for more information.


Transform Columns

Each launch window in JMP enables you to create one or more temporary transform columns for use in performing analyses. These transform columns are not part of the source data table and only can be used within the context of the current launch window. Transform columns use formulas or calculations to define the column values. Closing the launch window deletes any transform columns.

Each column listed in the Select Columns pane of the launch window includes an icon representing the column’s modeling type (continuous, ordinal, or nominal) and the column name. Right-click on a column name to create a transform column using Transform, Character, Combine, Pairwise, Aggregate, Distributional, Date Time, Random, Row, Vector, or Formula to calculate the column’s values.

Right-click options depend on the selected column’s data type and number of columns selected.

Figure 4.39 Example of Transform Column Menu



Group By For ordinal and nominal data, specifies the column to use for grouping data. A separate analysis is computed for each level of the specified column.

Notes:

- The transform column is available only in the current launch window. To make the transform column available outside of the current launch window, right-click the transform column and select **Add to Data Table**. The transform column is added to the source data table.
- You can paste a transform column into a Roles box on the launch window. For example, you might copy a transform column from a script. Right-click in the appropriate launch window Cast Selected Columns into Roles box and select Paste. This is an alternative to right-clicking the column in the Select Columns list, selecting the transform, and adding the transform column to a role.
- Define your own transform by writing a JSL script. See the Data Tables chapter in the *Scripting Guide*.

Transform Menu

Select a function from the Transform menu to create a transform column containing the calculations based on the selected function. For details, see the Scripting Index in the Help menu or the Model Specification chapter in *Fitting Linear Models*.

Note: You can apply unary functions to multiple columns resulting in multiple transform columns.

Table 4.2 Descriptions of the Transform Menu Options

Round	Rounds date values. For example, in a chart of weeks, Round converts the date values into the first date of each week they occur on.
Scale Offset	Enables you to specify a general linear transform. For example, you might multiply the value by 1.8 and apply an offset of 32 to convert Celsius temperatures to Fahrenheit.
Square Root	Takes the square root of the values of the selected column.
Square	Calculates the square for the selected column values.
Log	Applies the natural logarithm transformation to the selected column.
Log x+1	Calculates $\text{Log}(\text{col}+1)$.
Exp	Applies the exponential transformation to the selected column.
Log10	Applies the base-10 logarithm transformation to the selected column.
Pow10	Calculates 10 raised to the power of the selected column values.
Cube Root	Calculates the cube root for the selected column values.
Cube	Calculates the cube for the selected column values.
Reciprocal	Calculates the reciprocal ($1/\text{column}$) for the selected column values.
Absolute Value	Calculates the absolute value for the selected column values.
Negation	Calculates the negative for the selected column values.

Table 4.2 Descriptions of the Transform Menu Options *(Continued)*

Arrhenius	Applies the Arrhenius transformation to the variable T (temperature in degrees Centigrade): $X = \frac{11605}{T + 273.15}$ This is the component of the Arrhenius relationship that is multiplied by the activation energy.
Arrhenius Inverse	Applies the inverse of the Arrhenius transformation to the variable X: $T = \frac{11605}{X} - 273.15$
Logit	Calculates the inverse of the logistic function for the selected column (where p is in the range of 0 to 1): $\text{Logit}(p) = \log\left(\frac{p}{1-p}\right)$
Logistic	Calculates the logistic (also known as Squish and Logist) function for the selected column (where the result is in the range of 0 to 1): $\text{Logistic}(x) = \frac{1}{(1 + e^{-x})}$
Logit Percent	Calculates the logit as a percent for the selected column (where pct is a percent in the range of 0 to 100): $\text{LogitPct}(pct) = \log\left(\frac{\left(\frac{pct}{100}\right)}{1 - \left(\frac{pct}{100}\right)}\right)$
Logistic Percent	Calculates the logistic (or logist) as a percent for the selected column (where the result is in the range of 0 to 100): $\text{LogisticPct}(x) = \frac{100}{(1 + e^{-x})}$

Combine Menu

Select multiple columns to access the Combine menu. The Combine menu creates a transform column containing the calculations based on the selected function.

The following functions are included in the menu:

Sum Calculates the sum of the first and second columns ($A + B$).

Difference Calculates the difference between the first and second columns ($A - B$).

Difference (reverse order) Calculates the difference between the second and first columns ($B - A$).

Product Calculates the product of the first and second columns ($A \times B$).

Ratio Calculates the ratio of the first column to the second column (A / B).

Ratio (reverse order) Calculates the ratio of the second column to the first column (B / A).

Minimum Returns the minimum value of the selected columns.

Maximum Returns the maximum value of the selected columns.

Average Returns the average value of the selected columns.

Standard Deviation Calculates the standard deviation of the values in the selected column.

Median Calculates the median value for the selected column.

Quantile Calculates the quantile of the specified percentage for the selected column.

Geometric Mean Returns the n th root of the product of the data.

Pairwise Menu

Select a function from the Pairwise menu to create pairwise results for two or more columns. This menu appears only when the number of selected columns is even and greater than or equal to four.

Sum Calculates the sum of the first and second columns ($A + B$).

Difference Calculates the difference between the first and second columns ($A - B$).

Difference (reverse order) Calculates the difference between the second and first columns ($B - A$).

Product Calculates the product of the first and second columns ($A \times B$).

Ratio Calculates the ratio of the first column to the second column (A / B).

Ratio (reverse order) Calculates the ratio of the second column to the first column (B / A).

Minimum Returns the minimum value of the selected columns.

Maximum Returns the maximum value of the selected columns.

Average Returns the average value of the selected columns.

Geometric Mean Returns the n th root of the product of the data.

Aggregate Menu

Select a function from the Aggregate menu to create a transform column containing the statistics calculated from the selected column (or part of a column if you specified a Group By column).

Note: The **Group By** option is useful for these functions.

The following functions are included in the menu:

Mean Returns the average value of the selected column.

Sum Calculates the sum of the values in the selected column.

Count Calculates the number of values in the selected column.

Median Calculates the median value for the selected column.

Quantile Calculates the quantile of the specified percentage for the selected column.

Minimum Returns the minimum value of the selected column.

Maximum Returns the maximum value of the selected column.

Standard Deviation Calculates the standard deviation of the values in the selected column.

Distributional Menu

Select a function from the Distributional menu to create a transform column containing the statistics calculated from the selected column. For details, see the Scripting Index in the Help menu.

The following functions are included in the menu:

Center Subtracts the column mean from each value across all rows of the selected column.

Standardize Calculates the column value minus the mean divided by the standard deviation across all rows of the selected column.

Range 0 to 1 Scales the data up or down so that the minimum value is greater or equal to 0, and the maximum value is less than or equal to 1.

Box Cox Transforms the data using the Box-Cox equation. For details, see the Standard Least Squares chapter in *Fitting Linear Models*.

Johnson Normalizing Transforms the data using one of the Johnson equations. The new column name indicates either Johnson Su, Johnson Sb, or None, depending on which equation was used to calculate the new data.

Informative Missing Creates two columns. The Informative column replaces missing values with the column mean. The Is Missing column indicates 1 for missing values, and 0 otherwise.

Rank Returns the rank, ranging from 1 as the lowest, with row-order tie-breaking.

Cumulative Probability Calculates the cumulative probability: $\text{Col Rank}(\text{col}) / (\text{Col Number}(\text{col}) + 1)$.

Normal Quantile Calculates the quantile from a Normal distribution.

Random Menu

For numeric columns, select a function from the Random menu to create columns with random values.

The following functions are included in the menu:

Random Uniform Generates random numbers uniformly between 0 and 1.

Random Normal Generates random numbers that approximate a normal distribution based on the mean and standard deviation of the column or columns selected, with mean as 0 and standard deviation as 1.

Sample without Replacement Shuffles the values randomly each time it's evaluated. The result for the first value affects the result for the second value.

Sample with Replacement Generates a random integer. The result for the first value does not the result for the second value.

Date Time Menu

For column values containing date or time values, select a function from the Date Time menu to create a transform column containing values calculated from the selected column.

The following functions are included in the menu:

Day Returns the day of the month for the date in the selected column.

Month Returns the month number for the date in the selected column.

Month Abbr. Returns the abbreviated month for the date in the selected column.

Year Returns the year for the date in the selected column.

Month Year Returns the month number and year for the date in the selected column.

Quarter Returns the year's quarter (1, 2, 3, or 4) for the date in the selected column.

Week Returns the number of the week in the year for the date in the selected column.

Year Quarter Returns the year and the year's quarter (1, 2, 3, or 4) for the date in the selected column.

Year Week Returns a string representing the ISO-8601 week of year format (for example, June 12, 2013 results in "2013W24").

Day of Year Returns the day of the year for the date in the selected column.

Day of Week Returns the day of the week for the date in the selected column.

Day of Week Abbr. Returns the abbreviated day of the week for the date in the selected column.

Date Returns the month, day, and year for the date in the selected column.

Time of Day Returns the time for the date in the selected column.

Hour Returns the hour part of the date in the selected column.

Minute Returns the minute part of the date in the selected column.

Second Returns the seconds part of the date in the selected column.

Character Menu

Select a function from the Character menu to create a transform column containing strings formed by the selected Character function.

The following functions are included in the menu:

Length Calculates the number of characters in each string in the selected column or columns.

- Concatenate** Concatenates the strings in the selected column or columns into a new string.
- Concatenate with Space** Concatenates the strings in the selected column or columns into a new string with each sub-string separated by a whitespace.
- Concatenate with Comma** Concatenates the strings in the selected column or columns into a new string with each sub-string separated by a comma character.
- Titlecase** Converts the strings to titlecase (for example, “Sheila Smith”).
- Uppercase** Converts the strings to uppercase (for example, “SHEILA SMITH”).
- Lowercase** Converts the strings to lowercase (for example, “sheila smith”).
- First Word** Extracts the first word from a character string in the selected column or columns.
- Last Word** Extracts the last word from a character string in the selected column or columns.
- Rank** Returns the rank, ranging from 1 as the lowest, with row-order tie breaking.

Row Menu

Select a function from the Row menu to create a transform column containing calculations determined by the selected Row function.


In addition to the functions described in the appendix, the following functions are included in the menu:

- Row** Returns the current row number.
- Selected** Returns the selected index.
- Difference** Calculates the difference of each value in the selected column using the formula:

$$\text{If} \left(\begin{array}{l} \text{Row}() == 1 \Rightarrow . \\ \text{else} \Rightarrow \text{Dif}(kHours, \sim) \end{array} \right)$$


Note: The Difference function also supports the Group By option.

- Lag** Returns the value in the previous row for the selected column.
- Lag Multiple** Returns the values from multiple previous rows for the selected column.
- Cumulative Sum** Calculates the cumulative sum for each value in the selected column using the formula:



Note: The Cumulative Sum function also supports the Group By option.

Moving Average Calculates the exponentially weighted moving average, EWMA (using a smoothing parameter between 0 to 1.0) for each value in the selected column. The following example uses a smoothing parameter of 0.25:



Weighting Determines how the values are weighted. Incremental weighting is a ramp or triangle. The exponential moving average is EWMA or EMA.

Items Before Controls the size of the range (or window) by including the specified number of items before the current item in the average (in addition to the current item). -1 means all prior items.

Items After Controls the size of the range (or window) by including the specified number of items after the current item in the average (in addition to the current item). -1 means all following items.

Report missing values for partial window Controls how missing values are treated. By default, missing values are ignored.

Note: JMP evaluates the formula entered on-demand therefore complex formulas might require a lot of processing time.

Vector Menu

Select a transform from the Vector menu to create transform columns from vector data.

To Columns Expands the vector into individual number columns.

Sum Returns the sum of the arguments or of the values within the matrix.

Min Returns the minimum value among the values within the matrix.

Max Returns the maximum value among the values within the matrix.

Loc Min Returns the first position of the minimum value.

Loc Max Returns the first position of the maximum value.

Transform Column Options

After creating a transform column, you can perform the following actions:

Rename Renames the transform column.

Add to Data Table Adds the transform column to the data table as a formula column.

Remove Transform Column Removes the transform column from the launch window.

Recode Data

Use the recoding tool to change all of the values in a column at once. For example, suppose you are interested in comparing the sales of computer and pharmaceutical companies. Your current company labels are Computer and Pharmaceutical. You want to change them to Technical and Drug. Going through all 32 rows of data and changing all the values would be tedious, inefficient, and error-prone, especially if you had many more rows of data. Recode is a better option.


Note: If you need to recode similar values within multiple columns, use the Recode option in **Cols > Standardize Attributes**. See [“Standardize Attributes”](#) on page 295 in the “The Column Info Window” chapter.

1. Select **Help > Sample Data Library** and open Companies.jmp.
2. Select the Type column by clicking once on the column heading.
3. Select **Cols > Recode**.

Notice that New Column is selected by default to place the recoded values in a new column. The new column will be named Type 2.

4. In the Recode window, enter the desired values in the **New Value** boxes. For this example, enter Technical in the Computer row, and Drug in the Pharmaceutical row.

Figure 4.40 Recode Window



All cells are updated automatically to the new values.

Notes:

- If the data table contains value labels, the labels appear in a column in the Recode window called New Labels. Editing the labels also modifies the Value Labels column property. You can also select **Replace values with value labels** to modify the data in the New Values column.
- If you enter a non-numeric value in a column with a Numeric data type, you are prompted to convert the data type to Character. Click **Yes** to convert the column and display the new value. Click **No** to keep the column Numeric and display a missing value.

Recode Options

When you are finished recoding data, click **Done** to view the following options:

New Column creates a new column for the changed data and retains the original column.

Formula Column creates a new column with the changes as a formula instead of values. Changing a value in the original column in the data table causes the formula column to update that value automatically.

In Place applies any change to the original data column.

The remaining options are available on the Recode window:

Undo  reverses the last change made to the window.

Redo  recalls the last change made to the window.

Filter searches for specific values. Click the down arrow to select search options. For details about each option, see [“Search Filter Options”](#) on page 241 for details. Note that you can type a regular expression to customize the filter.

View Groups deselect to view ungrouped values. Selected by default.

Show Only Grouped shows recoded values that have been grouped.

Show Only Ungrouped shows values that have not been grouped.

Group becomes active when multiple values are selected. Click **Group** to make highlighted values part of the same group. If you previously edited a value before grouping, the edited value becomes the group representative in the New Value column. Otherwise, the group representative is the value that occurs most often.

Red Triangle Options for Recode

The red triangle menu contains options for the Recode window.

Convert to Titlecase converts the first letter of each word to uppercase, and the remaining letters to lowercase.

Convert to Uppercase converts values to uppercase.

Convert to Lowercase converts values to lowercase.

Tab characters, space characters, and line separators are often imported into a data table. Remove these characters using the following commands:

Trim Whitespace removes leading and trailing whitespace characters. For example, if an extra space was imported before and after the name John, this command would delete the spaces.

Collapse Whitespace removes leading and trailing whitespace characters and removes duplicate interior whitespace characters. That is, if more than one whitespace character is present, the **Collapse Whitespace** command replaces the two spaces with one space.

Remove Punctuation removes special characters (such as quotation marks and ampersands) from the beginning, middle, and end of words.

Replace String replaces all occurrences of specified characters with a new string or with nothing. Note that you can type a regular expression to customize the replacement.

Split on specifies the item to split values on.

Split delimiter specifies the delimiter to split on.

Match specifies point at which the items are split. For example, if you match on a comma, and the data is "first, second, third", then **First occurrence** matches "second, third". **Last occurrence** matches "third".

Keep specifies the text that you want to keep before or after the match.

Keep text if no match avoids deleting the values that have no match.

See ["Example of Splitting on a Comma"](#) on page 244 for an example.

Use the following commands to group data based on value:

First Word groups values based on the first word of the value. For example, if "John Smith" and "John Adams" were values, this command would group them under "John."

Last Word groups values based on the last word of the value.

All But First Word groups values based on the remaining value after the first word is excluded.

All But Last Word groups values based on the remaining value after the last word is excluded.

Group Similar Values enables you to customize how data is grouped. Choose from the grouping options list. See [“Grouping Options for Recode”](#) on page 241.

Add Value Labels enables you to assign value labels to each value.

Replace values with value labels replaces the values with the value labels that you specified.

The following options are also available:

Recall recalls previous changes made in the Recode window.

Start Over returns the window to the default condition.

Script view options to import, merge, or save Recode scripts.

- Import from File: imports a JSL script to recode previously recoded data. Run the same script on different data to recode data the same way.
- Import from Data Table: imports a JSL script saved to a data table.
- Import from Recode Result Column: imports data from the column that you select, usually the column in which you saved previous recode results.
- Save to File: saves Recode changes to a JSL script. After selecting Save, you are prompted to name and save the file.
- Save to Data Table: saves Recode script to current data table. You are asked whether you want to create a new column with the edited data or overwrite the original data. If you are recoding a data table and plan to work with the data later, it's safer to create a new column to avoid losing the original data.
- Merge with Data Table Script: merges changes made in the Recode window to the current Recode script saved to the data table. If there are multiple scripts, you are prompted to choose which script to merge your recoded data with.
- Save to Script Window: appends the Recode script to the script window.

Publish to Formula Depot publishes the recode script to the Formula Depot, which enables you to reuse the code in other scripts.

Right-Click Options for Recode

Right-click values in the Recode window to view the following options:

Group to new value Enables you to specify a new value for the selected data.

Group To right-click selected values to select a different grouping value, or group representative. The **Group To** command displays the Old Values that occur most often in the data table with their corresponding New Values (if they are different). The list displays the first 8 possible group representatives.

Swap New Values when two values are highlighted, select **Swap New Values** to make the new value of the first value adopt the new value of the second value, and vice versa.

Remove From Group after values are grouped, right-click a single value or multiple values to remove them from that group.

Make Representative right-click a single value from a group and select **Make Representative** to make the selected value the New Value.

Group Similar Values right-click a single value to find values that are similar. The Grouping Options window appears. See “Grouping Options” in the section below.

Grouping Options for Recode

Select the following **Group Similar Values** commands to increase the accuracy of grouping:

Ignore Case item case is ignored.

Ignore Non-Printable Characters non-printable characters are ignored. Some data can include non-printable characters (such as file separators) that only the computer can read.

Ignore Whitespace white space is ignored.

Ignore Punctuation punctuation is ignored.

Allow Character Edits allows characters to be replaced by the new value when similar values are grouped.

Difference Ratio groups values according to proportional difference. For example, type “.25” to group values that are at most 25% different.

Max Character Difference groups values according to a maximum number of nonadjacent character differences. For example, type “5” to group values that differ by 5 characters or less.

Search Filter Options

Click the down arrow button next to the search box to refine your search.

Contains Terms Returns items that contain a part of the search criteria. A search for “ease oom” returns messages such as “Release Zoom” but not “Partial Least Squares”.

Contains Phrase Returns items that contain the exact search criteria. A search for “text box” returns entries that contain “text” followed directly by “box” (for example, “Context Box” and “Text Box”).

Starts with Phrase Returns items that start with the search criteria.

Ends with Phrase Returns items that end with the search criteria.

Whole Phrase Returns items that consist of the entire string. A search for “text box” returns entries that contain only “text box”.

Regular Expression Enables you to use the wildcard (*) and period (.) in the search box. Searching for “get.*name” looks for items that contain “get” followed by one or more words. It returns “Get Color Theme Names”, “Get Name Info”, and “Get Effect Names”, and so on.

Invert Result Returns items that do not match the search criteria.

Match All Terms Returns items that contain both strings. A search for “t test” returns elements that contain either or both of the search strings: “Pat Test”, “Shortest Edit Script” and “Paired t test”.

Ignore Case Ignores the case in the search criteria.

Match Whole Words Returns items that contain each word in the string based on the Match All Terms setting. If you search for “data filter”, and Match All Terms is selected, entries that contain both “data” and “filter” are returned.

Example of Grouping Based on Character Difference

You can group similar values according to the number of characters that differ between them.

1. Select **Help > Sample Data Library** and open Candy Bars.jmp.
2. Select the Name column.
3. Select **Cols > Recode**.
4. From the red triangle menu, select **Group Similar Values**.
5. Select the **Max Character Difference** option and type “6”.
This allows JMP to group values that differ by a maximum of 6 characters.
6. Click **OK**.

Figure 4.41 Grouped by Character Difference

Count	Old Values (75)	New Values (49)
1	100 Grand	100 Grand
1	3 Musketeers	3 Musketeers
1	5th Avenue	5th Avenue
1	Abba-Zabba	Abba-Zabba
1	Almond Joy	Almond Joy
1	Almond Roca	Almond Joy
1	Baby Ruth	Baby Ruth
1	Bar None	
1	Big Cherry	Big Cherry
1	Big Hunk	
1	Bit-O-Honey	
1	Butterfinger	Butterfinger

In this example, the grouped values have no more than 6 characters different between them. The values shown in the New Value column represents the grouped values in the recoded data table.

7. Right-click Almond Roca and select **Make Representative** to change the new value to represent a different value within the group.

Figure 4.42 Make Representative

Count	Old Values (75)	New Values (45)
1	100 Grand	100 Grand
1	3 Musketeers	3 Musketeers
1	5th Avenue	5th Avenue
1	Abba-Zabba	Abba-Zabba
1	Almond Joy	Almond Joy
1	Almond Roca	Almond Joy
1	Baby Ruth	Baby Ruth
1	Bar None	

To remove values from a group, right-click and select **Remove from Group**.

8. Click **Recode** to replace the original data with the recoded data in the table.

Example of Grouping Based on Difference Ratio


You can group similar values according to the proportion of characters that differ between them.

1. Select **Help > Sample Data Library** and open Candy Bars.jmp.
2. Select the Name column.
3. Select **Cols > Recode**.
4. From the red triangle menu, select **Group Similar Values**.
5. Select the **Difference Ratio** option and type “.5”.

6. Click **OK**.

This allows JMP to group values that differ by 50% or less. In other words, values that share at least 50%, or half, of the same characters. The Difference Ratio is determined by comparing the total number of characters of each value and the total amount of unique characters between two given values.

Figure 4.43 Grouped by Difference Ratio

7. Click **Recode** to save the recoded data in a new column in the data table.


Making a new column preserves the original data.

Example of Splitting on a Comma

The Aircraft Incidents.jmp sample data table contains a column of city and state names separated by a comma. You can split the values in that column on the comma and recode the column with only state names.

1. Select **Help > Sample Data Library** and open Aircraft Incidents.jmp.
2. Select the Location column and select **Cols > Recode**.
3. Select **Split on** from the red triangle menu.
4. Select **Text** and type a comma next to **Split text**.
5. Do not change the default **First occurrence** setting. In these data, the state is the first occurrence after the comma.
6. Select **Text after** to recode the column with only state names.
7. Do not change the default **Keep text if no match** setting. You do not want to delete unmatched text.
8. Click **OK**.

Entries with a matching state name are recoded.

Figure 4.44 Recoded City, State Name

Count	Old Values (1537)	New Values (62)
7	Anchorage, AK	AK
5	Palmer, AK	
4	ANCHORAGE, AK	
4	FAIRBANKS, AK	


Example of Applying Recoded Values to a Different Column

When you recode a column, you can save the recoded values in a script. When you import or run the script, the column that you originally recoded is recoded again.

Suppose that you want to recode a different column with the same values. Save the recoded values in a formula column and then edit the formula.


1. Indicate the recoded values in the New Values column of the Recode window.
2. Select **Formula Column** from the list.
3. Click **Recode**.
4. Right-click the formula column and select **Formula**.
5. In the formula, select the column that was recoded.

In this example, the `sex` column was recoded.

Figure 4.45 Recoded Column

6. In the Columns list, select the column that you want to recode.


In this example, you want to recode the `gender` column

Figure 4.46 Recoding the gender Column

7. Right-click the gender column and select **Replace all occurrences of selected subexpression**.

Both occurrences of sex are replaced with gender.

Figure 4.47 Replacing All Occurrences



Edit the Data Table

- “Change Table Names”
- “Lock Tables”
- “Compress Tables”
- “Use Table Variables”
- “Create and Save Scripts”

Change Table Names

A data table’s name appears at the top of its window, in the table panel, and on all related analysis reports. You can change a data table’s name in any of the following ways:

- Select **File > Save As** and save as the new name.
- In the table panel, click table name, type the new name, and then press the Enter key.
- On Windows, select **Window > Set Title**.


Lock Tables

Locking a JMP data table prevents data and column properties from being added or edited. You can still assign row states, run analyses, and so on. To lock a data table, click the red triangle menu next to the table name in the table panel and select **Lock Data Table**.

A lock icon  appears next to the data table name. To unlock the file, select **Lock Data Table** again.

If you make a data table read-only outside of JMP (for example, by changing its properties on Windows), the data table contains a note informing you that it is locked. See Figure 4.48. This type of lock allows users to edit the data table, but not save the changes.

Figure 4.48 A Read-Only File



Compress Tables

Compressing a JMP (version 6 or higher) data table reduces the size of the stored file. You can still run analyses, assign characteristics, and so on. To compress a data table, click the red triangle menu next to the table name in the table panel and select **Compress file when saved** and save the data table.

After saving the data table, a compressed icon  appears next to the data table name. To decompress the file, select **Compress file when saved** again.


In addition, you can configure JMP to always use GZ compression when saving by selecting **Preferences > General > Save Data Table Columns GZ Compressed**.

Note: The **Compress file when saved** option only decreases the file size. This command does not affect the memory required to analyze the data. To reduce both the file size and memory required for analyzing, use **Cols > Utilities > Compress Selected Columns**. See [“Compress Selected Columns”](#) on page 222.

Use Table Variables

A table variable can contain textual information (for example, source information for the data), or a value that can be used by column formulas or JSL scripts. Table variable names appear in the table panel at the left of the data grid. See Figure 4.49.

Figure 4.49 Table Variables in the Table Panel



	Time	Cell Type	Treatment	Prior
1	3	Adeno	Standard	No
2	7	Adeno	Test	No
3	8	Adeno	Standard	Yes
4	8	Adeno	Test	No
5	12	Adeno	Standard	Yes
6	18	Adeno	Test	Yes
7	19	Adeno	Test	No
8	24	Adeno	Test	No

Uses for Table Variables

Use table variables in the following situations:

- To document tables
- In formulas
- In JSL scripts

Use Table Variables to Document Tables

Table variables are used primarily to document tables. Many sample data tables installed with JMP contain a table variable named Notes. This variable provides details about the data (for example, the source of the data). The example in Figure 4.49 shows a data table that contains Notes as one of its table variables. JMP also automatically creates table variables when you create a design table using the Design of Experiments commands in JMP. The design table has a table variable named Design with the name of the design type as its value.

Reference Table Variables in Formulas

Table variables can also be incorporated in formulas that you build using the Formula Editor. These formulas calculate values for a column by referring to a table variable. For details about constructing a formula that uses table variables, see [“Refer to Values in Columns and Table Variables”](#) on page 354 in the “Formula Editor” chapter.

Use Table Variables in JSL Scripts

You can also incorporate table variables into JSL scripts. See the Data Table chapter in the *Scripting Guide* for details.

Table Variable Actions

To add new table variables

1. In the Table panel, click the red triangle menu to the left of the data table name.
2. Select **New Table Variable**.
3. Give the variable a name and value in the boxes labeled **Name** and **Value**.
4. Click **OK**.

The table variable appears in the Table panel.

To view or edit table variables

1. Double-click on the content of an existing table variable.
2. Edit the content.

To edit a table variable name

1. Double-click the table variable name.
2. Edit the name.

To delete table variables

Select one or more table variables and press **Delete**, or right-click the selected variables and select **Delete**.

Concatenating Data Tables with Table Variables

See the [“Example of Concatenating Data Tables and Table Variables”](#) on page 320 in the “Reshape Data” chapter.

Create and Save Scripts

To automatically complete various analyses and tasks, you can create a JSL script and save it to the data table. See Figure 4.50. For details about writing data table scripts, see the Data Tables chapter in the *Scripting Guide*.

Figure 4.50 Scripts Saved With the Data Table

Big Class							
Distribution							
Bivariate							
Oneway							
Logistic							
Contingency							
Fit Model							
Set Sex Value Labels							
Set Age Value Labels							
Graph Builder Smoother Line							
Graph Builder Line and Bar Charts							
Graph Builder Line Chart							
Graph Builder Heat Map							
JMP Application: Six Quality Graphs							
Columns (5/0)							
name							
age							
sex							
height							
weight							
Rows							
All rows		40					
Selected		0					
Excluded		0					
Hidden		0					
Labelled		0					
			name	age	sex	height	weight
		1	KATIE	12	F	59	95
		2	LOUISE	12	F	61	123
		3	JANE	12	F	55	74
		4	JACLYN	12	F	66	145
		5	LILLIE	12	F	52	64
		6	TIM	12	M	60	84
		7	JAMES	12	M	61	128
		8	ROBERT	12	M	51	79
		9	BARBARA	13	F	60	112
		10	ALICE	13	F	61	107
		11	SUSAN	13	F	56	67
		12	JOHN	13	M	65	98
		13	JOE	13	M	63	105
		14	MICHAEL	13	M	58	95
		15	DAVID	13	M	59	79
		16	JUDY	14	F	61	81
		17	ELIZABETH	14	F	62	91
		18	LESLIE	14	F	65	142
		19	CAROL	14	F	63	84
		20	PATTY	14	F	62	85
		21	FREDERICK	14	M	63	93
		22	ALFRED	14	M	64	99
		23	HENRY	14	M	65	119
		24	LEWIS	14	M	64	92
		25	EDWARD	14	M	68	112
		26	CHRIS	14	M	64	99
		27	JEFFREY	14	M	69	113

Save a Report Script to a Data Table

Once you have run an analysis and you are in the report window, you can add a script to the data table. This script generates the JSL that reproduces your analysis.

To save a script to the data table

From the report window, click on the red triangle menu for the platform and select **Save Script > To Data Table**.

Example of Saving a Report Script to a Data Table

First, you create your analysis, then you save the script.

1. Select **Help > Sample Data Library** and open Big Class.jmp.
2. Select **Analyze > Fit Y by X**.
3. Select weight and click **Y, Response**.
4. Select height and click **X, Factor**.
5. Click **OK**.
6. From the red triangle menu for Bivariate Fit, select **Fit Line**.

7. From the red triangle menu, select **Save Script > To Data Table**.
8. In the Script Save As window, enter the name of the script.
9. To replace an existing script with the same name, select it from the Name list and select **Replace existing script**.
10. To save a script that has the same name as an existing script and use the same name, select **Append unique suffix**.
A number is added to the end of the script name.
11. Click **OK**.

The script is added to the bottom of the Table panel.


Tip: If you want a particular script to run automatically every time the data table is opened, name the script **OnOpen**. Only one script saved in the data table can be set to run automatically. If you name the script **Model** (or **model**) in a Fit Model script, the launch window is automatically filled in based on the script when you select **Analyze > Fit Model**.

Write a JSL Script for the Data Table

To add a script to a data table using JSL

1. Click the red triangle menu to the left of the data table name in the Table panel. See Figure 4.51.

Figure 4.51 Creating a Script



2. Select **New Script**.
3. Give the script a name by typing it into the box beside **Name**.
4. Add the script by entering JSL code into the box beside **Script**.
5. Perform one of the following actions:
 - If you want to run the JSL Debugger on the script to check it for errors, click **Debug Script**.
 - If you are finished editing the script, click **OK**. The script appears in the Table panel and the window closes.
 - If you are not finished editing the script and want to save it, click **Save**. The script appears in the Table panel and the window remains open for further editing.
 - If you want to run the script, click **Run**.

Run, Edit, Delete, or Copy Scripts

To run, edit, delete, or copy a script that is saved to the data table

1. In the Table panel, right-click the green triangle beside the script's name or right-click on the script name.

2. Select one of the following commands:

- Run Script
- Edit
- Delete
- Copy

Once you copy a script, you can then paste it into a script window or into the Table panel of another data table.

The Column Info Window

Set Column Attributes and Properties

Use the Column Info window to set specific properties on a column in a data table. Here are some examples of the actions that you can perform on a column:

- Change data and modeling types
- Change numeric formats
- Add formulas
- Specify restrictions on values or missing values
- Order categorical values or row data
- Save specification, control, or response limits
- Enter a known value for sigma

You can also standardize attributes and properties across multiple columns, assign a preselected analysis role to columns, and compress columns in a data table.

Figure 5.1 The Column Info Window

Add columns to 'Big Class'

Column Name:

☐ Lock

Data Type:

Modeling Type:

Format: Width:

☐ Use thousands separator (,)

Initialize Data:

Number of columns to add:

Contents


About the Column Info Window	257
About Modeling Types.....	260
The Short-Integer Format.....	260
Numeric Formats	261
Row State Columns.....	265
Initialize Data.....	267
Column Properties	268
Basic Column Properties	269
Properties That Validate Column Values.....	270
Properties That Attach Information to Column Values.....	271
Properties That Control the Display of Columns.....	276
Properties Used in Modeling and DOE.....	277
Properties Associated with Control Charts and Capability	278
Properties That Control How Columns Are Used in Platforms.....	279
SAS Properties	287
Virtual Join Properties	288
Additional Properties	289
Properties Assigned and Controlled by JMP	292
Standardize Attributes and Properties Across Columns.....	294
Recode Values	294
Standardize Attributes	295
Standardize Properties	295
Delete Properties.....	295
Example of Standardizing a Formula	296
Assign a Preselected Analysis Role	297

About the Column Info Window

Use the Column Info window to specify all of the attributes and properties of a column. You can access the Column Info window in any one of the following ways:

- Select **Cols > New Columns**.
- Click an existing column heading and select **Cols > Column Info**.
- Right-click an existing column heading and select **Column Info**.
- Double-click directly above a column name.
- In the Columns panel, right-click a column and select **Column Info**.

Figure 5.2 The Column Info Window



The Column Info window contains the following information:

Column Name Type or edit the name of the column.

Lock Lock the column so that none of its values can be edited. After you lock a column, the lock icon (🔒) appears next to the column name in the data table's Columns panel. If you add a formula to a column, the column automatically locks.

Data Type Select or change the data type of a column, which determines the following:

- How the column's values are formatted in the data grid
- How the column's values are saved internally
- Whether the column's values can be used in calculations

See [“About Modeling Types”](#) on page 260.

Choose from the following data types:

- Numeric columns contain only numbers (with or without a decimal point).
- Character columns contain any characters, including numbers. In character columns, numbers are seen as characters and are treated as discrete values instead of continuous values. The maximum field width for character values is 32,766 bytes.
- Row State columns contain row state information, which indicates whether the rows are excluded, hidden, labeled, colored, or marked. See [“Row State Columns”](#) on page 265.
- Expression columns contain JSL expressions that can range from simple entries to complicated statement sequences. In particular, an expression can correspond to a picture, a matrix, or an expression. You can drag-and-drop expressions, such as an image, from your desktop to cells in an expression column. See [“Expression Role”](#) on page 289.

Notes:

- If you change a column’s Data Type from Character to Numeric, any character values become missing data values and are not recoverable.
- If you enter non-numeric data in a column with a Numeric data type, a warning window is displayed, prompting you to change the data type to Character. Click **Try Again** to return to the data table to re-enter the value. Click **Change** to change the data type. Click **Revert** to cancel your edit and return the cell’s value.
- Short-integer formats might also be available. See [“The Short-Integer Format”](#) on page 260.

Modeling Type (Numeric or Character data types only) Select or change the modeling type of a column, which tells JMP how to treat the column’s values during analyses. You can change the modeling type to look at a variable in different ways. See [“About Modeling Types”](#) on page 260.

Choose from the following modeling types:

Continuous Only numeric data types. Continuous values are treated as continuous measurement values. JMP platforms use the numeric values directly in computations.

Ordinal Either numeric or character data types. JMP platforms treat ordinal values as discrete categorical values that have an order. If there are more than 50 discrete values, JMP treats the column as continuous.

- If the column has a numeric data type, the values are ordered according to their numeric magnitude.
- If the column has a character data type and a Value Order column property is saved to the column, values are ordered according to the Value Order property. Otherwise, values are ordered according to their alphanumeric data value ordering. However, in

special cases where the values have an obvious order, values are automatically ordered appropriately. See [“Value Ordering”](#) on page 273.

Nominal Either numeric or character data types. JMP platforms treat all values as discrete values with no implicit order.

Multiple Response Only character data types. Distinct entries in a single cell must be separated by commas. JMP platforms that support multiple response columns treat each entry in the comma-separated list as a separate data value. If your entries are separated by a character other than a comma, use the Multiple Response column property instead. See [“Multiple Response”](#) on page 283.

Unstructured Text Only character data types. These values are generally unique and are therefore not appropriate for categorical analysis. The Text Explorer platform is ideal for analyzing unstructured text values.

Vector Only expression data types. The entries in the cells are column or row vectors. JMP platforms that support the Vector modeling type recognize the vectors and treat them appropriately in calculations.

None Any data type. Use None as a modeling type when a column is not well represented by the other modeling types. For example, a column of pictures or ID values might be assigned the None modeling type. JMP launch windows do not allow you to assign roles to columns with the None modeling type.

Tip: You must use the Column Info window to change a column’s modeling type to Multiple Response, Unstructured Text, or Vector.

Format (Numeric data types only) Select or change the display format of a numeric column. See [“Numeric Formats”](#) on page 261.

Initialize Data (Appears only during new column creation) Specify the type of initial data values that you want to appear in the column. See [“Initialize Data”](#) on page 267.

Column Properties (Contains a list of different properties) Assign properties to columns. See [“Column Properties”](#) on page 268.

Tip: Click the **Next** button to continue adding columns.


About Modeling Types

A column in a JMP data table can contain different types of information. However, all information in a single column must have the same data and modeling types.

- When you import data, JMP guesses which data and modeling types to use. Therefore, you should verify that JMP has guessed correctly.
- When you manually insert data into JMP, you should assign a data type and a modeling type at that time.

Figure 5.3 illustrates the icons that identify the different modeling types.

Figure 5.3 Modeling Type Icons in the Columns Panel



Click on an icon to change the modeling type to **Continuous**, **Nominal**, **Ordinal**, or **None**.

For details, see [“Modeling Type”](#) on page 258.

Tip: You can select Continuous only if your data type is numeric. If the Continuous option is dimmed on the menu and you want to make the column continuous, you must first change the column’s data type in the Column Info window.

The Short-Integer Format

When you use the correct short-integer format for your data, you do not see any difference in how the numbers appear. However, the numbers occupy less disk space and use less memory. Short-integer formats must be activated in preferences to appear in the Column Info window.

To make short-integer formats available in the Column Info window

1. Select **File > Preferences** and click **Tables**.

2. Select the **Allow short numeric data format** option.
3. Click **OK** to return to the data table.

To store numeric data in short-integer format:

1. Double-click above the column name whose values you want to be short-integer.
The Column Info window appears.
2. From the Data Type menu, select **1-byte integer**, **2-byte integer**, or **4-byte integer**.

JMP stores values as integers in the range that you selected. The following numbers are examples:

- For 1-byte integer, the range of numbers that you can enter is from -126 to 127.
- For 2-byte integer, the range of numbers that you can enter is from -32,766 to 32,767.
- For 4-byte integer, the range of numbers that you can enter is from -2,147,483,646 to 2,147,483,647.

Numeric Formats

For numeric columns, the Format menu appears in the Column Info window. Specify the format to tell JMP how to display numbers in the column. For all format options, you can specify the number of total characters that you want the cells in the column to accommodate. See [“Specify Width”](#) on page 261.

For descriptions of the format options, see [“Numeric Format Options”](#) on page 261.

Tip: To add commas to values that equal a thousand or more, select the **Use thousands separator** option. You must account a space for each comma in the Width box, or else they might not appear. This option is available for the Best, Fixed Dec, Percent, and Currency formats.

Specify Width

When you specify a number in the Width field, be sure to include the total number of possible characters. Characters include: numbers, decimal points, commas, and currency symbols.

Numeric Format Options

Choose from the following numeric format options:

Best Allows JMP to consider the precision of each cell value and select the best way to show it. By default, the physical width of the column is 12 characters.

Fixed Dec Shows all values in the column rounded to the number of decimal places that you specify.

- To see only whole numbers, set the number of decimal places to zero.
- If the number of integers following the decimal point is smaller than the number of decimal places that you specify, zeros are added to reach the number of decimal places. For example, if the value is 1.23 and you type **5** in the Dec box, JMP shows the number with five decimal places: 1.23000.

Percent Multiplies numeric values by 100 and shows the number followed by a percent sign.

PValue Shows probability values. The default value of the width is 12. If a number is less than 0.0001, the number is displayed as <.0001. The format is mostly used in JSL scripts and rarely needed for a data table column.

Scientific Shows a number in standard scientific notation. If you enter the number 123456, it appears as 1.23456e+5. Select Dec to show the decimal points and enter the number of points.

Engineering Similar to Scientific, but the exponent is always a multiple of 3 and the Dec field represents significant digits.

Engineering SI Same as Engineering, but the exponent is replaced with an SI symbol.

Precision Rounds the number to a given number of significant digits. Specify the number of significant digits in the Dec field.

Currency Formats values with two decimal positions, thousands separators, and the currency sign that is specified in your computer's locale settings. The default width of the **Currency** format is 15. If you have a number that requires a wider field width, the format defaults to the **Best** format. Once assigned, the currency symbol appears in the column and in graphs that contain the column.

Date Shows all values in the column as a date. See [“Date Formats”](#) on page 263.

Time Shows all values in the column as a specific instance in time, such as 12/2/03 at 2:23 PM. See [“Time Formats”](#) on page 264.

Duration Shows all values in the column as a duration of time, such as hours, minutes, and seconds.

- **:day:hr:m**, **:day:hr:m:s** show a duration of time, such as 52:03:01:30, or fifty-two days, three hours, one minute, and thirty seconds.
- **hr:m**, **hr:m:s**, **min:s** shows a duration of time, such as 17:37, or seventeen hours and thirty-seven minutes.

Geographic Shows latitude and longitude number formatting for geographic maps. Latitude and longitude options include the following:

- DDD (degrees)
- DMM (degrees and minutes)
- DMS (degrees, minutes, and seconds)

In each format, the last field can have a fraction part. You can specify the direction with either a signed degree field or a direction suffix. To show a signed degree field, such as $-59^{\circ}00'00''$, deselect **Direction Indicator**. To show the direction suffix, such as $59^{\circ}00'00''$ S, select **Direction Indicator**.

To use spaces as field separators, deselect **Field Punctuation**. To use degrees, minutes, and seconds symbols, select **Field Punctuation**.

Custom Enables you to define a custom format for a numeric column. Select **Custom**, click **Set Custom Format**, and define the format in the Formula Editor window. For example, if you don't want to display the percentage sign next to a number, select this option and multiply the number by 100. This is an alternative to selecting the Percent format. Or if your data is in meters and you want to show it in kilometers with the unit, add the formula `Char(:value / 1000) || " km"`. You might also want to apply a date/time format that isn't available in the Format Date or Time lists, such as D/M/Y.

Date Formats

When you choose a Date format, you can also specify an Input Format. The Date format indicates how the date appears in the data table cells, and the Input Format indicates how you enter the date.

If you assign a date format to a numeric column that already contains data, then the numeric values are treated as the number of seconds since *January 1, 1904*. For example, if you have a numeric column with a cell value of 1,234,567,890 and you change the format to **Date > m/d/y**, the cell value appears as 02/13/1943.

The examples in Table 5.1 use the date of December 31, 2004.

Table 5.1 Date Formats

Format	Appears As
m/d/y	12/31/2004
mmddyyyy	12312004
m/y	12/2004
yyyyQq	2004Q4

Table 5.1 Date Formats *(Continued)*

Format	Appears As
d/m/y	31/12/2004
ddmmyyyy	31122004
ddMonyyyy	31Dec2004
Monddyyyy	Dec312004
y/m/d	2004/12/31
yyyymmdd	20041231
yyyy-mm-dd	2004-12-31
Date Long	Friday, December 31, 2004
Date Abbrev	Dec 31, 2004
Locale Date	Varies based on local OS setting. Here is an example: in the United States, the local OS setting is mm/dd/yyyy (12/31/2004).

Note: To change how a date appears in a graph without changing how it appears in a data table, see [“Change the Numeric Format of an Axis”](#) on page 456 in the “JMP Reports” chapter.

Time Formats

When you choose a Time format, you can also specify an Input Format. The Time format indicates how the time appears in the data table cells, and the Input Format indicates how you enter the time.

- You can add the number of hours, minutes, and seconds after midnight of the prepended date for the following date formats:
 - m/d/y
 - d/m/y
 - y/m/d
 - ddMonyyyy
 - Monddyyyy
 - Locale Date

For example, December 31, 2004 has a numeric value of 3,187,296,600, which represents 12/31/2004 12:10 AM.

- **:day:hr:m** and **:day:hr:m:s** show the number of days, hours, minutes, and seconds since *January 1, 1904*. For example, the results for December 31, 2004 are :36890:00:10: and :36890:00:10:00.
- **h:m:s** and **h:m** show the hours, minutes, and seconds portion of the date in the date field. For example, the results for December 31, 2004 at 12:10 AM are 12:10:00 AM and 12:10 AM.
- **yyyy-mm-ddThh:mm** and **yyyy-mm-ddThh:mm:ss** show the year, month, day, and time. For example, 2004-12-31T12:10:00. T is a literal value, representing itself.

Note: To change how a time appears in a graph without changing how it appears in a data table, see [“Change the Numeric Format of an Axis”](#) on page 456 in the “JMP Reports” chapter.

International Formats

If you are importing or entering data that contains formatting specific to country standards, you might need to make sure that your number formats are interpreted correctly. On Windows, access the Control Panel’s region and language option, and select the country for which the number should be formatted. On the Macintosh, from the Apple menu, select **System Preferences > Language & Text > Formats**, and select the correct country. On later versions of Macintosh, this option may appear under System Preferences > Language and Region.

Row State Columns

Similar to assigning row states to rows, you can create a column that contains only row state information. A row state column stores information about whether rows are excluded, hidden, labeled, colored, marked, or selected. To designate a column as a row state column, in the Column Info window next to Data Type, select **Row State**.

Figure 5.4 Row States in Rows and a Row State Column

	name	age	sex	height	weight	Row State
1	KATIE	12	F	59	95	•
2	LOUISE	12	F	61	123	•
3	JANE	12	F	55	74	•
4	JACLYN	12	F	66	145	•
5	LILLIE	12	F	52	64	•
6	TIM	12	M	60	84	•
7	JAMES	12	M	61	128	•
8	ROBERT	12	M	51	79	•

Since row state columns store the row states, you can apply them again later. Populate row state columns by copying them from the current row states or with column formulas.

To create a row state column

1. Select **Cols > New Columns**.
2. Next to Data Type, select **Row State**.
3. Click **OK**.

Populate the cells with new row state information or copy existing row state information from rows.

To populate cells with new row state information

1. To populate only certain rows in the row state column, highlight those rows. Or, to populate all rows in the column, highlight the row state column.
2. Right-click and select **Row States Cells**.
3. Select the row state that you want to apply.

To copy existing row state information

1. To populate only certain rows in the row state column, highlight those rows. Or, to populate all rows in the column, highlight the row state column.
2. Click the star icon (★) beside the column name in the Columns panel.
3. Select one of the following:
 - **Copy from Row States** replaces the row states in the column with the row states from the rows.
 - **Add from Row States** adds the row states from the rows to the row state column.
 - **Copy to Row States** replaces the row states in the rows with the row states from the column.
 - **Add to Row States** adds the row states from the row state column to the row states in the rows.

Permanently Select Cells

You can save a selection in a row state column just like you save other row state characteristics (hide, exclude, color, and so on). This places a “permanent” highlight on a cell.

To permanently select cells

1. Right-click a cell and select **Row States Cells > Select/Deselect**.
2. Repeat this for as many cells as you would like to select.
3. To remove the highlight, right-click on the cell and select **Row States Cells > Select/Deselect**.

Initialize Data

When you first add a new column to a data table, the Initialize Data menu appears in the Column Info window. Specify the type of initial data values that you want to appear in the new column. Initializing data is not available for Row State data types.

Select one of the following options:

Missing/Empty Places missing values in the column, represented by a black dot (•) for numeric data and a blank space for character data.

Constant Places one number or character in all of the column's rows. Enter the number or character into the box that appears. Enter any number of characters.

Today Places today's timestamp in the column for each row. This option is relevant only for the **Date** or **Time** formats.

Sequence Data Inserts sequential data based on the parameters that you specify. See [“Numeric or Character Sequence Data”](#) on page 268.

Random Inserts randomly generated data values into the column. Select a method for generating the random values:

Random Integer Enter minimum and maximum integer values. Integer values within this range are generated so that each occurs with approximately equal frequency.

Random Uniform Enter a range for continuous values. Random uniform values within this range are generated.

Random Normal Enter the mean and standard deviation for a normal distribution. Random normal values from this distribution are generated.

Random Indicator Enter up to three values and corresponding desired proportions. The proportions should sum to 1. Values are generated to have a distribution that corresponds as closely as possible to the specified proportions.

Note: This method generates values in the exact proportions that you specify unless the number of rows multiplied by one of the proportions results in a fractional value.

Suppose that there are n rows and that the three proportions are p_1 , p_2 , and p_3 . The values are generated as follows:

- Each row is assigned a random uniform value between 0 and 1.
- The rows are ordered according to their random uniform values.
- The rows corresponding to the smallest $\text{Round}(np_1)$ random uniform values are assigned the first value, the rows corresponding to the next smallest $\text{Round}(np_2)$

random uniform values are assigned the second value, and the remaining rows are assigned the third value.

Numeric or Character Sequence Data

To insert sequential data for numeric data

1. Next to **Data Type**, make sure **Numeric** is selected.
2. Next to **Initialize Data**, select **Sequence Data**.
3. In the **From** and **To** boxes, assign a starting and ending point.
4. In the **Step** box, assign the sequence.
5. (Optional) In the **Repeat each value N times** box, enter the number of times that you want each numeric value repeated.
6. Click **OK**.

For example, if you want the column to contain even numbers from 2 to 60, type 2 in the **From** box, 60 in the **To** box, and 2 in the **Step** box.

To insert sequential data for character data

1. Next to **Data Type**, make sure **Character** is selected.
2. Next to **Initialize Data**, select **Sequence Data**.
3. In the box next to **Add**, enter the character data and click **Add**.
4. (Optional) In the **Repeat each value N times** box, enter the number of times that you want each character value repeated.
5. Click **OK**.

Column Properties

A column property is information that is attached to a column. Once that information is entered, it is saved as part of the data table. You can select column properties and apply them to columns. There are some column properties that JMP creates for your convenience. Often, you can modify these.

Column properties are listed in the Column Info window's Column Properties menu. The area below the Column Properties menu shows column properties that have been saved to a column. To view or edit a property, select it from this list.

In the Columns panel of the data table, an icon appears next to the name of each column that contains a property, other than the Notes property. The Notes property is not denoted by an icon. Icons include the following:

-  Indicates that the range or list check property is applied
-  Indicates that the column contains a formula
-  Indicates that the column contains a property other than the Note, Range Check, or List Check column property

To assign a column property to one or more columns

1. Select the column or columns to which you want to assign a property.
2. Do one of the following:
 - Right-click the header area, select **Column Properties**, and select the property.
 - Right-click the header area, select **Column Info**, and select the property from the Column Properties menu.
 - Select **Cols > Column Info** and select the property from the Column Properties menu.
3. In the column property panel that appears, specify values and select options as appropriate.

Click **Apply** to add the column property or click **OK** to add the column property and close the column properties window.

A column might already contain a property that you want to apply to other columns. Use the Standardize Attributes command to apply that property to other columns. See [“Standardize Attributes and Properties Across Columns”](#) on page 294.

The following sections describe the properties that you can add to columns.

Basic Column Properties

Basic column properties that apply generally include Formula and Notes.

Formula

Insert a formula into a column to compute the values for that column. After a formula is added, the column is locked so that its data values cannot be manually edited (preventing invalidation of the formula).

- Click **Edit Formula** to create a formula. For details about creating a formula, see the [“Formula Editor”](#) chapter on page 349.
- If you do not want JMP to evaluate the formula, click **Suppress Eval**.
- If you do not want JMP to alert you about errors in your formula, click **Ignore Errors**.

- Once you have created a formula:
 - In the Column Info window, a visual of the formula appears at right. However, if your formula is long, only a portion of it might appear. Click and drag the borders of the formula box to resize it.
 - From the data table, edit the formula by clicking () next to the column name in the Columns panel.

Tip: To bypass the Column Info window when creating a formula, right-click on the column and select **Formula**.

Notes

Adds notes to the selected column.

Properties That Validate Column Values

The following properties help validate values in a column: Range Check, List Check, and Missing Value Codes.

Range Check

Range checking validates the data in a column. Set up the column to accept only numbers that fall within a specified range.

Select which formula to use to set up the range. x is the value entered into the column, a is the beginning of the range, and b is the end of the range.

- a = the lowest value that the column accepts
- b = the highest value that the column accepts
- For a single-sided range check, leave either a or b empty.
- From the data table, modify the range check by clicking () next to the column name in the Columns panel.

List Check

List checking validates the data in a column. Set up the column to accept only the individual values that you specify. List checking is useful when you want to specify how to order the data in your graphs or plots.

- You can use up to 127 values.
- Use the buttons to add new values, change, or reverse the order of values, and remove values.

- Once a list check is set on a column, the cursor changes to  when positioned over the cells. If you try to enter a value not included on the validation list, a warning message appears.
- To see a menu of acceptable values, right-click a cell and select **List Check Values**. You can select the cell value from the menu instead of entering it into the cell.
- From the data table, modify the list check by clicking  next to the column name in the Columns panel.

Missing Value Codes

Use missing value codes to specify column values that should be treated as missing. For example, sometimes the value 99 is used as a placeholder to represent missing values, or perhaps several values are used to represent different types of missing values.

Note: The Missing Value Codes column property is an extended attribute. If you plan to export to a SAS 9.4 server or Save As a SAS 9.4 file format, you should enable extended attributes in the SAS Integration Preference page. See [“SAS Integration”](#) on page 620 in the “JMP Preferences” chapter for details. Alternatively, you should select **Store table and column properties in SAS 9.4 extended attributes** in the Save As window. If extended attributes are not selected, JMP exports or saves Missing Value Codes as missing values. Extended attributes are supported only by SAS 9.4. Earlier versions of SAS disregard any extended attributes.

To remove missing value codes for a single column

1. In the Columns panel of the data table, next to the column, click  > **Missing Value Codes**.
2. Missing Value Codes is highlighted in the list. Click **Remove**.
3. Click **OK**.

To remove missing value codes across multiple columns

1. Select the columns containing the missing value codes that you want to delete.
2. Select **Cols > Standardize Attributes**.
3. Under Delete Properties, click **Column Properties > Missing Value Codes**.
4. Click **OK**.

Properties That Attach Information to Column Values

The following column properties attach information that is used in reports and plots to the values in a column:

- Value Labels

- Value Scores
- Value Ordering
- Row Order Levels
- Value Colors
- Color Gradient
- Short Name
- SPSS Name
- SPSS Label
- SPSS Label
- SAS Name
- SAS Label
- Long Name
- Question

Value Labels

Use value labels to show a label in the data table instead of a value. A label appears for each instance of the value. You can show the original values by double-clicking a label within a cell.

- Enter the value that you want to assign a label to in the Value box.
- Enter the label that you want to appear in the Label box.
- To use ranges, click **Allow Ranges** then specify the lower and upper values. If Allow Ranges is selected, Value Labels can be non-integers. Graph Builder can use the Value Labels for the x- and y-axes.

Tip: To assign a label to missing values, enter a period (.) for the lower bound and leave the upper bound empty. To assign a label to all other values, enter three periods (...) for the lower bound and leave the upper bound empty.

- Add, change, or remove labels.

Tips:

- To turn off value labels in the data table without deleting the value labels that you have set up, in the Column Properties window, deselect **Use Value Labels**. Or, to quickly show or hide value labels in a data table, right-click on a column and check or uncheck **Use Value Labels**.
- When your data table contains value labels, using the **Search** commands searches for actual values, but does not search for labels.

- When your data table contains value labels, the **Row Editor** displays the label, and when the cell is highlighted for editing, it shows the actual value.
- If you copy and paste a cell with a value label, the actual value is pasted.
- In a formula, when you reference a column using value labels, hold your mouse pointer over the value label to see the actual data value.

Value Scores

Use value scores to indicate a value-score pair for categorical data columns. The value is a data value and the score is a number. This property associates a data value with a score (for example, the column's data value could be "not satisfied", "satisfied", "very satisfied"). The user could assign a score of 0 to "not satisfied", 50 to "satisfied", and 100 to "very satisfied". Those scores are then used for computation purposes like computing the mean. See the Categorical chapter in *Consumer Research* for an example.

To use value scores

1. In the data table, right-click on the column and select **Column Info**.
2. From the **Column Properties** list, select **Value Scores**.
3. Enter the value that you want to assign a label to in the Value box (for example, "satisfied").
4. Enter the label that you want to appear in the Score box (for example, "50").
5. Click **Add**, **Change**, or **Remove**.
6. Click **OK**.

Value Ordering

Value Ordering assigns an ordering to values in a column that is then used in reports and plots. The default ordering for reports and plots is alphanumeric data value ordering, except in the following cases, where values are automatically ordered appropriately:

- January, February, March, April, May, June, July, August, September, October, November, December
- Jan, Feb, Mar, Apr, May, Jun, Jul, Aug, Sep, Oct, Nov, Dec
- Sunday, Monday, Tuesday, Wednesday, Thursday, Friday, Saturday
- Very Low, Low, Medium Low, Medium, Medium High, High, Very High
- Strongly Disagree, Disagree, Neutral, Indifferent, Agree, Strongly Agree
- Failing, Unacceptable, Very Poor, Poor, Bad, Acceptable, Average, Good, Better, Very Good, Excellent, Best

Tip: You can anonymize Value Ordering so that the Value Ordering properties are renumbered. To do this, highlight the column with the Value Ordering column property and select **Tables > Anonymize**.

When you construct a design using a DOE platform, the Value Ordering column property is automatically assigned to categorical factors. For examples of assigning and editing the Value Ordering column property, see the Column Properties chapter in the *Design of Experiments Guide*.

Note: If you use both the Value Ordering and Row Order Levels properties, the Value Ordering property overrides the Row Order Levels.

Row Order Levels

Use the Row Order Levels property to sort the column values by their occurrence in the data, rather than sort by value.

The row ordering applies only to the selected column. To apply it to other columns, repeat the above steps for each column, or use the Standardize Attributes command. See [“Standardize Attributes and Properties Across Columns”](#) on page 294.

Tip: To show the analyzed row data in another order (besides according to their values or their occurrence in the data table columns) use the Value Ordering property. See [“Value Ordering”](#) on page 273. The Value Ordering property overrides the Row Order Levels property when both are evoked.

Value Colors

Use value colors to assign the values of a nominal or ordinal column a certain color or range of color themes. The column's values appear with the assigned color in all applicable graphs, such as mosaic plots and plots with color-coded legends. You can also color the values in the data table column.

- To change the color of a specific value, right-click a color circle and select a color.
- To use a color theme, click **Color Theme** below the list of value colors and then select the color.
- To create a custom color theme, see [“Create a Custom Color Theme”](#) on page 275.
- To also color the cells in the data table, select **Color Cell by Value**.
- Select from the options in the Macros menu. See [“Macros Options”](#) on page 275.

Create a Custom Color Theme

To create a custom color theme

1. Click **Color Theme** below the list of value colors in the column properties.
2. Open the Custom Color Theme outline.
3. Click **New**.
4. Create the color using the sliders.
5. Name the color and click **Save**.
6. Click **OK**.

You can access the new custom color in the Color Theme menu the next time you use the Value Colors property. The color is also saved in your preferences. See [“Create Color Themes”](#) on page 214 in the “Enter and Edit Data” chapter for details about creating color themes.

Macros Options

The Macros menu contains the following options:

Gradient between ends Sets the colors of the top and bottom values. JMP applies a color gradient across the entire range of values. Use this command to make all of the colors in between for the other levels.

Gradient between selected points Sets the colors of the top and bottom values so that JMP can apply a color gradient to a range of values that you have highlighted in the Value Colors list.

Reverse colors Reverses the color of the values from top to bottom or bottom to top.

Revert to old colors Sets the colors back to their original color values.

Color Gradient

Select a color gradient to color a continuous column in a plot. Color gradients are supported in the Graph Builder, Bubble Plot, Treemap, and Cell Plot platforms.

- To also color the cells in the data table, select **Color Cell by Value** above the list of value colors.
- Select a color gradient from the menu.
- Enter the minimum, maximum, and center values:
 - Minimum values reflect the color at the left of the gradient.
 - Maximum values reflect the color at the right of the gradient.
 - Center values reflect the color in the middle of the gradient.

Note: To see color gradients in Graph Builder, you must assign the column to the Color zone. To see color gradients in Bubble Plot and Treemap, you must assign the column to the Coloring role.

Short Name, SPSS Name, and SAS Name

These column properties insert the specified long name in a Categorical structured report when the Show Columns Used in Report red triangle option is selected.

SAS Name is also a column property that is added when you import SAS data. It contains the name of the variable in the SAS data set. Modifying it will affect the SAS data set if the data are exported back to SAS.

SPSS Label, Long Name, SAS Label, and Question

These column properties insert the specified short name in a Categorical structured report when the Show Columns Used in Report red triangle option is selected.

SAS Label is also a column property for imported SAS data. It contains the description of the column in the SAS data set. Modifying it will affect the SAS data set if the data are exported back to SAS.

Properties That Control the Display of Columns

The Axis and Units column properties control how column values are displayed.

Axis

Use the Axis property to change the default axis settings for a column. JMP automatically uses your settings when the column appears in an analysis. See [“Customize Axes and Axis Labels in the Axis Settings Window”](#) on page 455 in the “JMP Reports” chapter for details about the properties.

When you add the Axis column property, you can save all column properties or only the properties that you changed. For example, you might want the axis to start at 0 and are not concerned about the upper bounds of the axis. Set the minimum axis value and select **Changed Properties Only** from the Save to column list.

To set default axis properties for a column from within a graph

1. Create the graph.
2. Change the axis to your preferred specifications.
3. Right-click the axis and select **Save to Column Property**.

Units

Use the Units property to specify the measurement units that were used to collect the data for the column. The units appear in parentheses after the column name in the data table and when the column appears in plots. For example, you might want a column to indicate that age values are measured in months, or that a monetary value is in thousands of dollars.

Properties Used in Modeling and DOE

When you construct a design using the DOE platforms, column properties are saved to the resulting design table. However, some of these column properties are useful in general modeling situations. To use the properties more generally, you can specify them yourself.

Note: The Column Properties chapter in the *Design of Experiments Guide* describes the properties associated with DOE in detail and presents examples. Only a brief description of these properties is provided here.

The following column properties are used in modeling and DOE:

- Response Limits
- Design Role
- Coding
- Mixture
- Factor Changes

Response Limits

The Response Limits column property defines a desirability function for the response. The Prediction and Contour Profilers use desirability functions to find optimal settings. For more information, see the Column Properties chapter in the *Design of Experiments Guide*.

Design Role

The Design Role column property indicates how a column is used in both a designed experiment and in the model used to fit the data. For example, a column could represent a continuous factor, a categorical factor, a blocking factor, and so on. For more information, see the Column Properties chapter in the *Design of Experiments Guide*.

Coding

The Coding column property applies a linear transformation to the data in a numeric column. The data are transformed to -1 and $+1$ based on bounds that you specify. JMP then uses the

transformed data values whenever the column is entered as a model effect in the Fit Model platform. For more information, see the Column Properties chapter in the *Design of Experiments Guide*.

Mixture

The Mixture column property is useful when a column in a data table represents a component of a mixture. The components of a mixture are constrained to sum to a constant. The Mixture column property identifies a column as a mixture component and defines a coding for that column. For more information, see the Column Properties chapter in the *Design of Experiments Guide*.

Factor Changes

The Factor Changes column property indicates how difficult it is to change factor settings in a designed experiment. It is used to create and analyze split-plot, split-split-plot, and two-way split-plot designs. For more information, see the Column Properties chapter in the *Design of Experiments Guide*.

Properties Associated with Control Charts and Capability

The Specification Limits, Control Limits, Sigma, and Process Capability Distribution properties are associated with control charts and capability.

Spec Limits

Specification limits are used when you perform a capability analysis using the Distribution and Capability platforms. Note that in old data tables, the column property might be named Capability Analysis.

You can specify any combination of a Lower Spec Limit, an Upper Spec Limit, or a Target. The **Show as Graph Reference Lines** option displays the specification limits and target that you specify as reference lines on appropriate plots.

Tip: To add specification limits to several columns at once, see the Statistical Details appendix in the *Quality and Process Methods* book.

Control Limits

The Control Limits column property enables you to specify control limits for a column, rather than having JMP calculate control limits from the values in the column. This is useful when you are comparing process data to historical control limits.

The Control Limits column property can be assigned only to a numeric column. To assign the Control Limits column property, select the control chart type and then enter the requested values. If any of these entries are missing, JMP replaces it with a calculated value in the control chart.

Sigma

Use the Sigma property to enter a known sigma value. This value is used by applications such as control charts or any application that requires a sigma value to complete computations. If no sigma value is supplied, sigma is calculated from the sample.

Process Capability Distribution

The Process Capability Distribution column property specifies a process distribution for the column. The Process Capability Distribution column property is used only in the Process Capability platform. See also [“Distribution and Process Capability Distribution”](#) on page 280.

QC Alarm Script

You can generate automatic alarms by writing a script and storing it as a column property or data table property named QC Alarm Script.

The following QC Alarm Script automatically writes a message to the log whenever a test fails:

```
Write(
    "Out of Control for test ",
    qc_test,
    " in column ",
    qc_col,
    " in sample ",
    qc_sample
)
```

Properties That Control How Columns Are Used in Platforms

The following properties control how columns are used in platforms:

- Distribution
- Time Frequency
- Map Role
- Supercategories
- Multiple Response

- Profit Matrix
- Informative Missing

Distribution

For a column that contains continuous numeric data, use the Distribution property to select a distribution type to fit to the column. This distribution is used in the Distribution platform and is used in the Process Capability platform under certain conditions. See [“Distribution and Process Capability Distribution”](#) on page 280.

When you obtain a Distribution report (by selecting **Analyze > Distribution**) for the column, JMP automatically estimates a fit using the specified distribution. A curve representing the fitted distribution is superimposed on the histogram.

If you set both the Distribution property and the Spec Limits property, then the Distribution platform produces a Capability Analysis report that is based on the distribution specified in the Distribution column property.

Note: In old data tables, the Capability Analysis column property might have been assigned to a column to specify spec limits. We recommend that you use the Spec Limits property instead.

Distribution and Process Capability Distribution

If you analyze a column that does not contain a Process Capability Distribution property using the Process Capability platform, the distribution specified in the Distribution column property results in a nonnormal fit in the Process Capability platform:

- If the distribution specified in the Distribution property is supported in the Process Capability platform, the Process Capability platform uses the specified distribution.
- If the distribution specified in the Distribution property is not supported in the Process Capability platform, the Process Capability platform uses a Johnson fit.

If both the Distribution and Process Capability Distribution column properties are saved for a given column, then the properties behave as follows:

- The distribution specified in the Distribution column property is used in the Distribution platform.
- The distribution specified in the Process Capability Distribution column property is used in the Process Capability platform.

Time Frequency

When using the Time Series platform, you can assign the Time Frequency property to data. The Time Frequency property specifies the frequency with which the data is reported (such as

annually, quarterly, monthly, and so on). Specifying a time frequency allows JMP to take things like leap years and leap days into account. If no frequency is specified, the data is treated as equally spaced numeric data.

Map Role

If you have created a data table that contains boundary data (such as countries, states, provinces, or counties), to see a corresponding map in Graph Builder, use the Map Role property.

Note the following:

- If the custom boundary files reside in the default custom maps directory, then you need to specify only the Map Role property in the -Name file.
- If the custom boundary files reside in an alternate location, then you must specify the Map Role property in the -Name file and in the data table that you are analyzing.
- The columns that contain the Map Role property must contain the same boundary names, but the column names can be different.

For an example using the Map Role property, see the Create Maps chapter in the *Essential Graphing* book.

To add the Map Role property into the -Name data table

1. Right-click on the column containing the boundaries and select **Column Properties > Map Role**.
2. Select **Shape Name Definition**.
3. Click **OK**.
4. Save the data table.

To add the Map Role property into the data table that you are analyzing

Note: Perform these steps only if your custom boundary files do not reside in the default custom maps directory.

1. Right-click on the column containing the boundaries and select **Column Properties > Map Role**.
2. Select **Shape Name Use**.
3. Next to **Map name data table**, click  to browse to a -Name map data table. You can enter the relative or absolute path.

If the map data table is in the same folder, enter only the filename. Quotation marks are not required when the path contains spaces.

4. Next to **Shape definition column**, enter the name of the column in the map data table whose values match those in the selected column.
5. Click **OK**.
6. Save the data table.

When you generate a graph in Graph Builder and assign the modified column to the Shape zone, your boundaries appear on the graph.

Supercategories


When a data set contains ratings (for example, on a five-point scale), you might want to know the percent of the responses in a subset of those ratings. Add a Supercategories column property to group specific categories into one category.

Supercategories are supported only in the Categorical platform.

To add the Supercategory property to a data column

1. Right-click the column that contains categories that you want to group.
2. Select **Column Properties > Supercategories**.
The column properties window shows the Supercategories options (Figure 5.5).
3. Select the categories in the Column's Categories list that you want to group.
4. Enter a descriptive name next to Supercategory Name.
Leave the name blank, and JMP names the supercategory after the categories that you selected.
5. Click **Add** to create the supercategory.
6. From the **Supercategories** red triangle menu, select from the following options:
 - **Options > Hide**: Hides data in the selected supercategory from reports and graphs.
 - **Add All**: Creates a supercategory from all of the categories in the column.
 - **Add Mean** and **Add Std Dev**: Calculate statistics for value scores. See the *Consumer Research* book for more information.
7. Click **OK** to add the property to the column.

Figure 5.5 Example of a Supercategories Configuration




Multiple Response

The term *multiple response* refers to the situation where the cells in a column contain more than one response value. For example, many cells in the Brush Delimited column in the Consumer Preferences.jmp sample data table contain multiple values. For example, row 6 contains “Wake, After Meal, Before Sleep”.

Add the Multiple Response column property if you want to specify a delimiter other than the comma. Otherwise, change the column’s modeling type to Multiple Response in the Column Info window. See [“About Modeling Types”](#) on page 260 for details about the Multiple Response modeling type.

JMP automatically assigns the Multiple Response modeling type to data tables saved in JMP 12 or lower. The column must contain the Multiple Response column property, and the delimiter must be a comma for the automatic assignment to take place. JMP does not remove the Multiple Response column property, though you might choose to do so.

Figure 5.6 Multiple Response Configuration Window



Note: You can use the Multiple Response property in the Categorical platform. See the Categorical platform chapter in the *Consumer Research* book for details. You can also use this property in the Data Filter. See [“The Data Filter”](#) on page 415 in the “JMP Reports” chapter. If the delimiter is a comma, consider using the Multiple Response modeling type instead.

Profit Matrix

Use the Profit Matrix column property to assign weights to the levels of a nominal or ordinal response variable for a predictive model. For a nominal response, you can specify the profit matrix entries using a probability threshold.

Note: The Profit Matrix column property is used by the following platforms: Model Comparison, Partition, PLS, and Fit Model. The personalities in Fit Model that use the Profit Matrix column property are Generalized Regression, Nominal Logistic, and Ordinal Logistic.

Profit Matrix

When you select **Column Properties > Profit Matrix**, a matrix template appears, with a row and column for each value in the selected column. The Actual levels are shown as rows and the

predicted levels are shown as columns. Correct decisions are those on the diagonal, where the predicted level equals the actual level.

- For diagonal entries, enter values that reflect profits or weights for correct decisions.
- For non-diagonal entries, enter values that reflect profits (or losses) or weights for incorrect decisions.
- For situations where no prediction is made, use the Undecided column to indicate associated profits or losses.

Probability Threshold Specification for Profit Matrix

When the response is binary, additional options appear beneath the profit matrix template. These options enable you to specify a probability threshold instead of entering weights directly into the profit matrix.

Specify the Target and Probability Threshold. Then click Set to update the profit matrix.

Target The level whose probability is modeled.

Probability Threshold A threshold for the probability of the target level. If the probability that an observation falls into the target level exceeds the probability threshold, the observation is classified into that level.

Set Enters values into the profit matrix template that reflect your specifications for Target and Probability Threshold. For details, see [“Probability Threshold Calculations”](#) on page 284.

Probability Threshold Calculations

Denote the threshold probability by t . When you click Set, the entries in the profit matrix are assigned as follows:

- 0 for each diagonal entry, reflecting no loss from correct decisions
- -1 for a prediction of the target level when the actual value is the non-target level
- $-t/(1 - t)$ for a prediction of the non-target level when the actual value is the target level

This implies that the profits for classifying into the two levels are given as follows:

$$\text{Profit for Target Level} = \left(\frac{-t}{1-t} \right) \text{Prob}[\text{Non-Target Level}]$$

$$\text{Profit for Non-Target Level} = -\text{Prob}[\text{Target Level}]$$

The Most Profitable Prediction is the level whose profit is the larger of these two values. It follows from the two Profit equations above that an observation is assigned to the target level whenever $\text{Prob}[\text{Target Level}]$ is at least t .

Profit Matrix and Predictive Models

For a nominal or ordinal column with the Profit Matrix column property, most modeling platforms enable you to save formula columns that reflect profit matrix entries. Fit your model and then select the Save Prediction Formula or Save Probability Formula option. In addition to saving the usual prediction formulas to the data table, JMP saves the following analogs of the usual formula columns:

- Profit for <level>: For each level of the response, a column gives the expected profit for classifying each observation into that level.
- Most Profitable Prediction for <column name>: For each observation, gives the level of the response with the highest expected profit.
- Expected Profit for <column name>: For each observation, gives the expected profit for the classification defined by the Most Profitable Prediction column.
- Actual Profit for <column name>: For each observation, gives the actual profit for classifying that observation into the level specified by the Most Profitable Prediction column.

See [“Example of a Profit Matrix for More Than Two Levels”](#) on page 285. For an example of using a profit matrix in modeling, see the Partition chapter in the *Predictive and Specialized Modeling* book.

Example of a Profit Matrix for More Than Two Levels

The example below (Figure 5.7) shows a profit matrix for the Airline column in the Travel Costs.jmp sample data table.

Figure 5.7 Example of Profit Matrix Window

Profit Matrix

Each matrix entry is the profit if you predict the response in the column when the response in the row is the actual response.

Enter values that reflect profits for correct decisions on the diagonal.
Enter values (usually negative) that reflect profits for incorrect decisions elsewhere.
Use the Undecided column to reflect profits for an alternative decision.

When you save prediction formulas, these values will be used to create best decision columns.
The best decision is the one with greatest expected profit.

Decision or Prediction

	Carrier 1	Carrier 2	Carrier 3	Carrier 4	Undecided
Actual Carrier 1	25	5	-5	-25	.
Carrier 2	5	20	-10	-30	.
Carrier 3	55	50	70	20	.
Carrier 4	45	40	30	60	.

To see how the values in this profit matrix were assigned, consider a travel agency that uses four airlines, Carrier 1 to Carrier 4, to service its customers. For each ticket sold, the agency realizes a profit that depends on the carrier selected by the customer. When the agency recommends, or *predicts*, a carrier, it reserves a ticket for a small fee. If the customer decides to use the predicted carrier, the agency profits by a certain amount less the reservation fee. However, if the customer decides to take a different carrier, the agency loses the reservation fee and must pay another reservation fee. The agency's profit is lower due to the incorrect prediction.

Suppose that the reservation fees for Carriers 1 through Carrier 4 are \$15, \$20, \$30, and \$50, respectively, and that the profits from ticket sales are \$40, \$40, \$100, and \$110, respectively.

If the agency recommends Carrier 1 to a customer who then decides to purchase the ticket, the agency reserves a ticket for \$15 and then receives \$40 for a net profit of \$25. If the agency predicts that a customer will choose Carrier 4 but the customer chooses Carrier 1, the agency loses \$50 for the Carrier 4 reservation and must also pay \$15 for the reservation on Carrier 1. This gives the agency a net loss of $\$40 - \$50 - \$15 = -\$25$.

Example of Using Probability Threshold to Define the Profit Matrix

The sample data table Liver Cancer.jmp gives disease Severity ratings for 136 patients. You are interested in modeling Severity using the predictors given in the columns from BMI to Jaundice. The usual prediction formulas for a model classify a patient into the Severity level that is most probable. However, classifying a patient as having Low severity when in actuality the patient's severity is High is a more costly error than classifying a patient as having High severity when in actuality the patient's severity is Low. As a result, you want to assign a higher cost to misclassifying a patient as Low, when the patient's severity is actually high.

You can assign this higher cost by setting a probability threshold. With input from experts, you determine that the following is a good strategy: Classify into the High level of Severity any patient whose predicted probability of being in the High level exceeds 0.4.

1. Select **Help > Sample Data Library** and open Liver Cancer.jmp.
2. Select the Severity column and select **Cols > Column Info**.
3. Select the Profit Matrix column property.
4. Change the Target to **High**.
5. Enter 0.4 as the Probability Threshold.
6. Click **Set**.

The profit matrix updates to show the corresponding weights.

Figure 5.8 Profit Matrix Showing Weights Corresponding to Probability Threshold

Profit Matrix

Each matrix entry is the profit if you predict the response in the column when the response in the row is the actual response.

Enter values that reflect profits for correct decisions on the diagonal.
Enter values (usually negative) that reflect profits for incorrect decisions elsewhere.
Use the Undecided column to reflect profits for an alternative decision.

When you save prediction formulas, these values will be used to create best decision columns.
The best decision is the one with greatest expected profit.

		Decision or Prediction		
		High	Low	Undecided
Actual	High	0	-1	.
	Low	-0.6667	0	.

To create a profit matrix for a binary response, enter a Target and Probability Threshold.
If the predicted probability exceeds the threshold, the best decision will be the target.

Target: High ▾ Set

Probability Threshold: 0.4

The profit matrix shows that the loss for misclassifying a patient with High severity as having Low severity is -1, while the loss for misclassifying a patient with Low severity as having High severity is smaller, -0.6667.

Informative Missing

The Informative Missing column property directs most fitting platforms to use a coding system for columns that contain missing values. For continuous columns, the coding system consists of two columns. The first column is a column of the original values with missing values replaced by the mean of the nonmissing values; the second column is an indicator column to denote which rows are missing. For categorical columns, missing values are treated as a distinct level of the column.

SAS Properties

SAS Label, SAS Name, SAS Format, and SAS Informat are assigned to columns when you import a SAS data set. You can change the value in the column property to control the label, name, format, or informat of the column that gets created in the SAS data set if the data is exported back to SAS.

Virtual Join Properties

Virtual Join links a main data table to one or more auxiliary data tables. The feature enables the main data table to access data from the auxiliary data tables without physically joining the tables. See [“Virtually Join Data Tables”](#) on page 335 in the “Reshape Data” chapter for details.

The Link ID and Link Reference column properties make the linking possible.

Notes:

- The data types of the Link ID and Link Reference columns must match.
- Link ID and Link Reference do not work for Row State and Expression data types.
- Consider adding the Link ID column property before adding the Link Reference column property so that the referencing column in the main table has a column to link to.

Link ID

The Link ID column property marks a column in the auxiliary data table as the ID column. That is, the rows of the data table are uniquely identified by the values of the ID column. The data table that has a Link ID column property is referred to as the *referenced* data table.

To add the Link ID column property, select the column, select **Cols > Column Info** and then select **Link ID** from the Column Properties list. Make sure that the Link ID checkbox is selected and click **OK**. The selected checkbox indicates that the column is the ID column for the data table.

Link Reference

The Link Reference column property maps a column in the main data table to the ID column in the referenced data table. The column that has a link reference is referred to as the *referencing* column. The referencing column can look up the data of the auxiliary data tables through the ID column.

To add the Link Reference column property, select the column, select **Cols > Column Info**, and then select **Link Reference** from the Column Properties list. Enter the path to the main table and click **OK**. If you enter the path correctly, the referenced columns show up in the Columns panel of the main table after you click **OK**.


Notes:

- The path is case sensitive.
- Consider putting the data tables in the same folder. Then you can omit the directory name from the Link Reference property and include only the data table name. Otherwise, include the full path to the data table (such as `c:/users/marie/My Data.jmp`).

- You can also increase portability by using a JMP path variable in the Link Reference path. Figure 5.9 shows an example. Enter a forward slash in the path to share the data tables with both Windows and Macintosh users. See the Types of Data chapter in the *Scripting Guide* for details about path variables.
- You can avoid entering the path by right-clicking a column to add the Link Reference property. See [“Example of Virtually Joining Columns”](#) on page 337 in the “Reshape Data” chapter for details.
- Select Row State Synchronization options to synchronize row states in data tables that contain virtually joined columns. See [“Example of Virtually Joining Columns and Showing Row States”](#) on page 340.

Tip: You can specify that the linked column name be used in virtually joined columns. This option lets you specify a shorter column name (for example, Cheese instead of Cheese[Choice]). In the Link Reference column property, select **Use Linked Column Name**.

Figure 5.9 Link Reference Column Property Definition



Additional Properties

There are three additional properties: Expression Role, Event Handler, and Other.

Expression Role

When you import a column of data that contains image data, the data type is set to Expression to show the data as pictures. Or you can assign the Expression data type in the column properties.

To customize how the image looks in the data table cell, or to display matrices and expressions as images, add the Expression Role column property. The default is set to Picture. If the Expression Role is set to Picture and the expression is a picture, then the expression evaluates

to a picture and the picture appears in the data table. Otherwise, the expression shows as a JSL expression. Change this setting to alter how expressions are used.

Note: Expression columns that contain images greater than 32KB in size are truncated when saved to Microsoft Excel. Those expression columns are not restored when imported back into JMP.

Select from the following options:

Picture If the expression contains picture data, the column evaluates and the picture is displayed.

Matrix If the expression contains a matrix, the column evaluates and the matrix is displayed. Otherwise, the data is displayed as an expression.

Expression If the expression is simply an expression, use this option to display it in the column.

Use Expression when you want to work with an expression that might contain picture data, but you want to prevent JMP from displaying the image.

Picture expressions To customize how images appear in a data table cell, select one of the following options after selecting Picture from the list.

maximum width and height Specifies the maximum width and height of the image in the data table cell.

Stretch Enlarges a small image to fill the data table cell.

Preserve aspect ratio Maintains the image's ratio of width to height in the data table cell. Selected by default.

Add a decorative frame to small images in a data table Displays a beveled edge around small images in the data table cell.

To drag images into an expression column

1. Create a new column in a data table.
2. Right-click the column, select **Column Info**, and then select the **Expression** data type.
3. Right-click the column, select **Column Properties**, and then select **Expression Role**.
4. Select options as described above.
5. Navigate to the website that contains the image that you want in your data table. You can also use an image that is on your computer.
6. Select the image, and drag it into an empty cell in the expression column.
Resize the cell to make the image larger.

The SAS Offices.jmp and Big Class Families.jmp sample data tables show an example of an expression column.

Tips:

- You can also import data that contains a column of images to create an expression column.
- For details about what you can do with images in an expression column, see [“Use Images as Markers”](#) on page 445 and [“Display Images on Hover Labels”](#) on page 450 in the “JMP Reports” chapter.

To add an expression column using Summary

1. Select **Help > Sample Data Library** and open CrimeData.jmp.
2. Select **Tables > Summary**.
3. Select State, and click **Group**.
4. Select Total Rate, and click **Statistics > Histogram**.
5. Click **OK**.

A new data table appears that contains a new expression column with images of histograms. Resize the row to make images larger.

For more details about Summary, see [Chapter 8, “Summarize Data”](#).

6. Right-click the Histogram(Total Rate) column, and select **Column Info**.
Notice the column’s data type is set to Expression.
7. Select **Expression Role** from the Column Properties menu.

The Expression Role is automatically set to Picture. In the rare case that a picture needs to be displayed as an Expression, change the setting to Expression.

8. Click **OK**.

Expression Role is assigned to the Expression column.

Event Handler

Use the Event Handler column property to define hyperlinks in a text column. The hyperlinks can be used to open web pages and other documents.

Add the Event Handler to a column of URLs to open the URLs in a browser. You can also modify the placeholder scripts on the column property to open different kinds of resources. For example, in a data table of geographical data, you might edit the Click script to display a Google map when the user clicks the hyperlink in the data table. The SAS Offices.jmp sample data table provides examples.

See the Data Tables chapter in the *Scripting Guide* for details about editing the scripts.

Other

Use the Other column property to create your own column property and assign it any name that you choose. This property is then available for JSL programming.

1. Right-click on the column and select **Column Properties > Other**.
2. Enter a name for the new property.
3. Enter a value for the property.

Properties Assigned and Controlled by JMP

To control how information flows between platforms, JMP assigns some properties that you cannot control. These properties do not appear on the Column Properties menu.

Response Probability

In Profiler reports, the Response Probability property makes all levels of the categorical response variable appear in a single row. JMP automatically assigns the Response Probability property when certain probability formulas are saved to the data table.

Follow these steps to save the property:

1. Fit a logistic regression model using the Fit Model platform.
2. Select the **Save Probability Formula** option in the report window.

JMP automatically assigns the Response Probability property to the new probability columns.

3. Select Prediction Profiler from the report's red triangle menu.

The levels of the categorical response appear on the vertical axis. Probabilities for each level are shown.

For more details, see the *Profilers* book.

Expand Formula

In the Profiler and Nonlinear platforms, if an ingredient column to the model might have a formula, JMP substitutes the inner formula, as long as it refers to other columns. Add the Expand Formula property to prevent an ingredient column from expanding. Assign the value of 0.

For more details, see the Introduction to Profiling chapter in the *Profilers* book.

Predicting

JMP automatically assigns the Predicting column property when you fit a model to a continuous response and save the prediction formula or prediction values. The Predicting column property identifies the platform used to create the prediction formula. That platform is listed as the Creator in the Model Comparison platform.

Informative Missing Terms

Missing levels of a categorical variable are treated as informative missing in certain JMP platforms, either by default or if you request an informative missing fit. In these cases, JMP automatically assigns the Informative Missing Terms column property to a prediction formula column that includes the categorical variable. This column property ensures that the missing value category is treated as a distinct level of the categorical variable in plots and analyses that involve the prediction formula. In particular, profiler plots show the missing values as a level.

Column ID

JMP automatically assigns the Column ID column property to the column that is used to split the initial Bootstrap results data table. This column property assists the split operation and ensures that the column names in the split Bootstrap results table are meaningful.

ConstraintState

When you select Save Constraints, the coefficients of each linear constraint appear in a column in a data table. Each constraint column is assigned the ConstraintState column property. This property specifies the direction of the inequality that defines the constraint. When you select Load Constraints from a design platform, the ConstraintState column property tells JMP the direction of the inequality.

RunsPerBlock

The RunsPerBlock property indicates the maximum allowable number of runs in each block. This property is used by the Evaluate Design and Augment Design platforms to indicate the blocking structure for the factor.

DF

The DF column property is added by many modeling platforms to formula columns that calculate the standard error of the predicted values. The value of this column property is used by the Prediction Profiler to draw confidence intervals when both a prediction formula column and a standard error formula column are provided.

Caution: We do not recommend that you remove or change the value of this property. Doing so could adversely affect the confidence intervals in the Prediction Profiler.

Standardize Attributes and Properties Across Columns

A column might contain attributes (data types, modeling types, numeric formats, and so on) or properties (formulas, notes, list and range checks, and so on) that you want other columns to have. You can use the existing column to *standardize* the attributes and properties across columns. This includes both adding and deleting attributes and properties.

To apply an existing column's attributes and properties to multiple columns

1. Select the column or columns containing the desired attributes or properties.
2. Select **Cols > Standardize Attributes**. The window in Figure 5.10 appears.

Figure 5.10 Standardizing Attributes across Columns

Use the values in the dialog to modify the attributes of the columns in the data table. The changes are applied to all the selected columns when the 'Apply' or 'OK' button is clicked.

OK
Cancel
Apply
Help

Recode the old values of selected columns to new values.
Recode

Standardize Attributes
Attributes Select the attributes to be standardized
Lock
Data Type Numeric
Modeling Type Continuous
Format Fixed Dec Width 5 Dec 0
Use thousands separator (,)

Standardize Properties
Column Properties Select the column properties to be standardized

Delete Properties
Column Properties Select the column properties to be deleted

Recode Values

Use the Recode option if you need to recode similar values within multiple columns in the same way. After you click **Recode**, the values that appear are generated from the union of all

of the selected columns. For example, suppose that you have two columns with user responses. One column contains the values Agree and Disagree. The other column contains the values Agree, Disagree, Unsure, and Strongly Disagree. You want to simplify all of the values in both columns to be A, D, U, and SD.

Note: If you want to recode values only in a single column, you can also use the Cols > Recode option. See [“Recode Data”](#) on page 237 in the “Enter and Edit Data” chapter.

Standardize Attributes

By default, the items within the Standardize Attributes panel are dimmed. To access an item, click the **Attributes** button and select the items to be duplicated across columns.

Note: The Input Format item is applicable only for the Date, Time, and Duration formats.

To change the values of any of the attributes, use the menus in the Standardize Attributes panel.

Standardize Properties

To standardize properties across columns

1. Select the columns that you want to standardize. One of those columns must contain the property that you want to add to the other columns.
2. Select **Cols > Standardize Attributes**.
3. Select **Column Properties** in the Standardize Properties area.
4. Select the property that you want to standardize. Modify the property settings if necessary.
5. Click **Apply** to standardize the property across selected columns. Changes are shown in the data table, open reports, and open graphs.

Or click **OK** to standardize the property across selected columns and close the column properties window.

Delete Properties

To delete the same properties across multiple columns

1. Select the columns containing the attributes or properties that you want to delete.
2. Select **Cols > Standardize Attributes**.
3. Under Delete Properties, click **Column Properties** and select the properties that you want to delete.

4. Click **OK**.

Note: Make sure you click **OK** and not **Remove**. Clicking **Remove** simply removes the property from the list, but does not delete it.

Example of Standardizing a Formula

If you have applied a formula to a column, and you want to apply that same formula to additional columns in the data table, use the **Substitute Column Reference** option.

Note: This option is dependent upon the location of the column that is referenced in the original formula. For example, if your original formula is based on the previous column, then any other formulas applied to additional columns are based on their previous columns.

For example, the *Blood Pressure.jmp* sample data table contains blood pressure measurements taken on five subjects three times each day, over a period of three days. You want to find the log of each blood pressure (BP) column.

1. Select **Help > Sample Data Library** and open *Blood Pressure.jmp*.

Create nine new columns, one for each existing BP column.

2. Select **Cols > New Columns**.
3. Add nine columns.
4. Click **OK**.

Apply your original formula as follows:

5. Right-click Column 1 and select **Formula**.
6. Select **BP 8M**.
7. Select **Transcendental > Log**.
8. Click **OK**.

Column 1 now contains the log of the BP 8M column. You want the rest of the empty columns to contain the log of the remainder of the BP columns.

9. In the data table, select all of the new columns that you created, including the one with the original formula (columns 1-9).
10. Select **Cols > Standardize Attributes**.
11. In the Standardize Properties panel, click **Column Properties** and select **Formula**.
12. Select the check box next to **Substitute Column Reference**.
13. Leave **BP 8M** selected.

You want that column reference to be substituted in the subsequent column formulas.

14. Click **OK**.

Now all of the new columns are populated with the log of the BP columns, in the order in which they appear. Column 1 contains the log for BP 8M, Column 2 contains the log for BP 12M, and so on.

See [“Copy a Formula to Columns on the Right”](#) on page 367 in the “Formula Editor” chapter for more information.

Assign a Preselected Analysis Role

You can assign an analysis role, such as x , y , weight, or frequency, to a selected column and save the role with the data table. When you do this and then run an analysis, JMP uses the preselected role to automatically fill in the role boxes in windows. Then you do not have to specify these roles each time you run an analysis. For example, you might want a column named height to take the x role in every analysis of that data table. To enforce the x role, you assign the preselected role of x to the column.

When you select Freq, the values in that column are what JMP uses as the frequency of the observation. If n is the value of the Freq variable for a given row, then that row is used in computations n times. If it is less than 1 or is missing, then JMP does not use it to calculate any analyses.

When you select Weight, the values in that column provide weights for each observation in the data table. The variable does not have to be an integer, but it is included only in analyses when its value is greater than zero.

To assign a preselected role to a column

1. Highlight the column.
2. Select **Cols > Preselect Role**.
3. Select a role: **No Role**, **X**, **Y**, **Weight**, or **Freq**.

After you select the appropriate roles, icons in the Columns panel signify what roles have been assigned. Click the icon to access a list of roles and select a different one. See [“Icons Representing Column Characteristics and Properties”](#) on page 45 in the “Get Started” chapter.

Chapter 6


Reshape Data

Create Subsets, Sort Data, and More

This chapter covers the following tasks that you can perform on JMP data:

- create a new data table from a subset of rows and columns
- sort by any number of columns
- stack multiple columns into a single column
- split a column into two or more columns
- transpose rows and columns
- concatenate multiple tables end to end
- join two tables side by side
- virtually join tables without physically joining them
- update columns in a table with values from another table
- anonymize the data

Figure 6.1 Creating a Subset Data Table from a Report



Contents

Create a Subset Data Table.....	301
Stratified Subsets.....	303
Create a Subset Data Table from a Report.....	303
Sort Data Tables.....	304
Stack Columns.....	306
Example of Stacking into One Column.....	308
Example of Stacking into More Than One Column.....	309
Split Columns.....	311
Examples of Splitting Columns.....	312
Transpose Rows and Columns.....	314
Examples of Transposing Rows and Columns.....	317
Concatenate Data Tables.....	318
Example of Concatenating Data Tables.....	319
Example of Concatenating Data Tables and Table Variables.....	320
Join Data Tables.....	321
Examples of Joining Data Tables.....	324
Query and Join Data Tables with JMP Query Builder.....	332
About Links to Data Tables in JMP Queries.....	335
Virtually Join Data Tables.....	335
Example of Virtually Joining Columns.....	337
Example of Virtually Joining Columns and Showing Row States.....	340
Example of Merging Referenced Data in Virtually Joined Data Tables.....	341
Update Data Tables.....	343
Example of Updating a Data Table.....	345
Anonymize Data.....	346


Create a Subset Data Table

You can produce a new data table that is a subset of all rows and columns, only highlighted rows and columns, or randomly selected rows from the active data table.

To create a subset

1. Select **Tables > Subset**.

Figure 6.2 The Subset Window



2. Specify the content that you want to subset. Select any combination of the following:
 - Subset by (the levels within selected columns)
 - Rows (all, selected, or random)
 - Columns (all or selected)

In Figure 6.2, the **sex** column will be subset.

3. Customize your subset table further using the additional options.
4. Click **OK** to create the subset table.

Subset Options

Subset by Subsets by the levels of a column. Select **Subset by** and then select the columns that you want to categorize for the subset.

Consider the fact that many new data tables might be created. A new data table appears for each level of the column that you specified in the Subset window.

All Rows Creates a subset table that contains all rows from the active table.

Selected Rows Creates a subset table that contains only the selected rows from the active table. Selected by default.

Random - sampling rate Creates a subset table whose data is a random proportion of the active data table. Enter the proportion of the sample that you want in the text box. For example, if you want a random 50% of the data to be included in the new table, enter 0.5 in the text box.

Random - sample size Creates a subset table whose data is a random sample of the active data table. Enter the size of the sample that you want in the text box. For example, if you want 16 random rows to be included in the new table, enter 16 into the text box.

If you select a random sample that is the entire source table, the result is a random shuffle of the rows of the data table. If you specify columns to stratify, the result is a random shuffle of each of the rows for each group. See [“Stratified Subsets”](#) on page 303.

All columns Creates a subset table that contains all columns from the active table. Selected by default.

Selected columns Creates a subset table that contains only the selected columns from the active table.

Keep by columns Retains the column that you subsetted by in the output data tables.

Output table name Specifies the name of the subset table.

Link to original data table Links the subset table to the original table. When you change values in one table, the other table is updated.

Copy formula Includes formulas from the original table in the output columns. Include all columns needed for the calculation of the formula. Selected by default.

Suppress formula evaluation Prevents JMP from evaluating columns' formulas when the new table is created. Selected by default.

Save Default Options Saves your current settings.


Note: Save Default Options only saves the settings for Selected Rows, Selected Columns, Linked to original data table, Copy formula, and Suppress formula evaluation.

Keep dialog open Keeps the Subset window open after you click OK.

Stratified Subsets

If you specify a sample size and add stratification columns, the sample size represents the size per stratum, rather than the size of the whole subset.

Figure 6.3 Stratified Subsets



For stratified random samples with a specified sample size, two columns can be saved: Selection Probability and Sampling Weight. Check the corresponding check box to save these columns.

Create a Subset Data Table from a Report


These two methods produce linked subsets of a data table.

Use a Histogram

Once you have produced output that contains a histogram (by selecting **Analyze > Distribution**), you can use the histogram to create a new data table. The new data table contains the data in the histogram's highlighted bars.

To create a subset, double-click a highlighted bar. Or, right-click anywhere in the histogram and select **Subset** from the menu. The subset table appears, as shown in Figure 6.4.

Figure 6.4 Subset Created from a Histogram



Note: The subset data table contains a view of the data, not the actual data. You must explicitly save the table if you want a copy. Note that the saved copy of the data table is no longer linked to the source table.

Using a Pareto Plot

Once you have produced output that contains a Pareto Plot (by selecting **Analyze > Quality and Process > Pareto Plot**), you can use the Pareto Plot to create a new data table. The new data table contains the data in the Pareto Plot's highlighted bars. To create a subset, double-click a highlighted bar.

Sort Data Tables

You can sort a JMP data table by columns in either ascending or descending order. By default, columns sort in ascending order. You can either create a new table that contains the sorted values, or you can replace the original table with the sorted table.


If columns contain value labels, sorting is based on the actual data values, not the value labels. (See [“Value Labels”](#) on page 272 in the “The Column Info Window” chapter.) However, the value labels are displayed in the sorted data table.

If your sorted column uses either the Value Ordering property or the List Check property, the column is sorted according to that order.

Example of Sorting Data Tables


1. Select **Help > Sample Data Library** and open Popcorn.jmp.
2. Select **Tables > Sort**.

Figure 6.5 The Sort Window



3. Highlight the names of the columns that you want to sort by. For this example, select popcorn and yield.
4. Click **By** to add the columns to the sort list.
The columns that you add to the list establish the order of precedence for sorting. The first column in the list is the major sort field. Each variable thereafter is sorted within the previous variable in the sort list. You can drag and drop within the By list to change the sort order.
5. Customize your sort further using the additional options. For this example, highlight yield and click the descending button. ▾
6. Enter a name for the new sorted table in the box beside **Output table name**. For this example, enter *sorted popcorn*.

Figure 6.6 Completed Sort Window



7. Click **OK**.

Figure 6.7 Sorted in Ascending and Descending Order

		popcorn	oil amt	batch	yield	trial
	1	gourmet	lots	small	18.0	1
	2	gourmet	lots	small	16.0	2
	3	gourmet	little	small	15.9	2
	4	gourmet	little	small	12.1	1
	5	gourmet	lots	large	9.8	2
	6	gourmet	lots	large	9.2	1
	7	gourmet	little	large	8.6	1
	8	gourmet	little	large	8.2	2
	9	plain	lots	small	10.6	1
	10	plain	lots	large	10.4	1
	11	plain	little	small	10.1	2
	12	plain	little	small	9.9	1
	13	plain	little	large	8.8	2
	14	plain	lots	large	8.8	2
	15	plain	little	large	8.2	1
	16	plain	lots	small	7.4	2

Sort Options

Select Columns Filter Menu Contains options to search and filter through columns. See [“Column Filter Menu”](#) on page 57 in the “Get Started” chapter.

Replace Table Replaces the original data table with the sorted table instead of creating a new table with the sorted values. This option is not available if there are any open report windows generated from the original table.

Output table name (Optional) Specifies the name of the sorted table.

Keep dialog open Keeps the Sort window open after you click **OK**.

By Adds the columns that you want to sort by. The columns that you add to the list establish the order of precedence for sorting. The first column in the list is the major sort field. Each variable thereafter is sorted within the previous variable in the sort list.

Remove Removes any highlighted columns.

Ascending and descending buttons (▲ ▼) You can change the ascending or descending list order of the values for the grouping variables. In the By variable list, select a variable and click the appropriate ascending or descending button. The icon beside the variable changes to indicate the sorting order.

Stack Columns


You can rearrange your data table by stacking two or more columns into a single new column, preserving the values from the other columns. Or, you can stack a set of columns into multiple

groups. The various ways that you can stack columns are explained in [“Stack Options”](#) on page 307.

To stack columns, follow these steps:

1. Select **Tables > Stack**.

Figure 6.8 Stack Window



2. Highlight the names of the columns that you want to stack and click **Stack Columns**.
3. Customize your stacking further using the additional options.
4. Click **OK**.

Stack Options

Select Columns Filter Menu Contains options to search and filter through columns. See [“Column Filter Menu”](#) on page 57 in the “Get Started” chapter.

Multiple series stack Stacks selected columns into two or more columns. Specify the number of columns into which you want the selected columns to be stacked by entering the number into the Number of Series box. This box appears when you check the box beside **Multiple series stack**.

Select the **Contiguous** option if the series consists of adjacent columns.

See [“Example of Stacking into More Than One Column”](#) on page 309.

Note: The order in which you add columns to the box on the right determines the group to which they belong.

Stack by Row Stacks columns by rows. Deselect the option to stack one column underneath another. Selected by default.

Eliminate missing rows Eliminates missing data from the new table. If Stack by Rows is checked also, only rows with *all* data missing are eliminated.

Non-stacked columns Includes or drops non-stacked columns from the new data table. Select one of these options:

Keep All Includes all of the non-stacked columns from the original table in the new table. Selected by default.

Drop All Omits the non-stacked columns from the new table.

Select Select the non-stacked columns that you want to include or drop in the new table.

Keep dialog open Keeps the Stack window open after you click **OK**.

Stack Columns Adds the columns that you want to stack.

Remove Removes any highlighted columns.

Output table name (Optional) Specifies the name of the new table.

Stacked Data Column Assigns a name to the column that will contain the data for the stacked columns. The default name is **Data**. Leave the box empty if you do not want this column to appear in the new table.

Source Label Column Assigns a name to the column that will contain the original table's column names. The default name is **Label**. Leave the box empty if you do not want this column to appear in the new table.

Copy formula Includes formulas from the original table in the output columns. Selected by default.

Suppress formula evaluation Prevents JMP from evaluating columns' formulas when the new table is created. Selected by default.

Example of Stacking into One Column

A researcher has two columns in their data table representing yield, and they want to stack the two columns into a single column. (This new single column is called **Data** by default.)

1. Select **Help > Sample Data Library** and open **Popcorn Trials.jmp**.
2. Select **Tables > Stack**.
3. Select **yield1** and **yield2** and click **Stack Columns**.
4. Click **OK**.

Figure 6.9 Stacked Data Table

	popcorn	oil amt	batch	Label	Data
1	plain	little	large	yield1	8.2
2	plain	little	large	yield2	8.8
3	gourmet	little	large	yield1	8.6
4	gourmet	little	large	yield2	8.2
5	plain	lots	large	yield1	10.4
6	plain	lots	large	yield2	8.8
7	gourmet	lots	large	yield1	9.2
8	gourmet	lots	large	yield2	9.8
9	plain	little	small	yield1	9.9
10	plain	little	small	yield2	10.1
11	gourmet	little	small	yield1	12.1
12	gourmet	little	small	yield2	15.9
13	plain	lots	small	yield1	10.6
14	plain	lots	small	yield2	7.4
15	gourmet	lots	small	yield1	18.0
16	gourmet	lots	small	yield2	16.0

The Label column represents the Source Label Column that identifies the source of the data. Its values are the column names in the original table from which the stacked values originated.

Example of Stacking into More Than One Column

Suppose that a researcher has data on blood pressure readings. The readings were taken over three days: Monday, Wednesday, and Friday. Three readings were taken each day, at 8am, 12pm, and 6pm.

1. Select **Help > Sample Data Library** and open **Blood Pressure.jmp**.


Each BP (blood pressure) column is delineated according to the date and time. The BP 8M column corresponds to readings that were taken at 8am on Monday. The BP 12W column corresponds to readings that were taken on 12pm on Wednesday, and so on. The researcher wants to stack all of the blood pressure columns into three columns that correspond to each day: Monday, Wednesday, and Friday.

2. Select **Tables > Stack**.
3. Select all of the BP readings and click **Stack Columns**.

The order of the columns reflects how the columns in the series should be grouped.

4. Select **Multiple series stack**.
5. Next to Number of Series, type 3.
6. Because you want to stack the columns vertically, select **Contiguous**.
7. Rename the Stacked Data Column from Data to BP (for blood pressure).
8. Rename the Source Label Column from Label to Day.

Figure 6.10 Completed Stack Window



9. Click OK.

Figure 6.11 Stacked Data Table

	Subject	Dose	Day	BP	Day 2	BP 2	Day 3	BP 3
1	1	A	BP 8M	183	BP 8W	174	BP 8F	171
2	1	A	BP 12M	174	BP 12W	178	BP 12F	178
3	1	A	BP 6M	180	BP 6W	181	BP 6F	171
4	2	A	BP 8M	173	BP 8W	170	BP 8F	175
5	2	A	BP 12M	181	BP 12W	179	BP 12F	185
6	2	A	BP 6M	181	BP 6W	176	BP 6F	188
7	3	A	BP 8M	181	BP 8W	188	BP 8F	183
8	3	A	BP 12M	189	BP 12W	175	BP 12F	183
9	3	A	BP 6M	177	BP 6W	182	BP 6F	180
10	4	A	BP 8M	181	BP 8W	176	BP 8F	183
11	4	A	BP 12M	177	BP 12W	173	BP 12F	187
12	4	A	BP 6M	182	BP 6W	184	BP 6F	183
13	5	A	BP 8M	184	BP 8W	172	BP 8F	170
14	5	A	BP 12M	180	BP 12W	175	BP 12F	190
15	5	A	BP 6M	176	BP 6W	176	BP 6F	183
16	1	B	BP 8M	171	BP 8W	183	BP 8F	185
17	1	B	BP 12M	181	BP 12W	176	BP 12F	182
18	1	B	BP 6M	180	BP 6W	174	BP 6F	184
19	2	B	BP 8M	175	BP 8W	183	BP 8F	184
20	2	B	BP 12M	180	BP 12W	180	BP 12F	185
21	2	B	BP 6M	180	BP 6W	173	BP 6F	180

In the stacked data table, note the following:

- The first Day column represents Monday.

- The Day 2 column represents Wednesday.
- The Day 3 column represents Friday.

Split Columns


You can create a new data table from the active table by splitting one column into several new columns. This column is split according to the values found in another column, referred to as the **Split By** column. You can also split columns according to the values of one or more grouping variables.

Note: If the split is on a categorical column that contains a missing value, the column name for the missing category is “.” for a numeric column.

To split columns, follow these steps:

1. Select **Tables > Split**.

Figure 6.12 Split Window



2. Highlight the names of the column or columns that you want to split and click **Split Columns**.
3. Highlight a column whose values you want to use as the basis for splitting the column.
4. Click **Split By**.
5. Customize your splitting further using the additional options.
6. Click **Split**.

Split Options

Select Columns Filter Menu Contains options to search and filter through columns. See [“Column Filter Menu”](#) on page 57 in the “Get Started” chapter.

Keep All Includes all columns in the new table.

Drop All Includes only columns used in the split in the new table. Selected by default.

Select Selects which columns to keep in the new table.

Keep dialog open Keeps the Split window open after you click **OK**.

Split By Adds the column whose values you want to use as the new column names, and as the basis for splitting the column.

Split Columns Adds the column or columns that you want to split.

Group Specifies a Group variable when you want your data to be split within each group of the selected variable. Each group results in a row in the output table. You must also specify the required variables, Split By, and Split Columns.

Note: If the variable that you want to group by contains unequal groups or is in a random order, specifying it as the Group variable ensures that your data is restructured properly, and any missing values are assigned in the appropriate places.

Sort by Column Property (Appears if a Value Ordering or Row Order Levels property is found) Sorts the order of the output columns by the Value Ordering or Row Order Levels column property. Value Ordering takes precedence over Row Order Levels.

If the column has neither property, and the data has an implied order (such as days or months), the implied order is applied.

Output table name (Optional) Specifies the name of the new table.

Copy formula (Appears if there is a formula in the data table) Includes formulas from the original table in the output columns.

Suppress formula evaluation (Appears if there is a formula in the data table) Prevents JMP from evaluating columns' formulas when the new table is created.

Examples of Splitting Columns

This section contains two examples using the Split command:

- In the first example, one column is split by a second column. See [“Split a Column: Basic Example”](#) on page 313.

- The second example uses a Group variable. See [“Split a Column: Grouping Rows Example”](#) on page 314.

Split a Column: Basic Example

In the Popcorn.jmp data table, the data in the trial column shows that there are two trials, 1 and 2. In this example, split the yield column into two new columns: one for trial 1 and one for trial 2. Proceed as follows:

1. Select **Help > Sample Data Library** and open Popcorn.jmp.
2. Select **Tables > Split**.
3. Select the yield column and click **Split Columns**.
4. Select the trial column and click **Split By**.
5. Under **Remaining columns**, select **Keep All**.


The default is Drop All, which omits any columns that are not in the Split By, Split Columns, or Group fields. Selecting **Keep All** includes these columns in the new table.

6. (Optional) Type Yield column split by Trial column in the Output table name field.
7. Click **OK**.

A new data table is created. See Figure 6.13. Notice the following:

- The yield and trial columns are gone.
 - The data table has two new columns, named after the unique values (1 and 2) from the original trial column.
 - The values from the original yield column are now split into the new columns named 1 and 2.
 - The columns other than trial and yield are exactly the same as they were in the original table.
8. (Optional) Rename the new columns to give them meaningful names. For example, rename 1 to yield (trial 1) and rename 2 to yield (trial 2).

Figure 6.13 New Table Created By Splitting yield Column by trial Column



	popcorn	oil amt	batch	1	2
1	plain	little	large	8.2	8.8
2	gourmet	little	large	8.6	8.2
3	plain	lots	large	10.4	8.8
4	gourmet	lots	large	9.2	9.8
5	plain	little	small	9.9	10.1
6	gourmet	little	small	12.1	15.9
7	plain	lots	small	10.6	7.4
8	gourmet	lots	small	18.0	16.0

Split a Column: Grouping Rows Example


The Drug Measurements.jmp sample data table contains measurements of three different drugs (a, b, and c) administered to 12 different subjects. You want to split the measurement into different columns, one for each drug type. You also want to group the measurements by subject.

1. Select **Help > Sample Data Library** and open Drug Measurements.jmp.
2. Select **Tables > Split**.
3. Select Drug Type and click **Split By**.
4. Select Measurement and click **Split Columns**.

Notice that the Subject variable contains unequal groups. Most of the subjects were given all three drugs, but subject 2 was given only one drug, and subjects 7 and 12 were given only two drugs. In this situation, to ensure that the correct measurements are associated with the correct subject, specify Subject as the Group variable.

5. Select Subject and click **Group**.
6. Click **OK**.

Figure 6.14 Drug Measurements.jmp Split by a Grouping Variable



	Subject	a	b	c
1	1	91	99	91
2	2	•	96	•
3	3	95	99	93
4	4	97	93	96
5	5	95	100	94
6	6	92	96	95
7	7	93	96	•
8	8	100	94	92
9	9	98	99	97
10	10	91	96	99
11	11	98	100	93
12	12	•	95	95

You can see that the appropriate missing values appear for subjects 2, 7, and 12.

Transpose Rows and Columns

You can create a new JMP table that is a transposed version of the active data table. The columns of the active table are the rows of the new table, and its rows are the new table's columns.

When you transpose columns, you do the following:

- Select the columns to be transposed.


- Specify a “label” column, from which the new columns get their names (optional).
- Specify “by” columns, which tells JMP to transpose data within groups (optional).

Note: Columns that you want to transpose must have the same data type. Also, if columns contain value labels, transposing uses the actual data values, not the value labels. (See [“Value Labels”](#) on page 272 in the “The Column Info Window” chapter.)

To transpose rows and columns, follow these steps:

1. Open a data table that contains the rows and columns that you want to transpose.
2. Select **Tables > Transpose**.

Figure 6.15 Transpose Window



3. Highlight the column name(s) you want to transpose in the **Select Columns** box on the left.
4. Click **Transpose Columns**.
5. (Optional) Customize your transposed table further using the additional options.
6. Click **OK**.

Transpose Options

Select Columns Filter Menu Contains options to search and filter through columns. See [“Column Filter Menu”](#) on page 57 in the “Get Started” chapter.

Transpose selected rows only Transposes only rows that are currently highlighted in the active table.

Output table name (Optional) Specifies the name of the subset table.

Label column name (Applicable only if you have specified a Label column.) Specifies an alternative name for the Label column. Otherwise, the default column name is **Label**.

Keep dialog open Keeps the Transpose window open after you click **OK**.

Transpose Columns Adds the columns that you want to transpose.

Label Uses the data from a column in the original table as the column names in the new table. Follow these steps:

- 1. Highlight a column from the Select Columns box on the left.
- 2. Click **Label**. The column name appears in the Label box.

The default column name is **Label**. You can specify an alternative name for the column using the **Label column name** option. Only one column is created for each distinct value in the label column. Therefore, if there are duplicate values in the label column, JMP creates only one column for the duplicated value using the value from the last duplicated row.

By Organizes the transposed columns into groups based on the columns that you put into the By box. Follow these steps:

- 1. Highlight the column name(s) in the Select Columns box whose values you want to see as a group.
- 2. Click **By**.

Table 6.1 describes the rules that apply to transposing.

Table 6.1 Rules for Transposing

If	Then
The original table has columns but no rows	The new table contains one column that lists those column names.
The original table has one column and it is assigned to Label	Its values become the column names in the transposed table.
The original table has multiple columns and contains a label column	JMP automatically inserts the label column into the Label box when the window appears. You can remove this column if you do not want it to appear.
There is no label column in the original table	The column names in the transposed table are Row 1, Row 2, ..., Row <i>n</i> where <i>n</i> is the number of rows in the original table.


Examples of Transposing Rows and Columns

This section contains three examples: a simple example of transposing, an example using the Label option, and an example using a By group.

Simple Example of Transposing

1. Select **Help > Sample Data Library** and open **Materials1.jmp**.
2. Select **Tables > Transpose**.
3. Select plastic, tin, and gold and click **Transpose Columns**.
4. Click **OK**.

Figure 6.16 Simple Transposed Table



	Label	Row 1	Row 2
1	plastic	1	4
2	tin	2	5
3	gold	3	6

The original table in Figure 6.16 has two rows and three continuous columns called plastic, tin, and gold. The transposed table has a row for each of the three columns in the original table, and columns named Row 1 and Row 2 for the original table's rows. The additional column called Label has the column names (plastic, tin, and gold) from the original table as values.

Example Using the Label Option

1. Select **Help > Sample Data Library** and open **Materials2.jmp**.
2. Select **Tables > Transpose**.
3. Select plastic, tin, and gold and click **Transpose Columns**.
4. Select item and click **Label**.
5. Click **OK**.

Figure 6.17 Transpose with a Label




	Label	nails	hooks
1	plastic	1	4
2	tin	2	5
3	gold	3	6

The values from the item column in the original table are used as column labels in the transposed table.

Example Using a By Group

1. Select **Help > Sample Data Library** and open **Animals Subset.jmp**.
2. Select **Tables > Transpose**.
3. Select **subject** and **miles** and click **Transpose Columns**.
4. Select **season** and click **Label**.
5. Select **species** and click **By**.
6. Click **OK**.

Figure 6.18 Transpose Using a By Group



	species	Label	fall	winter	spring	summer
1	COYOTE	subject	1	1	1	1
2	COYOTE	miles	4	2	7	8
3	FOX	subject	3	3	3	3
4	FOX	miles	4	3	6	2

The transposed table contains values that have been transposed in groups.


Concatenate Data Tables

When you concatenate data tables in JMP, you combine rows from two or more data tables. You can create a new data table *or* you can append rows to the first data table. A column name might be the same in the data tables that you want to concatenate. If so, then the column in the new data table lists the values from all of the data tables in the order of concatenation. If the two original data tables have columns with different names, those columns are included in the new data table showing missing values.

To concatenate two data tables with the same column names, follow these steps:

1. Select **Tables > Concatenate**.

Figure 6.19 Concatenate Window



2. Highlight the names of the data tables that you would like to combine, and click **Add**.
You can concatenate as many data tables as you choose, and you can also add the same data tables multiple times. The number of rows in the new data tables is the sum of the number of rows in all the data tables.
 3. (Optional) Click the **Save and evaluate formulas** choice to request that JMP include all formulas.
If you do not select this option, no formulas are included in the new data table.
-
- Note:** Columns with the same name can have different formulas. The formula from the first data table that contains a formula for that column is saved in the concatenated data table. This situation can occur when more than two tables are being concatenated and the second or third on has a formula for the column in question.
-
4. (Optional) Click the **Create source column** choice to add a column called **Source Table** to the new data table.
This column identifies the name of the source data table in the corresponding rows.
 5. (Optional) Select the **Append to first table** choice to append rows to the data table listed first in the **Data Tables to be Concatenated** field. This option is an alternative to creating a new data table.
 6. (Optional) Enter a name for the new data table in the **Output table name** field.
If you do not enter a name, JMP names the data table **Untitled#** (for example, **Untitled1**). The **Output table name** field is not available if you selected the **Append to first table** choice.
 7. Click **OK**.

Example of Concatenating Data Tables


Suppose that you want to concatenate two data tables (Trial1 and Trial2) into a new data table.

1. Select **Help > Sample Data Library** and open Trial1.jmp and Trial2.jmp.

2. From the Trial1.jmp table, select **Tables > Concatenate**.
3. In the **Opened Data Table** list, select Trial2 and click **Add**.
4. Click **OK**.

The data tables combine into a new concatenated table with all of the rows from the first data table followed by all of the rows from the second data table. See Figure 6.20.

Figure 6.20 Result of Concatenating Two Data Tables



	popcorn	oil amt	batch	yield
1	plain	little	large	8.2
2	gourmet	little	large	8.6
3	plain	lots	large	10.4
4	gourmet	lots	large	9.2
5	plain	little	small	9.9
6	gourmet	little	small	12.1
7	plain	lots	small	10.6
8	gourmet	lots	small	18.0
9	plain	little	large	8.8
10	gourmet	little	large	8.2
11	plain	lots	large	8.8
12	gourmet	lots	large	9.8
13	plain	little	small	10.1
14	gourmet	little	small	15.9
15	plain	lots	small	7.4
16	gourmet	lots	small	16.0

Concatenated data tables always contain a column for every column name found in the original data tables. However, if the column names do not match exactly, they are not merged. For example, if the yield column was instead named yield1 and yield2, a separate column would be created for each in the concatenated data table.

When you concatenate two or more data tables containing table variables, separate columns are created for each table variable. This ensures that important distinctions are not lost when concatenating data tables.

Note: Columns are not created for table variables that begin with the name Notes.

Example of Concatenating Data Tables and Table Variables

For example, suppose that two cancer trials were conducted at two different hospitals. One of the trials' data is in the Cancer1.jmp data table, and the other trial's data is in the Cancer2.jmp data table.

To consolidate the data and the variables into one table, follow these steps:

1. Select **Help > Sample Data Library** and open Cancer1.jmp and Cancer2.jmp.

Notice that there are two distinct table variables: Dosage Amount and Location. In the concatenated table, columns are created for these two table variables.

2. From the Cancer1.jmp data table, select **Tables > Concatenate**.
3. Select Cancer2 and click **Add**.
4. Click **OK**.

Figure 6.21 Data and Variables Concatenated

	Time	Cell Type	Treatment	Prior	Dosage Amount	Location
1	3	Adeno	Standard	No	150	Roanoke
2	7	Adeno	Test	No	150	Roanoke
3	8	Adeno	Standard	Yes	150	Roanoke
4	8	Adeno	Test	No	150	Roanoke
5	12	Adeno	Standard	Yes	150	Roanoke
6	18	Adeno	Test	Yes	150	Roanoke
7	19	Adeno	Test	No	150	Roanoke
8	24	Adeno	Test	No	150	Roanoke
9	3	Adeno	Standard	No	250	Asheville
10	7	Adeno	Test	No	250	Asheville
11	8	Adeno	Standard	Yes	250	Asheville
12	8	Adeno	Test	No	250	Asheville
13	12	Adeno	Standard	Yes	250	Asheville
14	18	Adeno	Test	Yes	250	Asheville
15	19	Adeno	Test	No	250	Asheville
16	24	Adeno	Test	No	250	Asheville

The data and the variables are concatenated. The variables appear as columns in the concatenated table. The notes from each data table are added to the new data table as table variables.

Join Data Tables

You can combine two data tables into one new table by selecting **Tables > Join**. For an overall description of how to join two data tables, see [“To join two data tables into a new data table, follow these steps:”](#) on page 322. Tables can be joined in three different ways:

- By combining them according to row number. See [“Example of Joining by Row Number”](#) on page 324.
- In a Cartesian fashion, where you form a new table consisting of all possible combinations of the rows from two original tables. See [“Examples of a Cartesian Join”](#) on page 326.
- By matching the values in one or more columns that exist in both data tables, or in a single data table. See [“Examples of Joining By Matching Columns”](#) on page 328.


Note: The JMP Query Builder option in the Tables menu provides an option to query data before performing a simple join. See [“Query and Join Data Tables with JMP Query Builder”](#) on page 332 in the “Reshape Data” chapter for details.

To join two data tables into a new data table, follow these steps:

1. Open the two data tables that you want to join.
2. Select **Tables > Join**.

In the window that appears, the names of all open tables appear below **Join...with**, as shown in Figure 6.22.

Figure 6.22 The Join Window



3. In the **Join...with** box, select the table to join with the active table.
4. From the Matching Specification area, select the option that specifies how to join the tables.
5. Enter the name of the new table in the text box beside **Output table name**.
6. (Optional) Customize the join procedure further using the additional options.
7. Click **OK** to create the joined data table.

Join Options

Keep dialog open Keeps the Join window open after you click **OK**.

Preserve main table order Maintains the order of the original data table in the joined table, instead of sorting by the matching columns. Selected by default.

Update main table with data from second table Column data from the second table change the data of the same name columns in the original table.

Note the following:

- JMP does not replace data with missing values.
- The output table uses the same columns as the original table. Thus, when you use **Update main table with data from second table**, **Select Columns for joined table** is not applicable.
- The **Update main table with data from second table** option is available only when joining by row number or by matching columns.

Merge same name columns Data from the second table replaces the data of the same name columns in the original table. Note that missing values in the first table are replaced by nonmissing values in the second.

If you are matching by column, Match Flag is selected when you select **Merge same name columns**. The new joined table contains a nominal column named Match Flag:

- If Main appears in this column, the data originated from the first (active) table.
- If With appears in this column, the data originated from the second table.
- If Both appears in this column, the data was found in both the first and second tables.

Match flag Determines whether the Match Flag column is created when you are matching by column. Selected automatically when you select **Merge same name columns**.

Copy formula (Main Table and Second Table) Includes formulas from the main table and/or the second table in the output columns. Selected by default.

Suppress formula evaluation (Main Table and Second Table) Prevents JMP from evaluating columns' formulas during the creation of the new table. Selected by default.

By Matching Columns To join rows, select columns in both tables whose values and data types match. Follow these steps:

1. Highlight a column name from each list in the **Source Columns** area. The first highlighted column in the top list pairs with the first highlighted column in the bottom list, the second columns are paired, and so on. Rows join only if values and data types match for all the column pairs.
2. Click **Match**. The selected pair of columns appears in the **Match columns** box. Matching columns do not have to have the same names and do not have to be in the same relative column position in both tables.
3. (Optional) To include only the first match found, check the boxes associated with **Drop multiples** in both tables. Only the first match found is written to the new table. If you specify this option for one table, the first match value is joined with all matches in the

other table. If you do not check the boxes associated with **Drop multiples** in either table, a Cartesian join is performed within each group of matching column values.

4. (Optional) To include all rows from the data table, even when there is no matching value, check the boxes associated with **Include non-matches**. You can specify this option for either or both data tables being joined.

By Row Number Joins the two tables side by side.

Cartesian Join Joins two tables using a Cartesian fashion, where it forms a new table consisting of all possible combinations of the rows from two original tables. JMP crosses the data in the first table with the data in the second to display all combinations of the values in each set.

Select Columns for joined table Selects a subset of columns from either table for inclusion in the output table. Follow these steps:

1. In the Source Columns area, highlight the columns from each table that you want to include in the new table.
2. Click **Select** in the Output Columns area.

Output table name Specifies the name of the joined table.

Examples of Joining Data Tables

The following sections provide examples using the Join command.

Example of Joining by Row Number

Joining tables by row number joins the two tables side by side. The new table has all of the columns from both tables, unless you specify to include only certain columns.

To join tables with an unequal number of rows

If the two tables that you want to join have an unequal number of rows, the new table contains values for the rows found in both tables.

1. Select **Help > Sample Data Library** and open Species1.jmp and Species2.jmp.
Notice that the Species1.jmp table has two rows, and the Species2.jmp table has four rows.
2. From the Species1.jmp table, select **Tables > Join**.
3. In the **Join...with** box, select Species2.
4. From the Matching Specification area, select **By Row Number**.
5. Click **OK**.

Figure 6.23 Joined Tables by Row Number

	species	season
1	FOX	spring
2	COYOTE	summer
3		fall
4		winter

If one table with two rows is joined with a table with four rows, then the new table contains four rows.

To join columns with the same name

If the two tables have column names that are the same, the names of these columns in the new table appear as “column name of table name.” For example, suppose that you want to combine the eight rows from the Trial1.jmp and Trial2.jmp data tables shown in Figure 6.24 into a single table. You want to combine them so that the new table contains all of the columns from both tables.

1. Select **Help > Sample Data Library** and open Trial1.jmp and Trial2.jmp.
2. From the Trial1.jmp data table, select **Tables > Join**.
3. In the **Join...with** box, select Trial2.
4. From the Matching Specification menu, select **By Row Number**.
5. Click **OK**.

Figure 6.24 Original Tables and the Joined Table

	popcorn of Trial1	oil amt of Trial1	batch of Trial1	yield of Trial1	popcorn of Trial2	oil amt of Trial2	batch of Trial2	yield of Trial2
1	plain	little	large	8.2	plain	little	large	8.8
2	gourmet	little	large	8.6	gourmet	little	large	8.2
3	plain	lots	large	10.4	plain	lots	large	8.8
4	gourmet	lots	large	9.2	gourmet	lots	large	9.8
5	plain	little	small	9.9	plain	little	small	10.1
6	gourmet	little	small	12.1	gourmet	little	small	15.9
7	plain	lots	small	10.6	plain	lots	small	7.4
8	gourmet	lots	small	18.0	gourmet	lots	small	16.0

A column name can be the same in the two original tables. The output column name is then qualified by the source table name. For example, the column names in the new table appear as <variable name> of table name.

To join only specified columns

Suppose that you do not want all of the columns from the original data tables to be in the joined table. Proceed as follows:

1. Select **Help > Sample Data Library** and open Trial1.jmp and Trial2.jmp.
2. From the Trial1.jmp data table, select **Tables > Join**.
3. In the **Join...with** box, select Trial2.
4. From the Matching Specification menu, select **By Row Number**.
5. Click **Select columns for joined table** to specify the subset of columns that you want to include.
6. In the Source Columns list, select popcorn and yield from the Trial1 list and select yield from the Trial2 list.
Because identical data exists in the popcorn column of both tables, you need to select only one column.
7. Click **Select**.
8. Click **OK**.

Figure 6.25 Joining Only Specified Columns

	popcorn	yield of Trial1	yield of Trial2
1	plain	8.2	8.8
2	gourmet	8.6	8.2
3	plain	10.4	8.8
4	gourmet	9.2	9.8
5	plain	9.9	10.1
6	gourmet	12.1	15.9
7	plain	10.6	7.4
8	gourmet	18.0	16.0

Examples of a Cartesian Join


When doing a Cartesian join, JMP joins two tables in a Cartesian fashion: the new table consists of all possible combinations of the rows from two original tables. This creates cases in the output table where there are one case for each combination of column values.

Simple Example of a Cartesian Join

1. Select **Help > Sample Data Library** and open Species1.jmp and Species2.jmp.
2. From the Species1.jmp table, select **Tables > Join**.
3. In the **Join...with** box, select Species2.
4. From the Matching Specification menu, select **Cartesian Join**.

5. Click **OK**.

Figure 6.26 Joining Tables Using Cartesian Join



The screenshot shows a JMP data table with two columns: 'species' and 'season'. The table contains 8 rows of data, representing all combinations of two species (FOX and COYOTE) and four seasons (spring, summer, fall, winter). The rows are numbered 1 through 8.

	species	season
1	FOX	spring
2	FOX	summer
3	FOX	fall
4	FOX	winter
5	COYOTE	spring
6	COYOTE	summer
7	COYOTE	fall
8	COYOTE	winter


The data in *Species1.jmp* is crossed with the data in *Species2.jmp* to produce the joined table, which shows all combinations of the values in each set.

Complex Example of a Cartesian Join

In this example, use the **Tables > Join** command twice:

- The first join combines the *Oil Amount.jmp* table with the *Batch.jmp* table using the **Cartesian** option.
 - The second join combines the resulting table (Cartesian oil amount + batch) with the *Popcorn Type.jmp* table and produces a final table with all tables joined.
1. Select **Help > Sample Data Library** and open *Oil Amount.jmp*, *Batch.jmp*, and *Popcorn Type.jmp*.
 2. From the *Oil Amount.jmp* table, select **Tables > Join**.
 3. In the **Join...with** box, select *Batch*.
 4. From the Matching Specification menu, select **Cartesian Join**.
 5. Under **Output table name**, type *Oil Amount and Batch*.
 6. Click **OK**.

Figure 6.27 Oil Amount and Batch Joined Table




The screenshot shows a JMP data table with two columns: 'oil amount' and 'batch'. The table contains 4 rows of data, representing all combinations of two oil amounts (little, lots) and two batches (small, large). The rows are numbered 1 through 4.

	oil amount	batch
1	little	small
2	little	large
3	lots	small
4	lots	large

The joined table contains all of the columns from the Oil Amount.jmp and Batch.jmp tables. Add the Popcorn Type.jmp columns, as follows:

7. From the Oil Amount and Batch table that you just created, select **Tables > Join**.
8. In the **Join...with** box, select Popcorn Type.
9. From the Matching Specification menu, select **Cartesian Join**.
10. Click **OK**.

Figure 6.28 Oil Amount and Batch Joined with Popcorn Type



	oil amount	batch	popcorn
1	little	small	gourmet
2	little	small	plain
3	little	large	gourmet
4	little	large	plain
5	lots	small	gourmet
6	lots	small	plain
7	lots	large	gourmet
8	lots	large	plain

The final table contains all of the columns from all three original tables. Keep in mind that the number of rows produced by a Cartesian join is the product of the number of rows in the original tables.

Examples of Joining By Matching Columns

When you join data tables by matching columns, JMP finds specified column values that exist in both tables. All values associated with the specified column values are combined into a new data table.

In order to join by matching columns, the columns must have the same data type (numeric, character, or row state).

You can also join a data table to itself, in order to remove duplicate values or rows from the data table.

To join tables with the same rows in a different order

1. Select **Help > Sample Data Library** and open Students1.jmp and Students2.jmp.


The Students1.jmp data table contains names, ages, and sexes of the students. The Students2.jmp data table contains names, height, and weight of the students. Instead of working with two separate tables, you would like to combine the tables into one. Notice that the students' names are not in the same order in both tables. For example, Alice is in row 7 and row 9.

2. From the Students1.jmp data table, select **Tables > Join**.
3. In the **Join...with** box, select Students2.

Because both tables have one column (name) that contains the same values, you need to tell JMP that they are matches. JMP then examines each of the values in the name column of the first table to determine whether there was a corresponding value in the second table's name column. For example, it detects that Alice is located in both tables. It creates a name column in the new table with Alice as a value. It then takes the age and sex of Alice from table one and puts it in the new table. Then it takes the height and weight of Alice and puts them in the new table.

4. Select **By Matching Columns** in the Matching Specification area.
5. From the Students1 and Students2 lists, select name.
6. Click **Match**.
7. You want the new table to contain only one row for each name, so select the **Drop multiples** boxes for both tables.
8. Click **OK**.

Figure 6.29 Joined Table



	name of Students1	age	sex	name of Students2	height	weight
1	KATIE	11	F	KATIE	56	85
2	TIM	11	F	TIM	62	85
3	LOUISE	11	F	LOUISE	57	69
4	JEFFREY	11	M	JEFFREY	56	88
5	JANE	11	F	JANE	54	69
6	JACLYN	11	F	JACLYN	62	104
7	ALICE	11	F	ALICE	56	84
8	JAMES	11	F	JAMES	54	81
9	ROBERT	11	F	ROBERT	58	96
10	BARBARA	11	F	BARBARA	53	64
11	CAROL	11	M	CAROL	60	95

To join tables with different numbers of rows and different column names

Suppose that Sarah and Joe are performing a popcorn experiment. They are popping different types of popcorn (gourmet and plain) in different amounts of oil. They are recording the amount (yield) of popcorn that is produced. Sarah gave you the first trial data in a file named Trial1.jmp. Joe gave you the second trial data in a file named Little.jmp. You want to combine the two tables into one table.

1. Select **Help > Sample Data Library** and open Trial1.jmp and Little.jmp.
2. From the Trial1.jmp table, select **Tables > Join**.
3. In the **Join...with** box, select Little.

You can see that three of the columns (popcorn, oil amt/oil, and batch) contain the same values in both tables. Identify these columns as matches. Also, because Sarah and Joe gave the oil and oil amt columns different names, you can tell JMP that oil amt and oil match.

4. Deselect **Preserve main table order**.

The joined table is sorted by matching columns, not by the order of data in Trial1.jmp,

5. Select **By Matching Columns** in the Matching Specification area.
6. From the Trial1 list, select popcorn, oil amt, and batch.
7. From the Little list, select popcorn, oil, and batch.
8. Click **Match**.


Looking at the two data tables, you can see that they have different numbers of rows. Trial1.jmp has values for eight experimental conditions, and Little.jmp has values for only four of those conditions. Sarah completed her experiment, but Joe only partially completed his experiment. You want the joined table to contain all of the rows in Trial1.jmp, even if that row in the Little.jmp table contains a missing value.

9. Select the **Include non-matches** boxes for both tables.

In the joined table, you want only one column for popcorn, one column for oil, and one column for batch. However, you want two columns for yield: one representing the yield from Trial1.jmp, and another representing the yield from Little.jmp.

10. Select the box beside **Select columns for joined table**.
11. From the Trial1 list, select all of the columns.
12. Click **Select**.
13. From the Little list, select yield.
14. Click **Select**.

Figure 6.30 Completed Join Window



15. Click OK.

Figure 6.31 Trial1.jmp and Little.jmp Joined

	popcorn	oil amt	batch	yield of Trial1	yield of Little
1	gourmet	little	large	8.6	8.2
2	gourmet	little	small	12.1	15.9
3	gourmet	lots	large	9.2	•
4	gourmet	lots	small	18.0	•
5	plain	little	large	8.2	8.8
6	plain	little	small	9.9	10.1
7	plain	lots	large	10.4	•
8	plain	lots	small	10.6	•

The joined table is sorted by the matching columns. Note that the yield column from the Little.jmp table (Yield of Little) has missing values indicating no matching values with the Trial1.jmp table.

To join a table to itself (to remove duplicate entries)

1. Select **Help > Sample Data Library** and open Coffee Shop Purchases.jmp.
You can see that some of the customers had the same drink on the same date. You want to consolidate these duplicate rows using **Join**.
2. Select **Tables > Join**.
3. In the **Join...with** box, select Coffee Shop Purchases.
4. Select **By Matching Columns** in the Matching Specification area.
5. From both Coffee Shop Purchases lists, select all three columns: Date, Customer, and Beverage.
6. Click **Match**.
7. Select the **Drop multiples** boxes for both tables (the Main Table and the With Table).
8. Type Coffee Shop Purchases Final for the **Output table name**.
9. Click **OK**.

Figure 6.32 Original and Joined Coffee Shop Purchases Data Tables

	Date	Customer	Beverage
1	01/05/2013	Jeff	Espresso
2	01/05/2013	Mike	Chai tea
3	01/05/2013	Sergio	Latte
4	01/05/2013	Mike	Espresso
5	01/05/2013	Mike	Espresso
6	01/05/2013	Lisa	Espresso
7	01/05/2013	Lisa	Espresso
8	02/13/2013	Lisa	Chai tea
9	02/13/2013	Lisa	Chai tea
10	02/13/2013	Mike	Chai tea
11	02/13/2013	Sergio	Espresso
12	02/13/2013	Sergio	Espresso

	Date	Customer	Beverage
1	01/05/2013	Jeff	Espresso
2	01/05/2013	Mike	Chai tea
3	01/05/2013	Sergio	Latte
4	01/05/2013	Mike	Espresso
5	01/05/2013	Lisa	Espresso
6	02/13/2013	Lisa	Chai tea
7	02/13/2013	Mike	Chai tea
8	02/13/2013	Sergio	Espresso

Query and Join Data Tables with JMP Query Builder

The JMP Query Builder option in the Tables menu enables you to query data tables and save selected data into a new data table. This feature is similar to using the Join command but lets you perform queries before saving the data. For example, you can query SAT data and save


only data for 2004 test scores in a data table. You can also include a prompt that lets the user run the query and choose a subset of the 2004 test scores.

1. Select **Help > Sample Data Library** and open SAT.jmp and SATByYear.jmp.
2. Display SATByYear.jmp.
3. Select **Tables > JMP Query Builder**.

The current data table, SATByYear.jmp, is selected as the Primary table.

4. Select SAT.jmp in the Available Tables list and click **Secondary**.
5. Select SAT.jmp next to the Secondary button and view the Columns tab. The Join column shows that two columns have the same name and were joined.

Figure 6.33 Joined Columns



6. Click **Build Query**.

Add Columns

1. In the Available Columns list, select t1.State, t1.%Taking (2004), t2.2004 Verbal, and t2.2004 Math.
2. Click **Add**.

The columns are added to the Included Columns tab.


3. Select **Distinct rows only** to avoid saving duplicate rows.
4. On the Query Preview tab, make sure that **Update preview automatically** is selected so that you can see the selected columns.

Add Filters

1. In the Included Columns list, select t2.2004 Verbal and t2.2004 Math, and then click **Add Selected Items to Filter** .

The columns are added to the Filters list.

Figure 6.34 Selected Filters



2. Click the red triangle next to each filter and select **Prompt on Run**. Accept the default prompt message.

Run the Query

1. Click **Run Query**.

You are prompted to indicate which math and verbal scores to save in the data table. To save all data, do not change the values in the prompt window.

2. Click **OK** to create the data table.

Figure 6.35 Queried Data

	State	% Taking (2004)	2004 Verbal	2004 Math
1	Alabama	0.1	560	553
2	Alaska	0.53	518	514
3	Arizona	0.32	523	524
4	Arkansas	0.06	569	555
5	California	0.49	501	519
6	Colorado	0.27	554	553
7	Connecticut	0.85	515	515

See [“Build SQL Queries in Query Builder”](#) on page 113 in the “Import Your Data” chapter for more information about features that also appear in Query Builder for databases.

Tips:

- To join data from different sources (for example, a database and Microsoft Excel), use Query Builder to import the database data into a data table; import the Excel data into a data table; and use JMP Query Builder in the Tables menu to query and join the tables.

- When you open a query, data tables in the query open as hidden files that you can open from the JMP Home Window. You can also open the hidden files from the Table panel when you build the query.
- If you try to query a Microsoft Excel file that has more than 255 columns, only 255 columns are imported. Instead, select **File > Open** to open the Excel file in the Excel Import Wizard, and save the file as a data table.

About Links to Data Tables in JMP Queries

When you query data tables, the resulting data table contains scripts for rerunning the query, updating the data, and editing the query. Data tables in these scripts have *absolute paths*. For example, the following portion of these scripts defines where two JMP sample data tables are stored.

```
JMP Tables(  
  ["SAT" => "C:\Program Files\SAS\JMPPRO\14\Samples\Data\SAT.jmp",  
   "SATByYear" => "C:\Program  
Files\SAS\JMPPRO\14\Samples\Data\SATByYear.jmp"]  
)
```

However, when you save a query as a .jmpquery file, the file contains *relative paths* to the original data tables if it is possible to create them. The following example shows data tables that are stored in the FuelData subfolder that is relative to the .jmpquery file.

```
JMP Tables( ["Cars" => "FuelData\Cars.jmp",  
  "Trains" => "FuelData\Trains.jmp"] )
```

In the .jmpquery file, if a relative path cannot be created, an absolute path is used with path variable substitutions if possible. When you run the query, you are prompted to select the data table if the table cannot be found. JMP then detects whether other missing data tables in the query are in the selected folder.

You can also use path variables to locate the data tables. For example, you might write a script that selects a data table in the \$DOCUMENTS folder. Or you can define a path variable in a JSL script and then run a query from the script. See the Types of Data chapter in the *Scripting Guide* for details about path variables.

Virtually Join Data Tables

Virtual Join links a main data table to one or more auxiliary data tables. This feature enables the main data table to access data from the auxiliary data tables without physically joining the tables. Virtually joining tables saves memory, because the same data are not replicated in

every table that references them. And updating linked data is simpler; linked data can be independently updated in the source table without being updated in the referencing table.

The Link ID and Link Reference column properties make the linking possible.

- The Link ID column property marks a column in the *auxiliary* data table as the ID column. That is, the rows of the data table are uniquely identified by the values of the ID column. The data table that has a Link ID column property is referred to as the *referenced* data table.
- The Link Reference column property links a column in the *main* data table to the Link ID column in the referenced data table. The column property specifies the path name of the referenced data table. The column that has a link reference is referred to as the *referencing* column. The referencing column can look up the data of the auxiliary data tables through the Link ID column.

Figure 6.36 shows an example of virtually joined data tables. Pizza Profiles.jmp is the referenced data table because the ID column contains a Link ID column property. The ID column contains unique values that correspond to data in the referencing data table, Pizza Responses.jmp.

Figure 6.36 Virtually Joined Data Tables

The screenshot displays two JMP Pro windows. The 'Pizza Responses' window (top) shows a table with 5 rows and 4 columns: Subject, Choice1, Choice2, and Choice. The 'Pizza Profiles' window (bottom) shows a table with 8 rows and 4 columns: Crust, Cheese, Topping, and ID. The ID column in 'Pizza Profiles' is highlighted with a Link ID property icon. The 'Columns' list on the left of 'Pizza Responses' shows that Choice1, Choice2, and Choice are all 'referenced by Choice1'.

Subject	Choice1	Choice2	Choice
1	ThickJack	TrimPepperjack	TrimPepperjack
2	TrimPepperjack	ThickElla	ThickElla
3	TrimOni	Trimella	TrimOni
4	ThickElla	ThickJack	ThickElla
5	Trimella	ThickJackoni	Trimella

Crust	Cheese	Topping	ID
1 Thick	Mozzarella	Pepperoni	ThickOni
2 Thick	Mozzarella	None	ThickElla
3 Thick	Jack	Pepperoni	ThickJackoni
4 Thick	Jack	None	ThickJack
5 Thin	Mozzarella	Pepperoni	TrimOni
6 Thin	Mozzarella	None	Trimella
7 Thin	Jack	Pepperoni	TrimPepperjack
8 Thin	Jack	None	TrimJack

Note: A column can have a Link Reference column property, but it does not necessarily have to link columns from the referenced data table. The virtual join icon next to the column in the Columns list is gray . This can happen if the referenced data table is not opened or the referencing column is excluded. See “[Virtual Join Icons](#)” on page 47 in the “Get Started” chapter for details about the other virtual join icons.

With the link column properties set up, all columns from the referenced data tables become part of your main data table. Therefore, if the main data table has a referencing column, the columns of the referenced table automatically appear in the Select Columns list of the launch window.

Example of Virtually Joining Columns

Suppose that respondents in a pizza experiment chose their favorite crust, topping, and cheese. To see which cheese the respondents preferred, follow these steps:

1. Select **Help > Sample Data Library** and open *Pizza Profiles.jmp* and *Pizza Responses.jmp*.
2. First, right-click the ID column in *Pizza Profiles.jmp* and select **Link ID**.

This column contains unique values that correspond to values in *Pizza Responses.jmp*. For example, row one in *Pizza Profiles.jmp* indicates that pizza with thick crust, mozzarella cheese, and pepperoni toppings is nicknamed ThickOni. When all responses in *Pizza Responses.jmp* are “ThickOni”, the subject chose pizza with these attributes.


3. In *Pizza Responses.jmp*, select the three columns that begin with “Choice”.
4. Right-click and select **Link Reference > Pizza Profiles.jmp**.

The selected columns are linked to the ID column in *Pizza Profiles.jmp* and appear in the main data table’s Columns list ([Figure 6.36](#) on page 336).

Note: Look at one of the column’s Link Reference properties again and notice that the *Pizza Profiles.jmp* data table is selected. See “[Virtual Join Properties](#)” on page 288 in the “The Column Info Window” chapter for information about changing the link.


5. In *Pizza Responses.jmp*, select **Analyze > Distribution**.
6. Scroll down to select the three Cheese columns in the referenced column groups, click **Y, Columns**, and click **OK**.

Figure 6.37 Distribution Launch Window



More respondents chose Mozzarella in the Choice column. In Choice1 and Choice2, the proportion of Mozzarella to Jack is nearly even.

Figure 6.38 Distribution of Pizza Responses



Notes:

- See the Movie Rentals.jmp sample data table for another example of virtually joined columns. The data are already joined with Movie Customers.jmp and Movie Inventory.jmp, so you do not need to specify the Link Reference.

- A data table can have only one Link ID column property. The Link ID column cannot have duplicate values.
- A data table can have multiple referencing columns. The columns can reference different or the same data tables.
- A referenced data table can also have a referencing column (a column that references another data table).
- If the Link Reference column property is removed from the column, or the referenced data table is closed, the corresponding referenced columns are removed from the main data table.
- The data types of the linked columns must match.
- The Expression and Row State data types do not support the Link Reference or Link ID column properties.
- When the main data table is saved, the Link Reference column property is saved, but referenced columns are not saved. The data tables are relinked when you open them.
- When a referenced data table is renamed, the corresponding Link Reference column property is automatically updated.
- Referenced columns are not included when you select Copy Table Script from the Table panel red triangle menu.
- Select Row State Synchronization options to synchronize row states in data tables that contain virtually joined columns. See [“Example of Virtually Joining Columns and Showing Row States”](#) on page 340.

Tips:

- In addition to right-clicking a column to add the Link ID and Link Reference column properties, you can add the properties through the Column Info window. See [“Virtual Join Properties”](#) on page 288 in the “The Column Info Window” chapter for details.
- You can specify that the linked column name be used in virtually joined columns that are shown in the Columns list. This option lets you specify a shorter column name (for example, Cheese instead of Cheese[Choice]). In the Link Reference column property, select **Use Linked Column Name**. You can also manually rename the column as usual.
- To share the data with another user, you might want to merge the data so that the data tables are permanently joined. This option is helpful because you provide one data table, not the main and auxiliary data tables. To merge the joined columns into the table that has a link reference, select **Merge Referenced Data** from the red triangle menu in the data table’s left pane. The data are replicated from the auxiliary data table to the main data table. When you save the main data table, the actual data are also saved. The Link Reference column property is removed from the referencing column in the main data table. See [“Example of Merging Referenced Data in Virtually Joined Data Tables”](#) on page 341.

Example of Virtually Joining Columns and Showing Row States


When row states change in one data table that has a virtually joined column, those row states can automatically show up in virtually joined columns in other linked data tables. Suppose that the main and auxiliary data tables have a subject ID column. The row states are changed in the data table that contains a Link ID property on the subject ID column. Then the row states are updated in the data table that contains virtually joined Link Reference columns. You can specify whether the Link Reference columns send (*dispatch*) row states to the other data tables or receive (*accept*) row states.

1. Select **Help > Sample Data Library** and open Nic Demographics.jmp, Nic Labs.jmp, and Nic Adverse Events.jmp.
2. View Nic Labs.jmp.

Notice that, in the Columns list, the blue Virtual Join icon  appears next to Unique Subject Identifier. The blue color indicates that the column has a Link Reference column property and the referenced data table (Nic Demographics.jmp) is open. The Link Reference column property links the Unique Subject Identifier column in the current data table to the Unique Subject Identifier column in the referenced data table. If the icon is gray , the referenced data table is not open, or the columns could be linked incorrectly.

Nic Adverse Events.jmp is set up the same way.

Figure 6.39 Link Reference Column Property on Unique Subject Identifier



3. In Nic Labs.jmp, select the Unique Subject Identifier column and select **Cols > Column Info**.
4. Select the **Link Reference** column property.

Notice that Accept is selected. This means that when rows in the referenced data table (Nic Demographics.jmp) contain a row state, the row state automatically appears in the current data table.

Also notice that the Select, Exclude, and Hide row states are selected. When these row states are selected in Nic Demographics.jmp, the row states will appear in Nic Lib.jmp and Nic Adverse Events.jmp.

5. In Nic Demographics.jmp, right-click the first row and select **Hide and Exclude**.

The first row contains data for Unique Subject Identifier 101001.

6. View Nic Labs.jmp to see the excluded rows for Unique Subject Identifier 101001.

Cautions:

- Dispatching row states in multiple tables with multiple columns can be complex and should be done with caution.
- Dispatching row states is best used when no multiple row states are assigned to the same ID value. If a Link Reference column dispatches the color row state, ambiguity quickly develops when there are multiple rows with the same ID value but different color row states. For example, the data table has two rows with an ID value of 001. You color one row red and the other row green. There is no way for JMP to know how to set the row state in the linked data table.

Notes:

- Multiple columns in table A can link to table B. And Table B can itself have multiple columns that link to table C. The row states of all of the rows appear in the data tables that contain linked columns. For example, if row 1 is excluded in table A and row 1 is hidden in table B, the main data table will show the row as excluded and hidden.
- If a data table is accepting a specific row state, avoid manually applying that row state in the data table. Let the dispatching column control that row state.

Example of Merging Referenced Data in Virtually Joined Data Tables

To share the data from virtually joined data tables with another user, you might want to merge the data so that the data tables are permanently joined. This option is helpful because you provide one data table, not the main and auxiliary data tables.

When you merge referenced data, the data are replicated from the auxiliary data table to the main data table. When you save the main data table, the actual data are also saved.

1. Select **Help > Sample Data Library** and open Pizza Profiles.jmp and Pizza Responses.jmp.
2. Right-click the ID column in Pizza Profiles.jmp and select **Link ID**.

- Right-click and select **Link Reference** > Pizza Profiles.jmp.

The selected column is linked to the ID column in Pizza Profiles.jmp.

Figure 6.40 Selected Column in Virtually Joined Data Table

	Subject	Choice1	Choice2	Choice
1	1	ThickJack	TrimPepperjack	TrimPepperjack
2	1	TrimPepperjack	ThickElla	ThickElla
3	1	TrimOni	Trimella	TrimOni
4	1	ThickElla	ThickJack	ThickElla
5	2	Trimella	ThickJackoni	Trimella
6	2	TrimJack	ThickElla	ThickElla
7	2	Trimella	TrimPepperjack	Trimella
8	2	TrimPepperjack	TrimOni	TrimOni
9	3	TrimOni	ThickJackoni	TrimOni
10	3	TrimPepperjack	ThickElla	ThickElla
11	3	ThickJackoni	TrimPepperjack	ThickJackoni
12	3	ThickOni	Trimella	ThickOni
13	4	ThickElla	ThickOni	ThickElla
14	4	TrimPepperjack	ThickJack	ThickJack
15	4	Trimella	ThickJack	Trimella
16	4	TrimJack	ThickJack	TrimJack
17	5	ThickJack	Trimella	Trimella

- In Pizza Responses.jmp, select Choice1.

Note: If you do not select the columns, then all columns will be in the merged data.

- From the data table's red triangle menu, select **Merge Referenced Data**.

Figure 6.41 Merging Referenced Data

	Subject	Choice1
1	1	ThickJack
2	1	TrimPepperjack
3	1	TrimOni
4	1	ThickElla
5	2	Trimella
6	2	TrimJack
7	2	Trimella
8	2	TrimPepperjack
9	3	TrimOni
10	3	TrimPepperjack
11	3	ThickJackoni

A message confirms that the selected column was merged. Notice that the virtual join icon for Choice1 no longer appears in the Column list. The Link Reference column property was removed.

Figure 6.42 Merged Data

	Subject	Choice1
1	1	ThickJack
2	1	TrimPepperjack
3	1	TrimOni
4	1	ThickElla
5	2	Trimella
6	2	TrimJack
7	2	Trimella
8	2	TrimPepperjack
9	3	TrimOni
10	3	TrimPepperjack
11	3	ThickJackoni
12	3	ThickOni
13	4	ThickElla
14	4	TrimPepperjack
15	4	Trimella
16	4	TrimJack
17	5	ThickJack

Update Data Tables


If you have two data tables and would like to update your original table with data from a new table, select **Tables > Update**. The Update command is a special case of Join in place. It is a Join with the Update option checked, and it does not result in a new table.

Before you update a table, make sure that the name of the column containing the values that you want to replace is the same as the name of the column containing the data that you want to replace it with.

To replace values in the active table with those found in another open table

1. Click on the original table that you want to update (this is the table whose values you want to replace) to make it the active table.
2. Select **Tables > Update**.


Figure 6.43 Updating a Table



3. Highlight the new table containing the data that you want to transfer to the original table.
4. (Optional) If you do not want JMP to replace the values in the original table with any missing values found in the new table, select the box next to **Ignore missing**. The original table retains its original values if they correspond to missing values in the new table.
5. If the two tables have one or more columns whose values uniquely describe each row, JMP uses those columns as the *match column values*. That is, JMP updates the rows whose match column values coincide. JMP uses these columns to preserve the sorted order of the data. If your tables do not have matching column values, you can incorporate the updated values according to their row order by continuing here. To proceed with tables containing matching column values, see [“To update a table using matching columns”](#) on page 344.
6. From the Add Columns from Update table area, select an option. Using these options, you can add columns (that do not exist) from the new table into the original table.
 - Choose **All** to add all columns from the new table into the original table.
 - Choose **Selected** to add only columns that you have selected from the new table into the original table.
 - Choose **None** if you do not want to add any non-existent columns from the new table into the original table.
7. Click **OK**.

To update a table using matching columns

1. Follow the first three steps outlined in the previous section, [“To replace values in the active table with those found in another open table”](#) on page 343.
2. Select **Match columns**.

Figure 6.44 This Window Appears When You Click Match Columns

3. Highlight the two column names (in the respective tables) that you want to match.
4. Click **Match**.
5. (Optional) Repeat to match more columns.
6. Click **OK**.

Note: Columns that have different names from the columns in the table that you are updating (and that have not been assigned matches) are appended as separate columns. To avoid this problem, select the **None** option in the **Add Columns from Update table** area.

Example of Updating a Data Table

Suppose a researcher has a data table containing height measurements for students. The researcher receives an updated table that contains more recent measurements of the students' heights. The researcher wants to avoid scrolling through the data tables to find the students whose height has changed, and copying and pasting the new values. Using the **Update** command, the researcher can quickly update the original data table with the new height values.

1. Select **Help > Sample Data Library** and open **Big Class.jmp** and **New Heights.jmp**.
The **Big Class.jmp** table contains the original data, and the **New Heights.jmp** table contains the updated data.
2. From the **Big Class.jmp** table, select **Tables > Update**.
3. In the **Update...with data from** box, select **New Heights**.
4. Select **Match columns**.
5. In the **Big Class** and **New Heights** lists, select **name**.
6. Click **Match**.

This tells JMP to use name as the match column value, since it is the column whose values uniquely describe each row.

7. Click **OK**.

Figure 6.45 The Updated Big Class.jmp Table



	name	age	sex	height	weight
1	KATIE	12	F	62	95
2	LOUISE	12	F	61	123
3	JANE	12	F	58	74
4	JACLYN	12	F	68	145
5	LILLIE	12	F	52	64
6	TIM	12	M	64	84
7	JAMES	12	M	63	128
8	ROBERT	12	M	70	79
9	BARBARA	13	F	62	112
10	ALICE	13	F	61	107
11	SUSAN	13	F	58	67
12	JOHN	13	M	68	98
13	JOE	13	M	64	105
14	MICHAEL	13	M	60	95
15	DAVID	13	M	61	79

You can see that the height values in the updated table no longer match the values in the original table. The values have been updated to use the newer values from the New Heights.jmp table.

Anonymize Data

The Anonymize Data feature enables you to create a new data table in which certain unique identifiers have been removed.

Data are updated as follows:

- Column headings, character data, and value labels are modified.
- Data in nominal columns are modified.
- Modified data in ordinal columns appear in the same order as in the original data table.
- Data in continuous columns are not modified.
- Column names in column properties are modified.

Note: Table scripts and some table variables cannot be anonymized. If your data table contains content that cannot be anonymized, a warning message appears in the log.

“Notes” column properties are removed. Other column properties are modified based on changes in the data table. For example, Value Ordering properties are renamed. Formulas except for prediction formulas are updated. Some column properties might no longer have the desired affect on the column.

To rename data, do one of the following:

- To rename data in specific columns, select the columns and then select **Tables > Anonymize**.
- To rename data in the entire data table, select **Tables > Anonymize**.

The data appear in a new data table.

DISCLAIMER: The Anonymize Data utility is provided merely to assist Users in removing certain unique identifiers from a data table as described above. The Anonymize Data utility might not remove all sensitive or personally identifiable information from a data table. Users should not rely exclusively on the Anonymize Data utility to remove such information where complete anonymization, pseudo-anonymization, or de-identification of data is desired or required by law or policy (such as where data are or might be disclosed to other parties). SAS does not represent, and specifically disclaims, that use of the Anonymize Data utility will by itself result in the User's compliance with any national, state, local or international laws, regulations, or policies that pertain to the privacy, de-identification, or anonymization of sensitive or personally identifiable information.


Chapter 7

Formula Editor Construct Formulas

Use the JMP Formula Editor to create a column whose values are computed by a formula and store that formula as part of a column's information. Formulas can be simple assignments of numeric, character, or row state constants, or they can contain complex evaluations based on conditional clauses. The Formula Editor window operates like a calculator with buttons, displays, and a list of functions.

For details about the functions that are available in the Formula Editor, see the [“Formula Functions Reference”](#) chapter on page 631.

Figure 7.1 The Formula Editor



Contents

Formula Overview	352
Create a Formula	352
Refer to Values in Columns and Table Variables	354
Use Local Variables	357
Incorporate Parameters	358
Insert Constants	359
Add Operators	361
Keypad Reference	361
Use Functions in a Formula	362
Customize the Functions List	365
Copy a Formula to Columns on the Right	367
Order Expressions in Formulas	369
Build a Formula in Order of Precedence	370
Use Formula Editor Options	371
Calculate Derivatives	371
Simplify Complex Formulas	372
Evaluate Formulas	373
Ignore Errors	374
View Formula Values from the Formula Editor	374
View a Formula in JSL	374
Edit Formulas	375
Correct Mistakes	375
Select Expressions	375
Delete Functions	376
Cut, Copy, and Paste	376
Click and Drag	377
Customize Formulas	377
Hide and Show Boxing	377
Change the Font Size	378
Specify the Matrix Size	378
Change the Orientation of a Formula	378
Open and Close Arguments	378
Examples and Tutorials	379
Use Basic Formula Editor Features	379
Use Local Variables in a Formula	380
Use the Munger Function	381
Use the Match Conditional Function	382
Use the Delete Expression Button	383
Keyboard Shortcuts	384

Glossary of Terms	385

Formula Overview

Formulas are an integral part of a data table for the following reasons:

- They are stored as part of a column's information when you save the data table.
- You can examine or change them at any time by opening the Formula Editor.
- Their values can be linked to, or dependent on, the values in other columns. Their values are automatically recomputed whenever you edit the values in the columns to which the formula is linked.
- Their values are locked in the data table so that they cannot be manually edited.

This chapter describes the Formula Editor and shows how to build formulas. For details about each function, see the [“Formula Functions Reference”](#) chapter on page 631.

Create a Formula

A formula is an expression stored in a column that performs operations in order to insert values into that column. Formulas can perform mathematical operations, such as addition and multiplication, or they can compare column values or join values by referring to other areas in the same data table. Formulas can consist of any JMP Scripting Language (JSL) command. Once you insert a formula into a column, the column is locked: its values can be edited only by changing or removing the formula.

There are three basic steps to building a formula:

1. Open the Formula Editor by right-clicking the column name to which you want to apply the formula and selecting **Formula**.

or

Double-click the column name to which you want to apply the formula, select **Formula** from the Column Properties menu, and then click **Edit Formula**.


In the Formula Editor, the empty formula is selected (highlighted in blue). You can start typing or select a column or function.

- When you type, a small text editor window appears, which enables you to edit the formula. You can click the **Maximize editor** button  if you need more room. Long formulas open in the maximized editor by default.
- When you select a column or function, that item is added to the selected blue box.
- You can also drag a column from the Columns list into the selected box.

Note: An element is selected when there is a blue outline around it. All terms within the smallest nesting box relative to the place that you clicked become selected. The subsequent actions apply to those combined elements.

2. Add expressions, functions, and terms. Then they appear in the highlighted blue box. The following sections in this chapter provide detailed instructions on how to add constants, elements, operators, and functions.

Figure 7.2 Building a Formula



See [“Use Basic Formula Editor Features”](#) on page 379, for an example of how to use the Formula Editor.

Notes:

- In a formula, when you reference a column using value labels, place your cursor over the value label to see the actual data value.
- Whitespace in a formula is automatically removed by JMP.
- You can also use the Formula Editor to define a custom format. For example, you might want to convert a number from inches to centimeters using the calculation `Char( :height * 2.54 ) || " cm"`. Realize that the underlying data, which you see when double-clicking a data table cell, would still be the value of `:height`.

- To move the cursor from one field to another in a formula, select the field and press the left arrow key.
- For aggregated functions such as Col Mean, the formula might evaluate faster if you separate the formula into two columns. One column should contain an expression that represents the target for the aggregated function. The second column should contain the aggregated function itself referencing the new target column. Here's an example of the original formula:

```
:Y - Col Mean( If( :Status == "nonsmoker", :Y, . ), :Cyc1e )
```

In a new Y2 column, create this formula:

```
If( :Status == "nonsmoker",  
    :Y,  
    .  
)
```

In another column, create this formula:

```
:Y - Col Mean( :Name( :Y2, :Cyc1e )
```

Refer to Values in Columns and Table Variables

You can create a formula that refers to values found in other parts of the data table, such as other columns and table variables.

When a formula uses values in other columns, the values in the column with that formula are dependent on the values in those other columns. Whenever a column that the formula refers to changes, the dependent column also changes. If you delete the referenced column, empty terms appear in the column containing the formula.

If you create a formula that refers to values found in table variables, those table variables must already exist in the data table. Table variables are character strings that are available to the entire table. Their names are displayed in the table panel at the left of the data table. (For details, see [“Use Table Variables”](#) on page 248 in the “Enter and Edit Data” chapter.)


Tip: To create a table variable from a value in the Formula Editor, right-click the value and select **Create Table Variable from Value**.

The following example shows how to re-create a formula column in the Companies.jmp sample data table.


1. Select **Help > Sample Data Library** and open Companies.jmp.
2. Right-click the last empty column and select **New Columns**.

The Column Info window appears.


3. Type "Profit by Sales" next to Column Name.
You are re-creating the formula found in the existing %profit/sales column.
4. In the Column Properties list, select Formula.
The Formula Editor opens. The blue outline around the box in the editing window indicates that the box is selected.
5. With the box selected, select **Profits (\$M)** from the Columns list.

Figure 7.3 Adding the Profits (\$M) Column

6. With the box selected, click the Divide button .


Figure 7.4 Adding the Division Symbol

7. With the box selected as shown, select **Sales (\$M)** from the Columns list.

Figure 7.5 Adding the Sales (\$M) Column


8. Select the outer box in the formula editing area by clicking it.

Figure 7.6 Selecting the Formula



9. Click the Multiply button .

Figure 7.7 Adding the Multiplication Symbol



10. With the new box selected, type "100" and press Enter.

Figure 7.8 Multiplying the Formula by 100



11. Click **OK**.

The column is filled with the calculated numbers.

12. Right-click the last column and select Column Info.

13. In the Column Info window, select **Fixed Dec** from the Format list, type "10" next to Width, and type "2" next to Dec.

The column width and number of decimal places are specified.

14. Click **OK**.

The new formula column matches the %profit/sales formula column.

Tips:

- Pressing Alt (Option on Macintosh) and clicking a column replaces both empty and non-empty selected fields with that column.
- The right-click menu for the Columns list has two replacement options: **Replace all occurrences of selected subexpression** replaces all occurrences of the selected expression with the currently selected column. **Replace the selected subexpression with columns** replaces the selected expression with multiple columns (formerly Shift + Click) for functions that support it (for example, Sum or Plus).
- Define your own functions and transform columns by writing a JSL script. See the Data Tables chapter in the *Scripting Guide*.

Use Local Variables

You can create and use temporary numeric variables in expressions. You can use ordinary local variables or you can use parameters, which are special types of local variables. Local variables exist only for the evaluation of the formula in which they are defined. They appear in formulas as bold italic terms.

Local variables are most often used with Assignment functions, which can assign expressions to local variables that are used in a complex equation. (For details, see [“Assignment Functions”](#) on page 690 in the “Formula Functions Reference” chapter.) This technique can sometimes simplify building an equation and improve the efficiency of its evaluation.

To build a formula that references values found in local variables, follow these steps:

Step 1: Create the Local Variable

1. Open the Formula Editor by right-clicking a column name in the data table and selecting **Formula**.
2. Select a box in the formula editing area by clicking it. (It is selected when there is a blue outline around it.)
3. In the middle pane of the Formula Editor, select **Local Variables** from the list.
4. Click **New Local**.
5. Enter a name for the local variable. By default, local variables have the names *t0*, *t1*, and so on, and have missing values.
6. Assign a starting value, and click **OK**.
7. (Optional) To copy, edit, or delete a local variable, right-click (Ctrl-click on the Macintosh) its name and select **Copy**, **Edit**, or **Delete**.

Step 2: Insert a Local Variable into a Formula

1. Select a term in the formula editing area by clicking it. (It is selected when there is a blue outline around it.)
2. Click the local variable name in the Local Variables list. It appears in the formula as a bold italic term.

Notes:

- Double-clicking or pressing Alt and clicking the local variable replaces the portion of the formula that is selected.
- Another way to create local variables is to use the Make Temporary Variable  button on the Formula Editor keypad. The button automatically creates and displays local variables and places a semicolon after it. See [“Add Operators”](#) on page 361 for details.

- You can also create a local variable from an expression. Right-click the expression in the Formula Editor and select **Create Local Variable from Expression**.
- Pressing Alt and Shift and clicking enables you to edit the selected variable in place instead of in a new window.

See [“Use Local Variables in a Formula”](#) on page 380 for an example of referencing local variables in a formula.

Incorporate Parameters

Parameters are special types of local variables that are recognized as model parameters in some platforms, such as Nonlinear fitting. They can be used in formulas just as ordinary local variables can.

To view examples of parameters

1. In the sample data folder that was installed when you installed JMP, open the Nonlinear Examples folder and then US Population.jmp.
2. Right-click the column name x-formula and select **Formula**.
3. In the middle pane of the Formula Editor, select **Parameters** from the list.

Notes:

- After completing a nonlinear fit or after clicking the Reset button in the nonlinear control panel, the parameter's value is the most recent value computed by the nonlinear platform.
- Each time the fitting algorithm takes a step, the updated parameter values are shown in the Nonlinear report.
- When you paste a formula with parameters into a column, the parameters are automatically created for that column unless it has existing parameters with the same names.
- Double-clicking or pressing Alt and clicking the parameter replaces the portion of the formula that is selected.
- Pressing Alt, Shift, and clicking enables you to edit the selected parameter in place instead of in a new window.

To build a formula that references values found in parameters

Step 1: Create the Parameter

1. Open the Formula Editor by right-clicking a column name in the data table and selecting **Formula**.
2. Make sure the formula is selected in the formula editing area. (It is selected when there is a blue outline around it.)

3. In the middle pane of the Formula Editor, select **Parameters** from the list.
4. Click **New Parameter**.
5. Enter a name for the parameter. By default, parameters have the names *b0*, *b1*, and so on, and have missing values.
6. Assign a starting value. It is important to enter this value when using a parameter in a model for the nonlinear platform. After completing a nonlinear fit, the parameter's value is the most recent value computed by the nonlinear platform.
7. (Optional) To add several parameters (one for each level of a categorical variable, for example) at once, select **Expand into categories, selecting column**. Then select the column for which you want to expand the parameter.
8. Click **OK**.
9. (Optional) To copy, edit, or delete a parameter, right-click (Ctrl-click on the Macintosh) its name and select **Copy**, **Edit**, or **Delete**.

Step 2: Insert a Parameter into a Formula


1. Select a term in the formula editing area by clicking it. (It is selected when there is a blue outline around it.)
2. Click the parameter name in the Parameters box. The parameter appears in the formula as bold type.

Tip: Pressing Alt and Shift and then clicking enables you to edit the selected parameter.

Insert Constants

Formulas can be simple assignments of numeric, character, or row state constants, or they can contain complex evaluations based on conditional clauses. Constants include commonly used numeric terms, such as *e*, *pi*, -1, 0, 1, and 2. There are two ways to add a constant value to a formula:

- Enter them manually using the keyboard
- Select them from the list in the middle pane, as shown in Figure 7.9.

Figure 7.9 The Formula Element Browser with Constants Selected

To add constants to a formula, follow these steps:

1. Open the Formula Editor by right-clicking a column name in the data table and selecting **Formula**.
2. Select a box in the formula editing area by clicking it. (It is selected when there is a blue outline around it.)
3. Either type in a number or select **Constants** in the middle pane, as shown in Figure 7.9. Then click a value in the list that appears: 0, 1, 2, -1, pi, e. The value appears in the outlined box.
4. Complete the remainder of the formula using the keypad and functions. (See [“Refer to Values in Columns and Table Variables”](#) on page 354, [“Add Operators”](#) on page 361, and [“Use Functions in a Formula”](#) on page 362.)

Note: Double-clicking or pressing Alt and clicking the constant replaces the portion of the formula that is selected.

Add Operators

You can add operators to a formula using the keypad, which contains buttons that help build formulas. It includes common operators (also referred to as functions).

To build a formula using keypad operators at the top of the window, follow these steps:

1. Open the Formula Editor by right-clicking a column name in the data table and selecting **Formula**.
2. Select a box in the formula editing area by clicking it. (It is selected when there is a blue outline around it.) The operator performs its action on the area that is highlighted.
3. Select the column or variable that you want to use in your formula.
4. Click the keypad button(s).

Keypad Reference

Table 7.1 describes the keypad buttons.

Table 7.1 Keypad Buttons in the Formula Editor

Name	Description
 Arithmetic buttons	Work as they normally do on a pocket calculator, providing addition, multiplication, subtraction, and division operators.
 Insert	Inserts a new clause or function argument. First select the existing clause or argument that you want the new element to follow, and then click this button. The new clause appears and is selected. You can also insert a new clause or argument by typing a comma. Pressing ALT and the Insert icon  inserts a new field before the selected field
 Delete	Deletes an element's value, or deletes a clause. The delete button functions the same as the Delete key on the keyboard.
 Exponent	Raises a given value to a specified power. It has an exponent of two by default.

Table 7.1 Keypad Buttons in the Formula Editor *(Continued)*

Name	Description
 Root	Calculates the specified root of the radicand. It has an implied index of two (a square root), which is not displayed.
 Switch terms	Looks at the operator that is central to the selected expression and switches the expressions on either side of that operator.
 Unary sign function	Inverts the sign of the argument. Apply the unary sign function to variable expressions or use it to enter negative constants.
 Local variable (Make Temporary Variable)	Creates and displays a local variable and assigns it the value of the selected expression. The local variable has the default name <i>t0</i> in an expression and a semicolon after it. See “Use Local Variables” on page 357, for details about creating and inserting local variables. See “Use Local Variables in a Formula” on page 380, for an example.
 Delete expression (Peel)	Removes the outermost expression with the first argument. You can repeat this process to delete a formula term by term. See “Use the Delete Expression Button” on page 383, for an example.

Use Functions in a Formula

Tip: Within JMP, tooltips are available to help you understand what each function does.

You can add many types of functions to a formula. All of these functions are organized in the Functions list. The browser groups collections of functions in lists organized by topic. The list contains functions that are commonly used in formulas. Use the Functions list to specify the type of calculation that you want to perform on the elements in a formula.

To create a formula that contains a function, follow these steps:

1. Open the Formula Editor by right-clicking a column name in the data table and selecting **Formula**.

2. Select an expression in the formula editing area by clicking it. (It is selected when there is a blue outline around it.) The function performs its action on the area that is highlighted.
3. In the Functions list, select a group of functions to view. See Table 7.2 for details.
The functions that belong to that group are then displayed in the list below the menu. The function groups are briefly described in the following list.
4. Click any function in the Functions list to apply it to the selected item. When you click some items, you reveal a submenu from which you should make a selection.
5. Continue to build the formula by highlighting terms and clicking items in the formula element browser, keypad, or Functions list.

Tips:

- Pressing Alt and selecting the function replaces the selected function in a formula with the function that you select from the Functions list or the button that you select from the keypad.
- Pressing Alt (Option on Macintosh) and clicking a column or other element replaces the item even if it is non-empty.
- Most functions give hints about appropriate arguments through gray words inserted in the boxes in the formula editing area. Functions also show a small caret in the argument area if additional arguments can be added.
- To find out what a function does, right-click the function in the Functions list or in the formula and select **Show in Scripting Index**.
- Define your own functions by writing a JSL script. See the Data Tables chapter in the *Scripting Guide*.

Table 7.2 Groups of Functions

Group	Functions Included
Row	Displays a list of functions that contains miscellaneous functions such as Lag, Dif, Subscript, Row, and NRow. See “Row Functions” on page 633 in the “Formula Functions Reference” appendix.
Numeric	Displays a list of functions that are terms commonly used in formulas. See “Numeric Functions” on page 635 in the “Formula Functions Reference” appendix.
Transcendental	Displays a list of functions that are functions such as natural log, common log, exponential, root, factorial, combinatorial, beta, and gamma. See “Transcendental Functions” on page 636 in the “Formula Functions Reference” appendix.

Table 7.2 Groups of Functions (*Continued*)


Group	Functions Included
Trigonometric	Displays a list of functions that are the standard trigonometric functions: sine, cosine, tangent, inverse functions, and hyperbolic functions. See “Trigonometric Functions” on page 639 in the “Formula Functions Reference” appendix.
Character	Displays a list of functions that operate on character arguments such as trimming, finding the length of a string, converting between numbers and characters. See “Character Functions” on page 640 in the “Formula Functions Reference” appendix.
Comparison	Displays a list of functions that are the standard logical comparisons such as less than, less than or equal to, not equal to, and so on. See “Comparison Functions” on page 650 in the “Formula Functions Reference” appendix.
Conditional	Displays a list of functions that are programming-like functions, such as If, Match, and Choose. See “Conditional Functions” on page 651 in the “Formula Functions Reference” appendix.
Probability	Displays a list of functions that compute probabilities and quantiles for standard statistical distributions, such as normal, Student’s <i>t</i> , Chi-squared, and <i>F</i> -distributions. See “Probability Functions” on page 656 in the “Formula Functions Reference” appendix.
Discrete Probability	Displays a list of functions that compute discrete probabilities, such as Poisson, Gamma Poisson, and Hypergeometric. See “Discrete Probability Functions” on page 669 in the “Formula Functions Reference” appendix.
Statistical	Displays a list of functions that calculate standard statistical quantities such as the mean or standard deviation. See “Statistical Functions” on page 672 in the “Formula Functions Reference” appendix.
Random	Displays a list of functions that generate random numbers based on predefined distributions such as the uniform, normal, Cauchy, and so on. There is also a function to randomize the order of table rows. See “Random Functions” on page 676 in the “Formula Functions Reference” appendix.

Table 7.2 Groups of Functions (*Continued*)

Group	Functions Included
Date Time	Displays a list of functions that require arguments with the <i>date</i> data type, which is interpreted as the number of seconds since January 1, 1904. Date Time functions return values such as day, week, or month of the year. They can also compute dates and can find data intervals. See “Date Time Functions” on page 681 in the “Formula Functions Reference” appendix.
Row State	Displays a list of functions that assign or detect row state status of color, marker, label, hidden, excluded, or selected. See “Row State Functions” on page 684 in the “Formula Functions Reference” appendix.
Assignment	Displays a list of functions that place the value on the right side of the assignment operator into the variable on the left side of the operator. See “Assignment Functions” on page 690 in the “Formula Functions Reference” appendix.
Parametric Model	Lets you construct a Linear, Interactions, or Full Quadratic model for columns that you choose. After choosing the type of model, a window appears that lets you select the variables from which to construct the model. Hold the Ctrl key and click to select more than one. See “Parametric Model Functions” on page 690 in the “Formula Functions Reference” appendix.
Finance	Lets you create formulas to calculate principal payments, interest rate, rate of return, and so on. See “Finance Functions” on page 691 in the “Formula Functions Reference” appendix.

Customize the Functions List

You can customize the Functions list to make it easier to find the functions that you typically work with. The functions appear at the top of the list. Show frequently used functions at the top of the list, create your own function categories, delete functions, delete categories, move functions up and down in the list, and delete functions.

Figure 7.10 Customizing the Functions List


To quickly bookmark a favorite function

1. Right-click the function in the Functions list.
2. Select **Add as favorite**.

To bookmark a favorite and specify the location

1. Select **Customize functions list** from the red triangle menu.
2. Select the function in the Available Functions list.
3. Click the right arrow button to place it in the Functions list.
4. Click the up or down button to rearrange the favorite.

To rearrange or delete favorites

1. Select **Customize functions list** from the red triangle menu.
2. Select **<Top level items>** in the Categories list.
3. Select the favorite function that you want to rearrange and click the up or down button.
4. Select the favorite function that you want to delete and click the X button.

To rearrange, add, or delete categories

1. Select **Customize functions list** from the red triangle menu.
2. In the Categories list, select a category and rearrange, add, or delete the category.

To rearrange or delete functions


1. Select **Customize functions list** from the red triangle menu.
2. In the Categories list, select the category that contains the function you want to rearrange or delete.
3. Click the up, down, or X buttons to rearrange or delete the selected function.

Note: Deleting a function only deletes it from the Functions list. You can still type the function in a formula.


Copy a Formula to Columns on the Right

The Standardize Attributes option in the Cols menu provides a way to replicate a column formula while incrementing each column reference in the formula. This option is an alternative to manually creating new column formulas whose columns increment by one in each of the subsequent columns. For example, if column B contains the formula $A \times 2$, then the standardized column C would contain the formula $B \times 2$, and the standardized column D would contain the formula $C \times 2$.

1. Select **Help > Sample Data Library** and open Semiconductor Capability.jmp.
2. Select **Cols > New Columns**.
3. Type 3 next to **Number of columns to add** and click **OK**.
4. Select the first new column, select **Cols**, and then select **Formula**.
5. Create the formula $NPN1/PNP1$ and click **OK**.

Figure 7.11 Create the Formula NPN1/PNP1

6. Select the three new columns and then select **Cols > Standardize Attributes**.
7. In the Standardize Properties section, select **Formula** from the list.
8. Select **Substitute Column Reference** and leave NPN1 and PNP1 selected.

Figure 7.12 Standardize Properties Options

Note: In this example, we want to change both NPN1 and PNP1. You can deselect the column that you do not want to change in the subsequent formulas.

9. Click **OK**.

A formula that is relative to the formula in the first new column is copied to the second and third selected columns.

The formulas in the second and third selected columns increment by one column.

- Original formula in the first column: NPN1/PNP1
- Relative formula in the second column: PNP1/PNP2

In the data table, PNP2 comes after PNP1.

- Relative formula in the third column: PNP2/NPN2

In the data table, NPN2 comes after PNP2.

Figure 7.13 Resulting Data Table

NPN1	PNP1	PNP2	NPN2	X	Y	Z
114.55576	322.616752	469.39029	115.958473	0.3550831117	0.687310238	4.0479171331
120.043693	333.12808	437.781113	120.974137	0.3603529704	0.7609466694	3.618799212
114.92651	348.978757	532.128147	117.753124	0.3293223673	0.6558171354	4.5190151087
111.756446	268.548094	373.058629	114.092608	0.4161505811	0.7198549341	3.2697879024
111.545085	295.073166	338.900737	113.778098	0.3780251749	0.8706772615	2.9786113754
113.523596	323.833299	469.992171	116.488049	0.3505618367	0.6890184949	4.0346814413

Note: Some columns in Semiconductor Capability.jmp were deleted to show the new columns X, Y, and Z in Figure 7.13.

See [“Example of Standardizing a Formula”](#) on page 296 in the “The Column Info Window” chapter for another example.

Order Expressions in Formulas

As you build a formula, keep in mind that all functions have an order of precedence shown in the following table, where level one is the highest order of precedence. Expressions with a high order of precedence are evaluated before those at lower levels. When an expression has operators of equal precedence, it is evaluated from left to right. You can use parentheses to override other precedence rules when necessary because any expression within parentheses is always evaluated first. Terms have no order of precedence because they cannot be evaluated further. Table 7.3 shows the first six levels of the order of precedence.

Table 7.3 Order of Precedence of Operators in Formulas

Level 1	Parentheses
Level 2	Functions in the Functions lists, And, Or, Not

Table 7.3 Order of Precedence of Operators in Formulas *(Continued)*

Level 3	$\ast, \div$, Modulo
Level 4	$+, -$
Level 5	Comparisons: $<, \leq, =, \neq, \geq, >, \leq x <, < x \leq, < x <$
Level 6	Logical Operators $\&, $, and $!$


Note: When a function has an expression as its argument, the argument has a higher order of precedence than it would if enclosed in parentheses outside the function.

Build a Formula in Order of Precedence

It is best to build a formula starting with any expression that serves as an argument. This is because functions have a high order of precedence and are always grouped with their corresponding arguments. It is also a good idea to create expressions working from highest to lowest order of precedence when possible. If you need parentheses, be sure to enter the open parenthesis before entering the expression to be enclosed.

For example, given a data table with the columns A, B, and C, use the following steps to compose the expression $A(B + C)$. Note that this expression is not the same as $A \times B + C$, which evaluates as $(A \times B) + C$.

To enter the expression, follow these steps:

1. Click column A in the Columns list. 
2. Click the multiplication button  in the Formula Editor keypad. 
3. Enter an open parenthesis. 
4. Click column B in the Columns list. 
5. Click the addition button  in the Formula Editor keypad. 
6. Click column C in the Columns list. 

Because the order of precedence determines which arguments are affected by each functions, it also affects the grouping of expressions. Select functions in the formula to verify how the order-of-precedence rules have been applied.

Structure Formulas for Efficient Evaluation


Usually, it is not necessary to structure formulas with efficient evaluation in mind. Most formulas evaluate almost instantaneously regardless of their structure. This is because

statistical functions and constant expressions are evaluated only once when a column's values are calculated.

However, when you are creating conditional expressions, keep in mind that Match evaluates faster and uses less memory than an equivalent Condition function, If. (Note that Match ignores trailing spaces and If does not.)

For example, using Big Class.jmp, you can predict a child's height from his age as shown in Figure 7.14. There is a base height of 58.125 inches to which a quantity is added depending on the value of the age variable.

Figure 7.14 The Match Conditional Evaluates Faster Than the If Function



The Match conditional evaluates faster than the If function because the age variable is evaluated only once for each row in the data table. The If condition must evaluate the age variable at each If clause for each row until a clause evaluates as true.

Use Formula Editor Options

- [“Calculate Derivatives”](#)
- [“Simplify Complex Formulas”](#)
- [“Evaluate Formulas”](#)
- [“Ignore Errors”](#)
- [“View Formula Values from the Formula Editor”](#)
- [“View a Formula in JSL”](#)


Calculate Derivatives

The JMP Formula Editor can find and display the derivative of a function. The derivative is found with respect to the function argument (a single variable name) you highlight. Therefore, in order to differentiate with respect to x , x must be one of the arguments in the expression. The red triangle menu next to the keypad contains the Derivative command.

To calculate a derivative, follow these steps:

1. Enter a function.
2. Highlight a variable.
3. Select **Derivative** from the menu. Figure 7.15 shows the completion of these steps.

Figure 7.15 Using the Derivative Option




Simplify Complex Formulas

When the Formula Editor contains a complex formula, JMP can simplify it using various algebraic rules. It can find constant expressions, distribute multiplication over addition, combine terms, and more.

To simplify complex formulas, follow these steps:

1. Select a portion or all of the formula.
2. Click the red triangle menu next to the keypad.
3. Select **Simplify** from the list as shown in Figure 7.16.

Figure 7.16 Selecting Simplify (Left) Produces a Simplified Formula (Right)

Evaluate Formulas

By default, JMP evaluates each formula that you create. You can turn this evaluation off, or you can use it before you have finished creating a formula.

Suppress Evaluation

Turning off evaluation is a useful formula development mode for building complex formulas. You can turn off evaluation and build sections of a formula, and evaluate only to test it. In particular, you can close the Formula Editor and reopen it at a later time to continue building a formula without JMP evaluating it.

To suppress formula evaluation, click the red triangle menu next to the keypad and select **Suppress Eval**. When evaluation is suppressed, the formula icon  appears dimmed.

Note the following:

- If the icon appears to the right of the red triangle menu in the Formula Editor, it indicates that formula evaluation is suppressed for that formula.
- If the icon appears beside the column name in the Columns panel, it indicates that the values in the column result from a formula. When formula evaluation is suppressed, this formula icon  appears dimmed. For details, see [“Icons Representing Column Characteristics and Properties”](#) on page 45 in the “Get Started” chapter.
- You can turn off formula evaluation for all formulas by selecting **Suppress Formula Eval** from the data table red triangle menu. To re-evaluate formulas, select **Rerun Formulas** from the data table red triangle menu. You can also click the **Apply** button in the Formula Editor for each column that contains a pending formula.

- When you turn off formula evaluation, edit a formula, and click **Apply**, you are prompted for whether to evaluate the formula. To allow formula evaluation once, click **Evaluate formula this time**.

Ignore Errors

Once you construct a formula and click **OK**, JMP checks behind the formula for error and alerts you of any errors that it finds. An error message appears for each error and asks whether you want to ignore further errors.

Sometimes you might want to suppress error messages while a formula is under development. For example, you might want the evaluated values for some rows without seeing an error message for each row that causes errors.

To ignore errors, follow these steps:

1. Create a formula.
2. Click the red triangle menu next to the keypad and select **Ignore Errors**.

View Formula Values from the Formula Editor

While in the Formula Editor, you can see the value of any expression within a formula with the Evaluate command. For column variables, you get the value at row 1. This is also true for parameters and expressions that evaluate to a constant value.

To view values, follow these steps:

1. While in the Formula Editor, select the expression that you want to know about.
2. Right-click the selected expression.
3. Select **Evaluate**. The current value of the selected expression appears in a box until you move the cursor.


View a Formula in JSL

You have the option of entering or changing any part of a formula in *text mode*. Text mode displays the formula in JMP Scripting Language (JSL). The entire formula (or any of its terms) appears in the Script Editor when you double-click the formula. If the formula is long, it opens in a maximized Script Editor window. Otherwise, you can click the **Maximize editor** button  to maximize the window.

Any element of a formula can be displayed in the Script Editor and then edited. After editing formula scripting commands, click outside the formula (or click **OK** below the maximized window) to see its formatted form and to save the change. To enter an If statement in text form, add pairs of arguments for each If/Then clause in the statement, and a single last

argument for the else clause if needed. In text form, the If statement in Figure 7.17 looks like this: `If(:total!=0, (:count/:total)*100, 0)`.

Figure 7.17 An If Statement in Formula Mode



Edit Formulas

- “Correct Mistakes”
- “Select Expressions”
- “Delete Functions”
- “Cut, Copy, and Paste”
- “Click and Drag”

Correct Mistakes

If you make a mistake while entering a formula, hold down the Ctrl key and press Z. This reverses the effect of the last (undo-able) command.

Other commands to help modify formulas include the following:

- Click the delete button () on the Formula Editor keypad to remove the selected expression.
- Use the cut, copy, and paste keyboard shortcut commands or right-click a highlighted part of the formula and select **Cut**, **Copy**, or **Paste** from the menu.
- Drag portions of the formula to rearrange them.

Select Expressions

Use the keyboard arrow keys to select expressions for editing. You can also use the arrow keys to view the formula’s order of precedence when either parentheses or the boxing option are not present. (See “[Hide and Show Boxing](#)” on page 377.)

Clicking an operator (+, −, *, ÷) in an expression selects the operator and its operands. A blue box appears around the items. Once an operator is selected:

- The left and right arrow keys move the selection across other associative operators having equal precedence within the expression.
- The up arrow extends the current selection by adding the operand and operator of higher precedence to the selection.
- The down arrow reduces the current selection by removing an operand and operator from the selection.

Delete Functions

Deleting a function also deletes its arguments. Deleting a required argument or missing term from a function sometimes deletes the function as well. You can peel a function to delete it from its argument.

To peel a function from a single argument, follow these steps:

1. Select the function.
2. Click the peel button  in the Formula Editor keypad. Or use the hand tool to drag the argument on top of its function.

Figure 7.18 Peeling an Argument



3. Complete formula changes.
4. Click **Apply**, and the new values fill the data table column automatically.
5. Once you have created a formula, you can change values in columns that are referenced by your formula. JMP automatically recalculates all affected values in the formula's column.

Cut, Copy, and Paste

You can cut or copy any expression or an entire formula and paste it into another formula display. Use the cut, copy, and paste shortcut commands or right-click a highlighted part of the formula and select **Cut**, **Copy**, or **Paste** from the menu. The following aspects apply when you cut, copy, and paste a formula:

- When you paste it into another formula display, the formula appears in formatted form.
- The formula is saved on the clipboard as a JSL statement. Thus, if you copy it into other applications, it appears as a JMP Scripting Language (JSL) statement.

Note: Press the Shift key on your keyboard, and then click the red triangle to reveal a command called **Copy As SAS Formula**.

Click and Drag

You can drag any part of a formula that can be selected to any other location that can be selected.

To click and drag in a formula, follow these steps:

1. Place the arrow cursor inside an expression.
2. Click the expression. It is highlighted and the cursor changes to a hand cursor.
3. Drag across the formula. Destination expressions are highlighted.
4. Drag the selected expression to the new desired location. The selected expression is copied to the new location, where it replaces the existing expression.

Customize Formulas

There are several ways that you can customize formulas in the Formula Editor.

- [“Hide and Show Boxing”](#)
- [“Change the Font Size”](#)
- [“Specify the Matrix Size”](#)
- [“Change the Orientation of a Formula”](#)
- [“Open and Close Arguments”](#)

Hide and Show Boxing

By default, JMP outlines specific terms within the formula. This is called *boxing*. Boxing is useful when you want to select and modify a specific portion of a formula, or need to determine the order of evaluation that takes place.

To turn boxing on or off, follow these steps:

1. Build a formula.
2. Click the red triangle menu next to the keypad and select **Show Boxing**. When a check appears on the menu beside **Show Boxing**, the outline appears in the formula. When it does not, the outline does not appear.

Change the Font Size

To incrementally increase or decrease the font used to display the formatted formula, follow these steps:

1. Click the red triangle menu next to the keypad.
2. Select **Larger Font** or **Smaller Font**.
3. Repeat this process to further increase or decrease the font size.

Specify the Matrix Size

You can set the maximum width and height of matrices by selecting **Max matrix size to show** from the red triangle menu. If the width or height is greater than the specified size, the matrix dimensions show instead of the data. You can still see the data by editing the formula in the text editor window.

Change the Orientation of a Formula

By default, JMP determines the size of a formula and displays it in the Formula Editor in the best orientation (horizontally or vertically). However, if you create a long formula, you might want to display it in a different layout.

To change a formula's orientation, follow these steps:

1. Build a formula.
2. Highlight an argument or formula.
3. Right-click what you have highlighted.
4. Select **Orientation**.
5. Select from the Orientation options: Best, Horizontal, or Vertical.

Open and Close Arguments

When a formula is too large to fit on the screen, you can close formulas and arguments.

To close an argument, follow these steps:

1. Build a formula.
2. Highlight an argument or formula.
3. Right-click what you have highlighted.
4. Select **Close** or **Close Arguments** from the menu that appears.

Examples and Tutorials

To better familiarize yourself with building formulas, review the following examples and tutorials.

- [“Use Basic Formula Editor Features”](#)
- [“Use Local Variables in a Formula”](#)
- [“Use the Munger Function”](#)
- [“Use the Match Conditional Function”](#)
- [“Use the Delete Expression Button”](#)

Use Basic Formula Editor Features

The following example uses the Big Class.jmp sample data table to walk you through using the basic features of the Formula Editor. You can find Big Class.jmp in the sample data folder, which was installed when you installed JMP.

Big Class.jmp has a column called weight. Suppose you want a new column that computes standardized weight values.

To create this column using a formula to obtain its values, follow these steps:

1. Select **Help > Sample Data Library** and open Big Class.jmp.
2. Select **Cols > New Columns**.
3. Type the new name, standard weight, in the box beside Column Name.
4. Select **Formula** from the Column Properties menu.
5. Click the empty formula element in the formula editing area to select it.

When you create a formula and Show Boxing is checked, the selected portion of the formula is outlined with a thin blue line. See [“Hide and Show Boxing”](#) on page 377. All terms within the smallest nesting box relative to the place that you clicked become selected, and the subsequent action applies to those combined elements.

Next, enter the formula that standardizes the weight values.

1. While the initial missing term is selected, click weight in the Columns list.
2. Click the minus button  in the Formula Editor keypad.
A new missing term appears after the minus sign as shown in Figure 7.19.
3. Click weight again.
4. Click the Functions list, and select **Statistical**.
5. Select **Col Mean** from the Statistical list.

6. Select the entire expression.

The blue box should now enclose the whole formula.

7. Click the division button $\div$ in the keypad.

The result gives a selected missing denominator for the whole expression.


8. Click weight again from the column selector list.

It becomes selected in the denominator.

9. Select **Col Std Dev** from the Statistical list.

Figure 7.19 shows the completed formula.

Figure 7.19 Building a Formula



10. Close the Formula Editor by clicking **OK**.

11. Close the Column Info window by clicking **OK**.

In the data table, the new Standard Weight column fills with values. When a weight value changes, the calculated Standard Weight value automatically recalculates.

Use Local Variables in a Formula

Suppose you want to compute the slope in a simple linear regression of y on x using the standard formula shown in Figure 7.20. One way to do this is to create two local variables, and name them XY and $Xsqrd$. (See [“Use Local Variables”](#) on page 357.) Then assign them to the

numerator and the denominator calculations of the slope formula. Delimit each assignment with a semicolon, as shown in Figure 7.20. (Statements in the Formula Editor are actually JSL programming statements. Multiple statements in a formula must be separated by a semicolons.) The slope computation is simplified to XY divided by Xsqrd.

Figure 7.20 Local Variables in a Standard Slope Formula

$$\frac{\sum (x - \bar{x})(y - \bar{y})}{\sum (x - \bar{x})^2}$$

$$XY = \sum_{i=1}^{NRow()} [(X_i - Col Mean(X)) * (Y_i - Col Mean(Y))];$$

$$Xsqrd = \sum_{i=1}^{NRow()} (X_i - Col Mean(X))^2;$$

$$\frac{XY}{Xsqrd}$$

Note: You can also create local variables using the  button on the on-screen keypad. Clicking this button creates a local variable with a default name in an expression and places a semicolon after it. The default name is *t1*, and additional local variables are named *t2*, *t3*, and so on. You can change these default names by double-clicking and editing the name. However, you must be careful to rename each instance of the variable to avoid errors.

Use the Munger Function

The following examples show uses of the Munger function. In these examples, assume that there is a character column of names with “Veronica Layman” as one of its values. To simplify the examples, the literal name “Veronica Layman” is the search string instead of a column name.

For instructions on how to incorporate Character functions, such as Munger, into a formula, see [“Character Functions”](#) on page 640 in the “Formula Functions Reference” appendix.

Insert Characters

This Munger example finds the blank between the first and last name, and inserts the middle initial “J.” The formula `Munger("Veronica Layman", 1, " ", " J. ")` inserts the middle initial J., and evaluates as Veronica J. Layman.

Double quotation marks are required by the Munger function for literal strings, including strings that consist of a blank or when leading or trailing blanks are part of a string.

Delete Characters

To delete one or more characters from a string, follow these steps:

1. Designate the characters to delete as the Find string in the Munger function.
2. Enter an empty Replace string: two quotation marks with nothing between them.

For example, the function, **Munger("Veronica Layman", 1, "onic", "")** removes the "onic" from Veronica and evaluates as Vera Layman.

Note: A Replace field with a null (no value) string enclosed in quotation marks is different from a Replace field with no value. If you delete the Replace string altogether, Munger shows the argument name ("Replace") in the Formula Editor window and behaves as if that optional argument does not exist. The resulting data type can also change from character to numeric, depending on the value of the Find/Length argument.

Find the Position (Index) of a Value

When the Find/Length field contains characters, Munger behaves like an index function and returns the numeric position of the first instance of the search string if it exists. For example, **Munger("Veronica Layman", 1, " ")** searches for a single blank and finds it in position nine. If the search string is not found, Munger returns a zero. This use of Munger produces the same result as the Contains function, as shown in ["Character Functions"](#) on page 640 in the "Formula Functions Reference" appendix.

Find a Substring

Munger can extract substrings. For example, to extract only the first name, **Munger("Veronica Layman", 1, 8,)** starts at position one and reads through position eight. The remaining characters are ignored because the replace argument is not defined. This yields "Veronica" and produces the same result as the Substring, as shown in ["Character Functions"](#) on page 640 in the "Formula Functions Reference" appendix.

An alternative way to find a substring is with a start value, any negative find value, and a no replace argument. **Munger("Veronica Layman", 9, -1,)** returns "Layman".

Use the Match Conditional Function

This example walks you through using the Match conditional function.

Suppose that you want a Match conditional for the nominal variable Type from the Hot Dogs.jmp sample data table.

1. In the Formula Editor, select Type from the Columns list.
2. Select **Conditional** from the Functions list.

3. Select **Match**.
4. Select **Add Arguments from Data**.

The values are automatically filled in. See Figure 7.21.

Note: Rather than complete step 2 through step 4, hold down the Shift key, select **Conditional** from the Functions list, and then select **Match**.

Figure 7.21 Automatically Filling a Match Conditional Statement




If you do not want the values filled in for you, select **Do Not Add** from the Match list instead of **Add Arguments from Data**.

Use the Delete Expression Button

The following steps illustrate the results of repeatedly clicking the delete expression (or peel) button :


1. Start with a formula.




2. Select a formula element.



3. Click the delete expression button .



4. Click the delete expression again.



5. Click the delete expression again.



6. Click the delete expression again.



7. Click the delete expression again.



8. Click the delete expression again.



9. Click the delete expression again.



Keyboard Shortcuts

Table 7.4 describes the keyboard shortcuts that you can use in the Formula Editor.

Table 7.4 Keyboard Shortcuts in the Formula Editor

Insert This Item	Using This Keyboard Shortcut
A missing element (•)	DELETE
Subscript	[
Exponent	^ (Hold down the Shift key and type 6.)
Set of parentheses ()	(


Table 7.4 Keyboard Shortcuts in the Formula Editor *(Continued)*

Insert This Item	Using This Keyboard Shortcut
Set of quotation marks " "	"
New argument before the selected field	Alt + 
* (multiplication symbol)	* on keypad or keyboard
+	+ on keypad or keyboard
-	- on keypad or keyboard
÷	/ on keypad or keyboard
+/-	Hold down the Shift key and press the - (Minus) key
And	&
Not	!
Or	
Power	^
New argument	,
x<y	<
x==y	=
x>y	>


Glossary of Terms

The following terms are used in the Formula Editor:


Element The name of a constant, table variable, local variable, or parameter that appears in the element browser list.




Argument Any element or an entire expression (including mathematical operands) that is operated on by a function. Arguments are always grouped with functions. To find which expressions serve as a function's arguments, select that function in the formula.




Term Indivisible parts of an expression, such as constants and variables.



Expression Any part of a formula that can be selected as a single unit, including terms, missing terms, and functions grouped with their arguments, as well as the entire formula.



Clause A complete segment in a conditional function.



Function A mathematical or logical operation that performs a specific action on one or more arguments. Functions include most items in the Functions list and all keypad operators. Functions always operate upon selected expressions, and arguments are always grouped with functions. To find which expressions serve as a function's arguments, select that function in the formula.

The boxed groupings also show how order-of-precedence rules apply and show which arguments are deleted when you delete a function. See [“Order Expressions in Formulas”](#) on page 369 for details.



Missing term Any empty place holder for an expression, represented by an empty box.



Missing value Excluded or null data consisting of the missing value mark (•) for numeric data or null character strings for character data.

	name	age
1	KATIE	•
2		12
3	JANE	12

Chapter 8

Summarize Data The Table Summary Command

This chapter describes how to create a summary data table, which includes summary statistics such as the mean and median, standard deviation, and minimum and maximum values.

Figure 8.1 Summary Table for Companies.jmp

Request Summary Statistics by Grouping Columns.

Select Columns: 8 Columns

- Type
- Size Co
- Sales (\$M)
- Profits (\$M)
- # Employ
- profit/emp
- Assets
- %profit/sales

☐ Include marginal statistics

For quantile statistics, enter value (%): 25

statistics column name format: stat(column)

Output table name:

☒ Link to original data table

☐ Prompt to save when closing summary tables.

☐ Keep dialog open

Statistics: Mean(profit/emp) optional

Group: Size Co optional

Subgroup: Type optional

Freq: optional

Weight: optional

Action: OK, Cancel, Remove, Recall, Help

	Size Co	N Rows	Mean(profit/emp, Computer)	Mean(profit/emp, Pharmaceutical)
1	big	9	4530.478	17140.699
2	medium	7	-3462.506	24035.115
3	small	16	7998.815	38337.191

Contents

Summarize Columns 391

 Launch Window Roles 391

 Create a Summary Table 391

 Add a Statistics Column to an Existing Summary Table..... 395

Explanation of Statistics 396

Example of Creating a Summary Table 398

Summarize Columns

The **Tables > Summary** command calculates various summary statistics, including the mean and median, standard deviation, minimum and maximum value, and so on.

Summary tables have the following characteristics:

- A single row exists for each level of a grouping variable that you specify. If no grouping variable is specified, a single row exists for the full data table.
- When there are several grouping variables, the table contains rows for each combination of levels of all the grouping variables.
- In addition to one column for each grouping variable, the table contains frequency counts in a column named **N Rows** with counts for each grouping level.
- The summary table can be linked to its source table. When you select rows in the summary table, the corresponding rows are highlighted in its source table.
- If the source table's column(s) contain value labels, the value labels are displayed in the new table.
- A summary table is not saved when you close it unless you select **File > Save As** to give it a name and location.

Launch Window Roles

Statistics Defines the summary statistics (such as mean, standard deviation, and median) for a numeric column in the source table. See [“Add Summary Statistics”](#) on page 392 for details.

Group Summarizes the statistics by group. See [“Use One or More Grouping Columns”](#) on page 392 for details.

Subgroup Summarizes the statistics by subgroup. See [“Create a Two-Way Table of Summary Statistics by Adding a Subgroup Variable”](#) on page 395 for details.

Freq Identifies a column whose values assign a frequency to each row.

Weight Identifies a column whose values assign a weight to each row.

Create a Summary Table

To create a summary table, follow these steps:

1. Open a data table.
2. Select **Tables > Summary**.

3. Highlight the columns that you want to summarize.

Note: For details about the options in the red triangle menu, see [“Column Filter Menu”](#) on page 57 in the “Get Started” chapter.

4. Add summary statistics, groups, subgroups, frequency variable, weight variable, and select any options needed:
 - [“Add Summary Statistics”](#) on page 392
 - [“Use One or More Grouping Columns”](#) on page 392
 - [“Use Quantile Statistics”](#) on page 394
 - [“Change the Format of the Statistics Column Name”](#) on page 394
 - [“Link to the Original Data Table”](#) on page 394
 - [“Prompt to Save When Closing Linked Summary Tables”](#) on page 395
 - [“Keep the Summary Window Open”](#) on page 395
 - [“Create a Two-Way Table of Summary Statistics by Adding a Subgroup Variable”](#) on page 395
5. Name the summary table by typing a name in the box beside **Output table name**.
6. Click **OK**.

Note: When the summary table is linked to the original data table, you cannot edit the data in the summary table, because that would modify and compromise the original data. To edit the data, create a subset of the summary table or save the table, close the table, and reopen it.

Add Summary Statistics

You can add columns that display summary statistics (such as mean, standard deviation, median, and so on) for any numeric column in the source table.

1. In the Summary window, highlight the column that you want to use in calculating the statistics.
2. Click the **Statistics** button.
3. Select one of the standard univariate descriptive statistics from the Statistics list. The statistics are described in [“Explanation of Statistics”](#) on page 396.

Use One or More Grouping Columns

If you want the statistics summarized by group, highlight the column(s) that you want to be your grouping variables and click **Group** to move the variable into the grouping variables list. See [“Example of Creating a Summary Table”](#) on page 398, for an example. If you add only grouping variables, the summary table shows a count for each group.

To change the order of the grouping variables

To change the order of the grouping variables (ascending or descending order), select a variable in the grouping variable list and click the ascending or descending button ( ). The icon beside the variable changes to indicate the sorting order.

You can also change the order of the grouping variables using the Value Ordering column property. See “[Value Ordering](#)” on page 273 in the “The Column Info Window” chapter.

To include marginal statistics

To add marginal statistics (for the grouping variables) to the output columns, click the box beside **Include marginal statistics**. In addition to adding marginal statistics for each grouping variable, JMP adds rows at the end of the table that summarize each level of the first grouping variable.

1. Select **Help > Sample Data Library** and open **Companies.jmp**.
2. Select **Tables > Summary**.
3. Select **Profits (\$M)** and click **Statistics**.
4. Select **Mean**.
5. Select **Type** and **Size Co** and click **Group**.
6. Select **Include marginal statistics**.
7. Click **OK** (or **Create**). See Figure 8.2 at left.

Figure 8.2 Summary Table with and without Marginal Statistics

	Type	Size Co	N Rows	Mean(Profits (\$M))
1	Computer	big	4	1,089.93
2	Computer	medium	2	-85.75
3	Computer	small	14	44.94
4	Computer		20	240.87
5	Pharmaceutical	big	5	894.42
6	Pharmaceutical	medium	5	698.98
7	Pharmaceutical	small	2	156.95
8	Pharmaceutical		12	690.08
9			32	409.32

	Type	Size Co	N Rows	Mean(Profits (\$M))
1	Computer	big	4	1,089.93
2	Computer	medium	2	-85.75
3	Computer	small	14	44.94
4	Pharmaceutical	big	5	894.42
5	Pharmaceutical	medium	5	698.98
6	Pharmaceutical	small	2	156.95

Compare the summary table with marginal statistics (at left) to the summary table without marginal statistics (at right). You can see that the marginal statistics are added, and a row showing that there are 32 total Computer and Pharmaceutical companies.

Use Quantile Statistics

To add specific quantile statistics, follow these steps:

1. In the box under **For quantile statistics, enter value (%)** type the desired quantile value (%) for the first quantile (for example, 25).
2. Select the applicable column and click **Statistics**.
3. Select **Quantiles**.
4. (Optional) Repeat this process for any additional quantiles.

Change the Format of the Statistics Column Name

To change the format of the statistics column name in the summary table, select from one of the formats in the **statistics column name format** menu. Table 8.1 illustrates the available options. Assume that you are creating a summary table of the mean profits for a company. Your original column name is Profits (\$M).

Table 8.1 Statistics Column Name Format Options and Examples

Option	Example
stat (column)	Mean (Profits (\$M))
column	Profits (\$M)
stat of column	Mean of Profits (\$M)
column stat	Profits (\$M) Mean

Link to the Original Data Table

You can select whether to link the summary table to the original data table. By default, the **Link to original data table** option is selected. If you want to edit the data in the summary table, deselect the **Link to original data table** option. When the summary table is linked to the original data table, you cannot edit the data in the summary table, because that would modify and compromise the original data. To edit the data, create a subset of the summary table or save the table, close the table, and reopen it.

Within linked tables, if you drag columns from the summary table into the column heading of a new column in the original data table, the values are expanded as if they were matched by grouping columns.

Prompt to Save When Closing Linked Summary Tables

To be prompted to save an unsaved linked summary table when you close it, select **Prompt to save when closing summary tables**. When you select this option in the Summary window, it is selected in the Tables preferences. If you do not want to be prompted to save linked summary tables in the future, deselect the preference.

Keep the Summary Window Open

If you select the **Keep dialog open** option, the Summary window remains open after you click **Create**. Notice that once you select this option, the OK button is replaced by a Create button.

Create a Two-Way Table of Summary Statistics by Adding a Subgroup Variable

1. Highlight the column(s) that you want to be the nested variable(s). These are your "subgroup variable(s)."
2. Click **Subgroup** to move the variable(s) into the subgroup list.
3. Highlight the column for which you want statistics summarized by subgroup.
4. In the Statistics list, select the specific statistic that you want.
5. Click **OK**.

For details about the types of statistics, see "[Explanation of Statistics](#)" on page 396.

Add a Statistics Column to an Existing Summary Table


After you have created a summary table, you can add columns of descriptive summary statistics for any numeric column in the source table. To do so, from an existing summary table, click on the upper red triangle in the data grid and select **Add Statistics Column**.

Example of Adding a Statistics Column to an Existing Table

Suppose that you have already created a summary table, and you want to add more statistics to the existing summary table.

1. Select **Help > Sample Data Library** and open **Companies.jmp**.
2. Select **Tables > Summary**.
3. Select **Type and Size Co** and click **Group**.
4. Click **OK**.
5. From the red triangle menu in the upper left corner of the data table grid, select **Add Statistics Column**.

Figure 8.3 Creating a Summary Statistics Column from Within a Data Table



A modified version of the Summary window appears.

- 6. Select the column that you want, click **Statistics**, and select the specific statistic that you want. For this example, select profit/emp and click **Statistics**, and then select **Mean**.
- 7. Click **OK**.

Figure 8.4 Example of a Summary Table with a Summary Statistics Column

	Type	Size Co	N Rows	Mean(profit/emp)
1	Computer	big	4	4530.478
2	Computer	medium	2	-3462.506
3	Computer	small	14	7998.815
4	Pharmaceutical	big	5	17140.699
5	Pharmaceutical	medium	5	24035.115
6	Pharmaceutical	small	2	38337.191

Summary statistics column

The Mean(profit/emp) column is added to the existing summary table.

Explanation of Statistics

You can add columns of descriptive summary statistics for any numeric column in the source table by clicking the **Statistics** button and making a selection from the menu.

The Statistics menu gives these summary statistics for numeric columns:

- N** The number of nonmissing values.
- Mean** The arithmetic mean of a column’s values. It is the sum of nonmissing values (and if defined, multiplied by the weight variable) divided by the Sum Wgt.
- Std Dev** The sample standard deviation, computed for the nonmissing values and calculated with the specified weight variable. It is the square root of the sample variance. The formula follows:

$$s = \sqrt{s^2} \text{ where}$$

$$s^2 = \sum_{i=1}^N \frac{w_i (y_i - \bar{y}_w)^2}{N-1}$$

$\bar{y}_w$ = weighted mean

Min The smallest nonmissing value in a column.

Max The largest nonmissing value in a column.

Range The difference between Max and Min.

% of Total The percent of the total count for each group. Or, if you have so specified, the percent of nonmissing values of the column to the total count for each group.

N Missing The number of missing values.

N Categories The number of distinct categories.

Sum The sum of all values in a column.

Sum Wgt The sum of all weight values in a column. (See [“Column Properties”](#) on page 268 in the “The Column Info Window” chapter.) Or, if no column is assigned the weight role, **Sum Wgt** is the total number of nonmissing values.

Variance The sample variance, computed for the nonmissing values. It is the sum of squared deviations from the mean, divided by the number of nonmissing values minus one.

Std Err The standard error of the mean. It is the standard deviation divided by the square root of **N**. If a column is assigned the role of weight, then the denominator is the square root of the sum of the weights.

CV (Coefficient of Variation) The measure of dispersion, which is the standard deviation divided by the mean multiplied by one hundred.

Median The 50th percentile, which is the value where half the data are below and half are above or equal to the 50th quantile (median).

Geometric Mean The n th root of the product of the data. For example, geometric means are often used to calculate interest rates. The statistic is also helpful when the data contains a large value in a skewed distribution.

Note: Negative values result in missing numbers, and zero values (with no negative values) result in zero.

Interquartile Range The difference between the third and first quartiles.

Quantiles the value at which the specific percentage of the argument is less than or equal to. For example, 75% of the data is less than the 75th quantile. The summary window has an edit box for entering the quantile percentage that you want.

Histogram Generates histograms for different groups. Images of the histograms are saved in data table Expression columns.

Example of Creating a Summary Table

Suppose a researcher is working with *Companies.jmp*, which groups companies by Type and Size. Follow along with this next example by opening *Companies.jmp* from the sample data folder that was installed when you installed JMP.

Suppose that the researcher wants to perform the following tasks:

- Create a table that shows the average profit per employee for small, medium, and big computer and pharmaceutical companies. In other words, create a table that contains a row for each size company and a column for the mean profit per employee of each type of company.
 - Create it so the cells hold the mean for the subgroup (defined by the intersection of the row and column).
1. Select **Help > Sample Data Library** and open *Companies.jmp*.
 2. Select **Tables > Summary**.
 3. Select **Size Co** and click **Group**.

The researcher selects **Size Co** as the grouping variable because he wants the values in that column to become rows in the new table.

4. Select **profit/emp** and click **Statistics**.
5. Select **Mean**.
6. Select **Type** and click **Subgroup**.

This tells JMP to create a column for the average profit per employee ($\text{Mean}(\text{profit/emp})$) for each level (computer, pharmaceutical) of subgroup variable (type).

Figure 8.5 shows the completed Summary window and the resulting summary table.

Figure 8.5 Summary Statistics for a Subgroup

Request Summary Statistics by Grouping Columns.

Select Columns

8 Columns

- Type
- Size Co
- Sales (\$M)
- Profits (\$M)
- # Employ
- profit/emp
- Assets
- %profit/sales

☐ Include marginal statistics

For quantile statistics, enter value (%)
25

statistics column name format
stat(column)

Output table name:

☒ Link to original data table

☐ Prompt to save when closing summary tables.

☐ Keep dialog open

Statistics: Mean(profit/emp)
optional

Group: Size Co
optional

Subgroup: Type
optional

Freq: optional

Weight: optional

Action

OK

Cancel

Remove

Recall

Help

	Size Co	N Rows	Mean(profit/emp. Computer)	Mean(profit/emp. Pharmaceutical)
1	big	9	4530.478	17140.699
2	medium	7	-3462.506	24035.115
3	small	16	7998.815	38337.191

Note: The summary table is named after the Group column name. If the column name contains characters that are not allowed in file names, a hyphen is substituted for the special character.

Chapter 9


JMP Reports

Navigate and Customize Report Windows

Most JMP platforms present the results of your analyses in a report window. The report window consists of graphs and statistical reports that are often linked to the data table. When you select data in the graph or report, the data is highlighted in the data table. Figure 9.1 shows an example of selected data in a report window and in a data table.

This chapter describes how to customize the colors, lines, data points, and other graphical elements in a report window.

Figure 9.1 Example of a JMP Report Window and Data Table



Contents

Navigate Reports.....	404
Use the Hand Tool	405
Access Report Display Options.....	405
Show and Hide Parts of a Report	407
Combine Several Reports.....	408
Rename a Title	408
Increase Font Sizes	408
Resize a Window.....	408
Red Triangle Options in a Report.....	409
Local Data Filter	409
Redo Menus.....	412
Save Script Menus.....	412
The Data Filter.....	415
Types of Filter Columns.....	416
Filtering Modes	416
The Data Filter Control Panel	417
Red Triangle Options for the Data Filter.....	420
Animation in Data Filters.....	423
Red Triangle Options for Variables	426
Reformat Report Tables	428
Modify Display Box Properties in a Report	429
Turn a Report Table Into a Matrix.....	430
Use Conditional Formatting	430
Select Points in Graphs.....	436
Select Rows in Graphs	437
Select a Rectangular Area of Points	437
Select an Irregular-Shaped Area of Points.....	438
Use Markers	439
Change Marker Shape	440
Change Marker Colors	440
Change Marker Size	440
Work with Crowded Markers.....	441
Add Outlines Around Markers.....	441
Marker Selection Modes.....	442
Specify Marker Transparency	443
Exclude and Hide Markers	443
Add Labels to Markers.....	444
Use Images as Markers.....	445
Change Marker Shape or Colors Based On Values	446

Change the Appearance of Graphs	448
Resize Graphs	449
Zoom In and Out	450
Display Images on Hover Labels	450
Pin Hover Labels on a Graph	451
Change Line Widths	453
Change the Background Color in a Graph	453
Change the Color of Histogram Bars	453
Display Coordinates and Temporary Reference Lines	453
Scroll and Scale Axes	454
Customize Axes and Axis Labels in the Axis Settings Window	455
Customize Axes and Axis Labels Using the Pop-Up Menu	464
Change the Order of Values	466
Change the Pattern and Format of Selected Objects	467
Add a Graph to a Data Table	467
Customize Graphical Elements	468
Add Images to a Graph or Report	474
Paste a Background Image into a Graph	474
Paste an Image at the End of a Report	475
Drag and Drop an Image into a Graph	475
Add Geographical Images and Boundaries	477
Extract Data from an Image	477
Add Annotations and Shapes to a Report	478
Add Annotations	478
Add Shapes	480

Navigate Reports

JMP reports are displayed in standard windows with scroll bars and options to resize. They also have other special buttons and menus like those illustrated in Figure 9.2 and those discussed in the following sections.

Figure 9.2 Basics of the Report Window




Table 9.1 Report Window Actions

Number	Action
1	Click on the disclosure icons to hide or show sections of the report.
2	Click on the red triangle menus to access report options.
3	Right-click in the table to access formatting options.
4	Click and drag on the borders to resize graphs.
5	Right-click anywhere in the graph to access formatting options.
6	Right-click within the axis to access formatting options.
7	The arrow cursor turns into a hand when you hold your mouse pointer over an axis. Click and drag using to scroll along the axis or to rescale the axis. See “Scroll and Scale Axes” on page 454.

Tip: Consider setting the Autosave Timeout value in the General preferences to automatically save open reports at the specified number of minutes. This autosave value also applies to data tables, journals, scripts, projects, and reports.

Use the Hand Tool

Select the hand tool using the Tools > Grabber option. There are many functions that you can use with the hand tool (also known as the grabber tool) in a report. Here are some examples of how the hand behaves in graphs and plots:

- On histograms, for continuous variables, use the hand tool to change the number of bars or to shift the boundaries of the bars.
- In all report tables, use the hand tool to click and drag columns for rearranging.
- Use the hand tool to change the displayed range of axis values. See [“Scroll and Scale Axes”](#) on page 454.

Access Report Display Options

Right-click a disclosure icon  to show a menu that lets you rearrange the report and gives you control over report outline levels. The resulting menu has the following report formatting options:

Close Closes (hides) that section of the report. This can also be accomplished by clicking the disclosure icon.

Horizontal if available, the option switches the outline of the report between a vertical and horizontal layout.

Open All Below Opens all outline levels beneath the level where this command is selected, including that level.

Close All Below Closes all outline levels beneath the level where this command is selected, including that level.

Open All Like This Opens all of the same type of reports as the one that is present in the analysis window. If you analyze several variables at a time, you often want to open many of the same type of report tables all at once. You might also want to open all of the same type of report tables at once when you select multiple options on a single analysis.

Close All Like This Closes all of the same type of reports as the one that is present in the analysis window.

Close Where No Outlines Closes all parts of the report that do not have sublevels. This command is usually used at the top level of the report outline. It is a quick way to see a nesting structure overview of a report.

Outline Close Orientation Specifies the orientation of the outline box when the disclosure icon is clicked closed. Available options are **Auto**, **Horizontal**, or **Vertical**. Default orientation is **Auto**.

Append Item Displays a submenu, which lists ways that you can add structural items to the report. Items include text, outline title bars, references to other JMP files and windows, a list of all open JMP files, URLs, and scripts.

Add Text Item Opens a window that enables you to add up to six text items. You can select whether the text items appear with a bullet or initially appear hidden. **Note:** You must click exactly on a hidden text box for the text item to become visible.

Add Outline Item Open a window that enables you to add a titled outline box. **Note:** The appended outline box contains a red triangle menu listing the append menu items.

Add Window Reference Opens a window that enables you to select an open JMP window for adding as a link to the selected outline box.

Add File Reference Displays the Open Data File window that enables you to select a file for adding as a link to the selected outline box.

Add Directory Reference Displays the Browse For Folder window that enables you to select a directory for adding as a link to the selected outline box. **Note:** Links to each file in the selected directory are appended to the outline box.

Add All Open Files For each file open in JMP, a new outline box is added. It contains a link to the file.

Add URL Reference Opens the Create Link to URL window that enables you to add a **Link Name** and **URL**. The URL reference link is added to the selected outline box.

Add Script Button Opens the Add Script Button window that enables you to add a named link to the selected outline box. Clicking the added link runs the specified script.

Edit Displays the submenu shown in Figure 9.3, which affect all reports at the outline level where they are used:

Select Highlights all reports for that outline level.

Deselect Deselects all selected reports for that outline level.

Journal Duplicates the report in a separate window titled Journal so that you can edit it or append other reports to it. See [“Create a Journal”](#) on page 512 in the “Save and Share Data” chapter.

Copy Picture Copies the report to the clipboard. You can then open another application and paste it.

Page Break Inserts a page break for printing purposes.


Show Properties Lets you modify the formatting of display boxes in the report window.

Show Tree Structure Opens a window that shows the display boxes that make up the report. This is mainly used by JSL programmers who are manipulating or reading parts of the report. See the Display Trees chapter in the *Scripting Guide* for details.

Restore Window Size Returns the selected window to its original size.

An alternative way to access these options is to hold down the Alt key and right-click the disclosure icon . This displays a window, as shown in Figure 9.3, with check boxes for commands and options so that you can select multiple actions at the same time. You can also do the same for the menu under a red triangle menu.

Figure 9.3 Outline Box Menu Items Window



Show and Hide Parts of a Report

JMP reports are organized in a hierarchical outline. Each level of the outline has a triangle-shaped disclosure icon . Click the disclosure icon to open and close that section of the report.

You can also change which columns appear in a report. Right-click the report and select the column from the Columns list. To select more than one column at once, press Alt before right-clicking.

Combine Several Reports

Suppose that you perform multiple analyses and want to show all of the results (and the data table) in one window. You can select and combine the reports and the data table in several ways. See [“Example of Combining Windows to Create a Dashboard”](#) on page 543 in the “Extend JMP” chapter for details.

Rename a Title

To rename a title in a report, double-click on any of the following titles:

- a title next to a red triangle menu
- a title next to a disclosure icon
- a column title

Increase Font Sizes

On Windows, change the font size that JMP uses in reports and data tables by selecting **Window > Font Sizes**. Then choose from one of the submenu items:

Increase Font Size Increases the font size. Select again to increase the font size again.

Decrease Font Size Decreases the font size. Select again to decrease the font size again.

On Macintosh, select **View > Make Text Bigger** or **View > Make Text Smaller**.

Resize a Window

Report windows are automatically sized to fit the contents of the window. On Windows, you can automatically resize a window after manually resizing it. Hold down the Ctrl key and click the lower right corner of the window.

Red Triangle Options in a Report

Click the red triangle menu in a report to access a list of options that apply for that particular report. In addition to clicking the red triangle menu, you can also:

- Select multiple actions at the same time. Hold down the Alt key and click the red triangle menu. A panel of all commands and options appears with check boxes.
- Apply a command to all similar reports in the report window. Hold down the Ctrl key and click the red triangle menu. For example, in a One-way analysis, if you hold down the Ctrl key, click the icon, and select **Means/Anova/t Test**, an analysis of variance is performed for all One-way analyses in the active report window.

The red triangle options applicable to each platform in the Analyze and Graph menus are described in the following books:

- *Basic Analysis*
- *Consumer Research*
- *Essential Graphing*
- *Fitting Linear Models*
- *Multivariate Methods*
- *Profilers*
- *Quality and Process Methods*
- *Reliability and Survival Methods*
- *Predictive and Specialized Modeling*


Local Data Filter

Local Data Filters limit the scope of the filter to the output of the platform that you are in. For example, say that you have data on the profits of 30 different computer and pharmaceutical companies. You want to examine profits by company type. You can run a distribution, then use the Local Data Filter to narrow the results in the Distribution platform to the type of company.

1. Select **Help > Sample Data Library** and open *Companies.jmp*.
2. Select **Analyze > Distribution**.
3. Select Profits (\$M) and click **Y, Columns**.
4. Click **OK**.
5. From the Distributions red triangle menu, select **Local Data Filter**.
6. Click Type and click **Add**.

- 7. In the Type box, click **Pharmaceutical** to see only their profits, then click **Computer** to see only their profits.

Figure 9.4 Local Data Filter Showing Pharmaceutical Profits



Local Filtering

When you use a Local Data Filter, it only filters in the platform, not in the data table (as the Data Filter does). For example, if you exclude rows in a Local Data Filter, these rows are not excluded in the data table. And, if you have row states in your data table, they are not impacted by the Local Data Filter.

Saving a Filter


You can script and therefore save a Local Data Filter, so that you can access your filter settings again quickly. To save a filter, from the red triangle next to Local Data Filter, select one of the Save Script options.

Counting Excluded Rows

The counts for each level of a variable (including excluded rows) are shown in the Local Data Filter by default. To omit the excluded rows from the count, deselect **Count Excluded Rows** in the Local Data Filter red triangle menu.

Figure 9.5 shows the difference between counting and omitting excluded rows. When the excluded rows are counted, the Local Data Filter shows 20 rows that contain the value “Computer”. When the excluded rows are omitted, only 16 rows contain “Computer”.

Figure 9.5 Counting (Left) and Omitting (Right) Excluded Rows



Note: The counts are not shown when Display Options is set to Blocks Display (as shown in [Figure 9.4](#) on page 410).

For details about more advanced scripting with Local Data Filters, see the Data Tables chapter in the *Scripting Guide*.

Using By-Groups and Subset Reports

If your analysis uses by-groups or combines together reports using linked subsets of the same table, a local data filter on the parent table can be shared between all the different by-groups and subset reports.

Using Local Data Filters in Dashboards and Applications

You can incorporate Local Data Filters into dashboards or applications:

- For an example using dashboards, see [“Example of Creating a JMP Query Dashboard and Add-In”](#) on page 546 in the “Extend JMP” chapter.
- For an example using applications, see the Creating Applications chapter in the *Scripting Guide*.

Redo Menus

After performing an analysis, you might want to run the analysis again using different options or variables. You might also want to perform the analysis again if data in the data table have changed. The Redo red triangle menus provide these options.

Column Switcher Lets you interactively exchange one column for another on a graph. See [“Column Switcher”](#) on page 413.

Redo Analysis Duplicates the analysis based on the previous launch window settings. The analysis appears in a new report window. This option is helpful if the data have changed.

Relaunch Analysis Opens the launch window and recalls the settings used to create the report.

Automatic Recalc Automatically updates analyses and graphics when data table values change. See [“Automatic Recalc”](#) on page 413.

Save Script Menus

After completing an analysis and receiving a report, you might want to save the process that you used to create the report as a JSL script. You do this by selecting an option from the Script red triangle menu. Most of the Save Script options are the same throughout JMP. A few platforms add extra options that are described in the specific platform chapters. The following Save Script menu options are common to all platforms.

To Data Table Saves the script to the data table that was used to produce the report. This enables you to run the script again from the data table to recreate the results. Select this option to save a script to the data table.

To Journal Saves a link in a journal window that runs the script for the analysis. If a journal window is already open, the script is added to that journal window. The script contains the path to the data table. Note that if the data table cannot be found, the script does not run.

To Script Window Opens a script editor window and adds the script to it. If a script window is already open, the script is added to the bottom of that open window.

To Report Adds the script to the top of the report window.

To Project Adds the script to the open project.

Data Table Window Brings the corresponding data table used to create the report to the front. Available only when the report window contains different platforms.

Script All By-Groups

If you specified a By variable in the launch window, the Save By-Group Script menu enables you to save a script for all levels of the By variable to the script window.

In the Save Script menu, **To Data Table (All Objects)** and **To Script Window (All Objects)** save a script for all levels of the By variable.

Automatic Recalc

The Automatic Recalc feature immediately reflects changes that you make to the data table in the corresponding report window. You can make any of the following data table changes:

- exclude or unexclude data table rows
- delete or add data table rows

This powerful feature immediately reflects these changes to the corresponding analyses, statistics, and graphs that are located in a report window.

To turn on Automatic Recalc for a report window, click on the platform red triangle menu and select **Redo > Automatic Recalc**. To turn it off, deselect the same option. You can also turn on Automatic Recalc using JSL.

Platforms that support Automatic Recalc include a preference in the Platforms preferences.

Note: For some platforms, the Automatic Recalc feature is not appropriate and therefore is not supported. These platforms include the following: DOE, Profilers, Choice, Partition, Nonlinear, Neural, Neural Net, Partial Least Squares, Fit Model (REML, GLM, Log Variance), Gaussian Process, Item Analysis, Cox Proportional Hazard, Response Screening, and Control Charts (except Run Chart).

Column Switcher

Within a report, use the Column Switcher to quickly analyze different variables without having to re-create your analysis. To activate the Column Switcher, from a report window, click on the red triangle menu. Select **Redo > Column Switcher**.

If you have multiple columns, use the buttons to animate the column switching or step through each column manually. Move the slider control to change the speed of the animation.

Note: You cannot copy or move the column switcher within a report. Also, a column switcher cannot be saved to a JMP journal.

Example of the Column Switcher

You have data about nutrition information for candy bars. You want to examine different factors, to see which factors best predict calorie levels.

1. Select **Help > Sample Data Library** and open Candy Bars.jmp.
2. Select **Graph > Graph Builder**.
3. Click Total fat g and drag to the **X** zone.
4. Click Calories and drag to the **Y** zone.
5. Click Cholesterol g and drag to the **Wrap** zone.
6. From the red triangle next to Graph Builder, select **Redo > Column Switcher**.


Choose the column that you want to switch from:

7. Select Cholesterol g and click **OK**.

Choose the columns that you want to switch to:

8. Select Saturated fat g, Cholesterol g, Sodium mg, Carbohydrate g, Dietary fiber g, and Sugars g and click **OK**.

Figure 9.6 Column Switcher in Graph Builder Window



9. Click the **Play** button to cycle between the different factors. Use the slider to control the speed of the animation. Alternatively, you can step through each factor individually.

You can see that the relationship between calories and fat is relatively strong for each level of carbohydrate. Therefore, Carbohydrate g appears to be the best predictor of calorie levels.

Note: The Record and Save buttons in the Column Switcher record the animation and then save it as an animated GIF. This feature is available only on Windows.


The Data Filter

The Data Filter gives you a variety of ways to identify subsets of data. You can interactively select complex subsets of data, hide these subsets in plots, or exclude them from analyses.

1. Select **Rows > Data Filter**.

Tip: In addition to the main Data Filter, you can also launch a local Data Filter within a platform report. Click the Local Data Filter icon  from the Report toolbar, or select **Local Data Filter** from the red triangle menu in a report.

Figure 9.7 Initial Data Filter Window



2. Select the columns that you want to use as filters, and then click **Add**.

Notes:

- To restore your current row states when the Data Filter window is closed, select the **Save and restore current row states** option.
- If you have a long list of columns, you can sort, show, hide, or search for columns in the list. Use the options in the Add Filter Columns red triangle menu. See [“Search Filter Options”](#) on page 425 for details about refining your search.
- By default, the Data Filter window is attached to the data table. You can detach it temporarily or persistently, as follows:

- Detach it temporarily by deselecting the **Use Floating Window** option from the Data Filter red triangle menu.
- Detach it persistently by selecting **File > Preferences > Tables** and deselecting the **Use a Floating Window for Data Filters** option.

Types of Filter Columns

There are three types of filter columns, as follows:

Continuous columns Numeric columns whose modeling type is set to continuous. A continuous filter column is represented by a slider that spans the data range.

Categorical columns Nominal and ordinal columns. For each categorical column, the Data Filter generates a set of distinct categories. These categories can be displayed in different forms.

Note: For categorical columns with value labels, if you want to include responses that are not present in the data, select the **Include Responses Not in Data** option from **File > Preferences > Tables**.

Multiple Response columns Character columns that have the Multiple Response column property or Multiple Response modeling type assigned. Each data cell of the column generally consists of multiple categories, separated by some common separator, like a comma. Since each data cell can contain more than one category, multiple response columns have a richer set of filtering options.

Filtering Modes

There are three modes of filtering: **Select**, **Show**, and **Include**. You can set and clear these modes using the corresponding check boxes in the Data Filter.

Note: The Select mode is not available for the local Data Filter.

Select Shows the selected rows in the data table in a highlighted state.

You can turn off the automatic selection of this option using the **Data Filter Select Check** preference. See also [“Changing the Row State in the Data Table After Making Data Filter Selections”](#) on page 418.

Show Shows the unselected rows with the Hide icon .

You can turn on the automatic selection of this option using the **Data Filter Show Check** preference. For details about row states, see the [“Row State Columns”](#) on page 265 in the [“The Column Info Window”](#) chapter.

Include Shows the unselected rows with the Exclude icon .


You can turn on the automatic selection of this option using the **Data Filter Include Check** preference. For details about row states, see the [“Row State Columns”](#) on page 265 in the [“The Column Info Window”](#) chapter.

There are two additional options when filtering: **Auto clear** and **Conditional**. These options are available from the red triangle menu for the Data Filter. For more information, see [“Red Triangle Options for the Data Filter”](#) on page 420.

The Data Filter Control Panel

Once you have added columns in the initial window, the Data Filter control panel appears.

Figure 9.8 Data Filter Control Panel



The main controls in the Data Filter include the following:

Clear Clears all selections that you have made on variables in the Data Filter window.

Favorites Saves your current data filter criteria as a favorite. Once you have created a favorite, selecting it resets the current conditions to the criteria in the favorite. You can also remove the favorite. To retain favorites once the current session ends, save the data filter script by selecting one of the Save Script options from the Data Filter red triangle menu.

Select, Show, and Include See [“Filtering Modes”](#) on page 416.

Inverse Inverts the current selection state of the rows in the data table.

Note: Only the rows in the data table are inverted, not the selection in the Data Filter. To invert the selection in the Data Filter, from the column's red triangle menu, select **Invert Selection**.

AND The AND button opens the **Add to Selected Group** list. The *and* operator restricts the selection. You can add variables to the filter process at any time.


OR The OR button opens the **Add new OR Group** list. The *or* operator extends the selection. You can add variables to the filter process at any time.

Changing the Row State in the Data Table After Making Data Filter Selections

If you modify a row state that you have set in the Data Filter and subsequently alter row states in the data table, or select points in a graph or plot, the selections in the Data Filter might not match the selections in the data table. The Data Filter contains a warning message that says: "Your selection was changed in another window". The **Reset Selection** button appears. Clicking the **Reset Selection** button changes the data table selections back to reflect the selections in the Data Filter.

Example of Modifying Selections


1. Select **Help > Sample Data Library** and open Big Class.jmp.
2. Select **Analyze > Distribution**.
3. Select age and sex and click **Y, Columns**.
4. Click **OK**.
5. Select **Rows > Data Filter**.
6. Select sex and click **Add**.
7. In the Data Filter control panel, select all of the males by clicking on the M block.

Figure 9.9 Rows Containing Males Highlighted in Data Table and Histograms

You can see that all of the rows containing males are highlighted in the data table and in the histograms. Now you decide that you only want to see the students who are age 12.

8. In the age histogram, select the bar representing age 12.

Now the selection does not match the Data Filter selection. A warning message and a **Reset selection** button appear in the Data Filter window.

Figure 9.10 Data Filter Warning Message and Reset Button

Red Triangle Options for the Data Filter

The red triangle menu next to Data Filter contains the following options:

Auto clear If you have more than one nominal or ordinal column selected in the Data Filter, this option clears any other selections before making a new selection. For example, using *Big Class.jmp*, suppose that you have the columns **sex** (nominal) and **age** (ordinal) in your Data Filter. If you have males (M) selected for sex, and you click on an age group, say age 12, your selection of males will be automatically cleared. This means that selecting age 12 is not conditional on selecting males. Conversely, if you turn off Auto clear, you can then select both males and age 12 at the same time. Auto clear is on by default.

Conditional Limits the categories displayed for the unselected filter column. See [“Conditional Data Filters”](#) on page 420.

Grouped by AND Enables you to control the AND and OR behavior of multiple groups of column filters. See [“Grouped by AND in Data Filters”](#) on page 422.

Use Floating Window Keeps the Data Filter window on top of its associated data table. If you do not want the Data Filter window to remain on top, deselect this option.

Start Over Closes the current Data Filter session and shows the original Data Filter window.

Animation Sequentially highlights the values of a single variable in the data table. See [“Animation in Data Filters”](#) on page 423.

Show Subset Creates a new data table that contains only the following:

- The rows identified by the Data Filter.
- The columns selected in the active data table. If no columns are selected, then all columns are included.

This option is similar to the Tables > Subset command, only without subsetting options.

Save Where Clause Builds a WHERE clause based on the value selections that you make.

Save Script Provides options for saving scripts. See [“Save Script Menus”](#) on page 412.

Conditional Data Filters

For filter columns with hierarchy, you can use the Conditional option to filter what appears in the column lists. For example, you could filter by region so that only the states in the selected region appear in the list.

Note: If there is more than one OR group, the conditional filter is not available.

The following example illustrates how the Conditional option helps show the subcategories clearly, without the extra categories that do not belong.


1. Select **Help > Sample Data Library** and open **Cities.jmp**.
2. Select **Rows > Data Filter**.
3. In the Data Filter window, select **city**, **State**, and **Region**, and then click **Add**.

The Data Filter window appears, showing a list for each variable.

4. Select **Conditional** from the Data Filter red triangle menu.
5. Select **MW** in the Region list.
6. Select **OH** from the State list.

The cities that are in Ohio and in the Midwest region are selected in the data table. In the Data Filter window, only Midwestern states appear in the State list, and only cities in Ohio appear in the cities list. See Figure 9.11.

Figure 9.11 Using the Conditional Option



The bracketed number in front of the column name indicates the order in which the column values were selected. In Figure 9.11, **Region** was selected first, so it has a [1] in front of the column name. **State** was selected second, so it has a [2] in front of the column name.

When you rearrange hierarchical filters that are in ascending order, the filter number changes to match the ascending position in the hierarchy.

To clear the selections and reset the order of the hierarchy, click **Clear**.

Grouped by AND in Data Filters

When you add a filter column, click **AND**, and add another filter column, you create a filter group. Within that group, columns that meet all criteria are selected in the data table.

When you then click **OR** and add one or more filters, you create a second filter group. With **Grouped by AND** deselected, this is the default behavior.

If you select **Grouped by AND**, you reverse the behavior.

The following example shows what happens when **Grouped by AND** is selected.

1. Select **Help > Sample Data Library** and open **Big Class.jmp**.
2. Select **Rows > Data Filter**.
3. Select **Grouped By AND** from the Data Filter red triangle menu.
4. In the Data Filter window, select the **age** column and click **Add**.
5. Click **OR** and add the **sex** column.
sex is added to the same group as **age**.
6. Hold down the **Ctrl** key, select **14** from the **age** filter, and select **M** from the **sex** filter.
age and **sex** are in the same group. In the data table, rows that meet either the **age OR sex** conditions are selected. That is, all 14-year-olds and all males are selected in the data table.
7. Click **AND** and add the **weight** column.
A new group is added.
8. Move the *left* weight slider to approximately 112.
Another filter group has been added. The second filter group limits the selection to those rows where weight is greater than 112.
The two filter groups together select rows that satisfy the condition in the first group **AND** the condition in the second group, that is, a student who is 14 or any male but must weigh more than 112.

Figure 9.12 Data Filter with Grouped by AND Condition

The Data Filter dialog box is shown on the left, with the following settings:

- Data Filter** (red triangle icon)
- Buttons: Clear, Favorites, Help
- Checkboxes: ☒ Select, ☐ Show, ☐ Include
- Text: 9 matching rows
- Checkboxes: ☐ Inverse, ☐ OR
- Grouped conditions:
 - age (6)**: 12 (8), 13 (7), **14 (12)**, 15 (7), 16 (3), 17 (3)
 - sex (2)**: F, M
- AND** (highlighted)
- Condition: **112.0 ≤ weight ≤ 172.0**
- Buttons: AND, OR

The data table on the right shows the following data:

	name	age	sex	height	weight
7	JAMES	12	M	61	128
8	ROBERT	12	M	51	79
9	BARBARA	13	F	60	112
10	ALICE	13	F	61	107
11	SUSAN	13	F	56	67
12	JOHN	13	M	65	98
13	JOE	13	M	63	105
14	MICHAEL	13	M	58	95
15	DAVID	13	M	59	79
16	JUDY	14	F	61	81
17	ELIZABETH	14	F	62	91
18	LESLIE	14	F	65	142
19	CAROL	14	F	63	84
20	PATTY	14	F	62	85
21	FREDERICK	14	M	63	93
22	ALFRED	14	M	64	99
23	HENRY	14	M	65	119
24	LEWIS	14	M	64	92
25	EDWARD	14	M	68	112
26	CHRIS	14	M	64	99
27	JEFFREY	14	M	69	113

Animation in Data Filters

The animation feature sequentially highlights the values of a single variable. The variable's values highlight in the data table. However, patterns are more interesting if you first create a plot and then animate a variable using the Data Filter to see how it behaves on the plot.

To use the animation feature, from the red triangle menu next to Data Filter, select **Animation**. Then select the variable that you want to animate. The highlighted frame around the variable indicates which variable is selected for animation.

Figure 9.13 Animation Control Panel in the Data Filter

The Animation Control panel is shown with the following controls:

- Buttons: Previous, Next, First, Last
- Slider: slower — faster
- Dropdown: Forward

The Animation Control panel (Figure 9.13) contains the following controls:

- The middle button () starts and pauses the animation. After you start the animation cycles, the button changes to a pause button (). By default the animation begins with the first value of the topmost variable.
- The backward arrow () moves the animation backward one cycle. Click more than once to go backward more than one cycle.
- The forward arrow () moves the animation forward one cycle. Click more than once to go forward more than one cycle.
- The square button () hides the Animation Control section on the Data Filter window. Select **Animation** from the menu on the Data Filter title bar again to see the Animation Control.

Use the slider to adjust the speed of the animation (slower to faster).

The Animate drop-down menu contains the following options:

Forward Highlights values from first to last.

Backward Highlights values from last to first.

Bounce Highlights forward and then backward repeatedly.

Save WHERE Clause in Data Filters

Once you have filtered variable values in the Data Filter, that information can be expressed as a JMP WHERE clause. The WHERE clause is used in JSL (JMP Scripting Language) programs to identify specific rows of data for processing or analysis. The Data Filter builds a WHERE clause based on the value selections that you make.

The options in the Save Where Clause menu include the following:

To Clipboard Creates a WHERE clause from the filter criteria and puts it on the clipboard.

To Row State Column Creates a row state column in the data table that has a formula equivalent to the filter criteria.

To Data Table Creates a WHERE clause from the filter criteria and saves it as a JSL command with the current data table in a table property called Filter.

To Script Window Creates a WHERE clause from the filter criteria and appends it to the current script text window, or creates a new script if one does not exist already.

To Journal Creates the WHERE clause from the filter criteria and appends it to the current journal, or creates a new journal if one does not already exist.

Example of Saving a WHERE Clause

1. Select **Help > Sample Data Library** and open Big Class.jmp.

2. Select **Rows > Data Filter**.
3. Select age, sex, and height and click **Add**.

Select all females who are twelve and fourteen years old and whose height is between 56 and 60 inches:

4. Hold down the Ctrl key and click on the 12 and 14 blocks and the F block.
5. Click on 51 and type 56.
6. Click on 70 and type 60.
7. From the red triangle menu next to Data Filter, select **Save Where Clause > To Script Window**.

The WHERE clause that is created from this example appears in a script window, as follows:

```
Select Where(
  (:age == 12 | :age == 14) & :sex == "F" & (:height >= 56 & :height <= 60)
);
```

Search Filter Options

The red triangle menu below Add Filter columns enables you to customize your search for columns, which is particularly helpful with long lists of columns.

Click the down arrow button next to the search box to refine your search.

Contains Terms Returns items that contain a part of the search criteria. A search for “ease oom” returns messages such as “Release Zoom” but not “Partial Least Squares”.

Contains Phrase Returns items that contain the exact search criteria. A search for “text box” returns entries that contain “text” followed directly by “box” (for example, “Context Box” and “Text Box”).

Starts with Phrase Returns items that start with the search criteria.

Ends with Phrase Returns items that end with the search criteria.

Whole Phrase Returns items that consist of the entire string. A search for “text box” returns entries that contain only “text box”.

Regular Expression Enables you to use the wildcard (*) and period (.) in the search box. Searching for “get.*name” looks for items that contain “get” followed by one or more words. It returns “Get Color Theme Names”, “Get Name Info”, and “Get Effect Names”, and so on.

Invert Result Returns items that do not match the search criteria.

Match All Terms Returns items that contain both strings. A search for “t test” returns elements that contain either or both of the search strings: “Pat Test”, “Shortest Edit Script” and “Paired t test”.

Ignore Case Ignores the case in the search criteria.

Match Whole Words Returns items that contain each word in the string based on the Match All Terms setting. If you search for “data filter”, and Match All Terms is selected, entries that contain both “data” and “filter” are returned.

Red Triangle Options for Variables

Some of the red triangle options for a variable can vary, depending on the type of variable.

Options for All Types of Variables

The red triangle menu next to any type of variable contains the following generic options:

Delete Removes the variable from the Data Filter control panel.

Clear Selection Clears any selection in effect for that variable only.

Invert Selection Deselects any selected values, and selects all values previously not selected, for that variable only.

Options for Continuous Variables

For continuous variables, values appear in a range with a slider that you can adjust in one of the following ways:

- Click and drag the slider bar. You can drag from either end of the slider bar. The selected values appear above the slider bar.
- Click anywhere in the empty (not selected) part of the slider to set the filter range at that point.
- Click on the number to enter the value that you want.

By default, the range of values includes an equal sign, which includes the endpoints. You can remove the equal sign by holding down the Shift key and clicking on the $\leq$ or the $\geq$.

The Select Missing option highlights any missing values in the data table.

Options for Nominal or Ordinal Variables

For nominal and ordinal variables, values appear in blocks, in a list, or in a menu. If the variable contains only a small number of categories, the values appear in blocks. If the variable

contains a large number of categories, the values appear in a list or in a menu. However, you can change these default settings.

The following options are available for nominal or ordinal variables only:

Display Options Changes the appearance of the display. Options can include the following:

- **Blocks Display** shows each level as a block.
- **List Display** shows each level as a member of a list, followed by its frequency.
- **Single Category Display** shows each level, followed by its frequency, in a menu.
- **Check Box Display** adds a check box next to each value. To make this the default setting, select the **Data Filter Check Box Display** option in **File > Preferences > Tables**.

Order by Count Orders the values in decreasing sort order by count.

Find Provides a text box where you can enter a search string for the selected column. Press the Enter key to perform the search. Once **Find** is selected, the following Find options appear in the red triangle menu:

- **Clear Find** clears the results of the Find operation and returns the window to its original state.
- **Match Case** uses the case of the search string to return the correct results.
- **Contains** searches the data for values that includes the search string.
- **Does not contain** searches the data for values that do not include the search string.
- **Starts with** searches the data for values that start with the search string.
- **Ends with** searches the data for values that end with the search string.

Options for Variables with the Multiple Response Modeling Type or Column Property

The following options are available for variables with the Multiple Response modeling type or column property:

Match None Selects only rows containing values that do not match any of the selections

Match Any Selects all rows that contain values that match any of the selected values. By default, this option is selected.

Match All Selects only rows with values that include all of the selected values.

Match Exactly Selects only those rows with values that exactly match the checked values.

Match Only Selects only those rows with contents exactly matching the checked values.

Match At Least Selects at least n of the selected values.

Match At Most Selects a maximum of n of the selected values.

Match Between Selects between n and m of the selected values.

Note: For more details about the Multiple Response property, see the [“Multiple Response”](#) on page 283 in the “The Column Info Window” chapter.

Reformat Report Tables

There are many ways to change the formatting of a report table. Right-click a report table to access the following formatting options:

Table Style Adds borders, shading, and dividing lines to the table. Select from the following options:

- Underline Headings shows the preference setting for Underline Table Headings.
- Shade Headings shows the preference setting for Shade Table Headings.
- Heading Column Borders shows divider lines between columns in headings.
- Column Borders contains borders outside columns and divider lines between columns.
- Row Borders contains borders outside rows and divider lines between columns.
- Shade Alternate Rows shades alternate rows.
- Shade Cells shades the body of the table. When used with Shade Alternate Rows, a darker shade is used on alternate rows.

Note: Change the format of all report tables by selecting the preceding options in the JMP preferences. On Windows, the Report Tables options are in File > Preferences > Styles. On Macintosh, select the Report Tables options in **JMP > Preferences > Styles**.

Columns Shows or hides columns in the table.

Note: Columns whose names begin with a tilde (~), such as ~Bias, are not applicable to the analysis that you ran and do not appear in the table, even if you place checks next to their names.

Sort by Column Sorts the columns in descending or ascending order by the selected column.

Make into Data Table Creates a JMP data table from the report table. The data table script enables you to recreate the data table that the report came from.

Make Combined Data Table Searches the report for other tables like the one you selected and combines them into a single data table. The data table script enables you to recreate the data table that the report came from.

Make Into Matrix Creates a JMP matrix from a report table. See [“Turn a Report Table Into a Matrix”](#) on page 430.

Format Columns Changes the numeric formatting of one or more columns in the table.

Copy Column Copies the contents of the right-click column to the Clipboard for pasting into another window or application.

Copy Table Copies the right-click table to the Clipboard for pasting into another window or application.

JMP PRO Bootstrap Approximates the sampling distribution of a statistic. For more information, see the Bootstrapping chapter in the *Basic Analysis* book.

Modify Display Box Properties in a Report

For each display box in a report, you can change properties such as the font, text color, padding, and alignment. Your changes are included when you save the report as a script, a graphic, or a journal.

To modify display box properties, follow these steps:

1. Right-click the disclosure icon next to the report and select **Edit > Show Properties**.
The Properties pane appears.
2. Modify the report properties.
3. Click the report to view your changes.

Tips:

- In the Properties pane, use the arrow buttons to navigate among display boxes in the display tree.
- After you open the Properties pane, use the Selection tool  to select a specific report and change its properties.

Modify the Format of Numeric Columns

In the Show Properties pane, you can modify the appearance of a report, including modifying the format of selected numeric columns. For example, you might want to specify two decimal places for all numeric columns. Your changes are included when you save the report as a script, a graphic, or a journal.

To modify the numeric formats, follow these steps:

1. Right-click the disclosure icon next to the report and select **Edit > Show Properties**.
The Properties pane appears.
2. Press Shift and select the columns whose format you want to change.
3. From the Format list in the Properties pane, select the Format properties.

Tips:

- To select all display boxes of a specific type (for example, all NumberColBoxes), select one of the boxes in the report. From the Select list in the Properties pane, select **Boxes of type 'NumberColBox'**.
- To select all columns that have a specific format, select one of the boxes in the report. From the Select list in the Properties pane, select **Columns with matching format**.

Turn a Report Table Into a Matrix

You can create a JMP matrix from a report table. For example, when working with JMP Scripting Language (JSL), you might want to access a report's table that has been stored into a JSL variable. Or, you might want to store a report table's values into a table property as either a table property or as a JSL assignment, which is stored within the data table and is accessible via a script or the Formula Editor.

To store a table in matrix form into a global variable, into a table property, or into a table property as an assignment:

1. Right-click anywhere in a report table.
2. Select **Make into Matrix**.
3. In the window that appears, tell JMP how you want to store the table.
4. (Optional) Rename the variable or property by entering a new name into the box beside Name.

Use Conditional Formatting

Note: You must enable **Show conditional formatting** in the Reports preferences for your conditional formatting to appear in JMP reports.


To configure reports to use conditional formatting, you must first set your report preferences to enable showing conditional formatting. See [“Reports”](#) on page 583 in the “JMP Preferences” chapter for details.

To configure conditional formatting, follow these steps:

1. Open the JMP Preferences window.
2. Select the Reports preference group.
3. Click **Manage Rules**.

The Conditional Format Rule window appears.

Figure 9.14 Conditional Format Rule Window



By default, JMP includes conditional formatting for Correlation, Factor Patterns, and PValue. These rules are enabled by default. The PValue rule is applied to columns that contain probability values.

From this window you can add, edit or delete a rule.

Disable or Enable a Rule

To disable or enable a rule:

1. Open the JMP Preferences window.
2. Select the Reports preference group.
3. Click **Manage Rules**.
The Conditional Format Rule window appears.
4. Select the rule from the list.
5. If **Rule enabled** is selected, select to disable.
6. If **Rule enabled** is not selected, select to enable.

Add a Rule

To add a rule:


1. Open the JMP Preferences window.
2. Select the Reports preference group.
3. Click **Manage Rules**.

The Conditional Format Rule window appears.

4. Click **Add**.

The Conditional Format Rule window appears. A placeholder rule appears on the left.

Figure 9.15 Adding a Conditional Format Rule




5. Add and format conditions as described in [“Add a Condition”](#) on page 433.
6. Click **OK** to save the new rule and return to the previous Conditional Format Rule window.
7. Select **Rule enabled** to enable the rule.

Edit a Rule

To change the conditional formatting of a rule:

1. In the Conditional Format Rule window, select the rule from the list.
2. Click **Edit**.

The Conditional Format Rule window appears, showing the selected rule’s current conditions.

Figure 9.16 Conditional Format Rule Window

The default rule for PValue includes two conditions. The order of the list indicates the order that the rules are applied. For example, a p -value of 0.04 would not invoke the first rule ($x < 0.01$) but would invoke the second rule ($x < 0.05$).

Note: You cannot edit an existing condition within a rule. To edit an existing condition, you must delete the condition and then add it. See [“Edit an Existing Condition”](#) on page 435 for details.


Add a Condition

To add a condition to a rule:

1. Open the rule to view the Conditional Format Rule window.
2. In the Condition area, select a relation from the list and enter a value in the text box.
Or
If you want the condition to include a value range:
 - Select $>$ or $\geq$ from the relation drop list and enter the value in the text box.
 - Select the check box, select the $<$ or $\leq$ relation, and enter the value.
3. Format the condition using the procedure described in [“Format a Condition”](#) on page 434.

Tip: When you click **Add**, the condition and its format settings are immediately added to the bottom of the condition list and the Condition and Format areas return to their default settings. Verify your settings before you click **Add**.

4. After verifying your settings, click **Add** to add the condition to the rule.
5. Use the  and  buttons to position the condition within the list.

Figure 9.17 Example of Adding a Condition with Formatting Rules


6. Click **OK** to save your changes and return to the previous Conditional Format Rule window.

Delete a Condition

To delete a condition from a rule:

1. In the Conditional Format Rule window, select the condition and click **Delete**.
2. Click **OK** to save your changes and return to the previous Conditional Format Rule window.
3. Click **OK** to return to the Preferences window.

Format a Condition

To format values that fall within a condition:

1. With a Condition entered, select a Text Color from the drop list:

Default The value appears without color.

Solid The value appears in the specified color.

Dimmed The value appears dimmed by the specified transparency.

Color Range For ranged conditions, the values appear in color gradients within the specified color range.

Dimmed Range For ranged conditions, values appear in dimmed gradients by the specified transparency range.

2. To specify a text color, click the color swatch and select a color.
3. To specify a transparency, enter the percent value (for example, '60%').

The Sample area displays a preview of the appearance of the text column.

4. Select a Background Color from the drop list:

Default The value appears without a color background.

Solid The value appears with the specified color background.

Color Range For ranged conditions, the values appear with background color gradients within the specified color range.

5. To specify a background color, click the color swatch and select a color.
The Sample area displays a preview of the appearance of the text column.
6. To have condition values noted, select an Annotation from the drop list:

None No notation is used on the value.

Box The value appears in the table with a box around it.

Circle The value appears in the table with an ellipse around it.

*** (asterisk)** An asterisk (*) appears to the right of values in the table.

The Sample area displays a preview of the appearance of the text column.

7. To style the value text, select the **Font Style** from the drop list:

None No style is used to format the value.

Plain No style is used to format the value.

Bold The value appears bolded in the table.

Italic The value appears italicized in the table.

Bold Italic The value appears bolded and italicized in the table.

See Figure 9.17 for an example of condition formatting.

Note: After configuring the formatting, remember to click **Add** to add the new condition to the rule.

Edit an Existing Condition

To change the formatting for an existing condition:

1. In the Conditional Format Rule window, select the condition and click **Delete**.
2. Re-create the condition by using the procedure described in [“Add a Condition”](#) on page 433.

3. Format the conditional using the procedure described in [“Format a Condition”](#) on page 434.


Tip: When you click **Add**, the condition and its format settings are immediately added to the bottom of the condition list and the Condition and Format areas return to their default settings. Verify your settings before you click **Add**.

4. After verifying your settings, click **Add** to add the condition to the rule.
5. Use the  and  buttons to position the condition within the list.
6. Click **OK** to save your changes and return to the previous Conditional Format Rule window.

Select Points in Graphs

To select a point in a graph, click the point with the arrow cursor. This selects the point as well as the corresponding row in the current data table. To select multiple points, hold down the Shift key while you select points. A point's label appears when you place the cursor over the point with or without clicking.

Figure 9.18 Label for a Data Point




Tips:

- You can paste the contents of a label into another document. Right-click the label and select **Copy**. Paste the text into the other document.
- A photo can be displayed in the label if you store the image in an Expression role column. See [“Expression Role”](#) on page 289 in the “The Column Info Window” chapter for details.

Select Rows in Graphs

All graphs and plots that represent the same data table are linked to each other and to the corresponding data table. When you click points in plots or bars of a graph, the corresponding rows highlight in the data table. The example in Figure 9.19 shows a histogram with the SPEEDYTYPE bar highlighted, and the corresponding rows highlighted in the table. You can also extend the selection of bars in a histogram by holding down the Shift key and then making your selection.

Figure 9.19 Highlighting Rows in a Histogram



Select a Rectangular Area of Points

You can select all points that fall in a rectangular area using the arrow cursor. Click and drag the arrow to highlight points. Alternatively, you can use the brush tool. As you move the brush over the graph, points that fall within the rectangle are selected. Any points marked in the data table as hidden are not selected. See [“Hide Rows”](#) on page 198 in the “Enter and Edit Data” chapter.


To select points using the brush tool, follow these steps:

1. Click the brush tool  in the toolbar.
2. Click and hold the cursor (now brush-shaped) in a plot. A rectangle appears.

3. Move the rectangle over points. As it passes over them, they appear highlighted both in the plot and in the active data table.

To keep all points selected as you move the brush-shaped cursor over points, press the Shift key before you click on a point in the plot. The selected points are also selected in the data table.

Figure 9.20 Using the Brush Tool



4. Release the mouse. The points within the rectangle and the data table remain selected.
 - To change the size of the selection rectangle, press the Alt key before you click in the plot. Drag the cursor to resize the selection box. This shape acts like a slicing tool that can traverse and highlight slices of points across either axis. **Note:** The size of the selection box is remembered for the next time you use the brush tool.
 - If you press the Ctrl key and click the brush tool on selected points, the points within the selection rectangle are deselected. Points outside the selection rectangle remain selected.

Select an Irregular-Shaped Area of Points

You can use the lasso tool to select points that fall in an irregular-shaped area. Any points marked in the data table as hidden are not selected. See [“Hide Rows”](#) on page 198 in the [“Enter and Edit Data”](#) chapter.


To select points within an irregularly shaped area, follow these steps:

1. Click the lasso tool  in the toolbar.
2. Click and hold the cursor (now lasso-shaped) in a plot.

Note: To keep all points selected as you drag the lasso around several sets of points, press the Shift key before you click in the plot.

3. Drag the lasso around any set of points.

Figure 9.21 Using the Lasso Tool



4. Release the mouse. JMP automatically closes the lasso and highlights the points within the enclosed area.

Use Markers

Markers are points on a graph that represent data. Once they are changed from their default setting, they also appear next to rows in the data table.

- [“Change Marker Shape”](#)
- [“Change Marker Colors”](#)
- [“Change Marker Size”](#)
- [“Work with Crowded Markers”](#)
- [“Add Outlines Around Markers”](#)
- [“Marker Selection Modes”](#)
- [“Specify Marker Transparency”](#)
- [“Exclude and Hide Markers”](#)
- [“Add Labels to Markers”](#)
- [“Use Images as Markers”](#)
- [“Change Marker Shape or Colors Based On Values”](#)

Change Marker Shape

You can assign a character from the JMP markers palette to replace the standard points in scatterplots. These markers also appear next to row numbers in the data table.

1. Highlight one or more markers whose shape you would like to change.
2. Right-click anywhere in the graph. In a histogram, right-click the box plot area on the right.
3. Select **Row Markers**.
4. Select a marker shape from the options that appear, or click **Custom** to enter a character to use as a marker.

Change Marker Colors

You can assign any color to highlighted rows. When you do this, the points in scatterplots appear in the color that you select from the colors palette. The active color assigned to a row appears next to the row number in the data grid.

To change the color of markers (or points) on a graph:

1. Highlight one or more markers whose color you would like to change.
2. Right-click anywhere in a graph. In a histogram, right-click the box plot area on the right.
3. Select **Row Colors**.
4. Select one of the colors, or click **Custom** to apply a custom color.

Change Marker Size

To increase or decrease the size of markers on a graph:

1. Right-click anywhere in a graph. Hold down the Ctrl key and right-click to broadcast the command and apply it to all plots of the same type located in the same window. In a histogram, right-click the box plot area on the right.
2. Select **Marker Size**.
3. Select one of the marker sizes listed.

The default value, Preferred Size, is selected on the Graphs page in the JMP preferences.

Note: When the drawing speed is set to Fast, the smallest marker size (Dot) is applied. See [“Work with Crowded Markers”](#) on page 441.

Work with Crowded Markers

A large number of markers on a graph can appear crowded on a graph. You might need to alter the transparency to gain a better view. Altering the transparency might also affect the marker drawing mode, which is the mode JMP uses when it refreshes a report window. As markers are drawn on a plot, JMP uses one of two speeds: normal or fast.

To change the marker drawing speed

1. Right-click anywhere in a graph. In a histogram, right-click the box plot area on the right.
2. Select **Marker Drawing Mode**, and then select either **Normal** or **Fast**.

Normal If JMP is in normal drawing mode and the number of markers on a graph are more than the specified threshold number, JMP automatically switches to fast mode. See [“Reports”](#) on page 583 in the “JMP Preferences” chapter, for details about setting the marker threshold.

Fast Graphs that display a large number of markers appear faster if you set the marker drawing speed to Fast. Note that when the drawing speed is set to Fast, the smallest marker size (Dot) is applied, and marker transparency settings revert to the default opaqueness.

Outlined See [“Add Outlines Around Markers”](#) on page 441.

To fill hollow markers

In the JMP preferences, select **Graphs** and then select **Fill Hollow Markers**. Hollow markers on all graphs are filled with an opaque background.

Add Outlines Around Markers

You can add a black outline, or frame, to markers in a plot. Outlined markers are available at the medium, larger, XL, XXL, and XXXL marker size. See [“Change Marker Size”](#) on page 440 for details.

To add outlines

1. Right-click a plot or graph.
2. Select **Marker Drawing Mode**.
3. Select **Outlined**.

To use an outline effectively, it is best if your marker is a color other than black.

To change marker colors

1. Highlight the markers whose color you want to change.
2. Right-click anywhere in the graph.
3. Select **Row Colors**.
4. Select a marker color from the options that appear.

Marker Selection Modes

When you select markers on a graph, only the selected markers are highlighted. You can change how markers are highlighted on the current graph. The options are applied to the top two triangles in the following figure.

Figure 9.22 Examples of Highlighted Triangular Markers



To change the marker highlighting on the current graph, follow these steps:

1. Right-click anywhere in a graph and select **Marker Selection Mode**.
2. Select one of the following options:

Preferred Mode the Marker Selection Mode that is selected on the Graphs page in the JMP preferences. The default value is Unselected Faded.

Unselected Faded only the selected markers are highlighted. Everything else is dimmed by the percent specified by **Faded amount for unselected markers** in Preferences > Graphs.

Selected Larger the selected markers are larger than the deselected markers.

Selected Haloed the edges of the selected markers are outlined in blue.

Selected Outlined the selected markers are outlined in black.

Selected Same Color the selected markers are shaded with the Marker Selection Color that is selected in the Graphs preferences.

Specify Marker Transparency

You can change the transparency of markers (points) on a graph. For example, this enables you to control the visibility of overlapping points.

Note: When the drawing speed is set to Fast, the default marker transparency is applied. See [“Work with Crowded Markers”](#) on page 441.

1. In a graph, right-click anywhere and select **Transparency**. In a histogram, right-click the box plot area on the right and select **Transparency**.
2. Enter the level of transparency that you want the markers (points) to have on the graph, and click **OK**.

A value of 1 indicates total opaqueness and 0 indicates invisibility. Values between 1 and 0 are semi-transparent.

Exclude and Hide Markers

Use the Rows > Hide and Exclude command to suppress the appearance and exclude from statistical analyses the highlighted rows. Data remains hidden and excluded until you select Rows > Hide and Exclude again.

Using the Exclude/Unexclude command, you can exclude highlighted rows from statistical analyses. Data remains excluded until you select Rows > Exclude/Unexclude for those highlighted rows.

Note: Excluded data are not automatically hidden in plots even though they are excluded from calculations in text reports and graphs.

Using the Hide/Unhide command, you can suppress (hide) the appearance of highlighted points in scatterplots. For example, you can exclude points from analysis and then hide those same points in scatterplots. The data remain hidden until you select Rows > Hide/Unhide for highlighted hidden rows.

Note: Hidden points are not automatically excluded from statistical computations that affect text reports and graphs, even though they are not displayed in the plots. To exclude hidden observations from analyses, you must highlight them and select Rows > Exclude/Unexclude characteristic.

To exclude or hide markers (points) from analyses, follow these steps:

1. Highlight the marker(s) that you would like to exclude or hide.
2. Right-click anywhere in a graph.
3. Select **Row Exclude** or **Row Hide**.

Add Labels to Markers

When you position the arrow cursor over a point in a plot, the point's label appears. By default, the label is the row number. There are three ways that you can customize the label:

- You can change the label so that it displays values found in one or more columns instead of the row number.
- You can enable the label to appear always, not just when you position the cursor over points.
- You can click the label with the Arrow tool and drag it to a new location. If a label is dragged a certain distance away from the marker, then a tail is added connecting the label to its point.

For details about changing the appearance of marker labels, see [“Reports”](#) on page 583 in the “JMP Preferences” chapter.

To display values found in one or more columns instead of the row number

1. In the data table, highlight the column(s) whose values you want to appear as the label in plots.
2. Select **Label/Unlabel** from one of the following places:
 - the **Cols** menu
 - the red triangle menu in the Columns panel
 - the top red triangle menu in the upper left corner of the data grid

A label or yellow tag icon  beside the column name in the Columns panel indicates that points on plots are identified by the column value. If there are multiple labeled columns, their values appear on plots separated by a comma. Data remains labeled until you highlight the column and select **Label/Unlabel** again.

To enable the label to appear always, not just when you position the cursor over points

1. Highlight the point(s) whose label you want to always appear in plots.
2. Right-click anywhere in a graph. In a histogram, right-click the box plot area on the right.
3. Select **Row Label**.

A label or yellow tag icon  beside the row number in the data table indicates that points on plots corresponding to the row appear with a label.


Use Images as Markers

Place images in an expression column to use those images as markers on graphs. Then you indicate which column to use for markers. This feature prevents the need to look at a marker color and refer to the legend for its meaning, which is particularly helpful with data that contain many levels.

If you use a character or numeric column as the marker, the data value is used for the marker.

1. Create a new column in your data table.
2. Right-click the column, select **Column Info**, and select the **Expression** data type.
3. Click **OK**.
4. Drag graphics from your computer into each cell of the column. You can also import data that contains a column of images.
5. Select the column, select the **Cols** menu, and then select **Use for Marker**.
6. Create a graph that uses markers. Figure 9.23 was created in Graph Builder.
7. (Optional) To resize the markers, right-click the graph, and select **Graph > Marker Size** (or right-click and select **Marker Size** in some platforms). Medium markers are selected in this example.
8. Deselect **Show Legend** from the Graph Builder red triangle menu.

Figure 9.23 Pictures Used as Markers

**Notes:**

- In the Big Class Families.jmp sample data table, the picture column used for markers on graphs.
- This feature is not supported in Bubble Plot.


Change Marker Shape or Colors Based On Values

In some plots, you can change marker shapes or colors based on the values of points by adding a *row legend*. It is called a row legend because JMP automatically inserts a legend using row color or row marker settings. When you assign markers or colors in this way, it assigns the characteristic(s) to all points in a graph, regardless of what points you have selected. All previous marker and color settings are overwritten.

To add shapes or colors based on column values, follow these steps:

1. Right-click anywhere in a graph. In a histogram, right-click the box plot area on the right.
2. Select **Row Legend**.
3. In the window that appears (Figure 9.24), highlight the column whose values you want to color or mark. A preview of the legend is shown on the right.

Figure 9.24 Adding a Row Legend



4. Refine your row legend using the following options:

Colors Lets you choose among several pre-defined color schemes.

Tip: If you already have a color scheme applied in the data table, select None to maintain it. Colors should be consistently applied and uniquely grouped.

Continuous Scale Assigns colors on a spectrum that corresponds to the ascending or descending order of the values. Use this option when the highlighted column contains continuous values.

Reverse Scale Reverses the scale of colors.

Markers Lets you choose among several marker schemes.

Tip: If you already have a marker scheme applied in the data table, select None to maintain it. Markers should be consistently applied and uniquely grouped.

Make Window with Legend Creates a separate legend window that tells you what colors and shapes correspond to which value.

Save Column Property Adds a column property that stores the selected color theme.

Save Table Property Adds a table property that preserves the selected color and marker configuration.

Excluded Rows Assigns colors or markers to rows that are excluded.

Most legends have one column. However, the following platforms have multi-column legends when there are more than 20 levels:

- Recurrence
- Oneway (for CDF Plot and all three Densities red triangle commands)

- Fit Model (for the Regression Plot in Standard Least Squares)
- Survival

Remove the Row Legend

Delete a row legend by right-clicking it and selecting **Remove**.

Change the Appearance of Graphs

There are many ways that you can format your report to meet your needs. The sections that follow detail how to make changes to the graphical portions of your output reports.

Tip: If you have a touchscreen, you can pan and zoom most graphs and axes in JMP. Graphs and axes change scale and zoom out if pinched, and zoom in if stretched.

- [“Resize Graphs”](#)
- [“Zoom In and Out”](#)
- [“Display Images on Hover Labels”](#)
- [“Pin Hover Labels on a Graph”](#)
- [“Change Line Widths”](#)
- [“Change the Background Color in a Graph”](#)
- [“Change the Color of Histogram Bars”](#)
- [“Display Coordinates and Temporary Reference Lines”](#)
- [“Scroll and Scale Axes”](#)
- [“Customize Axes and Axis Labels in the Axis Settings Window”](#)
- [“Customize Axes and Axis Labels Using the Pop-Up Menu”](#)
- [“Change the Order of Values”](#)
- [“Change the Pattern and Format of Selected Objects”](#)
- [“Add a Graph to a Data Table”](#)
- [“Customize Graphical Elements”](#)

Resize Graphs

There are two main ways to resize graphs: using the click and drag method or resizing it according to pixel size.

Note: You can also change the default size of a graph using the Graph Height option in File > Preferences > Graphs.

Use Click and Drag

To resize a plot or graph using the click and drag method:

1. Place the cursor on the right edge, bottom edge, or lower right corner of the plot frame. The cursor changes to a small double-arrow pointer.
2. Click and drag to change the size of the plot. When you resize, the height and width of all plots in that frame adjust independently of other frames in the same report window. Table 9.2 describes how to adjust the plot.

Table 9.2 Resizing Actions

Action	Instructions
Adjust the plot frame but preserve the proportions (aspect ratio)	Hold down the Shift key and click and drag the corner of the frame.
Adjust a plot in 8-pixel increments	Hold down the Alt key and click and drag the corner of the frame.
Adjust all plots of the same type simultaneously	Hold down the Ctrl key and click and drag the corner of one of the plots. If you do this for one scatterplot, the action is broadcast to all scatterplots in the window, and they resize together. Any other types of plots remain unchanged.

Specify Size in Pixels

To resize a plot or graph to a specific pixel size:

1. Right-click the plot or graph.
2. Select **Size/Scale > Frame Size**.
3. Enter the number of pixels for the frame's height and width.

Note: For details about the other options in the Size/Scale menu, see [“Scroll and Scale Axes”](#) on page 454.

Zoom In and Out

The magnifier  lets you automatically zoom in on any area of a plot. When you click the magnifier, the point or area where you click becomes the center of a new view of the data. The scale of the new view enlarges, giving you a closer look at interesting points or patterns. You can perform any of the following actions:

- Click and drag the magnifier to focus in on a particular region of the plot.
- On a ternary plot, drag the magnifier to zoom the triangular axes.
- Zoom repeatedly to look closer at the data.
- Hold down the Control key and click the magnifier to return to your previous state before the last zoom.
- Double-click or hold down the Alt key and click the magnifier to restore the original plot.

On Windows, you can also zoom by holding down the Control key and using the mouse wheel.

On Macintosh, zoom by pressing Option and clicking the area.

Note: You can zoom in and still see a center point by dragging from the axis to inside the graph. For a vertical axis, click on a position and drag right into the graph. This zooms in on the scale, adjusting both endpoints of the scale but keeping the clicked value in about the same position. Dragging left zooms out.


Display Images on Hover Labels

Place images in an expression column to display them on a label in a graph. When you place your cursor over a data point or histogram bar, the label with data and the image appears.

1. Create a new column in your data table.
2. Right-click the column, select **Column Info**, and select the **Expression** data type.
3. Click **OK**.
4. Drag graphics from your computer into each cell of the column. You can also import data that contains a column of images.
5. Right-click the column in the data table and select **Label**.
6. Create a graph (for example, in Graph Builder or Distribution).
7. Place your cursor over a data point or a histogram bar.

The image appears on the label. Run the Graph Builder script in the SAS Offices.jmp sample data table to see an example (Figure 9.25).

Figure 9.25 Image on Hover Label




Tips:

- Images in an expression column can also be used as markers. See [“Use Images as Markers”](#) on page 445 for details.
- You can pin the hover label so that the label always appears on the graph. See [“Pin Hover Labels on a Graph”](#) on page 451 for details.

Pin Hover Labels on a Graph

When you place your cursor over data on a graph, a hover label that contains data values appears. You can pin the hover label so it always appears on the graph as a label. When you save the graph, the label is saved. When you print the graph, the label prints.

Note: The hover label remains pinned after you redo an analysis. However, if the data changed, you might have to reposition the label.

Figure 9.26 Pinned Hover Labels


To pin a hover label, place your cursor over the data point until the label appears. Click the pin icon in the upper right corner of the label. You can then drag the label to reposition it.

Right-click the label to select the following formatting options:

Background Color Applies the selected color to the label background.

Frame Color Applies the selected color to the label border and tag line.

Text Color Applies the selected color to the text.

Filled Applies the background color and frame color to the label. Selected by default.

Use Gradient Shades the background color vertically from light to dark. Selected by default.

Font Applies the selected font family to the text. The default font is determined by your JMP Font preferences.

If a script with a pinned label refers to a font that is not on the computer, the script does not run.

Add Text Adds text to the bottom of the label.

Replace Text Change the text on the tooltip. If you redo the analysis, the tooltip text remains updated.

Tag Line Draws a line between the label and the data point. The Frame Color is applied to the line.

Close Removes the label. You can also remove the label by clicking the X in the upper right corner of the label.

Note: To return to the default label formatting, remove the label and add it again.

Change Line Widths

After fitting a line to a graph, or producing a graph with a line already present, you can adjust the width of the line:

1. Right-click anywhere in a graph.
2. Select **Customize**.
3. Select **Smoother** (for example, if the graph contains a smoother).
4. Change the line width. The value is in pixels.
5. Click **OK**.

Change the Background Color in a Graph

To change the background color in a graph, follow these steps:

1. Right-click anywhere in a graph. (To change only the color of a box plot, right-click the box plot area.)
2. Select **Background Color**.
3. Select one of the predefined colors, or create your own color.
4. Click **OK**.

Change the Color of Histogram Bars


To change the color of histogram bars, follow these steps:

1. Right-click anywhere in a histogram and select **Histogram Color**.
2. Click a color, or click **Other** and create your own color.

See your operating system documentation for details about creating your own colors.

Display Coordinates and Temporary Reference Lines

You can measure points and distances in graphs, or easily find the exact value, or coordinates, of points and distances on plots and graphs. To do this, click the crosshairs tool  and click and hold anywhere on a graph. The coordinate values appear where the crosshairs intersect the vertical and horizontal axis as you drag the crosshairs within a plot.

Figure 9.27 Using the Crosshairs Tool


On a fitted line or curve, the crosshairs identify the response value for any predicted value. On a ternary plot, this tool displays triangular crosshair lines.

Scroll and Scale Axes

The hand tool (also known as the grabber tool) () provides a way to change the axes and view of a plot:

- On a y -axis, dragging  scrolls the y -axis; dragging  or  scales the y -axis.
- On an x -axis, dragging  scrolls the x -axis;  or  scales the x -axis.

Tip: When you drag an axis to change its scale, JMP automatically updates the major and minor tick increments based on the new axis width. To prevent this (retaining your original increments), hold down the Shift key while dragging.

You can also right-click in a plot or graph, and select **Size/Scale** (or **Graph > Size/Scale**). Choose one of the following options:

- To adjust the scale of the X axis, select **X Axis**. To adjust the scale of the Y axis, select **Y Axis** or **Right Y Axis**. For more details about this window, see [“Customize Axes and Axis Labels in the Axis Settings Window”](#) on page 455.
- For details about the Frame Size option, see [“Specify Size in Pixels”](#) on page 449.
- Select **Size to Isometric** when the x - and y -axes are measured in the same units and you want distances on the graph to be represented accurately regardless of direction.


Customize Axes and Axis Labels in the Axis Settings Window

Double-click a numeric axis to customize it using the Axis Settings window. Or, right-click the axis area and select **Axis Settings** to access the window.

Note: In the Graph Builder and Distribution platforms, you can also customize nominal axes using the Axis Settings window.

Customization features in the window depend on the data type of the axis and the specific platform JMP uses to create the plot or chart. Figure 9.28 shows a typical Axis Settings window for numeric (continuous) axes.

Figure 9.28 Axis Settings Window for a Numeric (Continuous) Axis



The Axis Settings window contains the following panels:

- [“Scale”](#) on page 455
- [“Tick/Bin Increment”](#) on page 458
- [“Axis Label Row”](#) on page 460
- [“Reference Lines”](#) on page 463
- The Preview panel shows how your current selections will appear on the axis.

Scale

In the Scale panel, you can do the following:

- [“Change the Axis Scale Type”](#) on page 456

- [“Change the Numeric Format of an Axis”](#) on page 456
- [“Establish Minimum and Maximum Axis Values”](#) on page 457

Change the Axis Scale Type

When viewing a graph with a numeric axis, you can change the axis scale to one of the following types:

- Linear
- Log
- Power
- Geodesic
- Geodesic US
- Probability Scales (Normal, Weibull, Fréchet, Logistic, Exponential, and Gamma)

Notes:

- Specific platforms might use other scale types that are fixed and cannot be changed. For example, Destructive Degradation, Degradation, and the X axis in Fit Y by X scatterplots use custom scales. Do not change the scale in these graphs through the Axis Settings window.
- If you selected a scale type of Log, enter the **Base** to use.
- If you selected a scale type of Power, enter the **Power** to use.

To set a default scale type for a variable, which avoids making this change every time you run an analysis, see [“Axis”](#) on page 276 in the “The Column Info Window” chapter.

Change the Numeric Format of an Axis

For plots and charts that contain a numeric axis area, you can change the format of the axis. For details about numeric formats, see [“Numeric Formats”](#) on page 261 in the “The Column Info Window” chapter.

Notes:

- If you selected Date, Time, or Duration, you need to specify the format of the increments. See [“Add and Remove Axis Labels”](#) on page 465. You can also specify label row nesting. See [“Label Row Nesting”](#) on page 459.
- If you selected Fixed Dec, enter the number of decimal places that you want JMP to display in the Dec box.
- If you selected Precision, select whether you want to keep trailing zeros and all whole digits.
- To add commas to values that equal a thousand or more, select the **Use thousands separator** option. You must account a space for each comma in the Width box, or else they

might not appear. This option is available for the Best, Fixed Dec, Percent, and Currency formats.

- For a numeric axis, you can adjust the width of the tick mark labels using the Width box.

Note: When you change the numeric format of an axis, you do not change the numeric format of the way the values appear in the corresponding data table. To change how a date or time appears in a data table, see [“Numeric Formats”](#) on page 261 in the “The Column Info Window” chapter.

Selecting a date interval from the date increment drop-down menu divides the JMP date (number of seconds) into the appropriate units. This gives the plot scale that you want for your data. The date axis must be a column with a JMP date value and appear in the Axis Settings window in the date format found in the Column Info window. However, you can use the Axis Settings window to format the date’s appearance in the plot.

Establish Minimum and Maximum Axis Values


For plots and charts that contain a numeric axis area, you can change the minimum and maximum values that you want the graph to display.

Note the following:

- To restore the default minimum and maximum axis settings of a numeric axis, right-click a numeric axis and select **Revert Axis**.
- Select **Reverse Order** to reverse the axes by reversing the minimum and maximum values. Note that this option is not supported for ternary plots.

Tip: To set a default minimum and maximum axis value for a variable, which avoids making this change every time you run an analysis, see [“Axis”](#) on page 276 in the “The Column Info Window” chapter.

The example on the right in Figure 9.29 is an enlargement of the point cluster that shows between 80 and 140 in the plot to the left. The enlarged plot is obtained by reassigning the maximum and minimum axis values and changing the number of increments to 20.

Figure 9.29 Rescale Axis to Enlarge a Plot Section

Tick/Bin Increment

In the Tick/Bin Increment panel, you can do the following:

- “Change Axis Increments” on page 458
- “Add Minor Tick Marks” on page 459
- “Change the Tick Offset” on page 459
- “Label Row Nesting” on page 459

Change Axis Increments

While viewing a graph, you can change the axis increments.

If the axis Format is set to **Date**, **Time**, or **Duration**, a format menu appears beside **Increment**. See Figure 9.30. Select which format you want the increments to take.

Figure 9.30 Selecting the Format for Date and Time Increments

Scale

Type: Linear ▼

Format: m/d/y ▼

Width: 12

Minimum: 01/01/1904

Maximum: 01/01/1904

☐ Reverse Order

Tick/Bin Increment

Increment: 5

Minor Ticks:

Label Row Nesting:

Preview

Numeric ▼

Numeric

Year

Quarter

Month

Week

Day

Hour

Minute

Second

Tip: To set a default axis increment for a variable, which avoids making this change every time you run an analysis, see [“Axis”](#) on page 276 in the *“The Column Info Window”* chapter.

Add Minor Tick Marks

You can add tick marks to a numeric axis, or change the number of minor tick marks that appear on a numeric axis. In the Axis Label Row panel, be sure to select the **Minor** Tick Marks box so that the tick marks appear on the axis.

Tip: To set default minor tick marks for a variable, which avoids making this change every time you run an analysis, see [“Axis”](#) on page 276 in the *“The Column Info Window”* chapter.

Change the Tick Offset

To change the starting point of the tick marks, enter a number in the **Tick Offset** box. For example, if the Tick Offset is currently set to 0, setting it to 1 will move all the values on the axes up by 1.


Label Row Nesting

This option appears only if you have selected Date, Time, or Duration as the axis Format. Label row nesting enables you to split a date axis into multiple rows based on the format. For example, you might put the year on the outermost row, then the month, then the day:

1. Select **Help > Sample Data Library** and open *Stock Prices.jmp*.
2. Select **Graph > Graph Builder**.

3. Drag Date into the **X** zone.
4. Drag Open into the **Y** zone.
5. Double-click the X axis.
6. For **Format**, select **Date > ddMonyyyy**.
7. Increase the value for **Label Row Nesting** to 3.
8. Click **OK**.
9. Click **Done** to see the finished graph.

Figure 9.31 Example of Label Row Nesting



Axis Label Row

In the Axis Label Row panel, you can do the following:

- [“Change Axis Label Font”](#) on page 461
- [“Add Tick Marks, Grid Lines, or Labels”](#) on page 461
- [“Change the Orientation for Tick Labels”](#) on page 463

Note: In Graph Builder, if you have nested labels in an axis, tabs appear in the Axis Label Row panel. You can modify each row of labels separately in its own tab.

Change Axis Label Font

You can modify the axis label font on any axis type. Your changes only apply to the active graph. To set the default axis label font, see “[Fonts](#)” on page 610 in the “JMP Preferences” chapter.

Note: Windows 7 does not support the Adobe Compact Font Format (CFF). As a result, JMP cannot render axis labels using CFF fonts (like certain OpenType fonts). Windows 8 supports CFF fonts. Therefore, JMP correctly renders axis labels using CFF fonts.

To change the current font type and size, perform one of the following steps:

- Right-click an axis label and select **Font**
or
- Right-click an axis and select **Axis Settings**. Click **Font**.

Notes:

- To change the font color, right-click an axis label and select **Font Color**.
- Select **Automatic Font Size** to have JMP attempt to decrease the font size (down to a certain minimum) if all of the labels cannot fit at the default size.

Add Tick Marks, Grid Lines, or Labels

These options can vary depending on whether your axis is continuous or categorical. Figure 9.32 shows axis settings for a categorical axis. [Figure 9.28](#) on page 455 shows axis settings for a continuous axis.

Note: Remember that the Axis Settings window is available only for categorical axes in Graph Builder and Distribution.

Figure 9.32 Axis Label Row for a Categorical Axis

Scale

Type: Linear ▼

Minimum:

Maximum:

☐ Reverse Order

Tick/Bin Increment

Increment:

Axis Label Row

Font... ☒ Automatic Font Size

☒ Automatic Tick Marks ☐ Show Tick Marks

☒ Show Tick Labels ☐ Show Grid

☐ Lower Frame ☐ Tick marks inside graph frame

Tick Mark Style: Long Mark ▼

Label Orientation: Automatic ▼

Value	Label
0	F
1	M

Reference Lines

☐ Allow Ranges

Value: Update optional item

Label:

Color: 100% ▼ Add

Line Style: 1 ▼ Remove

Preview

M

F

OK Cancel Help

Options for continuous axes:

- Select **Automatic Tick Marks** to turn on tick marks only if one or more labels is hidden (due to insufficient space).
- Add major or minor tick marks, grid lines, or labels, by selecting the corresponding check boxes.
- Click the color box to change the color of grid lines.
- Select **Tick Marks Inside Graph Frame** to move the tick marks inside the graph.

Options for categorical axes:

- The default is to not show tick marks if all of the labels are visible. To add tick marks, select **Show Tick Marks**.
- Select **Automatic Tick Marks** to turn on tick marks only if one or more labels is hidden (due to insufficient space).
- Add grid lines by selecting **Show Grid**.
- Click the color box to change the color of grid lines.
- Select **Tick Marks Inside Graph Frame** to move the tick marks inside the graph.
- Select **Lower Frame** to add a frame around the labels.

- Change the Tick Mark Style by selecting one of the options.
- Modify the labels by entering different values in the Label boxes.

Tip: To set default tick marks for a variable, which avoids making this change every time you run an analysis, see [“Properties That Control the Display of Columns”](#) on page 276 in the “The Column Info Window” chapter.

Change the Orientation for Tick Labels

To change the orientation for tick labels, select an option from the Label Orientation list.

Automatic Tick labels are oriented automatically to be readable, depending on the tick increment and length of the labels.

Horizontal Baseline at the bottom.

Vertical Vertical with the baseline on the right.

Perpendicular Horizontal for vertical axes and vertical for horizontal axes.

Note: Parallel and Perpendicular are useful with paired axes, like in Multivariate plots.

Parallel Vertical for vertical axes and horizontal for horizontal axes.

Angled Angled at about 45 degrees.

Reference Lines

To add reference lines to graphs, proceed as follows:

1. Double-click a numeric axis. Or, right-click a numeric axis and select **Axis Settings**.
2. In the Value text box, enter the value to which you want the reference line to correspond. This is the position on the graph at which the line is placed.

Note: If you opened the Axis Setting window by double-clicking on the graph, the default value corresponds to the point on the graph that you clicked.

3. Enter a Label for the line.
4. You can further customize the reference line by choosing either of these options:
 - Select **Allow Ranges** to enter a minimum and a maximum value, which define the beginning and the end of the reference line. The reference line appears over a range of data.
 - Color changes the line color. You can also specify the opacity.

- Line Style specifies the line style (when Allow Ranges is not selected). You can also specify the line width.
5. Click **Add**. The value moves into the box to the right of the Add button, indicating that it will be placed on the graph. Your changes appear in the Preview window.
 6. To add more lines, repeat the above steps.
 7. To modify an existing reference line, make your changes, and then click **Update**.

Tip: To set a default reference line for a variable, which avoids making this change every time you run an analysis, see [“Properties That Control the Display of Columns”](#) on page 276 in the [“The Column Info Window”](#) chapter.

Customize Axes and Axis Labels Using the Pop-Up Menu

Right-click on an axis to perform the following tasks:

- [“Extend Divider Lines and Frames for Categorical Axes”](#) on page 464
- [“Add and Remove Axis Labels”](#) on page 465
- [“Rotate Axis Labels and Tick Marks”](#) on page 465
- [“Copy and Paste Graph Contents”](#) on page 466
- [“Copy and Paste Axis Settings”](#) on page 466


Extend Divider Lines and Frames for Categorical Axes

Extending the vertical divider line(s) between tick labels is useful when there are many levels of a nominal or ordinal (categorical) variable.

To extend the divider line to the x -axis labels, follow these steps:

1. Right-click a nominal or ordinal axis.
2. Select **Tick Marks > Divider Lines** to add the lines, or **Lower Frame** to add a frame around the axis area.

Figure 9.33 Divider Lines



Add and Remove Axis Labels

You can add or remove labels in a numeric axis. To add an axis label:

1. Right-click a numeric axis and select **Add Axis Label**.
2. Enter a name for the axis label. The axis area enlarges to hold the number of label lines that you enter.

This command can be used multiple times to add multiple labels. To edit the label after it has been added to the axis, click it and it will turn into an edit box.

To remove an axis label, right-click a numeric axis and select **Remove Axis Label**. The last label added is removed.

Rotate Axis Labels and Tick Marks

You can modify the axis label on any axis type.

To rotate an axis label, follow these steps:

1. Right-click an axis label.
2. Select **Rotate Text**.
3. Select which direction to rotate the text: **Horizontal**, **Left**, or **Right**.

Tip: To set a default axis label position for a variable, which avoids making this change every time you run an analysis, see [“Properties That Control the Display of Columns”](#) on page 276 in the “The Column Info Window” chapter.

On a nominal axis, you can rotate tick marks. Right-click the tick label and select **Rotated Tick Labels**.

Copy and Paste Graph Contents

After customizing a graph by adding elements such as a fitted line, you can copy and paste the contents from one graph to another compatible graph:

1. Right-click the graph that you have customized.
2. Select **Edit > Copy Frame Contents**.
3. Right-click the graph to which you would like to copy the settings.
4. Select **Edit > Paste Frame Contents**.

Tip: If you are having difficulty pasting histogram bars, see the JSL workaround in the Scripting Graphs chapter in the *Scripting Guide*.

Copy and Paste Axis Settings

After customizing an axis (as described in [“Customize Axes and Axis Labels in the Axis Settings Window”](#) on page 455), you can copy and paste your new settings to another axis:

1. Right-click the axis that you have customized.
2. Select **Edit > Copy Axis Settings**.
3. Right-click the axis to which you would like to copy the settings.
4. Select **Edit > Paste Axis Settings**.

Tip: To broadcast the axis settings to multiple graphs, hold down the Ctrl key when you right-click the axis and select **Edit > Paste Axis Settings**.

Change the Order of Values

Data in a JMP report might not appear in the order that you prefer. To give data a specific order so that it appears that way in a report, assign the column the Value Ordering property before running the analysis, as described in [“Value Ordering”](#) on page 273 in the “The Column Info Window” chapter.

If your values include any of the following, they automatically appear in the appropriate order in reports:

- January, February, March, April, May, June, July, August, September, October, November, December
- Jan, Feb, Mar, Apr, May, Jun, Jul, Aug, Sep, Oct, Nov, Dec
- Sunday, Monday, Tuesday, Wednesday, Thursday, Friday, Saturday
- Very Low, Low, Medium Low, Medium, Medium High, High, Very High

- Strongly Disagree, Disagree, Neutral, Indifferent, Agree, Strongly Agree
- Failing, Unacceptable, Very Poor, Poor, Bad, Acceptable, Average, Good, Better, Very Good, Excellent, Best

Change the Pattern and Format of Selected Objects

Patterns appear on some objects such as bars and maps when you select them. You can change the pattern for a specific object in the legend.

Right-click the item in the legend and select **Fill Pattern** to select a new pattern.

To remove the pattern, right-click the item again and select **Revert**.

Modify the Format of Selected Objects in All Graphs

Select **File > Preferences > Graphs** (Windows) or **JMP > Preferences > Graphs** (Macintosh) to change the Filled Areas preferences.

- To change the highlight on selected objects, select one of the following Filled Selection Mode preferences:

Selected Patterned Striped pattern (the default setting)

Selected Darkened Solid darker color

Selected Outlined Outline


Selected Same Color The Fill Selection Color in the preferences formats the selected object.

- To change the color of selected rows in graphic objects when the Fill Selection Mode is “Selected Same Color”, click the Fill Selection Color bar. The default color is red.

Add a Graph to a Data Table

You can add a graph to a new data table. Right-click on a graph and select **Edit > Make table of graphs like this**. The graph and the variables appear in a new data table.

Tip: To make the graph larger, resize the table cell.


Figure 9.34 Histogram and Y Variable Added to Data Table


Customize Graphical Elements

Graphs consist of markers, lines, text, and other graphical elements that you can customize. For example, in a Scatterplot Matrix graph, you might want to highlight data points in one of the bivariate graphs with a pink solid marker. In a Contour Plot graph, you can increase the width or transparency of the contour lines.

Example of Customizing a Contour Plot


1. Select **Help > Sample Data Library** and open Little Pond.jmp.
2. In the Table panel, click the green triangle next to the Contour Plot script.
3. Click on the red triangle next to Contour Plot for Z and deselect **Fill Areas**.

Figure 9.35 Contour Plot before Customization


4. Right-click on the plot and select **Customize**.
The Customize Graph window appears.

5. Click **Shape**.
6. Change the **Line Width** to 2.0.
7. Click on the color next to **Line Color** and select a shade of green.
8. Click **OK**.

Figure 9.36 Customized Contour Plot



The graphical elements that you can customize differ on each graph. For example, in a Control Chart graph, there are three line elements (Lower Limit, Upper Limit, and Connect Line). In other graphs, the line element might be named Line or Custom.

To customize graphical elements in the current graph, follow these steps:

1. Right-click the graph and select **Customize**.
2. Select the element that you want to change, and then modify the properties.
Your changes are immediately shown on the graph.
3. Click **OK** to save your changes to the current graph.

Each element can include properties for line color, marker style and size, text style, and so on. Here are some common properties:

Line Color Changes the color of the line. Click to select any color in the window. Right-click to choose from more colors.

Line Style Changes the style of the line. Click to select one of five different styles.

Line Width Changes the width of the line. Click in the box and enter the desired line width in points.

Marker Changes the marker shape. For more information about markers, refer to [“Use Markers”](#) on page 439.

Marker Size Changes the size of the marker.

Arrow Adds an arrowhead to a line at either None, Start, End, or Both ends of the line.

Line of Fit Changes the color, width, or style of the line.

Text Color Changes the color of the text.

Font Changes the font, style, and point size of the text.

Text Style Changes the text alignment to centered, left-aligned, or right-justified. The **Fill** option applies the selected color to the background.

Fill Color Changes the color of objects such as box plots and Fit Confidence regions.

Fill Pattern Changes the pattern of filled objects.


Transparency Changes the marker or label transparency. Enter the level of transparency to draw markers (points) on the graph. The degrees of opacity ranges from 0 (clear) to 1 (opaque). For more information about changing the transparency of markers, see [“Specify Marker Transparency”](#) on page 443.

Clip Shape Crops the object (such as contours) around the boundary according to the selected Clip Shape. The display segs that make up the object then conform to the boundaries of the map. Select a sub-boundary to display the objects only over a portion of the boundary. For example, you might want to display the objects only over New York.

About Clip Shape Options

Graphical elements (display segs such as reference, grid lines, and contours) can be clipped to conform to the boundaries of a geographical map. The Customize Graph window provides Clip Shape options, where you can select a boundary around which to clip the shape. Figure 9.37 shows reference lines clipped around a map of the United States.

Figure 9.37 Unclipped (Left) and Clipped (Right) Reference Lines




Tips:

- See the Create Maps chapter in the *Essential Graphing* for an example of creating the maps shown in Figure 9.37.
- The Clip Shape option in the Customize window was also set to clip the contours to the boundaries of the map. See “[Clip Shape](#)” on page 470.
- Scripting provides additional options such as specifying the clipping path in a matrix or string. See the Scripting Graphs chapter in the *Scripting Guide*.


Create Scripts for Graphical Elements

In addition to customizing graphical elements, you can write JSL scripts that add elements. These scripts run when you display the graph. You can write the scripts from scratch, or you can select from the following lists of commands and scripts, accessed by clicking on the **Add a new script button** :

- Use the Templates list to insert a single JSL command. For example, the Polygon option inserts the Polygon command. The text enclosed in underscores are placeholders for point values, which you replace with your own values.
`Polygon([_x0_, _x1_ ... ], [_y0_, _y1_ ...]);`
- Use the Samples list to insert a script that creates elements such as bubble plots and sine waves. In this list, the Polygon option shows examples of the Transparency, Fill Color, and Polygon values, which you replace with your own values.

Figure 9.38 The Polygon Sample Script


In some graphs, you can view the JSL that creates graphical elements. Figure 9.39 shows the Group Label script for a Discriminant Analysis graph. The script defines markers and text for group labels. The commands included in these built-in scripts cannot be modified or deleted. You can insert commands from the Templates or Samples list, but you cannot click in the window and type new commands.

Figure 9.39 Example of JSL That Creates Group Labels


For information about JSL, see the *Scripting Guide* and the *JSL Syntax Reference*.

To create a graphics script, follow these steps:

1. Right-click on the graph and select **Customize**.
2. Click the **Add a new script** button (+) to create a new script.
The default name, Script, is highlighted.
3. With the default name highlighted, type a more descriptive name, and then press Enter. (If you already moved the cursor and the name is no longer highlighted, double-click Script, and then enter the new name.)
4. Do one or more of the following:
 - Enter JSL in the Properties window.

- Select one or more JSL commands from the Templates list, and modify the placeholder text. For example, change the Pen Color option from “blue” to “red.”
 - Select one or more sample scripts from the Samples list and modify, if necessary.
5. (Optional) Click **Apply** to update the graph with your changes without closing the window. Unlike other property changes, script changes do not take effect until you click **Apply** or **OK**.
 6. Click **OK** to save your changes.

One of the following occurs:

- The element that you created appears on the graph.
- An error message appears if the script contains an error. Select **View > Log** to read about the error, and then correct the script.

To delete a script that you created, select the script and then select the **Delete selected object** button ()

Change the Drawing Order of Graphical Elements

The graphical elements are drawn in the order in which they are listed. The first element on the list is drawn first, so it appears *behind* all other graphical elements. If one element hides another, you can rearrange the order of the elements.

To rearrange graphical elements

1. Right-click the graph and select **Customize**.
2. Select the element that you want to move.
3. Click the **Move up in drawing order** button () or **Move down in drawing order** () button one or more times until the elements are in the order in which you want them drawn.
4. Click **OK**.

Save Your Customizations

The graph customizations apply to the current graph and are also used when you redo an analysis. To re-create your graph at a later time with its customizations, select **Save Script** from the red triangle menu, and then select one of the Save options. For example, you can save the script to the data table, which applies your customized properties each time you run the script. See [“Save Your Analysis as a Script”](#) on page 509 in the “Save and Share Data” chapter for details.

Copy Your Customizations

You can copy your customizations from one graph to another. All objects that you created or modified, such as colored text or lines, are pasted to the other graph.

To copy lines from one graph to another, see [“Copy and Paste Graph Contents”](#) on page 466.

To copy other objects

1. Right-click in the graph with custom elements and select **Edit > Copy Customizations**.
2. Right-click in the destination graph and select **Edit > Paste Customizations**.

The objects appear on the current graph and are added to the list of customized elements.

Notes:

- The customizations are pasted into all similar graphs when you press Ctrl, click, and then paste.
- The copy customizations feature copies only the elements that you added or modified. It does not copy the other contents of the graph.

Add Images to a Graph or Report

To enhance your analyses with logos and other types of graphics, paste or drag and drop graphics into the graph or report. .bmp, .emf, .jpeg, .png, and .rtf graphic formats are supported.

- [“Paste a Background Image into a Graph”](#)
- [“Paste an Image at the End of a Report”](#)
- [“Drag and Drop an Image into a Graph”](#)
- [“Add Geographical Images and Boundaries”](#)
- [“Extract Data from an Image”](#)

Paste a Background Image into a Graph

1. Open the graphic file in a graphics program and select the graphic. Copy it to the computer's clipboard.
2. Right-click inside a graph.
3. Select **Edit > Paste Background Image**. The graphic is inserted at the point in the graph that you right-clicked.

Paste an Image at the End of a Report

You can also add the graphic to the end of a report window. Copy the graphic from a graphics program onto your computer's clipboard, display the report window, and select **Edit > Paste**.

Drag and Drop an Image into a Graph

To add an image that you created, generate your report and then drag and drop the image from your computer's file system onto the graph in the report. After you add the image, JMP provides several options such as resizing, formatting, and rotating an image. Right-click the image and select **Image** to see these options.

The following example shows a bivariate plot of wind speeds in the Chicago area. The plot on the left includes arrows to illustrate the wind direction and speed. A map image was dropped onto the plot and resized to line up the markers with the stations that provided the wind data (each dot representing a station).

Figure 9.40 Example of a Custom Map Image




Image Processing

JMP includes a variety of image processing options. Image processing includes filters that can sharpen, blur, resize, and enhance. JMP also allows flipping, rotating, and locking images. This section describes the processing options.

Notes:

- Repeated changes to images can degrade the image quality. If you are not happy with the results of sizing, scaling, or applying filters to the image, remove the image and start again.
- All JMP image filters are supported at the operating system level; images might be processed differently on Windows and Macintosh.

Lock

Locks the image in place so that it cannot be moved.

Size/Scale

- **Fill Graph:** Resizes the image proportionately to fit the graph.
- **Specify Size:** Resizes the image according to the values that you enter. (The units for these values are the same as your graph axes.)
- **Crop:** Crops the image according to the values that you enter. (The units for these values are the same as your graph axes.) For example, the left edge might be positioned at 50. You enter 60 next to Left, and the portion of the image between 50 and 60 is removed from the image.

Flip

- **Flip vertical:** Flips the image top to bottom.
- **Flip horizontal:** Flips the image left to right.
- **Flip both:** Flips the image both horizontally and vertically.

Rotate

Rotates the image the specified number of degrees. Enter a negative value to rotate the image counterclockwise.

Transparency

Changes the image transparency level. Enter a value between 0 and 1 (where 1 is completely opaque).

Filter

Provides filters found in many graphic editing programs to change the appearance of the image. Select a filter repeatedly to increase its effects on the image.

- **Contrast:** Optimizes the light and dark colors. Larger values lighten the image.
- **Despeckle:** Removes pixels that do not blend with surrounding pixels. For example, a black pixel surrounded by white pixels is converted to a white pixel.
- **Edge:** Darkens everything but the outlines of objects.
- **Enhance:** Reduces the contrast between pixels in a noisy image.
- **Gamma:** Balances the brightness of an image and the red, green, and blue (RGB) ratios. Larger values create a lighter image.

- **Gaussian Blur:** Blurs pixels by the specified radius. Larger radii create a smoother image. (In JSL, you can also specify the sigma value. Larger sigma values create a smoother image.)
- **Median:** Replaces each pixel color value with the median value of the surrounding pixels.
- **Negate:** Converts each pixel to its complementary color (such as pink to green and white to black).
- **Normalize:** Removes a percentage of the top and bottom color values. The color values are then stretched to fill the remaining image. This process increases the intensity of the colors.
- **Reduce Noise:** Finds the minimum and maximum color values and replaces them with values more consistent with the surrounding pixels. Larger values create a smoother image.
- **Sharpen:** Makes the edges of pixels more distinct.

Remove

Removes the image from the report.

Add Geographical Images and Boundaries

Adding map images and political boundaries to graphs provides visual context to geospatial data. For example, you can add a map to the graph that displays an image of the U.S. Another option is displaying the boundaries for each state (when data includes the latitudes and longitudes for the U.S.).

The data should have latitudinal and longitudinal coordinates. Otherwise, the map has no meaning in the context of the data. The x and y axes also have range requirements based on the type of map. These requirements are described in the following sections.

Two tools are especially helpful when you are viewing a map:

- The grabber tool () lets you scroll horizontally and vertically through a map.
- The magnifier tool () lets you zoom in and out.


For details about adding maps, see the Create Maps chapter in the *Essential Graphing* book.

Extract Data from an Image


JMP provides the ability to extract information from images into a data table and then analyze that information. Researchers at [WildTrack.org](https://www.wildtrack.org) analyze digital footprint photos in JMP to track endangered species. They drag and drop a footprint image into a JMP report and draw data points to capture the size and shape of the print. A JMP Scripting Language (JSL) script extracts those measurements into a data table. At that point, the researchers can analyze the

data and determine whether the footprint is from a new animal. This method helps them track populations of endangered species in specific regions of the world.

Figure 9.41 Example of Extracting and Analyzing Data



Analysis shows that the footprint above is from a tiger whom WildTrack has already cataloged.



The details for implementing this feature are beyond the scope of this book, because the needs of the user vary widely. For details about writing JSL scripts, see the *Scripting Guide* and the *JSL Syntax Reference*.

Add Annotations and Shapes to a Report

You can add text notes, lines, polygons, ovals, and rectangles to a report or graph using graphics tools found in the toolbar.

Add Annotations

You can add editable text notes to a JMP report or graph using the annotate tool . To add an annotation:

1. Select the annotate tool  from the Tools menu or toolbar.

2. In the report or graph, click where you want to add the annotation. Or, click and drag to size the annotation note. A white editable text box appears.
3. Enter text.
4. Click outside the annotation.
5. (Optional) To add a tag line, right-click the annotation and select **Tag Line**. Or, you can edit any of the following options:

Background Color Select the background color for the annotation.

Text Color Select the text color. The color of the text also defines the color of the annotation outline.

Font Change the font type, style, and size. To change the default font, see “[Fonts](#)” on page 610 in the “JMP Preferences” chapter.

Tag Line Draws a line between the annotation and the point or text it is anchored to. To move the line and annotation, press the Ctrl key and drag the annotation to a new position.

Filled Removes the background color from the annotation so that it looks transparent. A transparent note is handy for putting titles and footnotes on a graph.

Editable Makes the annotation editable by double-clicking on it.

Reanchor If you move an annotation, you can change where the tag line attaches to by reanchoring it.

Delete Deletes the entire annotation.

Note: When adding multiple annotations, press the Shift key when selecting the annotation tool for the first time. This causes subsequent clicks to add an annotation, and you do not have to select the annotate tool from the toolbar before the addition of each annotation.

Once you have added an annotation, you can do the following:

Table 9.3 Using Annotations

Action	Instructions
Add to or edit an annotation	Click inside the text box.

Table 9.3 Using Annotations *(Continued)*

Action	Instructions
Move an annotation	Click inside the annotation box and drag it. When an annotation is moved, it becomes selected, as indicated by a double blue line with handles around the perimeter.
Resize an annotation	Place the cursor on the handle of a selected note (showing in the middle of the edges and in the corners). The cursor appears as a single crossed arrow; drag to resize the annotation.
Delete an annotation	Highlight the annotation by clicking the handle of a note. Then press the Delete (or Backspace) key.

Add Shapes

You can add editable lines, polygons, and simple shapes (ovals or rectangles) to a JMP report using the drawing tools   . The following sections describe how each of these tools can be used.

Note: Each graphics tool remembers the most recent options chosen. This is useful if you need many annotations or other graphics with the same characteristics. For example, suppose you want many thick green lines with an arrow on one end. Create a line the way you want it, set the options, and subsequent lines appear with those options in effect. The options persist until you change them.

Add a Line

To add a line to a report window:

1. Click the line tool  in the tool palette.
2. Click and drag where you want to insert the line. The line appears selected, showing handles on both ends.
3. Click and drag the line to move it.
4. Click a handle and drag to rotate the line.
5. Right-click a line for a menu of options to customize the appearance of the line, as follows:

Point to and Point from Places arrows on either end (or both ends) of the line.

Thick Changes the width of a line to thick. Lines are thin by default.

Dashed Changes the line to dashed. Lines are solid by default.

Color Displays the JMP color palette to change the color of the shape.

Reanchor Reanchors the shape.

Delete Removes the shape from the report surface. You can also remove the shape by selecting it and then pressing the Delete (or Backspace) key.

Add a Polygon or Bezier Curve

To add a polygon (or Bezier curve) to a report window:

1. Click the polygon tool  in the tool palette.
2. Click to create the beginning point for the first side of a polygon.
3. Click again at the location where you want to complete the first side and begin an adjacent side. A square selection box with handles appears around the polygon area.
4. Click a third time to complete the second side.
5. Continue this process until the polygon is the way you want it. Each time a side is complete, the selection box adjusts to encompass the polygon sides.
6. Double-click to release the polygon tool.

Once you have added a polygon, you can perform the following actions:

Table 9.4 Working with Polygons

Action	Instructions
Select or deselect the polygon	Click the edge of a completed polygon.
Resize the polygon	Select it and drag one of the selection box's handles.
Move the polygon	Click between the box's handles and drag the selection box.
Change the number of sides of the polygon	Click and drag the sides to form the new shape.

Right-click a polygon for a menu of options to customize its appearance, as follows:

Filled Fills or empties the area of the shape.

Raised Displays thick shaded lines around the shape. If the shape is also filled, the lower edge of the figure appears raised, giving it a three-dimensional look.

Smooth Smooths the vertices of a polygon to produce a Bezier curve. The smoothed figure is reshaped and resized the same way as the polygon, and can be filled and raised.

Closed Opens or closes the last segment of a polygon.

Color Displays the JMP color palette to change the color of the shape's sides, and its fill color when the **Filled** option is in effect.

Reanchor Reanchors the shape.

Delete Removes the shape from the report. You can also remove the shape by selecting it and then pressing the Delete (or Backspace) key.

Add an Oval or Rectangle

To add an oval or rectangle to a report window:

1. Click the simple shape tool  in the tool palette.
2. Click and drag where you want to insert the shape. An oval appears with a selection box around it.
3. (Optional) To turn the oval into a rectangle, right-click on the oval and select **Shape > Rectangle**.
4. Double-click to release the simple shape tool.

Once you have added the shape, you can do the following:

- Select the shape and drag one of the selection box handles to reshape or resize.
- Click and drag an edge of the selection box (located between the handles) to move it.
- Select the shape, and then right-click it for a menu of options to customize its appearance, as follows:

Filled Fills or empties the area of the shape.

Raised Displays thick shaded lines around the shape. If the shape is also filled, the lower edge of the figure appears raised, giving it a three-dimensional look.

Shape Displays a submenu whose options transform the shape into either an oval or a rectangle when selected.

Color Displays the JMP color palette to change the color of the shape's sides and its fill color when the **Filled** option is in effect.

Reanchor Reanchors the shape

Delete Removes the shape from the report. You can also remove the shape by selecting it and then pressing the Delete (or Backspace) key.

Chapter 10

Save and Share Data Get Your Data Out of JMP

This chapter covers the following topics:

- saving data tables as text files, SAS data sets, Excel files, and other formats
- saving reports as interactive HTML, Adobe Flash files, and PowerPoint
- emailing reports and data tables
- saving analyses as scripts
- saving parts of a report as a graphic
- printing reports
- copying and pasting reports
- creating JMP journals or projects
- saving JMP sessions
- saving log windows

The method that you choose depends on how you want to interact with your analyses in the future:

- If you want to interactively present your data, you might choose to create a JMP journal.
- If you want to send data tables, linked reports, and other items to someone, you might choose to create a JMP project.
- If you want to continue to explore a report later, you might choose to create a JMP report.
- If you want to send a report to a non JMP user, you might convert the report to interactive HTML or a web report.

Contents

Save and Share Data Tables	486
Save as a Microsoft Excel File	487
Save as a CSV File	488
Save as a Text File	489
Save as a SAS Transport File	490
Save as a SAS Data Set	491
Save Data Tables to a Database	492
Replace a Database with a Data Table	493
Email a Data Table	494
Save and Share Reports	494
Email a Report	496
Share Interactive JMP Reports on the Web	496
Save as PDF	506
Save as PowerPoint	507
Save as Flash	508
Setting the Graphic DPI	509
Save Your Analysis as a Script	509
Save Parts of a Report in a Graphic Format	509
Print Reports	511
Copy and Paste Reports	511
Create a Journal	512
Example of Making a Journal for a Presentation	513
Create a New Journal	515
Manage Links in Shared Journals	515
Add and Edit Outlines	517
Journal Right-Click Options	517
Control the Display of Outline Levels	518
Add a Graph or Graphic	518
Customize Journal Items	519
Prevent Modifications	519
Append Reports to a Journal	519
Save the Journal in Another Format	520
Delete Items from a Journal	520
Create a Project	521
Save Files in a Project	524
Move Files to a Project	526
Share the Project	527
Projects Compatibility	528
Save JMP Sessions	529

Save Sessions upon Exiting	529
Save Sessions Manually	530
Save a Log Window	530

Save and Share Data Tables

JMP saves data tables in the formats listed in Table 10.1.

Here are the basic steps for saving a data table:

- On Windows, select **File > Save As** to save in multiple formats.
- On Macintosh, select **File > Save As** to save as a JMP file (.jmp). Select **File > Export** to save in Text (.dat), Microsoft Excel (.xls or .xlsx), SAS Transport (.xpt), and SAS Data Sets (.sas7bdat) formats.

Note: To save a data table as a journal, select **Edit > Journal** and then **File > Save As**.

Table 10.1 Supported File Types for Saving Data Tables

File Type(s)	OS Availability
JMP Data Table (.jmp)	All
Excel Workbook (.xls, .xlsx)	All
Text Export File (.txt)	All
Comma-delimited file (.csv)	Windows
Tab-delimited file (.tsv)	Windows
SAS Data Set (.sas7bdat)	All
SAS Data Set with Extended Attributes (.sas7bxat)	Windows
Note: JMP can save column properties and table properties as extended attributes in a SAS 9.4 .sas7bxat file. Select File > Save As , select the SAS Data Set file type, and then select the check box for saving extended attributes. JMP names the file with the .sas7bxat extension. The SAS Integration preferences also include this option, which is off by default.	
SAS Transport File (.xpt, .stx)	All
JSON (.json)	All

You can also save files for types that have a corresponding ODBC driver. See [“Save Data Tables to a Database”](#) on page 492, for details.

Notes:

- The maximum length of the data table's name depends on your computer's operating system. See your operation system documentation for details.
- JMP tries to save any modified files when a crash is detected.

Save as a Microsoft Excel File

There are two options for saving data tables as Microsoft Excel files:

- Save one data table in Microsoft Excel format (.xls or .xlsx). Data from a single table is saved in a workbook named after the data table.
- Generate a workbook in .xlsx format from multiple tables. Data from each table appear on a different worksheet in the workbook.

The .xlsx file includes data table cell colors. The file also provides hidden data and excluded data. Formulas and most formatting are not included.

The maximum length of the Excel filename is determined by your computer's operating system.

Save One Data Table as a Microsoft Excel Workbook

To save a data table as a Microsoft Excel workbook, follow these steps:

Windows

1. Select **File > Save As**.
2. Select **Excel Workbook (*.xlsx, *.xls)**.
3. Enter a name for your file in the File name box.
4. (Optional) To save the file as an .xls file, select **Use Excel 97-2003 Format (*.xls)**.
5. (Optional) To avoid opening the file in the default spreadsheet program after saving, deselect **Open the file after saving**.
6. Click **Save**.

Macintosh

1. Select **File > Export**.
2. Select **Excel** and select the format.
3. Click **Next**.
4. Enter a name for the file in the **Save As** box.

5. (Optional) To avoid opening the file in the default spreadsheet program after saving, deselect **Open the file after saving**.
6. Click **Export**.

Note: On Windows, data is split among several worksheets when the number of columns or rows exceeds the number that Excel supports.

Save Multiple Data Tables as a Microsoft Excel Workbook

To save multiple data tables in a new or existing Microsoft Excel workbook, follow these steps:

1. Open the data tables.
2. (Windows) Select **File > Create Excel Workbook**.
3. (Macintosh) Select **File > Export**, select **Export Multiple Data Tables** from the Excel list, and then click **Next**.
4. In the Include Table column, select only the data tables that you want to save.
5. In the Worksheet Name column, specify the name of the worksheet tab if necessary.
6. Enter a name for the workbook in the Workbook Name box.

The workbook is named after the current data table by default.

7. Click **Choose** and browse to select a directory to save the file in.

You can overwrite an existing workbook. Worksheets that already exist in the workbook are replaced. Worksheets that are not in the existing workbook appear at the end of the sheets.

8. Click **Save**.

The file is saved as an .xlsx file.

Save as a CSV File

JMP can convert data from a JMP data table to a comma-separated values (CSV) file. To save a data table as a CSV file:

1. With the specific data table open in JMP, select **File > Save As**.
2. Select CSV (Comma delimited) (*.csv) from the **Save as type** list.
3. Enter the filename.
4. Select the location for the CSV file.
5. Click **Save**.

Note: On Windows, exporting a data table to a CSV file uses the comma and carriage return line feed character (CRLF) as file delimiters. Use a different extension and later rename the file with the CSV extension if you need to use different delimiters.

Save as a Text File

JMP can convert data from a JMP data table to standard text format with rows and columns. To save a data table as a text file, follow the steps below based on your operating system and how you want to save the file.

Text formatting options are as follows:

Export Column Names to Text File To save column headings in the first line of text, and to save labels or header information with the data, select **Export Table Headers**.

Add quotation marks to all column names, Add quotation marks to all character values, Add quotation marks to all numeric values Select an option to add quotation marks even when they are not required. Some programs that import CSV files might need the quotation marks to display the text correctly. Quotation marks are always added to fields that contain special characters such as the field delimiter (typically a comma or tab), the line separator (typically a carriage return), or quotation marks.

End of Field Select the radio button next to the character that marks the end of a field (or cell). Select **Other** and enter a character if the appropriate character is not listed.

End of Line Select the radio button next to the character that marks the end of a line (or row). Select **Other** and enter a character if the appropriate character is not listed.

Notes:

- If a double quotation mark is found when importing text data, the delimiter rules change, and JMP looks for an end double quotation mark. Other text delimiters, including spaces embedded within the quotation marks, are ignored and treated as part of the text string.
- When you import text data, columns that contain image data are assigned the Expression data type.
- On Windows, when you save a data table as a text file and then modify the data table, the text file is updated. After you save the data table as a text file (unless you save, close and reopen the data table), changes will be autosaved to the text file, not to the data table.

Windows

1. Select **File > Save As**.
2. Select **Text Export File** from the **Save as type** list.

3. Click the **Options** button and specify end-of-line and end-of-field characters, and choose whether to export column headings as text.
4. Click **OK**.
5. (Optional) To avoid opening the file in the default text editor after saving, deselect **Open the file after saving**.
6. Click **Save**.
An alert appears regarding loss of formulas, formatting information, and other metadata.
7. Click **Yes**.

Macintosh

1. Select **File > Export**.
2. Select **Text** and click **Next**.
3. Enter a name for the file in the **Save As** box and change the extension to .txt.
4. Specify end-of-line and end-of-field characters, and choose whether to export column headings as text.
5. (Optional) To avoid opening the file in the default text editor after saving, deselect **Open the file after saving**.
6. Click **Export**.

Save as a SAS Transport File

You can save a JMP data table in SAS transport file format. JMP replaces spaces in filenames and column names with underscores, converts column headings to uppercase SAS variables, and makes other changes to follow the transport file specifications.

When you save the data table as a transport file, you can opt to append it to an existing transport file. When you reopen the transport file in JMP, the two data tables open in separate windows.

Note: The maximum length for SAS transport filenames is 8 characters. JMP warns that characters beyond that limit are omitted.

Windows

1. Select **File > Save As**.
2. Select **SAS Transport File** from the **Save as type** list.

3. (Optional) Append the data table to an existing SAS transport file. Select the file to which you want to append the data table, and then click the **Save** arrow. Select **Append To**, and then click **Yes** to replace the selected data table.

An alert appears regarding loss of formulas, formatting information, and other metadata.

Note: Images in Expression columns cannot exceed 200 characters, otherwise they are not supported.

4. Click **Yes**.
Alerts appear regarding other SAS format modifications.
5. Click **OK** on each alert.

Macintosh

1. Select **File > Export**.
2. Select **SAS Transport**.
3. (Optional) To append the data table to an existing SAS transport file, select the **Append** check box.
4. Click **Next**.
5. Do one of the following:
 - If you chose to append the data table, select the file to which you want to append the data table and click **Append**.
 - Enter a name for the file in the **Save As** box, and then click **Export**.Alerts appear regarding SAS format modifications.
6. Click **OK** on each alert.

Save as a SAS Data Set

You can save data tables as SAS version 7 and higher data sets. JMP writes columns as SAS variables, writes rows as SAS observations, and makes other changes to follow the SAS data set specifications.

When you export data to a SAS data set, JMP date columns become SAS date values with the appropriate SAS format.

On Windows, JMP can save column properties and table properties as extended attributes in a SAS 9.4 .sas7bxt file. The option is available in the Save JMP As window and in the SAS Integration preferences.

Windows

1. Select **File > Save As**.
2. Enter a name for your file in the File name box. The maximum length for the filename is 32 characters. JMP warns that characters beyond that limit are omitted.
3. Select **SAS Data Set** from the Save as type list.
4. (Optional) To save SAS variable names or SAS formats, select the **Preserve SAS column names** or **Preserve SAS formats** check boxes.
5. (Optional) To store JMP metadata as extended attributes for SAS 9.4, select **Store table and column properties in SAS 9.4 extended attributes**. JMP automatically assigns the .sas7bxat file extension.
6. Click **Save**.

An alert appears regarding loss of formulas, formatting information, and other metadata.

7. Click **Yes**.
8. If other alerts appear, click **OK** on each alert.

Macintosh


1. Select **File > Export**.
2. Select **SAS** and click **Next**.
3. Enter the filename and select export options.
 - To avoid exporting rows that have the Excluded row state, select **Honor Excluded Rows**. The other options are described in the preceding section.

Save Data Tables to a Database

You can save a data table to any database on your system that has a compliant ODBC (Open Database Connectivity) driver.

When exporting a data table to a database using ODBC, JMP exports the data as either character (CHAR or NCHAR) or numeric (FLOAT or DOUBLE PRECISION) data types. If a column is defined as a JMP date or time, the column exports as character data. The receiving database handles changing the data type to a proper date format.

1. First, connect to the database. See [“To add a new database connection”](#) on page 493.
2. Select **File > Database > Save Table**.

Figure 10.1 The Database Save Table Window

3. In the Connections box, highlight the name of the database to which you want to save the file (shown in Figure 10.1). The Connections box contains a list of databases to which your system is connected.
4. From the **JMP data table to be saved** menu, select the open JMP data table that you want to save to the database.
5. In the **Save to database table** box, enter the name that you want the table to have when you save it in the database.
6. Click **Save Table**.

To add a new database connection

1. Click **Connect**.
2. Select the data source that you want and click **OK**. Or, to create a new source, click the **New** button (Windows) or **Add** button (Macintosh).

Depending on which data source you select (and which database drivers you have installed on your computer), you might be presented with a variety of windows. Use them to create the database source.

3. Select the database to which you want to save the file.

Replace a Database with a Data Table

To replace a database with a data table, follow these steps:

1. First, connect to the database. See [“To add a new database connection”](#) on page 493.
2. Select **File > Database > Save Table**.

3. In the Connections box, select the name of the database to which you want to replace the file. The Connections box contains a list of databases to which your system is connected.
4. In the Schemas - Tables box, select the database table that you want to replace.

Note: Remember the name for the database table. You use this same name for the replacement database table.

5. Click **Drop Table**.
The database table is deleted from the database.
6. From the **JMP data table to be saved** list, select the JMP data table that you want to save to the database.
7. In the **Save to database table** box, enter the name for the deleted database table.
8. Click **Save Table**.
The data table is saved to the database.
9. Click **Disconnect**.
10. Close the Save Database Table window.

Email a Data Table

On Windows, you can email a JMP data table by selecting **File > Send**. Your default email application opens with the data table file attached to a new email.

Save and Share Reports

To save a report, select **File > Save As**.

- On Windows, you can save the report as any of the file types listed in Table 10.2.
- On Macintosh, the report is saved as a JMP report (.jrp). Note the following:
 - You can save the report as a journal by selecting **Edit > Journal** and then **File > Save**.
 - If you want to save the report as a text, image, HTML, PowerPoint, or RTF file, select **File > Export**. Supported image files include .eps, .png, .svg, .pdf, and .tiff.

Table 10.2 Windows Supported Report File Types

File Type	Description
Microsoft Word (.doc)	Word processing format; mixture of pictures, text, and tables.

Table 10.2 Windows Supported Report File Types (*Continued*)

File Type	Description
Enhanced Metafile (.emf)	Can contain both vector and bitmap components.
Encapsulated PostScript File (.eps)	Line drawing (or <i>vector</i> image) that can show a bitmap preview of the image.
CompuServe Graphics Interchange Format (.gif)	Compressed bitmap pictures.
Hypertext Markup Language (.htm, .html)	Browser format; marked up text and references to separate picture files. Save pictures within the HTML file by selecting one of these formats: PNG, JPEG, SVG, or GIF.
Interactive HTML (.htm, .html)	Saves the data, reports, and graphs in an interactive web page, so non JMP users can explore the data. See “Save as Interactive HTML” on page 496 for more information.
Joint Photographics Expert Group (.jpg, .jpeg)	Compressed bitmap pictures; standard for photographs. See “Setting the Graphic DPI” on page 509.
JMP Journal (.jrn)	Analysis report duplicated in a separate window titled Journal. You can edit it or append other reports to it. See “Create a Journal” on page 512. Note that on Macintosh, select Edit > Journal, and then File > Save. On Windows, choose File > Save, and then choose the journal format.
JMP Report (.jrp)	Analysis report originally created in JMP. It can be reopened for continued analysis. Contains the JSL and embedded data or reference to the data to reproduce a live report. Choose this format if you want to work with the report again, perhaps with new data.
Portable Document Format (.pdf)	Format for sharing documents regardless of the operating system or application in which they were created.
Portable Network Graphics (.png)	Compressed bitmap pictures; successor to GIF. See “Setting the Graphic DPI” on page 509.

Table 10.2 Windows Supported Report File Types *(Continued)*

File Type	Description
PowerPoint Presentation (.pptx)	Microsoft PowerPoint format; mixture of pictures, text, and tables.
Rich Text Format (.rtf)	Word processing format; mixture of pictures, text, and tables. Save pictures within the RTF file by selecting one of these formats: PNG, JPEG, or EMF.
Scalable Vector Graphic (.svg)	Pictures stored as text; best used for two-dimensional graphics.
Tagged Image File Format (.tif, .tiff)	Raster file format. See “Setting the Graphic DPI” on page 509.
Text Format (.txt)	Plain text format; no pictures.

Email a Report

On Windows, you can email a JMP report by selecting **File > Send**. Your default email application opens with the report file attached to a new email. Note that the report must be saved before you can email it.

Share Interactive JMP Reports on the Web

There are different ways you can share JMP reports on the web:

- [“Save as Interactive HTML”](#) saves a single, interactive JMP report as a web page.
- [“Publish to File”](#) saves multiple, interactive JMP reports as web pages.
- [“Publish to JMP Public”](#) saves interactive JMP reports to a public collaboration website, <https://public.jmp.com/>.


Save as Interactive HTML

Interactive HTML enables you to share JMP reports that contain dynamic graphs so that even non JMP users can explore the data. The JMP report is saved as a web page that includes interactive features, which you can email to users or publish on a website. Users then explore the data as they would in JMP.

Interactive HTML provides a subset of features from JMP:

- Explore interactive graph features, such as selecting histogram bars and viewing data values.
- View data by brushing.
- Show or hide report sections.

Figure 10.2 Brushing Data in Interactive HTML



Many changes that you make to the graphs, such as ordered variables, horizontal histograms, background colors, and colored data points, are saved in the web page. Graphs and tables that are closed when you save the content remain closed on the web page until the user opens them.

Interactive HTML Contains Data

When you save reports as interactive HTML in JMP, your data are embedded in the HTML. The content is unencrypted, because web browsers cannot read encrypted data. To avoid sharing sensitive data, save your results as a non-interactive web page. (Select **File > Save As > HTML File** on Windows, or **File > Export > HTML** on Macintosh.)

To create interactive HTML

1. In JMP, create the report and make it the active window.
2. Select **File > Save As** and select **Interactive HTML with Data** from the Save as type list. On Macintosh, select **File > Export > Interactive HTML with Data**.

3. (Optional) To avoid opening the HTML file in the default browser after saving, deselect **Open the file after saving**.
4. Name and save the file (or export on Macintosh).
The output is saved in the selected folder.

Which Reports Are Supported

When you save a report as interactive HTML, the Save Report As window warns when one or more features in the report are not supported.

- If the contents are fully supported, output is created with no warnings.
- Partially or unsupported features are still saved in an interactive web page. When you place your cursor over an unsupported feature, a tooltip states that the feature is not yet interactive.

For information about exploring interactive HTML output, visit <https://www.jmp.com/support/help/InteractiveHTML/14/ShareJMPReports.shtml>.

Publish to File


Save your JMP report to a web page that you can share with people who do not have JMP. The web page, graphics, and support files are saved in the directory that you specify so that you can zip the files and send them to another user.

Graphs can appear as interactive HTML (for example, bubble plots or profilers). When you click on the thumbnail of the graph in a web report, the graph appears on a new web page.

To generate a web report, follow these steps:

1. In JMP, open a data table. For this example, select **Help > Sample Data Library** and open SATByYear.jmp.
2. Run your report. For this example, run the Graph Builder Map and Bubble Plot by State scripts in the SATByYear.jmp table.
3. From any JMP window, select **File > Publish**.
4. Check the boxes of the reports you want to publish. For this example, check the boxes next to both SATByYear plots.


Figure 10.3 Selecting Reports



5. In the drop-down list, make sure **Publish to File** is selected.
6. To make the graphs interactive, select **Publish Data**.
7. (Optional) You can change the location of the parent folder that will contain the report, and the name of the subfolder for the web report files.

Note: You must have write permission to the parent folder.

8. Click **Next**.
9. Enter a title for your web report. For this example, in the Web Report Title box, enter *SAT By Year Reports*.
10. Add a title and description for each report, as shown in Figure 10.4.

Figure 10.4 Customizing the Web Report



11. (Optional) You can do any of the following:

- To customize a web report (layout, color, font, logo, etc.) click **Customize**. See [“Customize Web Report Options”](#) on page 501.
- To change the order of the reports, use the arrows at right.
- To delete a report, click the delete icon.
- To add back a report after deleting it, click **Restore Reports**. (This button appears only if you have deleted a report.)
- To append an image to the bottom of the report, click **Add Image**.

12. Click **Build Report**.

The web page opens in your default browser.

Figure 10.5 Web Report



13. Click on one of the thumbnails to open the report. See <https://www.jmp.com/support/help/InteractiveHTML/14/ShareJMPReports.shtml> for details about working with interactive reports.

Customize Web Report Options

Style Format Determines the layout of the reports.

Grid Shows the reports in rows.

Large List Shows the reports in a column with large thumbnail graphics.

Small List Shows the reports in a column with small thumbnail graphics.

Custom CSS Enables you to specify a CSS file to format the web page. The CSS file is copied into a subdirectory called `_css`. The link to the CSS file is relative so that you can send the report and support files to another user and maintain the CSS formatting.

Color Theme Specifies the color of the web page, headings, and borders. The default web page has a white background, orange headings, and blue borders.

Add Image Specifies an image to display along with the reports. Click the up or down arrow next to the image to move it above or below the reports.

Toggle Timestamp Shows or hides the date and time at which the web page was generated.

Publish to JMP Public

JMP Public is a platform for sharing JMP data, visualizations and dashboards. Prepare your reports in JMP and publish them as posts to JMP Public to collaborate with your colleagues—even those who may not have JMP. JMP Public offers the visual interactivity of JMP to explore your data, and lets you:

- Store all of your reports in one location.
- Control sharing of individual reports with those who need to see them.
- Maintain up-to-date reports for your team in an easily accessible location.
- Extend the functionality of JMP Public reports to other locations – embed and interact with your JMP Public reports in web pages, blogs, social media posts and more.

To start sharing reports on JMP Public, follow these steps:

Register and edit your profile

Note: If you're not signed up for JMP Public, you'll only see featured posts.


1. To register for JMP Public, go to <https://public.jmp.com/>.
2. At the top right, click **Sign In**.
3. If you already have a SAS profile, log in using those credentials, then click **Submit**.
4. If you don't have a SAS profile:
 - a. Click **Register**. Complete the form and click **Create profile**.
 - b. Follow the instructions in the email to set your password and activate your profile.
5. (Optional) To change your profile name or picture, once you are signed into JMP Public, click your name and select **My Profile > Edit**.

Create and publish a report


1. In JMP, create a report, or several reports.
2. (Skip if your report does not contain a Local Data Filter.) If your report contains a Local Data Filter, add columns before you publish. This means you must select a column or columns in the Local Data Filter and click Add.

You will not be able to add filter columns after you publish the report. It will simply be static instead of interactive. See Figure 10.6.

Figure 10.6 Static and Interactive Local Data Filters




Static (no column added)



Interactive (age column added)

3. From a report window, select **File > Publish**.
4. Check the box next to the reports that you want to share.

Figure 10.7 Select Publish to JMP Public

5. From the drop-down list, select **Publish to JMP Public**.
6. (Optional) To publish the data tables associated with the reports and make the reports interactive, click **Publish Data**. If you deselect this, data are not embedded, and the graphs are static.
7. Enter your **User Name** and **Password**.

Figure 10.8 Enter Credentials

Select Reports

Select from open reports

Select All

☒ Big Class - Bivariate of weight by height
☐ Big Class - Contingency of age by sex

Interactive HTML is partially implemented for this report. Please see log messages.

☐ Close reports after running

Publish to JMP Public ☒ Publish Data

Reminder:
JMP Public is a public Online Communication Channel subject to the SAS Website Terms and Conditions [1]. You should never upload data or other materials not suitable for public distribution.
[1] [SAS Website Terms and Conditions](#)

JMP Server: public.jmp.com

SAS Profile Credentials:

User Name:

Password:

☐ Save to Preferences

Next Cancel

8. (Optional) To remember your credentials, check **Save to Preferences**.
9. Click **Next**.

Figure 10.9 Configure the Web Report

Configure Report

Web Report Title:

Web Report Description:
Click any of the thumbnails below to launch interactive JMP reports.

Share with:
☒ Only me
☐ Everyone
☐ Groups

☒ Open published web report

Add Image

Previous Publish Replace Cancel Help

10. (Multiple reports only) At left, enter a title and optionally, a description for your overall post. You can also:
 - Change the order of the individual reports by clicking the arrows  on the right.
 - Delete a report by clicking .
11. On the right, enter a title and optionally, a description for each report.
12. (Optional) To open the post after creating it, check **Open published web report**.
13. Choose who to share with: **Only Me** or **Everyone**:
 - **Only Me** means your report is visible to you only.
 - To share your report with everyone on JMP Public, choose **Everyone**.

Note: If you choose **Only Me**, you are prompted to log in to confirm your identity before the post opens.

14. (Optional, multiple reports only) To add images, click **Add Image**. You can also enter a title and description.
15. Click **Publish**. Or, if you are updating an existing post, click **Replace**. When replacing a post, make sure that the titles match.
16. (Appears first time only) Read the alert, click **I understand and agree**, then click **Yes**.
17. Click **OK** to dismiss the informative window that says your reports are published.

The post opens in your default browser. For help using the web interface, see <https://www.jmp.com/support/help/JMPPublic/14/JMPPublicHelp.shtml>.

Save as PDF

You save reports as PDF files by selecting **File > Save As > PDF File (*.pdf)** (Windows) or **File > Export > Image > PDF** (Macintosh).

Windows

- On Windows, you control pagination features such as headers, footers, and margins by selecting **File > Save As**, selecting **PDF**, and then changing settings in the Page Setup window.
- You can also control pagination by selecting **File > Page Setup**. Note that you can click **Set as Default** to apply the settings to future page setups.
- You can also control pagination by selecting **File > Print Preview**.

Macintosh

- On Macintosh, select **File > Export > Image > PDF**. The resulting PDF file contains a single PDF image with no headers or footers.

- On Macintosh, you can also select **File > Print** and then select **Save as PDF** from the PDF window. The resulting PDF file is paginated into multiple pages as needed, with headers and footers, and using the page size, orientation, scaling, and margins that you selected in the Print and Page Setup windows.

Windows and Macintosh

Through JSL, you can control pagination on both Windows and Macintosh. See the JSL Messages chapter in the *JSL Syntax Reference* for details about **Set Page Setup**, **Set Print Headers**, **Set Print Footers**, and **Save PDF**.

Save as PowerPoint

Create a presentation by saving JMP results as a Microsoft PowerPoint presentation (.pptx). Rearrange JMP content and edit text in PowerPoint after saving as a .pptx file. Sections of a JMP report are imported into PowerPoint differently. Report headings are imported as editable text boxes, and graphs are imported as images. Certain graphical elements, such as legends, can be imported as separate images. Images resize once opened in PowerPoint to fit the slide. Typically, each outline in the JMP report appears on separate PowerPoint slides. If an outline in the report is closed when saving as a .pptx file, it is excluded from the PowerPoint. Larger content can spread across multiple PowerPoint slides. Delete unwanted content from the PowerPoint file.

Note: On Windows, PowerPoint 2007 is the minimum version required to open .pptx files created in JMP. On Macintosh, at least PowerPoint 2011 is required.

1. In JMP, create the report.
2. (Windows) Select **File > Save As** and select **PowerPoint Presentation** from the Save as type list.
3. (Macintosh) Select **File > Export > Microsoft PowerPoint** and click **Next**.
4. Select a graphic file format from the list.
On Windows, EMF is the default format. On Macintosh, PDF is the default format.
5. (Optional) To avoid opening the file in the default presentation program after saving, deselect **Open the file after saving**.
6. Name and save the file (or export on Macintosh).

Tips:

- The native EMF graphics produced on Windows are not supported on Macintosh. The native PDF graphics produced on Macintosh are not supported on Windows. For cross-platform compatibility, change the default graphics file format by selecting **File >**

Preferences > General. Then, change the **Image Format for PowerPoint** to either PNG or JPEG.

- It is sometimes necessary to auto-resize column widths using PowerPoint. PowerPoint often sizes objects differently from JMP, which can lead to abnormally sized table columns.
- Drag the column separators in PowerPoint to adjust column widths for a nicer layout. You can also double-click a column border to decrease the amount of white space in the column.
- A default PowerPoint template is installed in the JMP directory's pptx folder. You can save a copy of this PowerPoint template and replace the default template with your own if you want to always use an alternate template when exporting. For example, you might want to create a German PowerPoint template that has German default fonts. See [“Custom PowerPoint Templates”](#) for details.

Custom PowerPoint Templates

PowerPoint presentations use the default JMP template. You can use a custom template by overwriting the default template file. To do this, open `JMPExportTemplate.pptx` located in one of the following locations:

`C:/Program Files/SAS/JMP/14/pptx/`

`C:/Program Files/SAS/JMPPro/14/pptx/`

`C:/Program Files/SAS/JMPSW/14/ptx/`

Then, choose your own PowerPoint template, and select **File > Save**. The next time you save JMP content as a PowerPoint, it opens with your custom template. Alternatively, create your custom template in PowerPoint first, and save it as `JMPExportTemplate.pptx`.

Note: To use the JMP default template later, make a duplicate copy on your machine before overwriting the file.

Also, you can use a custom template with a JSL script. For more information in the *JSL Syntax Reference*, see the Save Presentation section.

Save as Flash

Certain types of reports can be exported into Flash and saved as a `.swf` file. You can embed `.swf` files into Microsoft PowerPoint presentations.

The following platforms support Flash output:

- Distribution
- Profiler
- Bubble Plot

For details, see <https://www.jmp.com/support/swfhelp/en/>.

Setting the Graphic DPI

On Windows, there are several ways to set the resolution (or DPI) for exported graphics:

- To change the default DPI for all graphics, set the DPI to in the Windows Specific preferences. The Default option uses the default setting of your operating system.
- The following script lets you set the default DPI to a different value. Change the number if you want a different DPI and then run the script.

```
Pref( Save Image DPI( 600 ) );
```

To verify the default DPI after you run the preceding script, run the following script:

```
Get Preferences( Save Image DPI );
```

The Windows Specific preferences and Save Report As window show Default as the DPI after you run this script. The setting applies until you change it. On the Save Report As window, select **Always use this setting** to save your choice across multiple JMP sessions.

- For a specific graphic, set the DPI in the Save Report As window.

On Macintosh, you cannot change the default DPI, which is 72.

Save Your Analysis as a Script

After completing an analysis and receiving a report, you might want to save the process that you used to arrive at the report as a JSL script. You can save the script inside the data table, inside the report, or in a separate script window. To do this, click the red triangle menu in the report title and select the Save Script option that you prefer. See “[Save Script Menus](#)” on page 412.

Non-English versions of JMP can save scripts in either English or your local language. See “[General](#)” on page 577 in the “JMP Preferences” chapter.

Save Parts of a Report in a Graphic Format

You can save part of an analysis report window as a graphic. You can save the selection in .png, .jpg, .gif, .eps, .emf, .pdf, .tiff, and .svg formats. On Macintosh, you can save the selection in .png, .jpg, .gif, .svg, .eps, .pdf, and .pptx formats.

To save a selection, follow these steps:

1. Click the selection tool (.

2. Highlight the area that you want to save.
3. On Windows, select **Edit > Save Selection As**. On Macintosh, hold down the Ctrl key and select **File > Save Selection As**.

The Save Selection As window appears (or the Save window on Macintosh).

4. Enter the filename for the graphic.

On Macintosh, change the file extension to save the file in a format other than .png, the default format.

Note: If you use Save Selection As and create a PDF file from the selection, the PDF file has headers and footers. With JSL, you can control pagination on both Windows and Macintosh. See the JSL Messages chapter in the *JSL Syntax Reference*.

5. Change options on Windows:
 - Select the graphics file format type to which you want to save the selection. See [“Save and Share Reports”](#) on page 494.
 - Select the Image DPI Setting. 300 or higher is best for graphics that must be stretched or printed.
 - To keep your selected DPI Setting for the current session, select **Always use this setting**.
 - To avoid opening the file in the default graphics program after saving, deselect **Open the file after saving**.
 - Select **Select this filter the next time this window is invoked** to save your file type selection for the current session.

Note: If you cannot see the Select this filter option, select a folder location for saving the graphic file.

6. Click **Save**.

Tips:

- You can change the default DPI setting selection in the Windows Specific preferences from 96 to 300 DPI. The following script lets you set the default DPI to a different value. Change the number if you want a different DPI and then run the script.
`Pref( Save Image DPI( 600 ) );`
- On Macintosh, you cannot change the default DPI, which is 72.
- When you export a graph or report that contains a bitmap image to an .svg file, the image is embedded in the .svg file. The exported content is then easier to reuse in other documents.

Print Reports

To print the report in the active window, select **File > Print**. This command displays the standard window for printing. The appearance of the window depends on your operating system and printer driver.

To insert a page break for printing purposes, follow these steps:

1. Right-click the disclosure icon  in the report window.
2. Select **Edit > Page Break**.

Copy and Paste Reports

When you need to use JMP reports or data tables in another program, you can paste or drag parts of a report or table into another program. For example, you might want to send a colleague a copy of a JMP report in a Microsoft Word file.

1. Click the selection tool .
2. Click and drag (or hold down the Shift key and click) to select items in a report window or data table. Clicking near the edge of the report window selects the entire report.
3. Click the selected items and drag them from JMP to the other program. Or, copy the selected items in JMP and paste them into the other program. When you paste an element into another application, the format used depends on the application into which you paste. If you use the applications' Paste Special command, you can select a format to use, such as text (.rtf), unformatted text (.txt), or bitmap (.bmp).

Notes:

- To copy all text (no graphs) from the active report window as unformatted text, select **Edit > Copy As Text**. On the Macintosh, select **Edit > Copy As Text**.
- To copy a graph, which includes labels and axes, right-click the graph and select **Edit > Copy Graph**.
- To copy anything other than a graph, right-click and select **Edit > Copy Picture**. For example, to copy a report, right-click on the bar containing the report title and select the option.
- To copy text from a text box onto the clipboard, right-click the text and select **Copy Text**.
- To copy text from one column onto the clipboard, right-click the column and select **Copy Column**.
- To copy and entire table onto the clipboard, right-click the table and select **Copy Table**.

- The Reports preference **Transparent background in report PNG images** determines whether reports that are saved as PNG images have transparent backgrounds. The preference is deselected by default.

Create a Journal


Create a JMP journal when you want to store results and present them. One of the benefits of journaling is that you can capture an analysis and not depend on external files. Another benefit is the ability to copy and paste specific reports or graphs into the journal. This enables you to create a custom report to present to other users.

There are two types of presentations that you can create using journals:

- A static presentation embeds the output of one or more JMP reports, fixed at a moment in time. The output is similar to what you get when you save output as a PDF file. There is no data table, points cannot be selected, colored, hidden, excluded, and so on. Only cosmetic changes (fonts, axes, sizes) can be made. The benefit is that there is no dependency on external files.
- A dynamic presentation is built from outlines containing text and buttons (or links) that help you organize, hide, or reveal a set of data tables and reports. This type of journal is dynamic because you can open reports and tables and interact with them, selecting points, subsetting data, making more graphs, or rerun an analysis.

Figure 10.10 shows some of the items that you can add to a journal.

Figure 10.10 Example of a Journal



Note: Links to directories of files, windows, and all open files look like other links, so they are not included in the preceding figure.

Tips:

- You can save journals to other formats, such as Microsoft Word, HTML, PDF, and so on. See [“Save the Journal in Another Format”](#) on page 520.

- Journals support GZ compression to reduce file size. See “General” on page 577 in the “JMP Preferences” chapter. This can be particularly helpful if large data tables are embedded in the journal.
- Consider setting the Autosave Timeout value in the General preferences to automatically save open journals at the specified number of minutes. This autosave value also applies to data tables, scripts, projects, and reports.

Example of Making a Journal for a Presentation

Most people use a presentation application like PowerPoint to give presentations. With JMP journals, you can avoid using a presentation application: all your bullet points can be combined with live links and buttons to help automate the analyses that you want to show. Interactivity is also maintained in reports.

Follow this example to create a presentation using a journal.


1. Select **File > New > Journal**.
2. Right-click in the journal. Start your outline by selecting **Add Outline Item**.
3. Enter the title of the presentation “My Bivariate Demo.”

Figure 10.11 Add an Outline Item




A presentation should have outline nodes. The nodes are nested, opened, and closed in sequence, as you give the presentation.

4. Add bullet points into the outline by clicking the red triangle in the My Bivariate Demo title bar and selecting **Add Text Item**.
5. Enter the text shown in the following figure.
6. Select the **Bullet Point** check box and click **OK**.


Figure 10.12 Add Text Item

Now add a window reference as a link. These links lets you open a file with one click during the presentation.

7. Select **Help > Sample Data Library** and open Big Class.jmp.
8. Click the red triangle in the My Bivariate Demo title bar and select **Add Window Reference**.
9. Select Big Class and click **OK**.

Figure 10.13 Add a Window Reference

10. Click the window reference to verify the link.
11. Display the window reference as a button by right-clicking the link and deselecting **Underline Style**.

Figure 10.14 Change the Link to a Button

Create a New Journal

1. Close all open journals, and do one of the following:
 - To create an empty journal, select **File > New > Journal**. Or, from the JMP Starter window, select **New Journal**.
 - To create a journal from an entire report or data table, select **Edit > Journal**.
 - To create a journal from a specific report or text in a report, click and drag the selection () tool to select adjacent items in a report or data table. To select discontinuous items, press Shift and click the items with the selection () tool. Then select **Edit > Journal**.
 - To create a journal from specific text in a data table, select the text, and then select **Edit > Journal**.
 - To create a journal from most graphs, right-click on the graphic, and then select **Edit > Journal**. (Not available for surface plots and 3-D scatterplots.)

Tip: If you prefer keyboard shortcuts, hold down Ctrl (Windows) or COMMAND (Macintosh) and press J to create the new journal.

2. Select **File > Save** and save the journal in .jrn format.

Manage Links in Shared Journals

When you insert a link to a data table on your computer, the entire path to that data table is embedded in the journal. To share the journal or move it to another computer, store the linked files in the same directory as the journal or on a shared network drive. Because the files are in the same directory, the full pathname is unnecessary. Then the links are intact no matter where the journal is opened.

Tips:

- Zip the journal and supporting files so that another user can extract them to a directory. If the files remain in that directory, the links work.
- If you create a link to a sample data table, consider using the \$SAMPLE_DATA variable in the path. Likewise, you can use \$DESKTOP if the files are on your desktop or \$DOCUMENTS for your personal documents folder.
- You can edit several links at once within an outline. There is also an option to replace strings in the links. Right-click the disclosure icon next to the outline, and then select **Append Item > Edit Links**.

To create portable links in a journal

1. Put the data tables and other files that you want to reference in the same folder.

2. Save the journal in that folder.
3. Right-click at the bottom of the journal, select **Add File Reference**, select the file, and then click **Open**.

4. Right-click the link in the journal and select **Edit > Set Script**.

Notice the full file path.

```
Open("C:\Users\shlori\journals\San Francisco Traffic.jmp")
```

5. Delete everything in the string except for the file name.


```
Open("San Francisco Traffic.jmp")
```

To embed a data table in a journal

To avoid linking to an external data table, copy the data table into a script and place it in the journal. The advantage is that other users always have access to your data, and you do not need to edit links. The disadvantage is that, if you want to edit the data, you must edit the script.

1. In the data table, select **Copy Table Script** from the data table red triangle menu.

Figure 10.15 Copying a Table Script



2. In the journal, right-click and select **Add Script Button**.
3. Enter a script name in the Name box.
4. Paste the table script into the Script box and click **OK**.
5. Right-click the link and deselect **Underline Style** display the link as a button.

Add and Edit Outlines

You can group text and links in an outline and then click the gray disclosure icon to expand and collapse the group.

- To add an outline, right-click in the journal, and then select **Append Item > Add Outline Item**. You can also add nested outline levels to outline levels that you have created. (When you click the red triangle menu of a graph that you have journaled, the **Add Outline Item** option is unavailable.) Click the outline's red triangle menu and select **Add Outline Item**.
- To edit the outline heading, double-click the heading, enter the new name, and press **Enter**.
- To add text or links within an outline, click the outline's red triangle menu and select an option described in [“Journal Right-Click Options”](#) on page 517. Note that these options are not available when you click a scripted item's red triangle menu.
- To add text or links outside an outline, right-click on the journal and then select one of the options described in [“Journal Right-Click Options”](#) on page 517.
- To edit a link, right-click the link, select **Edit > Set Script**, edit the path, and then click **OK**.
- To edit the name of the link displayed in the journal, right-click the link, select **Set Button Name**, enter the new name, and then click **OK**.

Tip: On Windows, show the preceding options by holding down the Alt key and right-clicking the outline level's gray disclosure icon.

Journal Right-Click Options

Add Outline Item Groups text and links into collapsible and expandable lists.

Add Text Item Enter up to six paragraphs with the option to add a bullet or hide the text. To unhide, right-click the hidden text and deselect **Hide**.

Note: To add text outside an outline level, you can also double-click at the end of the journal and enter text in the box that appears. Click outside the box to exit the editing mode.

Add Window Reference Creates a link to a window already opened in JMP.

Add File Reference Creates a link to a file on your computer.

Add Directory of Files Creates links to all files (including non JMP files) in the selected directory.

Add All Open Files Creates outline levels and links to open files in JMP (except for the log). For example, a link to the open Big Class.jmp data table and chart is displayed below a

collapsible heading named Big Class. Files such as journals, scripts, and tutorials are grouped below a collapsible heading called *Other Files*.

Add URL Reference Creates a link to files that are delivered through an Internet protocol such as HTTP, FTP, or FILE://.

Add Script Button Creates a link to a JSL script. Right-click the link and deselect **Underline Style** to display the link as a button.

Edit Links Enables you to rename file links (for example, to remove a hard-coded path). An option to test links is also provided. If the web address is valid, nothing happens when you click Test Links. If it is not valid, an error message appears in the log. To update an invalid link, click Replace.

Size to Fit Resizes the window to ensure that button names are fully displayed.

Control the Display of Outline Levels

You can instantly control which outline levels are displayed (for example, closing all sublevels below the selected level). Click the red triangle menu for that level, select **OutlineBox**, and then select one of the Open or Close commands. For details about the Open and Close commands, see [“Access Report Display Options”](#) on page 405 in the “JMP Reports” chapter.

Tip: On Windows, show the OutlineBox options by holding down the Alt key and right-clicking the outline level’s gray disclosure icon.

Add a Graph or Graphic

PNG, GIF, JPG, BMP, and TIF files are supported in journals. Do one of the following to add a graphic to a journal:

- Copy a graph from within JMP or a graphic from another application and then select **Edit > Paste**. JMP places the graphic at the end of the journal.
- Drag and drop the graph or graphic from another window to the journal. (See [“Paste a Background Image into a Graph”](#) on page 474 in the “JMP Reports” chapter.) A blue line indicates where you can drop the graphic.

Tip: Consider resizing the graphic in an external program. Then you can insert the graphic at 100% resolution in the journal without dragging to resize the graphic.

Customize Journal Items

- To click and drag journal items to different positions, select the selection tool () , select the item, and then drag the item to the new position. A line indicates where you can drag the item.
- To adjust text wrapping, right-click the text and select **Set Wrap**. Enter the number of desired pixels per line and click **OK**. To apply the wrap to all text items, select **Set Wrap**, select **Extend this to other text boxes**, and then click **OK**.
- To modify a plot axis, double-click or drag the axis. See [“Customize Axes and Axis Labels in the Axis Settings Window”](#) on page 455 in the “JMP Reports” chapter.
- To add text or shapes anywhere in the report, use the drawing tools (Annotate, Line, Polygon, and Simple Shape). For details about the drawing tools, see [“Add Annotations and Shapes to a Report”](#) on page 478 in the “JMP Reports” chapter.
- To resize plots and graphs, do one of the following:
 - Click and drag the edge.
 - Right-click the plot or graph, and then select **Size/Scale > Frame Size**. See [“Resize Graphs”](#) on page 449 in the “JMP Reports” chapter.
- To modify the format of a numeric column, you edit the Properties pane for the display box. See [“Modify the Format of Numeric Columns”](#) on page 429 in the “JMP Reports” chapter for details.

Prevent Modifications

When a journal is opened, and you then journal another report or data table, the second report or data table is added to the end of the open journal.

To prevent modifications to a journal, right-click the blank area at the bottom of the journal and select **Lock**. Additional reports are not added to the journal (as described in the following section). JMP instead finds an open unlocked journal or creates a new journal when you select the **Edit > Journal** command again.

To unlock the journal, right-click the blank area at the bottom of the journal and deselect **Lock**.

Append Reports to a Journal

To append other reports to a report that you already journaled, open the journal and select **Edit > Journal**. If an area of an analysis window is selected, **Edit > Journal** saves only the selected area instead of the entire window.

Notes:

- The journal window has the same functions as the report window: you can click icons, click and drag, and right-click to access menus.
- When a report is journaled, the journaled copy is no longer connected to the data table. To maintain that connection, save the report as JMP report and insert a link to it in the journal.

Save the Journal in Another Format

You can save a journal in another format (such as HTML or PDF). When you save the journal as HTML, buttons and links are active when the file is viewed in a web browser.

Note: The header and footer defined in your printer setup appears in the PDF file. However, you can set the left, center, and right header and footer in a JSL script. For more information, search for the `Set Print Footers` message in the JMP Scripting Index. (Select **Help > Scripting Index** in JMP.)

Windows

1. Select **File > Save As**.
2. Select the format. See [“Save and Share Reports”](#) on page 494.
3. Click **Save**.

Macintosh

1. Select **File > Export**.
2. Select the format. See [“Save and Share Reports”](#) on page 494.
3. Click **Next**.
4. Enter a name for the file in the **Save As** box.
5. Click **Export**.

Delete Items from a Journal

1. Click the selection tool (.
2. Select the item that you want to delete and press Delete.

Create a Project

A JMP project provides a way to organize files that you use in an analysis. You can add JMP files (reports, data tables, scripts, journals, and so on) and non JMP files, such as Microsoft PowerPoint or Adobe PDF files. After you perform an analysis, the graph and report appear in the project on tabs. You can display multiple reports or graphs, display the log, and run scripts from the project. Reports and graphs remain linked to the data table.

Projects help you avoid overlapping or concealed JMP windows. You can maximize the project window to have a bigger view of the project. And when you save the project, the state of the project is saved (for example, the open reports and the layout of the window).


Create a New Project and Add Data Tables

1. To start a new project, select **File > New > Project**. A window appears that shows the untitled project.
2. Select **File > Open** and navigate to the JMP Samples/Data folder.
3. Press Ctrl and click Car Physical Data.jmp and Car Poll.jmp.
4. Click **Open**.

The data tables are added to the project.

5. Select **File > Save Project** and save the file as Cars.jmpproj.

Figure 10.16 Initial Project




Tip: When you open a file using File > Open, and a project is active, the file is added to the project automatically.

Add and Organize Bookmarks

Bookmarks provide quick access to files that you regularly open.

1. In the Window List, right-click one of the file names and select **Bookmark All**.
You can also drag the files from the Window List to the Bookmarks pane.
2. Create a group for the data tables by selecting **New Group** from the Bookmarks red triangle menu. The group organizes the files but does not move them on your computer.
3. Enter Data and click **OK**.
4. In the Bookmarks pane, select the Car data tables and drag them into the Data group.

Figure 10.17 Bookmarked Files




Rearrange Reports

You can rearrange reports to display them in a separate pane. As you drag the report tab, zones appear that show you where to place, or “dock”, the report.

1. In Car Physical Data.jmp, run the Contingency script.
2. In Car Poll.jmp, run the Distribution script.


The data tables and reports appear in tabs.

Figure 10.18 Tabbed Reports




3. Drag the Distribution report tab to the right until the *Dock right* zone appears on the far right.

Figure 10.19 Dragging a Report



4. Drop the report into the *Dock right* zone.
The tab appears in a new pane.


Figure 10.20 Report in New Pane



5. Drag the Contingency tab to the middle of the Distribution report.

6. When the *Dock tab* zone appears, drop the report.

Figure 10.21 Docked Report Tabs



Tips:

- Keyboard shortcuts that work in JMP windows outside of projects work the same in projects. For example, press Ctrl and then W to close a selected pane or press Ctrl and then S to save a document.
- If the data table associated with a report is updated on your computer, the report in your project is updated when you reopen the project.

Save Files in a Project

When you modify a file (for example, a data table or script) inside a project, an asterisk appears on the tab to indicate that the file is not saved. Select **File > Save** and save the file to your computer. Then, select **File > Save Project** to save the project.

You can also create and save new files from within the project.

1. Follow step 1 through step 4 in [“Create a New Project and Add Data Tables”](#) on page 521 to create a project.
2. In the project, select the Car Poll.jmp tab.
3. Select **Tables > Subset**.
4. Select **Subset by**.
5. Select country from the Columns list and click **OK**.

Three new data tables subset by country are created in the project. Notice the asterisk on the tab of each new data table.

Figure 10.22 New Subset Data Tables

Car Physical Data

Car Poll

country...merican*

country...uropean*

country...apanese*

country=Japanese

country Japanese

Notes Example data for category

Source

Distribution

Contingency

Partition

Multiple Cor...nce Analysis

Multiple Cor...tary Variable

	sex	marital status	age	size	type		
1	Male	Single	36	Small	Sporty		
2	Male	Married	23	Small	Family		
3	Male	Single	34	Medium	Family		
4	Male	Single	25	Small	Sporty		
5	Female	Single	27	Medium	Family		
6	Male	Married	28	Small	Family		

6. Select each new tab, select **File > Save**, and save the file on your computer.

Tip: If you plan to share the project, save the data table in the same folder as (or in a subfolder of) the project.

7. Select **File > Save Project** to save the data tables in the project.

Save Files in a Different Format and Save to the Project

You can save a graph in another format (such as Interactive HTML or PowerPoint) and then bookmark it in the project.

1. Select **File > New > Project** to create an empty project.
2. Select **File > Open**, navigate to the JMP Samples/Data folder, and open Big Class Families.jmp.
3. Run the Graph Builder script.
4. (Windows) Select **File > Save As** and select **PowerPoint Presentation** from the Save as Type list.

Tip: Select **Bookmark in project** to add a bookmark to the file.

Navigate to the desktop and click **Save**.

The PowerPoint file opens automatically.


5. (Macintosh) Select **File > Export** (Macintosh) and select **Microsoft PowerPoint**.

Click **Next**, navigate to the desktop, and then click **Export**.

The PowerPoint file opens automatically.

6. In JMP, from the Bookmarks red triangle menu, select **Add Files**, navigate to the **Graph Builder.pptx** file that you created, and then click **Open** (Windows) or **Choose** (Macintosh).

The PPTX file is added to the Bookmarks pane.

Figure 10.23 Bookmarked PPTX File


Move Files to a Project

Suppose you generated graphs and reports from open data tables and you want to put all the files in a new project. The Move to/from Project option in the Window menu enables you to quickly combine open windows into a project. You can move windows to a new project or move to windows to an open project.


1. Select **Help > Sample Data Library**.
2. Open **Big Class Families.jmp**.
3. Run the Distribution, Text Explorer, and Graph Builder scripts.
4. From any window, select **Window > Move to/from Project**.
5. Leave Source Project as "(None)" because you are not moving files from another project.
6. Leave Destination Project as "(New Project)" because you want to put the files in a new project.
7. Select the check box next to **Big Class Families.jmp**.

The graphs associated with the data table are also selected.

8. Click **Bookmark** next to Big Class Families.

A bookmark to the data table is included in the project.


Figure 10.24 Moving Files to a New Project



9. Click **OK**.

A new project with the selected files and bookmark appears.

Figure 10.25 New Project



Share the Project

Sometimes you want to archive a project and share it with others. JMP zips the files in the project and saves the state of the project (the bookmarks, open panes, pane sizes, and so on).

When other users open the archived project on their computer, the links are resolved as follows:

1. If the file is in the same folder as the project or in a subfolder, the link contains a relative path, such as `My Data/Corn Trials.jmp`.
2. If the file is in a directory that JMP represents as a path variable (such as the desktop or documents directory), the links contain the path variable (for example, `$DESKTOP/Corn Trials.jmp`). See the Types of Data chapter in the *Scripting Guide* for more information.
3. Otherwise, the link contains an absolute path, such as `C:/2017Data/Corn Trials.jmp`.

Caution: An absolute path does not work on other users' computers unless their file system is set up like yours.

To Archive a Project

1. Make sure the project is saved.
2. Select **File > Archive Project**.
3. Navigate to the folder where you want to save the project files.
4. Click **Save**.

To Unarchive a Project

1. Use Windows Explorer or Macintosh Finder to create the folder in which you want to extract the files.
2. Open the archive in JMP.
3. Select the folder that you just created and click **Extract**.

Projects Compatibility

When you open a project created in JMP 13 or earlier, the project is renamed with the `_Original` suffix. JMP imports the project and creates a log that explains which items could not be imported. For example, URLs, database queries, and SAS stored processes cannot be imported.

JMP 14 projects cannot be opened in JMP 13 or earlier versions of JMP.

Save JMP Sessions


Each time you use JMP is called a *session*. A *saved session* is a JSL script that re-opens documents and re-runs analyses to restore JMP's state when the session script was saved. A saved session can help get you back to a previous state without having to manually re-open files and re-run analyses.

If you are an advanced user, it is important to understand what session information is preserved in a saved session. Any documents (such as data tables, scripts, and journals) that have been saved are re-opened. JMP windows that support script saving are re-run (equivalent to clicking the red triangle in a report and selecting **Redo > Redo Analysis**). Side effects of running scripts, such as global variable values or custom windows, are not saved. The state of highly interactive analyses is also not saved.

Save Sessions upon Exiting

The most common use of saved sessions is to save the state when JMP exits so that it can be restored when JMP restarts. By default, JMP asks whether you would like to save the state of your session each time you exit the program (Figure 10.26). This enables you to quit JMP, and then return to it later without having to open the files with which you were previously working.

Figure 10.26 Saving Session upon Exiting



To always save the session upon exiting, select **Do not ask me again about saving the session** and click **Yes** or **No**. This option also prevents JMP from saving the session upon exiting,

You can change this option later in Preferences:

1. Choose **File > Preferences**.
2. Select the **General** icon.
3. Next to the **Save the session when exiting** option, choose when you want JMP to save the session. Always, never, and prompt whether you want to save are the options.

Save Sessions Manually

You can also save a session to a location of your choosing and continue working, so you can restore the saved state whenever you like. Manually saving sessions is useful when you want more control of session saving and restoring. This option is especially helpful when you want to maintain multiple independent session states. Each state has a different set of files and analyses.

To create a script of a JMP session

1. Select **File > Save Session Script**.
2. Enter the name of your script in the window and click **Save**.

Another way of manually saving a session is by creating a journal of each session. A journal can be a notebook-style or project-style file. With it, you can collect references to files in a project, develop presentation launch pads, document projects, and store many scripts in one place. See [“Create a Journal”](#) on page 512 for details.

To create a journal of a JMP session

1. Open the files that you would like to include in the journal.
2. Select **File > New > Journal**. Or, to append your open files to an existing journal, open that journal.
3. Right-click in the empty journal and select **Add All Open Files**.

Save a Log Window

Selecting **View > Log** displays a window that monitors JMP activities, such as JSL statements as they execute and script errors. You might also encounter instances where running a formula, matrix, or another operation writes information of interest to the log window.

To save a log


1. Open the Log window.
2. Select **File > Save As**.
3. (Windows only) To open the log automatically when text is added to it, select **File > Preferences > Windows Specific**. In the **Open the JMP Log window** list, select **whenever text is added**.

Chapter 11

Extend JMP Create Dashboards

JMP is an extensible program that lets you broaden its functionality to create your own JMP components. With Dashboard Builder, you combine reports into a dashboard, a visual tool that lets you run and present reports on a regular basis. No JSL knowledge is required. Start with a template, click report components, insert graphs and pictures, and the dashboard is done. You can also combine windows outside Dashboard Builder to create dashboards.

Figure 11.1 A Dashboard with Two Reports



Contents

Combine Reports by Creating a Dashboard	533
Example of Creating a Dashboard with Two Reports	533
Details about Using the Dashboard Builder	534
Dashboard Builder Red Triangle Options	535
Sample Dashboards	537
Edit a Dashboard	537
View a Running Dashboard	540
Example of Combining Windows to Create a Dashboard	543
Example of Adding Selection Filters to a Dashboard	544
Example of Creating a JMP Query Dashboard and Add-In	546
Example of Creating a Dashboard from Two Data Tables	548

Combine Reports by Creating a Dashboard

With Dashboard Builder, you combine reports to create your dashboards without writing JSL scripts. Similar to Application Builder, Dashboard Builder has a drag-and-drop interface but with pre-configured display boxes. In Dashboard Builder, the display boxes do not require customization as they do in Application Builder. You can put reports and graphs in tabs, embed database queries, save the dashboard as an add-in, and more.

You can also quickly create dashboards by combining several open windows using the Window > Combine Windows option. For example, you might combine two reports and a data table to arrange them on a dashboard. See [“Example of Combining Windows to Create a Dashboard”](#) for an example.

Example of Creating a Dashboard with Two Reports

Suppose that you created two reports and want to run the reports again the next day against an updated set of data. This example shows how to create a dashboard from the reports.

1. Select **Help > Sample Data Library** and open *Hollywood Movies.jmp*.
2. To create the reports, run the table scripts named “Distribution: Profitability by Lead Studio and Genre” and “Graph Builder: World and Domestic Gross by Genre”.
3. From any window, select **File > New > Dashboard**.

Templates for common layouts appear.

4. Select the **2x1 Dashboard** template.


A box with room for two reports appears on the workspace.

5. In the Reports list, double-click the report thumbnails to put them on the dashboard (Figure 11.3).

6. Select **Preview Mode** from the Dashboard Builder red triangle menu.

A preview of the dashboard appears. Notice that the graphs are linked to each other and the data table. They also have the same red triangle options as the Distribution and Graph Builder platforms.

Figure 11.2 A Dashboard with Two Reports



7. Click **Close Preview**.

8. In Dashboard Builder, select **File > Save**, and then save the file as a .jmpapp file.

Users who have JMP can open the data table and double-click this file to display the dashboard. Note that the .jmpapp file cannot be edited.

9. Return to the Dashboard Builder window, select **File > Save As**, and then save the file as a .jmpappsource file.


The dashboard is saved in a file that you can edit in the future.

Note: You might also want to save the dashboard as an add-in. Users then view the dashboard by selecting a menu item in the main Add-Ins menu instead of opening the .jmpapp file. See [“Example of Creating a JMP Query Dashboard and Add-In”](#) on page 546 for details.

Details about Using the Dashboard Builder

Figure 11.3 shows a dashboard in development. The two reports in the left pane were generated from the Hollywood Movies.jmp sample data table. Those reports were added to the right pane. “Hollywood Movies.jmp” is displayed in a text box that was added to the dashboard and centered using the toolbar buttons.

Figure 11.3 The Dashboard Builder Window



Dashboard Builder Red Triangle Options

The Dashboard Builder red triangle menu provides options such as running the dashboard, previewing the dashboard, and saving the dashboard as an add-in.

Run Dashboard Starts the dashboard.

Preview Mode Displays a preview of the dashboard. Click **Close Preview** on the dashboard to return to the dashboard mode.

Start Over Remove objects from the workspace and select a new template.

Show Grid Displays dotted grid lines on the workspace. Selected by default.

Show Properties Shows or hides the Objects and Properties panels for editing display boxes. See the Creating Applications chapter in the *Scripting Guide* for details about editing properties.

Auto Scroll Automatically scrolls horizontally or vertically as you drag an object near the edges of the workspace. Selected by default.

Dashboard Mode Deselect to display the dashboard in Application Builder, where you can fully customize the application and write scripts. See the Creating Applications chapter in the *Scripting Guide* for details. Select **Dashboard Mode** to return to the dashboard.

Source Panel Shows or hides the Sources panel (the left column in which report components are displayed) and categorizes the icons. Both settings are selected by default.

Save Script Contains options that enable you to save a script that reproduces the report to several destinations.

To Data Table Saves the script to the data table that was used to produce the report. This enables you to run the script again from the data table to recreate the results.

To Journal Saves a link in a journal window that runs the script for the analysis. If a journal window is already open, the script is added to that journal window. The script contains the path to the data table. Note that if the data table cannot be found, the script does not run.

To Script Window Opens a script editor window and adds the script to it. If a script window is already open, the script is added to the bottom of that open window.

To Add-In Lets JMP users install the application and launch it from a JMP menu. See the Creating Applications chapter in the *Scripting Guide* for details.

To Template Saves the application as a template from which you can create new dashboards. The templates are saved in the following locations based on your operating system and JMP version:

- Windows (JMP): "/C:/Users/<username>/AppData/Roaming/SAS/JMP/<version number>/DashboardTemplates"
- Windows (JMP Pro): "/C:/Users/<username>/AppData/Roaming/SAS/JMPPro/<version number>/DashboardTemplates"
- Windows (JMP Shrinkwrap):
"/C:/Users/<username>/AppData/Roaming/SAS/JMPSW/<version number>/DashboardTemplates"
- Macintosh: "/Users/<username>/Library/Application Support/JMP/<version number>/DashboardTemplates"

Sample Dashboards

Examples of dashboards are shown when you open Dashboard Builder. You can modify these samples instead of starting with an empty dashboard. The dashboards are also installed in the JMP Samples/Dashboards folder.

The following sample dashboards are available:

Instant Dashboard.jmpappsource Combines two Multivariate reports (Principal Components/Factor Analysis and T Square with All Principal Components).

Six Quality Graphs Dashboard.jmpappsource Creates three Control Charts, a Distribution report, and a Capability Analysis report.

Edit a Dashboard

[“Example of Creating a Dashboard with Two Reports”](#) on page 533 shows how to create a dashboard from two reports. This section shows how to arrange those reports and preview the final dashboard.

Rearrange Reports in Dashboard Edit Mode

To help you rearrange reports while editing a dashboard, the outline around a report includes drop zones. When you drag the report into a different area of the box, a portion of the box is highlighted. The highlight shows where you can drop the box.

Figure 11.4 shows how to create tabbed reports. To put the Distribution report inside a tab, drag the report over the other report until the upper right corner of the bar chart report is highlighted. The Distribution report appears in a tab on top of the other report.

To remove a tabbed report, click the middle of the report and drag it outside of the tab.

Figure 11.4 Working with Tabbed Reports in Dashboard Edit Mode




Figure 11.5 shows an example of placing a data table inside the bottom border of the report.

To display the data table *below* the report instead of inside it, drag the Data Table box onto the dashboard below the report. The box snaps inside the bottom border of the report.

Figure 11.5 Displaying a Data Table Inside a Report





Figure 11.6 shows a data filter that appears to the left of a report.


Figure 11.6 Adding a Data Filter to the Left of a Report



Format Text in a Text Box

When you edit a dashboard, you can format text in a text box. Drag the text box to the dashboard and click the middle of the text box. Formatting options appear (Figure 11.7).

Figure 11.7 Formatting Options for a Text Box



Preview the Dashboard

When you edit the dashboard, you can see a preview of the final dashboard by selecting **Preview Mode** from the Dashboard Builder red triangle menu. Previewing the dashboard is particularly helpful when testing interactive elements such as data filters and tabbed reports.

Note that if you resize panes in preview mode, your changes are not saved.


View a Running Dashboard

When you view a running dashboard, the same red triangle options that you find in JMP platforms are available in the reports. Dashboard Builder also provides several other options.

View a Summary of the Report

A report that contains graphs and statistics can grow fairly large. To view only the graphs while running the report, select the top red triangle in a report and then select **Report View > Summary**. The report shown in Figure 11.8 originally showed parameter estimates. In the Summary view, only the graphs are shown.


Figure 11.8 Viewing a Summary of the Report



Rearrange Reports in a Running Dashboard

You rearrange reports in a running dashboard by dragging the reports into highlighted drop zones. The drop zones indicate where you can place the report. Figure 11.9 shows an example of moving a report into a tab. The Distribution report is dropped inside the “Dock tab” drop zone to place it on the first tab.

Figure 11.9 Creating Tabbed Reports in a Running Dashboard




To remove a tabbed report, click the middle of the report and drag it outside of the tab.

Maximize a Report in a Running Dashboard


To see only a specific report while running a dashboard, select the report’s **Maximize Tab** box (Figure 11.10). Note that the box is named Maximize Tab even if the reports are not in tabs.

Figure 11.10 Maximizing a Tab




To restore the report to its original size, select the **Restore Tab** box (Figure 11.11).

Figure 11.11 Restoring a Maximized Report



Resize Reports in a Running Dashboard

The thick gray line that appears between reports in a dashboard is called a *splitter*. Drag the splitter to resize the panes. When the pane is too wide to display the enclosed report, the pane closes. Drag the splitter from the outer edge of the dashboard to see all reports again. Figure 11.12 shows the collapsed and expanded reports.

Figure 11.12 Resizing Panes in a Running Dashboard

You can also drag the edge of a graph. The graph widens as far as the width of the window and the other reports allow.

Share Reports with Users Working Outside JMP

You can share reports with users working outside JMP by saving a dashboard as interactive HTML. First, select **Run Dashboard** from the Dashboard Builder red triangle menu to run the dashboard. In the running dashboard, select **File > Save As** and then select **Interactive HTML with Data** from the list. The reports are saved in a web page that also contains the data. Email the web page to users or publish the page on a website. Users then explore the data as they would in JMP. See [“Save as Interactive HTML”](#) for details.

Edit a Platform Script

A dashboard consists of a JSL script, which you can edit in Dashboard Builder. For example, you might edit the script for the Multivariate platform to show the scatterplot matrix or to use different columns.

Right-click the object for a platform in the dashboard and select **Edit Platform Script**. The script opens in a script editor window.

After you edit the script and click OK, the object on the workspace is updated.

Example of Combining Windows to Create a Dashboard

Instead of creating a dashboard in Dashboard Builder, you can combine open windows to create a dashboard. Dashboard Builder provides more options. However, combining windows is a quick way to create a simple dashboard.

This example shows how to combine two reports from Hollywood Movies.jmp into a dashboard.

1. Select **Help > Sample Data Library** and open Hollywood Movies.jmp.
2. Run the first two table scripts
3. Select **Window > Combine Windows**.
4. In the Combine Windows window that appears, make the following changes:
 - In the Combine column, select the two report windows.
 - In the Filter By column, select **Hollywood Movies - Distribution**.
5. Click **OK**.

The two reports are combined into one window. Notice the filter icon  at the top of the Distribution report. When you select a bar in one of the histograms, the corresponding data in the Graph Builder graph and in the data table are selected.

You can rearrange the reports as shown in [“Rearrange Reports in a Running Dashboard”](#) on page 541.

Tips:

- To combine reports on Windows, you can also select Combine Windows from the Arrange Menu option in the lower right corner of JMP windows.
- In the Combine Windows window, select **Summary Report View** to see only the graphs in a report and omit the statistics.

Example of Adding Selection Filters to a Dashboard

In a dashboard that contains several reports, you can select data in a report and then view only that data in other reports contained in the same window. This example shows how to add selection filters to the primary report when you edit a dashboard.

Open Reports and Create a Dashboard


1. Select **Help > Sample Data Library** and open Hollywood Movies.jmp.
2. To create the reports, run the table scripts named “Distribution: Profitability by Lead Studio and Genre”, “Graph Builder: World and Domestic Gross by Genre”, and “Bubble Plot: Theaters Open Week by Domestic Gross”.
3. From any window, select **File > New > Dashboard**.
Templates for common layouts appear.
4. Select the **2x1 Dashboard** template.
A box with room for two reports appears on the workspace.

5. In the Reports list, double-click the Graph Builder and Distribution report thumbnails to put them on the dashboard.

Add and Use Selection Filters

1. Right-click the center of the left report (Graph Builder) and select **Use As Selection Filter**.
2. To add another report as a second selection filter, click the Bubble Plot thumbnail and drag it into the blue line around the Graph Builder graph.


Figure 11.13 Dragging the Bubble Plot into the Graph Builder Graph



A filter icon appears on both thumbnails.

3. Select **Preview Mode** from the Dashboard Builder red triangle menu.
4. Select one of the bars for the Fantasy genre in the left report.

Figure 11.14 Filtering Data



In the right report, you can see that Warner Bros and Independent studios produced the most fantasy movies. In the bottom report, you can see that Harry Potter was the most profitable fantasy movie.

Example of Creating a JMP Query Dashboard and Add-In

Suppose that you used JMP Query Builder to import portions of two data tables into JMP. A dashboard displays reports of the data. You want to create an add-in that queries the data and shows the updated reports on a dashboard.

Build the Query

1. Select **Help > Sample Data Library** and open **Hollywood Movies.jmp**.
2. Select **Tables > JMP Query Builder**.
3. Click **Build Query**.
4. In the Available Columns list, double-click **t1.Movie Name**, **t1.Rotten Tomatoes Score**, **t1.Audience Score**, and **t1.Theaters Opening Wknd** to add them to the Included Columns tab.
5. Click **Run Query**.


The queried data appears in a new data table. Note the Source table script. When you open the dashboard, JMP runs this Source script to query the data in **Hollywood Movies.jmp**.

6. In the new data table, run the **Graph Builder: Scores by Opening Weekend** table script to create a report.

Create the Dashboard


1. From the report window, select **File > New > Dashboard**.
2. Select the **Blank Dashboard** template.
3. Double-click the **Data Filter(Local)** box in the left pane to add it to the dashboard.
4. Double-click the Graph Builder report in the left pane to place it next to the local data filter.

Figure 11.15 Dashboard for Hollywood Movies



Create and Run the Add-In

1. From the Dashboard Builder red triangle menu, select **Save Script > To Add-In**.
Add-In Builder opens.
2. Next to Add-In name, type Hollywood Movies Dashboard (the add-in filename).
3. Click the **Menu Items** tab and type Hollywood Movies Dashboard next to **Menu item name** (the name of the add-in menu item).
4. Click **Save** and save the add-in to your desktop.
The add-in is saved and installed in your Add-Ins menu.
5. Click **Close** on the Add-In Builder window.
6. From the JMP main menu, select **Add-Ins** and select **Hollywood Movies Dashboard**.
The Hollywood Movies.jmp data table is queried, and the dashboard opens to show the local data filter and updated report.

Figure 11.16 Hollywood Movies Add-In

Example of Creating a Dashboard from Two Data Tables

The graphs or reports in a dashboard can be created from multiple data tables. The data table used for the first graph on the dashboard is considered the current data table by default. This gives the user the flexibility to use any current data table to create the graph or report. The dashboard author can also hard-code the path. Specifying the name gives the dashboard author control over which data table is used.

1. Select **Help > Sample Data Library**, open *Big Class.jmp*, and run the Bivariate script.
2. Select **Help > Sample Data Library**, open *Hollywood Movies.jmp*, and run the Distribution script.
3. From any JMP window, select **File > New > Dashboard**.
4. In Dashboard Builder, select the **2 x 1 Dashboard** template.
5. Double-click the Distribution graph to add it to the dashboard first.

By default, this graph uses whatever data table is the current data table. In this example, *Hollywood Movies.jmp* stored in the *Samples/Data* folder is the current data table.

6. Double-click the Bivariate graph to add it to the dashboard.

You are prompted to determine whether the first graph uses the current data table or whether you want to hard-code the path to the data table (reference the table by name) in the dashboard.

7. Select **Reference table by name** to make sure the specified data table is always used to create the graph.

8. Click **OK**.

In this example, Hollywood Movies.jmp in the Samples/Data folder will always be used as the current data table for the first graph, despite the current data table that is open.


Tip: Sometimes a named data table cannot be found when the dashboard is run. This is particularly common when the dashboard is moved to a different computer. You can either open the data table before running the dashboard or run the dashboard and select the data table when prompted.

To Change the Location of the Data Table

After you assign the location of the data table (current data table or name), you can change the setting in the dashboard Objects and Properties panes.

1. Select **Show Properties** from the Dashboard Builder red triangle menu.

Figure 11.17 The Objects and Properties Panes



2. In the Objects pane, select **DataTable1**.
3. In the Properties pane, change the Location as shown in Figure 11.17.

For example, if you change the Name location to Current Data Table, the selected graph on the dashboard is based on the current data table.

Note: The Location value of Current Data Table applies only when you are running the dashboard. When you are editing the dashboard, Dashboard Builder uses the full path to locate the data table.

Chapter **12**

Personalize JMP

Customize Menus and Toolbars

This chapter describes how to customize JMP menus and toolbars to show only the commands that you need. For example, you might remove the SAS option in the File menu if you do not use SAS. Or you might assign a shortcut key to the Run Script command.

Customizing JMP also lets you set up JMP for groups with special interests. If one group does not design experiments, you could remove DOE from the JMP menu.

Contents

Personalize Toolbars and Menus on Windows.....	553
Change Customization Sets.....	554
Create Toolbars.....	555
Create Main Menus.....	558
Create Menu Items and Toolbar Buttons.....	559
Rearrange Toolbars.....	563
Copy and Paste Menus, Menu Items, Toolbars, and Buttons.....	563
Rearrange Custom Menus, Menu Items, and Buttons.....	565
Delete Custom Items.....	566
Show and Hide Items.....	567
Import Customizations.....	568
Remove Customizations.....	568
Personalize Toolbars on Macintosh.....	570
Personalize Menu Items on Macintosh.....	571
Customize Menus and Toolbars for an Add-In.....	572


Personalize Toolbars and Menus on Windows

Toolbars consist of buttons that execute commands and dividers that help you organize the buttons. In Windows, there are many ways to personalize toolbars. For example, you can create, rename, hide, and modify toolbars or buttons. You can also rearrange or delete toolbars and buttons that you create.

Menus consist of commands, submenus, and separators. As with toolbars and buttons, you can create, rename, hide, and modify menus. You can also rearrange or delete menus and menu items that you create.

You personalize toolbars and menus in the Menu Editor. The names of modified items are formatted to indicate which items were created, modified, or hidden, and which items are unsaved, as shown in Figure 12.1.

Figure 12.1 Menu Editor Options



Change Customization Sets

JMP gives you the flexibility to specify which users see your customized toolbars and buttons. Your changes are saved in a text file with the .jmpcust extension called a *customization set*. By default, your customizations are shown only to the current user; other users who log on to the computer and open JMP do not see your personal toolbars and menus.

All customization sets include the built-in JMP buttons and menus. You can also base customization sets on other customization sets. For example, you might create a new customization set that shows the JMP add-in menus and toolbars along with your modifications.

When you modify the **Current user** customization set, JMP creates a backup file of the set. The file is located in your Windows Users folder within the JMP, JMPPro, or JMPSW folder.

C:/Users/<user name>/AppData/Roaming/SAS/JMP/14/

When you modify the **All users** customization set, JMP creates a backup file of the set. The file is located in the Windows All Users folder within the JMP, JMPPro, or JMPSW folder.

C:/Users/All Users/SAS/JMP/14/

The All Users folder does not appear when you try to browse for it, so you must type the path into the Windows Explorer address field.

Note: To find the customization set files in Windows Explorer, show all hidden files in the Windows Explorer Folder Options. See your operating system documentation for details.

To change the customization set, follow these steps:

1. Select **View > Customize > Menus and Toolbars**.

The Menu Editor appears.

2. Click **Change**.

When you try to change the customization set, and changes to the selected set are not saved, you are prompted to save the changes. Click **Save Changes**.

3. Select the customization set in the Customization Set to Modify area. (By default, changes apply only to the **Current user** customization set.) “[Customization Set Options](#)” on page 555 describes the options.
4. (Optional) To change the set on which the selected customization set is based, select the set in the Starting Set area. (Not available for the *All users* customization set.) “[Customization Set Options](#)” on page 555 describes the options.
5. Click **OK**.





Application Builder Shows icons for commands in Application Builder.



Data Table Shows icons for performing common tasks in a data table, such as opening the Data Filter, Fit Model, and Recode windows.



Script Editor Shows icons for running, debugging, and reformatting scripts.



Report Shows icons for opening the Local Data Filter, Column Switcher, and saving a script to the data table.



Create your own toolbars for frequently used commands that are not included in the default toolbars. You assign a command to the button and can add other properties such as shortcut keys, icons, and JMP Scripting Language (JSL) scripts.

When you want to create a toolbar based on an existing toolbar, make a copy of the existing toolbar and then change settings as necessary. See [“Copy and Paste Menus, Menu Items, Toolbars, and Buttons”](#) on page 563 for details.

Step 1: Create the Toolbar

1. Select **View > Customize > Menus and Toolbars**.
The Toolbars list appears on the left.
2. (Optional) Change the customization set to control which users see your customizations. See [“Change Customization Sets”](#) on page 554 for details.
3. With the Menu Editor still opened, right-click one of the toolbars, such as **File_Edit**.
Select any toolbar, because all new toolbars appear at the end of the Toolbars list.
4. Select **New Toolbar**.
The toolbar is inserted at the end of the list. The toolbar includes an untitled button, because all toolbars must have at least one button.

Step 2: Specify the Caption and Internal Name

Toolbars have several basic properties:

- The caption appears in the **View > Toolbars** list, which lets you show or hide the toolbar. Give each toolbar a unique name. JMP merges toolbars with the same name after you close and reopen the Menu Editor.
- The internal name, which is case insensitive. JMP identifies the location of an item by its internal name rather than its caption.

To specify these toolbar properties, follow these steps:

1. With the Menu Editor still opened, select the toolbar.
The General properties appear on the right.
2. Enter the internal name next to **Internal name**.
3. Enter a unique name for the toolbar or button in the **Caption** box.
4. (Optional) To specify the translation for the caption, do the following:
 - Click the **Localize** button for the item that you want to customize.
 - Select the language.
 - Enter the translation next to **Text**.
 - Click **OK**.
5. (Optional) Click **Hidden** to keep the toolbar hidden after creation.
6. Customize the untitled button as described in [“Create Menu Items and Toolbar Buttons”](#) on page 559.
7. Click **Save** to save your changes.

Create Main Menus

Add your own menu items to the main menu bar in JMP. These menus appear before or after menus such as **File**, **Edit**, and **Tables**. An untitled command is inserted automatically in the menu, because all menus must have at least one command.

When you want to create a main menu based on an existing menu, make a copy of the existing menu and then change settings as necessary. See [“Copy and Paste Menus, Menu Items, Toolbars, and Buttons”](#) on page 563 for details.

To create a main menu

1. Select **View > Customize > Menus and Toolbars**.
The Main Menu list appears on the left.

2. (Optional) Change the customization set to control which users see your customizations. See [“Change Customization Sets”](#) on page 554 for details.
3. Right-click the menu next to which you want to add a new menu.
4. Select **Insert Before** or **Insert After**.
An untitled menu and a menu item are added to the list.
5. Complete [“Step 2: Specify the Caption and Internal Name”](#) on page 558 to rename the main menu.
6. Customize the menu item as described in [“Create Menu Items and Toolbar Buttons”](#) on page 559.
7. Click **Save** to save your changes.

Create Menu Items and Toolbar Buttons

Menus consist of the following menu items:

- Commands are the items that you click to execute a command (such as Data Table and Script).
- Submenus are menu items that you click to reveal more menu options. An example of submenu is New inside the top-level File menu. New is also a submenu because it contains commands (such as Data Table and Script).
- Separators () are lines that divide or group commands and submenus.

The button on a toolbar is considered a type of command, so you also complete the following steps to create new toolbar buttons.

When you want to create a menu item or button based on an existing item, make a copy of the existing item and then change settings as necessary. See [“Copy and Paste Menus, Menu Items, Toolbars, and Buttons”](#) on page 563 for details.

Step 1: Create a New Menu Item or Button

1. Select **View > Customize > Menus and Toolbars**.
The Menu Editor appears.
2. (Optional) Change the customization set to control which users see your customizations. See [“Change Customization Sets”](#) on page 554 for details.
3. Right-click where you want to add the menu item or button.
A list of possible locations appears.
4. Select **Insert Before** or **Insert After**.
The Specify Type window appears.

Figure 12.2 Specify Type Window

5. Do one of the following:
 - To create a button, select **Command**.
 - To create a menu within a menu, select **Submenu**. (Not available for buttons.)
 - To create divider between menu items or toolbar buttons, select **Separator**.
6. Click **OK**.

The new untitled button, submenu, or separator is added.

Step 2: Specify the Caption, Tooltip, and Internal Name

Buttons have several basic properties:

- The caption appears in the View > Toolbars list, which lets you show or hide the toolbar. Give each toolbar a unique name. JMP merges toolbars with the same name after you close and reopen the Menu Editor.
- The tooltip appears when you place the cursor over a menu item or button.
- The internal name, which is case insensitive. JMP identifies the location of an item by its internal name rather than its caption.

Submenu items include many of the same General properties as buttons, except that submenu items do not have tooltips.

To specify these properties, follow these steps:

1. With the Menu Editor still opened, select the menu item or button.

The General properties appear on the right.
2. Enter the internal name next to **Internal name**.
3. Enter a unique name for the menu item or button in the Caption box.
4. Enter a description for button in the Tip box.
5. (Optional) To specify the translation for the caption or tip, do the following:
 - Click the **Localize** button for the item that you want to customize.
 - Select the language.
 - Enter the translation next to Text.
 - Click **OK**.
6. Customize the untitled button or menu item as described in the following procedure.

Step 3: Assign Functionality

Clicking a menu item or button either executes a predefined command or runs a JSL script. The script can be stored in a separate file, or you can enter the JSL in the Run this JSL area of the Menu Editor. If users have access to a central location, such as a network, you typically want to run the script from that location. This also simplifies giving users access to updated scripts. Otherwise, store the JSL in the menu item or button definition.

To associate a menu item or button with an add-in JSL script, you have two options:

- Select **Run JSL in this file**, and then browse to find the external file.
- Type the relative path to the JSL script, and select the add-in from the **Use add-in home folder** list. For example, the following command runs the `mds_application.jsl` script from the selected add-in:

```
$ADDIN_HOME(com.jmp.mdswithr)/mds_application.jsl
```

In addition, you can select **Use the “Here” namespace for unqualified JSL variable names** if you include namespaces in the internal or external JSL script. See the Building Blocks chapter in the *Scripting Guide* book for details about namespaces.

To assign this functionality, follow these steps:

1. With the Menu Editor still opened, select the menu item or button that you want to modify.
The Action properties appear on the right.
2. Select the action that you want to execute.
3. To run an internal JSL script, delete the placeholder text `print(“Not implemented.”);` in the **Run this JSL** area and enter the JSL.
4. (Optional) If your internal or external JSL script includes namespaces, select **Use the “Here” namespace for unqualified JSL variable names**.
5. Click **Save** to save your changes.

Step 4: Show an Icon on the Menu Item or Button (Optional)

New menu items have no icon next to the item. New buttons show up as blue squares on the toolbars. You can assign a descriptive icon to the menu item or button. The graphic can reside on your computer or in an add-in folder. `.ico`, `.png`, `.jpg`, and `.bmp` graphics are supported.

Assigning an icon to a button is particularly important. Otherwise, the user must view the button’s tooltip to see what the button does.

To show an icon on the menu item or button, follow these steps:

1. With the Menu Editor still opened, select the menu item or button.
The Icon properties appear on the right.

2. Select one of the following options:

None Select this option to show a blue square instead of an icon.

Built-in icon Select this option to show an icon that JMP provides, and then select the icon from the list.

Use image from file Select this option to show an image that you created. Click **Browse**, select the graphic, and then click **OK**.

Use add-in home folder Select this option to display an icon from an add-in to the left of the menu item. After you select the checkbox, select the add-in, click **Browse**, and then select the icon. The path to the image is displayed in the **Use image from file** field. The image can be an ICO, PNG, JPG, or BMP graphic.

3. Click **Save** to save your changes.

Step 5: Assign a Shortcut Key (Optional)

A shortcut key executes an action so that you do not have to select the menu item or click the button on the toolbar. This option is also helpful when the button's toolbar is not shown, but you still want to execute the action.

Shortcuts begin with Ctrl, Ctrl+Shift Ctrl+Alt and end with a number, letter, or symbol that appears on the keyboard. The Function keys (such as F1) are also supported. Many Ctrl + *letter* and Function shortcuts are already assigned in JMP, but you can reassign them to your buttons if you want.

Shortcut keys appear in menus next to each menu item.

To assign a shortcut key, follow these steps:

1. With the Menu Editor still opened, select the menu item or button.

The Shortcuts properties appear on the right.

2. Do one of the following:

- To assign a new shortcut, click in the **New shortcut** area and press the shortcut keys. If the keystrokes then appear in the **Currently assign to** box, press another combination of shortcut keys. (You do not have to delete the keystrokes before pressing the shortcut keys.)
- To change a shortcut that you previously specified, click **Remove**, click in the **New shortcut** area and press the shortcut keys.

3. Click **Assign**.

The shortcut appears in the **Current shortcuts** list.

4. Click **Save** to save your changes.

To remove a shortcut, select the shortcut and click **Remove**.

Rearrange Toolbars

On Windows, there are two ways to rearrange toolbars:

- To rearrange toolbars quickly for the current user, drag the toolbar above, below, to the left, or to the right of the adjacent toolbar.
- To specify the new location rather than drag the toolbar, right-click the toolbar and select a position from the Location menu. This method lets you move toolbars to the top or bottom of the window. You can also position the toolbars vertically on the left or right side of the window.

In some windows, the toolbar is hidden by default. Specifying a new location shows the toolbar in all windows of that type. On Windows, you can change the toolbar preferences to always show toolbars. See [“Windows Specific”](#) on page 606 in the “JMP Preferences” chapter

To drag a toolbar

1. Click the left corner of the toolbar until the Move  cursor appears.
2. Drag the toolbar to the new location. When a toolbar is too wide to show completely, click the arrow to show all of the buttons, as shown in Figure 12.3.

Figure 12.3 Expanding a Toolbar



To position the toolbar

1. Right-click the toolbar that you want to move.
2. Select **Location**, and then select the new position.

Note: After you move a toolbar to the left, right, or bottom positions, you can add other toolbars to the same position. For example, you might relocate the **File Edit** toolbar to the right side of the JMP window. To add other toolbars on the right side, right-click the bar and select the toolbar that you want to add.

Copy and Paste Menus, Menu Items, Toolbars, and Buttons

Copying existing items is a shortcut to creating new items in a menu or toolbar. This option lets you change only a few settings in the new item when possible.

To copy and paste menus and menu items

1. Select **View > Customize > Menus and Toolbars**.

The Menu Editor appears.

2. (Optional) Change the customization set to control which users see your customizations. See [“Change Customization Sets”](#) on page 554 for details.
3. Right-click the menu or menu item that you want to copy and select **Copy**.
4. Right-click the menu or menu item before, after, or into which the item will appear and select **Paste**.

One of the following occurs:

- A list of possible locations appears.
 - The menu or menu item appears below the selected item. Skip to step 7.
5. Select the location of the menu by doing one of the following:
 - To paste the item *before* the selected menu, select **Paste before**.
 - To paste the menu *after* the selected menu, select **Paste after**.
 - To paste the menu *inside* the selected menu, select **Paste into**. (Available only when you select a menu as the new location.)
 - To cancel the action, select **Cancel**.

The item appears as you indicated.

6. Modify the item.
7. Click **Save** to save your changes.

See [“Create Main Menus”](#) on page 558 and [“Create Menu Items and Toolbar Buttons”](#) on page 559 for details about modifying the items.

To copy and paste toolbars and buttons

1. Select **View > Customize > Menus and Toolbars**.

The Menu Editor appears.

2. (Optional) Change the customization set to control which users see your customizations. See [“Change Customization Sets”](#) on page 554 for details.
3. Right-click the toolbar or button that you want to copy and select **Copy**.
4. Do one of the following:
 - To paste a toolbar, right-click **Toolbar** and select **Paste**. The toolbar appears at the end of the list of toolbars.
 - To paste a button, right-click the button before or after which you want the new button, and select **Paste**. If you selected the first button on the toolbar, select the location of the button. Otherwise, the button is pasted below the selected button.

5. Modify the item.
6. Click **Save** to save your changes.

See [“Create Toolbars”](#) on page 555 and [“Create Menu Items and Toolbar Buttons”](#) on page 559 for details about modifying the items.

Rearrange Custom Menus, Menu Items, and Buttons

On Windows, you can rearrange the order of menus, menu items, and buttons that you create. For example, under the **File > New** menu, you could move your custom menu before the **Data Table** command.

In the item’s General properties, the Source determines whether you can move the item. You can move items if the Source is *Custom Item*. Built-in items cannot be moved. Items that are defined in other customization sets can be moved only in that customization set. See [“Change Customization Sets”](#) on page 554 for details.

Note: The right-click menu has options for cutting and pasting items. To cut an item, you can also hold down the Ctrl key and press X, or hold down the Shift key and press Delete. To paste, hold down the Ctrl key and press V, or hold down the Shift key and press Insert.

To rearrange custom menus and menu items

1. Select **View > Customize > Menus and Toolbars**.

The Main Menu list appears on the left.

2. Do the following:
 - Select the item that you want to move.
 - Verify that the Source is *Custom Item*.
 - If the Source is *All Users* or *JMP Add-In*, select the specified customization set and verify that the Source is *Custom Item*.
3. Right-click the custom menu or menu item that you want to move and select **Cut**.
4. Right-click the new location of the cut item and select **Paste**.

One of the following occurs:

- A list appears with the possible locations of the cut item. This occurs when you select a menu (such as **File** or **New**) or the first item in a menu (such as **Data Table** in the **File > New** menu).
 - The cut menu item appears below the selected menu item. Skip to step 6.
5. Select the location of the cut item by doing one of the following:
 - To paste the cut item *before* the selected item, select **Paste before**.

- To paste the cut item *after* the selected item, select **Paste after**.
- To paste the cut item *inside* the selected menu, select **Paste into**. (Available only when you select a menu as the new location.)
- To cancel the move, select **Cancel**.

The item appears as you indicated.

6. Click **Save** to save your changes.

To rearrange custom buttons

1. Select **View > Customize > Menus and Toolbars**.

The Toolbars list appears on the left.

2. Do the following:

- Select the custom button that you want to move.
- Verify that the Source is *Custom Item*.
- If the Source is *All Users* or *JMP Add-In*, select the specified customization set and verify that the Source is *Custom Item*.

3. Right-click the custom button that you want to move and select **Cut**.

4. Right-click the new location of the cut button.

One of the following occurs:

- A list appears with the possible locations of the cut button. This occurs when you select the first button on the toolbar (such as **New Data Table** in the **File_Edit** toolbar).
- The button is pasted at the end of the toolbar. This occurs when you select the name of the toolbar. For example, when you select **File_Edit** and paste, the button appears after the last button, **Run Script**. Skip to step 6.
- The cut button appears after the selected button. Skip to step 6.


5. Select the location of the cut button by doing one of the following:

- To paste the cut button *before* the selected button, select **Paste before**.
- To paste the cut button *after* the selected button, select **Paste after**.

6. Click **Save** to save your changes.

Delete Custom Items

Rather than temporarily showing or hiding toolbars, buttons, menus, and menu items, you can delete items that you created to remove them permanently from JMP. The Source determines whether you can delete the item and which customization set contains the item. Figure 12.4 shows examples of customization Source types.

Figure 12.4 Examples of Customization Sources

Empty menus are not supported. When you delete the only item in a menu, the entire menu is deleted, not just the selected item.

Note: Make sure that you really want to delete custom items. They are removed immediately without confirmation.

To delete a custom item, follow these steps:

1. Select **View > Customize > Menus and Toolbars**.
The Menu Editor appears.
2. Select the item that you want to delete.
3. Verify whether the item can be deleted, and change the customization set, if necessary.
4. Right-click the selected item and select **Delete**.
The item is immediately deleted.
5. Click **Save**.
Your changes are saved.

Show and Hide Items

In the Menu Editor, you show or hide toolbars, buttons, menus, and menu items in specific customization sets. The item's Source determines where you show or hide the item. For example:

- When the Source is *All Users*, change the customization set to **All users** to hide the item from all users.
- When the Source is *JMP Add-In*, change the customization set to **JMP Add-In** followed by the name of the add-in. The item is shown or hidden in all sets that include the selected JMP add-in.

If you do not change the customization set, the item is shown or hidden only in the currently selected set. See [“Change Customization Sets”](#) on page 554 for details about customization sets.

Note: To quickly hide or show toolbars for the current user, select or deselect them from the **View > Toolbars** list.

To show and hide items in a customization set, follow these steps:

1. Select **View > Customize > Menus and Toolbars**.
The Menu Editor appears.
2. Select the customization set that you want to modify.
3. Select the item that you want to show or hide.
4. Select or deselect **Hidden** in the General properties. See [“Step 2: Specify the Caption and Internal Name”](#) on page 558 for details about the General properties.
5. Click **Save** to save your changes.

Import Customizations

Changes to toolbars and menus are stored in customization sets, or plain text files. You open a customization set in JMP to import your modified toolbars and menus. The customizations are then shown in the Menu Editor. See [“Change Customization Sets”](#) on page 554 for details about the menu customization files.

To import customizations, follow these steps:

1. Select **File > Open**.
2. In the File name list, select **All JMP Files** (or **JMP Menu Files**) and then select the customization set.
3. Click **Open**.
A confirmation is displayed, stating that the customizations have been imported. The Menu Editor is also opened.
4. Display the Menu Editor and click **OK** to save the changes, or click **Cancel** to discard them.

Remove Customizations

As you modify items, you discard unsaved changes by clicking the Menu Editor's **Cancel** button and clicking **Yes** to confirm. After saving customizations, you can also remove all customizations and revert to the original menus and toolbars.

To remove all of the current user's customizations

1. Select **View > Customize > Revert to Factory Defaults**.
2. Click **Yes** to remove the current user's customizations.

When JMP finds customizations from a previous version of JMP, a confirmation appears. Do one of the following:

- Select **No** to avoid adding those customizations to the current installation of JMP.
- Select **Yes** to add those customizations to the current installation of JMP.

Note: Select **Do not ask me again about merging my old menus** for JMP to ignore customizations found in a previous JMP version *every time* you open JMP. However, when you revert toolbars and menus to the factory defaults, you always have the opportunity to merge old menus, whether you previously checked the merging old menus option.

To remove customizations from another customization set

1. Select **View > Customize > Menus and Toolbars**.
- The Menu Editor appears.
2. Click **Change**.
 3. Select the customization set, and click **OK**.
 4. Click **Revert All**.

A confirmation window appears.

5. Click **Yes** to remove your customizations.

To remove customizations from the selected item

1. Select **View > Customize > Menus and Toolbars**.
- The Menu Editor appears.
2. (Optional) Select the customization set that contains the item.
 3. Select the item that you want to modify.
 4. Do one of the following:
 - To restore the *previous* properties of an *unsaved* item, click **Reset**.
 - To restore the *original* properties of a *built-in* item, click **Revert All**, and then click **Yes** to confirm.
 5. Click **Save** to save your changes.

Personalize Toolbars on Macintosh

On the Macintosh, you can set up toolbars to display only the icons that you need. Icons are available based on the type of window. For example, in a script window, icons for options such as reformatting, encrypting, and running the script are available. Table icons are available only for data table toolbars.

You can specify whether the icon, icon and icon name, or just the name appear on the toolbar. Displaying small icons is also an option.

To add, remove, or rearrange toolbar icons


1. Open the type of window whose toolbar you want to customize.
2. Select **View > Customize Toolbar**.

A window appears that shows icons relevant to the current type of window.

3. Do any of the following:
 - To add an icon to the toolbar, drag the icon from the window onto the toolbar.
 - To move an icon on the toolbar, drag the icon to its new location onto the toolbar.
 - To remove an icon from the toolbar, drag the icon from the toolbar onto the window.

Your changes are applied to the current window and all open windows of the same type.

Figure 12.5 Add, Rearrange, and Remove Toolbar Buttons on the Macintosh



4. Click **Done**.

When a toolbar is too wide to display completely, click the right arrows on the toolbar to show and then select other icons. Alternatively, you can click and drag the window until the entire toolbar appears.

Note: To display the original set of toolbar icons, drag the default set from the bottom of the toolbar customization window to the toolbar.

To change the appearance of toolbar icons

1. Open the type of window whose toolbar you want to customize.
2. Select **View > Customize Toolbar**.
A window containing toolbar icons appears.
3. At the bottom of the window, select one of the following options from the Show list:
 - To display only an icon, select **Icon**.
 - To display an icon and its name, select **Icon and Text**.
 - To display only the icon name, select **Text**.
4. To display small or standard icons, select or deselect **Use small size**.
Your changes are applied to the current window and all open windows of the same type.
5. Click **Done**.

Personalize Menu Items on Macintosh

Customize JMP menus to quickly access files or modify existing menu items. Selecting a menu item runs a JSL script from your computer or executes the JSL commands that you specify. For example, you can create a menu item to open a frequently used script. This option is an alternative to adding the script as a favorite on the Home Window.

Features include adding and renaming menu items, hiding menu items, inserting menu item separators, and associating a menu item with JSL.

JMP customizations are stored in <username>/Library/Application Support/JMP/14/usercust.jmpcust.

Note: You cannot delete default JMP menus or delete submenus (which open to reveal other menu items). Default and custom submenus also cannot be renamed.

Example of Adding a Menu Item

In this example, create a menu item that runs a script.

1. Select **View > Customize Menus**.
2. In the JMP Menu Editor, select **File** and then **Open**.
3. Press Control and then select **Add New Menu Item after**.
4. Type *What is the Current Time?* in the Menu Label box.
5. Select **Run JSL in this file:** and select Library/Application Support/JMP/14/Scripts/timeAnnouncer.jsl.
6. Click **Add Item** and close the Menu Editor window.

7. Select **File > What is the Current Time?**.

The Scheduler window appears, and the current time is spoken.

Example of Adding a Submenu Item

A submenu opens to reveal submenu items. In this example, create a submenu item that opens a data table.

1. Select **View > Customize Menus**.
2. In the JMP Menu Editor, select **File** and then **Open**.
3. Press Control and select **Add New Submenu** after.
4. Type Open My Data Tables and select **JSL Commands**.

Note: Selecting **JSL Script** lets you select a JSL script from your computer.

5. Click **Add**.
6. Select **Open My Data Tables**, delete **Subitem placeholder** in the Menu Label box, and then type Open Napoleons March.jmp.
7. In the Run this JSL box, type `Open("$SAMPLE_DATA/Napoleons March.jmp");`.
8. Click **Save**.
9. Select the **File** menu to see the new menu item.

Tip: If the new menu item appears in the menu but not the menu editor, close the menu editor window and reopen it.

To delete a custom menu or submenu item

- Delete one custom menu item by selecting the item and selecting **Delete Selection** from the options list.
- Delete all custom menu items by selecting **Revert All** from the options list.
- To delete items within a submenu, you must delete the entire submenu. Empty menus are not permitted. Select the submenu and select **Delete Selection** from the options list.

Customize Menus and Toolbars for an Add-In

To add new features to JMP, you can write the scripts and compile files to create an add-in. One way to compile the scripts is to use Add-In Builder as described in the Creating Applications chapter in the *Scripting Guide*.

Add-In Builder provides a menu editor that enables you to create menu items in the Add-Ins menu. You can also use the JMP Menu Editor to create menu items and add toolbar buttons for an add-in.

Chapter 13

JMP Preferences The Preferences Window

JMP preferences enable you to specify general and specific settings and save the settings.

To change preferences

1. Select **File > Preferences** (Windows) or **JMP > Preferences** (Macintosh). The window in Figure 13.1 appears. The previous preferences page that you selected appears.
2. Click a category and make selections. Click **Apply** to see the results, and then click **OK**.

Contents

Overview	577
General	577
Reports	583
Graphs	587
Styles	591
Tables	593
Platforms	598
Print	600
Text Data Files	601
Windows Specific	606
Macintosh OS Settings	609
Fonts	610
Communications	613
File Locations	614
Script Editor	617
SAS Integration	620
JMP Updates	623
JSL Debugger	625
Menu Preferences	626
Query Builder	628

Overview

The Preferences command on the File menu (on the JMP menu on Macintosh) displays the Preferences window. See Figure 13.1. Each category is described in this chapter.

Changes that you make to preferences are stored in a version-specific JMP.PFS file located in one of the following folders:

C:/Users/<user name>/AppData/Roaming/SAS/JMP/14/

C:/Users/<user name>/AppData/Roaming/SAS/JMPPro/14/

C:/Users/<user name>/AppData/Roaming/SAS/JMPSW/14/

JMP looks for this file when you open the program and considers your changes to be the factory defaults. And all subsequent changes are stored in this file.

Note: The Reset to Defaults button is on every page of the preferences. Clicking the button on the General, Graphs, Reports, or Styles pages resets preferences on all of those pages. On the remaining pages, clicking the button resets preferences only on the current page.

General

Most General preferences customize your JMP session at start-up. Others set preferences for file handling and the general appearance of the JMP workspace.

Figure 13.1 General Preferences

Filter  ▼

Preference Group

- General**
- Reports
- Graphs
- Styles
- Tables
- Platforms
- Print
- Text Data Files
- Windows Specific
- Fonts
- Communications
- File Locations
- Script Editor
- SAS Integration
- JMP Updates
- JSL Debugger
- Menu
- Query Builder

☒ Show the Tip of the Day at startup

☒ Initial Splash Window

Initial JMP Window Home Window ▼

☒ Reopen the initial JMP window on last window close

Excel Open Method Use Excel Wizard ▼

Use Excel Labels as Headings Use best guess ▼

Image Format for PowerPoint Default OS format ▼

☒ Use SPSS labels for column names during import

☒ Use Triple-S Labels as Headings

☒ Show menu tips

☐ Annotate error lines in log

☒ Show log warnings for JSL compatibility changes in JMP 12

Allow Unquoted Strings in JSL Yes (no warning) ▼

Open Text File Charset Best Guess ▼

☒ Save Text Files as Unicode

☐ Save Journals GZ Compressed

☐ Save Data Table Columns GZ Compressed

☒ Save Scripts in English

☒ Display indexes in English

☐ Report Invalid Display Box Messages

☒ Add files opened by scripts to the Recent Files list

Internet Open Timeout 60

Autosave Timeout 0

Autosave Maximum Data Table Rows 10000

Autosave Maximum Data Table Columns 1000

Save the session when exiting Prompt ▼

OK Cancel Apply Reset to Defaults Help

Table 13.1 Preferences on the General Page

Preference	Description
Show Tip of the Day at startup	Select this option to show the Tip of the Day window at start-up. This option is selected by default. Clear this option to prevent the Tip of the Day window from appearing at start-up.
Initial Splash Window	Select this option to show the initial splash window at start-up. This option is selected by default. Clear this option to prevent the initial splash window from appearing at start-up.
Initial JMP Starter Window	(Macintosh only) Select this option to show the JMP Starter window every time you start JMP. This option is on by default.
Initial JMP Window	(Windows only) Select one of the listed windows as the default window. When JMP starts, this window appears.
Home Window	(Macintosh) Select this option to show the JMP Home window when you start JMP on Macintosh.
Reopen the initial JMP window on last window close	(Windows only) Select this option to open whichever window you have set as the Initial JMP Window when you close the last JMP window. If this option is turned off, closing the last JMP window also quits JMP. This option is on by default.

Table 13.1 Preferences on the General Page (*Continued*)

Preference	Description
Excel Open Method	Select one of the options to determine how JMP imports Microsoft Excel worksheets. Excel Wizard Lets you preview a Microsoft Excel worksheet and modify the settings before importing the data. This is the default setting on Windows. On Macintosh, all .xlsx files open in the Excel Wizard. Open All Sheets Opens all worksheets in the workbook. On Macintosh, this preference is only for .xls files. Select Individual Worksheets Lets you select the worksheets that you want to open from a workbook. On Macintosh, this preference is only for .xls files. The option is also provided on Macintosh when you open an Excel (.xls) file. On Windows, you can also select File > Open, select the workbook, click the Open button arrow, and select Open Selected Worksheets or Use Excel Wizard. See the Data Tables chapter in the <i>Scripting Guide</i> for more information about importing Microsoft Excel workbooks through JSL.
Use Excel Labels as Headings	Select this option to allow JMP to use Excel label names as column headings when importing Excel files. Available settings include: • Use best guess (default) • Always • Never
Image Format for PowerPoint	Select the default file format for images exported to Microsoft PowerPoint. Windows does not support the native PDF graphics produced on Macintosh. Macintosh does not support the native EMF graphics produced on Windows. For cross-platform compatibility, specify the PNG or JPEG graphic format. Additional file formats are available through scripting. See <code>Save Presentation()</code> in the <i>JSL Syntax Reference</i> for details.

Table 13.1 Preferences on the General Page (*Continued*)

Preference	Description
Use SPSS Labels for column names during import	Select this option to allow JMP to use SPSS label names as column headings when importing SPSS files.
Use Triple-S Labels as Headings	Select this option to allow JMP to use Triple-S label names as column headings.
Show menu tips	(Windows only) Select this option to see tooltips on main menu options and options in red triangle menus. This option is selected by default.
Annotate error lines in log	Select this option to print more informative error messages to the log. This option is deselected by default.
Show log warnings for JSL compatibility changes in JMP 12	Select this option to print warnings about JSL compatibility to the log.
Allow Unquoted Strings in JSL	Select this option to print a warning to the log when a string value in a platform message is unquoted. Quoted string values are preferred over literal names. Yes (no warning) Allows unquoted string values and does not print a warning to the log. This option is selected by default. Yes (warning) Allows unquoted string values and prints a warning to the log. No Ignores the unquoted string value and does not print a warning to the log.
Open Text File Charset	Select one of the options from the menu to determine what character encoding JMP uses to open files. Best Guess is the default.
Save Text Files as Unicode	JMP uses the Unicode character set, which supports special characters such as é and ½. It saves files without special Unicode characters as plain text automatically. This option is selected by default. Clear this check box to save all your files as plain text. Note that versions of JMP earlier than 5.1.2 cannot read Unicode files.

Table 13.1 Preferences on the General Page (*Continued*)

Preference	Description
Save Journals GZ Compressed	Select this option to save JMP journals in a compressed format to save disk space. Clear this option to save journals normally. This option is not selected by default.
Save Data Table Columns GZ Compressed	Select this option to allow JMP to save data tables using GZ compression. For backward compatibility, JMP 10 can read the compressed files but not save them. This option is not selected by default.
Save Scripts in English	Non-English versions of JMP can save scripts in either English or your local language. User-specified values (such as column names and text strings) in these scripts appear as they do in the data table. However, command words (such as Distribution and Set Value) appear in English rather than the local language in order for the script to run on JMP in English. JMP properly displays non-Roman characters (such as Japanese variable names) in JMP in English when the fonts support the necessary characters. Select this option to save scripts in English no matter what language JMP is using. Clear this option to save scripts in your local language. Note that these scripts run correctly <i>only</i> if JMP is running in the same language. This option is selected by default.
Display indexes in English	Shows sections of the JMP Indexes in English or the current locale's language. The preference is selected by default. When you deselect it, the following items are displayed in the current locale's language: • The message list for objects • The message list for display boxes. • The category list for JSL functions. Note: The description of each index item is always displayed in the current locale's language. Examples are always in English.
Report Invalid Display Box Messages	Sends information about invalid display box messages to the log. This option is off by default. This option can be useful during script development, but can cause unwanted log messages for existing scripts.

Table 13.1 Preferences on the General Page *(Continued)*

Preference	Description
Add files opened by scripts to the Recent Files list	(Windows only) Select this option to include files opened by the JSL Open() command in the Home Window Recent Files pane and the File > Recent Files list.
Internet Open Timeout	When you use Internet Open to open a web page, JMP waits the specified number of seconds before stopping the import due to an error. 60 seconds is the default value.
Autosave Timeout	Automatically saves the contents of opened data tables, journals, reports, projects, and scripts except for untitled files at the specified interval. The default value is 0 minutes, which indicates no autosave.
Autosave Maximum Data Table Rows	Autosaves data tables if the number of rows does not exceed the specified value. 10,000 is the default value.
Autosave Maximum Data Table Columns	Autosaves data tables if the number of columns does not exceed the specified value. 1,000 is the default value.
Save the session when exiting	This option enables you to save the state of the JMP window when exiting JMP. When opening JMP, the saved state is restored, including any open files and windows.

Reports

Report preferences customize the appearance of reports.

Figure 13.2 Reports Preferences




Table 13.2 Preferences on the Reports Page

Preference	Description
Date Title on Output	Select this option to display the date and time the analysis occurred in your report windows. This option is cleared by default.

Table 13.2 Preferences on the Reports Page *(Continued)*

Preference	Description
Data Table Title on Output	Select this option to display the name of the data table and notes, if there are any, at the top of the report. This option is cleared by default.
Hover Help	On some numeric output, JMP provides tooltip-style help when you circle the mouse over a result. Select this option to see a tooltip where it is available. This option is selected by default.
Close report action	Select one of the options from the menu to determine what happens when you close a report: Prompt When you close a report, you are prompted to save it. Discard When you close a report, you are not prompted to save it, and the report is not saved. This is the default selection. Save / Auto-save When you close a report, it is automatically saved using the preference selected in the “Auto-save the report to” menu.
Auto-save the report to	Select one of the options from the menu to determine where a report is saved: Prompt When you close a report, you are prompted for a location to save it. This is the default selection. Data Table Script When you close a report, it is saved as a script in the open data table. Journal Script When you close a report, it is saved to a journal window. Log Window When you close a report, its script is written to the log window.

Table 13.2 Preferences on the Reports Page (Continued)

Preference	Description
Save table with report	Select one of the options from the menu to determine how a table is saved to a report: Embed When you save a report, the table is embedded into the report. Choose this option if you want to share the report with others. The data table that is stored in the report is reopened (unchanged) each time the report is opened. If you make changes to the table, they are not saved into the report unless you re-save the report. Separate When you save a report, the table is referenced in the report. Prompt When you save a report, you are prompted to specify how to save the report: either to embed the table within the report, or to add a reference to the table in the report. Prompt is selected by default.
Automatically save previously saved documents when saving a project	Saves previously saved documents when you save a project. For example, if you saved a data table inside a project, the data table is saved automatically again when you save the project.
Laser pointer	JMP has a built-in laser pointer that enables you to visually emphasize parts of a report. It is off by default. To turn it on, select a color for the laser pointer from the list.

Table 13.2 Preferences on the Reports Page (*Continued*)

Preference	Description
Show conditional formatting	Conditionally formats the color of the text that represents the values. Available for correlation values, p-values, and factor pattern values. Select one of the options from the menu: Always Conditional formatting is always applied to correlation values, p-values, and factor pattern values. Screen Only Conditional formatting is always applied to correlation values, p-values, and factor pattern values. However, the conditional formatting does not show when the report is printed. Never Conditional formatting is never applied to correlation values, p-values, and factor pattern values.
Manage Rules	Creates custom conditional formatting rules that can be applied to numeric columns or matrices. See “Use Conditional Formatting” on page 430 in the “JMP Reports” chapter. Note: Verify the Use an Asterisk with the PValue Format preference to ensure asterisk (*) is or is not used for any p-value conditions.
Use an Asterisk with the PValue Format	Select this option to display an asterisk (*) next to significant p-values. This option is on by default. Note: Verify any conditional formatting rules for PValue to ensure asterisk (*) is not used for any defined conditions.
Transparent background for report PNG images	Select this option to display a transparent background when a report is saved as a PNG file.

Graphs

Graph preferences customize the appearance of graphs. See [“Styles”](#) on page 591 for additional details about configuring the appearance of graphs.

Figure 13.3 Graphs Preferences




Table 13.3 Preferences on the Graphs Page

Preference	Description
Graph Border	Draws a border line around the area of the graph. This option is not selected by default.
Y-Axis Title Above Graph	Shows the Title for the Y-Axis above the line rather than beside the line. This option is not selected by default.
Hide Overlapping Labels	Select this option to hide overlapping chart labels. This option is selected by default.

Table 13.3 Preferences on the Graphs Page (*Continued*)

Preference	Description
Graph Height	Sets the default height (in pixels) for a graph. Default is 240 pixels. Some platforms take the value and multiply it by a certain amount. Note: With Graph Builder windows, specifying the Graph Height enlarges the window proportionally, but the exact value is not applied.
Line Width	Sets the default width (in pixels) for lines that pertain to content. Default is 2 pixels. Note: Does not apply to grid lines.
Graph Marker Size	Select a default size for the markers in graphs: Dot, Small, Medium, Large, XL, XXL, or XXXL. This preference is applied when the marker size is set to Preferred on a graph. If the Marker Threshold is Fast, the Dot marker size is applied.
Graph Marker	Select a default marker shape for the markers in graphs.
Graph Marker Theme	Select a default theme for the markers in graphs when you mark by row or column.
Marker Selection Mode	Select the default formatting for selected markers. See “Marker Selection Modes” on page 442 in the “JMP Reports” chapter.
Marker Selection Color	When the Marker Selection Mode is Selected Same Color, this setting applies the specified color to selected markers. Default color is Red.
Marker Selection Fade	When the Marker Selection Mode is Unselected Faded, this setting fades the unselected markers by the specified amount (in percent). The default is 65%.

Table 13.3 Preferences on the Graphs Page (*Continued*)

Preference	Description
Marker Label Color Style	Select the color of the marker label that appears on a graph when you label a column in the data table. Marker Color The marker label is the same color as the marker. This option is selected by default. Marker Color Faded The marker label is faded according to the Marker Selection Fade preference. Fixed Color The marker label color is as specified. The Marker Label Fixed Color preference determines the color.
Marker Label Fixed Color	Select the color of fixed-color marker labels, an option that you select in the Marker Label Color Style preference. The default color is gray.
Fast Marker Threshold	When JMP refreshes a report window, it can draw markers or points on a plot at two different speeds: normal and fast. If JMP is in normal drawing mode, and the number of markers on a graph are more than the specified threshold number, JMP automatically switches to fast mode. Enter the number of markers that separate normal and fast mode. The default is 50,000. The Dot marker size is applied for the Fast Marker Threshold.
Fill Hollow Markers	Select this option to apply an opaque background to markers.
Fill Selection Mode	Select the default highlight for selected rows in graphic objects: Selected Patterned A striped pattern (default) Selected Darkened A solid darker color Selected Outlined An outline Selected Same Color The Fill Selection Color in the preferences formats the selected object.

Table 13.3 Preferences on the Graphs Page (*Continued*)

Preference	Description
Fill Selection Color	Select the default color of selected rows in graphic objects when the Fill Selection Mode is “Selected Same Color”. The default color is red.
Continuous Color Theme	Select a default color theme for continuous data. The default theme is Blue to Gray to Red. See “Create Color Themes” on page 214 in the “Enter and Edit Data” chapter.
Categorical Color Theme	Select a default color theme for categorical data. The default theme is JMP Default. See “Create Color Themes” on page 214 in the “Enter and Edit Data” chapter.

Styles

The Style pages enables you to customize colors, tick marks and grid lines, and report colors. See [“Graphs”](#) on page 587 for additional details about configuring the appearance of graphs.

Figure 13.4 Styles Preferences




Table 13.4 Preferences on the Styles Page

Preference	Description
Color Presets	The Color Presets provides a set of predefined colors for use in customizing the appearance of reports, graphs, charts, and so on. Tints of the selected color are applied to the various elements. Note: The selected color is applied also to windows.
Frame Color	Defines the color applied to a graph frame and tick marks. Click to change the default color.
Major Grid Line Color	Defines the major grid line color. Click to change the default color.
Minor Grid Line Color	Defines the minor grid line color. Click to change the default color.

Table 13.4 Preferences on the Styles Page *(Continued)*

Preference	Description
Graph Background Color	Click the color box to select a background color for all graphs. Click to change the default color.
Window Background Color	Click the color box to select a background color for all reports and data tables. Click to change the default color.
Original	Click to restore default color settings.
Frame Border	Shows borders only on the axes.
Tick Marks Inside Graph Frame	Shows axis tick marks inside the graph frame.
Major Grid Lines	Shows major grid lines on graphs.
Minor Grid Lines	Shows minor grid lines on graphs.
Underline Table Headings	Shows border under table headings.
Shade Table Headings	Shows table headings with shading.
Table Heading Column Borders	Shows divider lines between columns in table headings.
Table Column Borders	Shows borders between table columns.
Table Row Borders	Shows borders between table rows.
Shade Alternate Table Rows	Shows alternate table rows with shading.
Shade Table Cells	Shows table cells with shading.

Tables

Table preferences customize JMP data tables, including formula handling, appearance, and compatibility with SAS data sets.

Figure 13.5 Tables Preferences




Table 13.5 Preferences on the Tables Page

Preference	Description
Evaluate OnOpen Scripts	If you save a script to a data table and name it OnOpen or On Open, JMP can automatically run the script whenever you open the data table. On Open scripts that execute other programs are never run. Prompt is selected by default. Your choice is remembered each time you open the data table in the current JMP session. Select Always to allow On Open scripts to run without prompting. Select Never to prevent On Open scripts from automatically running when a data table is opened.
Prompt to save when closing summary tables	Prompts you to save an unsaved linked summary table when you close it. Note that, when you select this option in the Summary window, it is selected in the Tables preferences. If you do not want to be prompted to save all linked summary tables in the future, deselect the preference. This option is cleared by default.
Allow short numeric data format	JMP has the ability to store numeric data in as few as 8 bits (one byte). This option makes short-integer formats available to you when you select Cols > Column Info and assign a column a data type. When you use the correct short-integer format for your data, the numbers are not displayed differently, but the data table uses less disk space. See “The Short-Integer Format” on page 260 in the “The Column Info Window” chapter.
Print Data Grid as is	Select this option to print the JMP data table as it appears on the screen. Clear this option to resize column widths to accommodate the content width. This option is cleared by default.
Preserve SAS variable names when exporting to SAS	Select this option to use variable names that are compliant with SAS when you export a JMP data table to a SAS data set. This option is cleared by default.
Preserve SAS formats when exporting to SAS	Select this option to use formats that are compliant with SAS when you export a JMP data table to a SAS data set. This option is selected by default.

Table 13.5 Preferences on the Tables Page *(Continued)*

Preference	Description
Show Alternate Column Name	Select this option to show the name-label pair of the column. A column has name-label pair if the two column properties are defined and the Column Name equals one of the two properties. JMP recognizes the following name-label pairs: • SAS name-label pair, where the properties are “SAS Name” and “SAS Label” • SPSS name-label pair, where the properties are “SPSS Name” and “SPSS Label” • Short-long name-label pair, where the properties are “Short Name” and “Long Name” If the preference is checked, then both the name and label appear in the dialog.
Use Thousands Separator	Select this option to display numbers using the locale-appropriate thousands separator. This option is not selected by default.
Default Field Width	Changes the number of digits that appear in numeric columns. The default value is 12.
Use a Floating Window for Data Filters	Select this option to float the Data Filter window on top of its associated data table. Clearing this option causes the Data Filter window to behave like any other window. This option is selected by default.
Data Filter Select Check	Select this option to show the Select check box in the Data Filter. This option is selected by default.
Data Filter Show Check	Select this option to show the Show check box in the Data Filter. This option is not selected by default.
Data Filter Include Check	Select this option to show the Include check box in the Data Filter. This option is not selected by default.
Data Filter Group is AND	Select this option to reverse the AND and OR behavior between groups in the Data Filter.
Data Filter Auto Clear	Select this option to show the Auto clear option in the Data Filter red triangle menu. This option is selected by default.

Table 13.5 Preferences on the Tables Page (*Continued*)

Preference	Description
Data Filter Conditional	Limits the categories displayed in hierarchical data for the unselected filter column. For example, you could filter by region so that only the states in the selected region appear in the list.
Data Filter Check Box Display	Select this option to always use check boxes for categorical filter columns. This option is not selected by default.
Include Responses Not in Data	(Categorical columns only) Shows all of the possible responses listed in value labels, even if the response is not present within the data.
Numeric keypad Enter key moves down	(Windows only) When a data table cell is selected and you press the Enter (or Return) key on the keyboard, the next table cell down is selected. Pressing either the TAB key or the ENTER key on the numeric keypad located to the right of the keyboard selects the next table cell to the right. Select this option to change the behavior of the ENTER key on the numeric keypad to select the next table cell down instead of to the right. This option is cleared by default.
Suppress Formula Eval on Open	Select this option to prevent columns formulas from being evaluated when you open data tables. Clear this option to allow formulas to be evaluated when you open data tables. This option is cleared by default.
ODBC Hide Connection String	Select this option to have the Open Database command hide the ODBC connection settings (that is, user ID and password). See the Extending JMP chapter in the <i>Scripting Guide</i> book for additional information.
Data Table Background Color	Click the color box to select a background color for data tables.
Data Table Grid Color	Click the color box to select a color for the grid lines in a data table.
Data Table Header Grid Color	Click the color box to select a background color for the column names.

Platforms

Each analysis report has a variety of plot and table options that are shown by default. However, there might be additional options that you want to see each time you run a particular analysis. For example, a bivariate analysis shows a scatterplot by default, but you might also always want to see a linear fit each time. By selecting the Platforms option in the left panel of the Preferences window, you can set the default options for analyses. (Analyses are run by using platforms, such as the Bivariate platform. Thus, the name of this category is Platforms.)

Highlight an analysis name in the Platforms list. Its available options appear in the Options box with the defaults selected.


Some platform preferences include a Set check box to control whether an option appears in a report.

- To prevent an option from appearing in the report, next to an option, select **Set** but do not select the option.
- To ensure an option appears in the report, select **Set** and select the option.

Click **Reset Platform to Defaults** to return the selected platform options to the default settings.

Click **Reset to Defaults** to return all platforms to their default settings.

Figure 13.6 Platforms Preferences



Print

The Print pages enables you to configure default print settings such as, margins, header, and footers.

Figure 13.7 Print Preferences

Filter

Preference Group

- General
- Reports
- Graphs
- Styles
- Tables
- Platforms
- Print**
- Text Data Files
- Windows Specific
- Fonts
- Communications
- File Locations
- Script Editor
- SAS Integration
- JMP Updates
- JSL Debugger
- Menu
- Query Builder

Margins

Top

Left Right

Bottom

Headers

Left Center Right

Footers

Left Center Right

Orientation

☒ Portrait ☐ Landscape

Scaling

Scale Factor %

OK Cancel Apply Reset to Defaults Help

Table 13.6 Preferences for Print Settings

Preference	Description
Top (margin)	Sets the print page's top margin. The default value is 0.75 inches.
Left (margin)	Sets the print page's left margin. The default value is 0.75 inches.
Right (margin)	Sets the print page's right margin. The default value is 0.75 inches.
Bottom (margin)	Sets the print page's bottom margin. The default value is 0.75 inches.
Left (header)	Sets the page's left-side header information. The default value is &wt; (that is, the title).
Center (header)	Sets the page's center header information. The default value is blank.
Right (header)	Sets the page's right-side header information. The default value is Page &pn; of &pc; (that is, Page # of count).
Left (footer)	Sets the page's left-side footer information. The default value is blank.
Center (footer)	Sets the page's center footer information. The default value is blank.
Right (footer)	Sets the page's right-side footer information. The default value is blank.
Orientation	Sets the page's print orientation as either Portrait or Landscape. The default value is Portrait.
Scale Factor	Sets the page's print scaling factor (in percent). The default value is 100%.

Note: The code for printing the current date in the header or footer is **&d**.

Text Data Files

Text Data File preferences customize the handling of importing and exporting text files.

Figure 13.8 Text Data Files Preferences

Filter  ▼

Preference Group

- General
- Reports
- Graphs
- Styles
- Tables
- Platforms
- Print
- Text Data Files**
- Windows Specific
- Fonts
- Communications
- File Locations
- Script Editor
- SAS Integration
- JMP Updates
- JSL Debugger
- Menu
- Query Builder

Import Settings

☐ Use best guess
☒ Use these settings

End Of Field:

☒ Tab ☒ Comma
☐ Space ☐ Other:
☐ Spaces ☒ CSV standard

End Of Line:

☒ <CR> + <LF> ☐ Semicolon
☒ <CR> ☐ Other:
☒ <LF>

☒ Table contains column headers
 Column Names are on line:
 Data starts on line:
 Two-digit year rule:

When determining column types

☒ Scan whole file
☐ Scan for 5 seconds
☐ Treat empty columns as numeric

Try to compress (requires Scan whole file)

☐ Numeric columns ☐ Character columns ☐ Allow List Check

☒ Strip enclosing quotation marks
☐ Recognize apostrophe as quotation mark (not recommended)
☐ Use Regional Settings

Export Settings

☒ Export Table Headers
☐ Add quotation marks to all column names
☐ Add quotation marks to all character values
☐ Add quotation marks to all numeric values

End Of Field:

☐ Tab
☐ Space
☐ Spaces
☒ Comma
☐ None
☐ Other:

End Of Line:

☒ <CR> + <LF>
☐ <CR>
☐ <LF>
☐ Semicolon
☐ Other:

OK Cancel Apply Reset to Defaults Help

Table 13.7 Preferences for Import Settings for Text Files

Preference	Description
Import Settings	Select the strategy JMP uses to open text files. The default selection is Use these settings. In that case, you need to ensure that the settings reflect your text files. If you select Use Best Guess, JMP collects statistics in the text file on tabs, commas, blanks, and a few other characters and uses a rule-based system to decide what the file format might be. The rules try to make reasonable field widths and a reasonable number of fields per line. If your data format is too different from what the rules are designed to guess, JMP guesses incorrectly. In that case, either use the wizard or explicitly describe your data in these preference settings.
End Of Field	Select one or more characters to use as the delimiter that signifies the end of a field when importing text data. Select the Other option and enter a character to specify a delimiter that is not listed.
End Of Line	Select one or more characters to use as the delimiter that signifies the end of a line (row). Select the Other option and enter a character to specify a delimiter that is not listed. Note that if double-quotes are encountered when importing text data, the delimiter rules change to look for an end double-quote. Other text delimiters, including spaces, that are embedded within the quotes are ignored and treated as part of the text string.
Table contains column headers	Select this option if your text file contains column names. If you select this option, enter the line number where the column names are located in the field next to Column Names are on line.
Column Names are on line	If you select the Table contains column headers option, enter the line number where the column names are located in this field.
Data starts on line	Enter the line number where the data starts in your text file.

Table 13.7 Preferences for Import Settings for Text Files (Continued)

Preference	Description
When determining column types	Set how long JMP scans a text file to determine data types for the columns. Scan whole file is selected by default. Note that the Scan whole file option can cause importing a text file to be slow for large files. Consider selecting Scan for 5 seconds instead. When your text file contains columns of missing data, select Treat empty columns as numeric to import the columns as numeric rather than character. A period, Unicode dot, <i>NaN</i>, or a blank string are possible missing value indicators. This option is deselected by default.
Two-digit year rule	Select the rule that you want to use to import dates that have two-digit years instead of four. For details about these rules, see “Two-digit year rule” on page 152 in the “Import Your Data” chapter.
Try to compress	Select the options used for compressing text files. Available options are: • Numeric columns • Character columns • Allow List Check Note: This feature requires a scan of the entire file.
Strip enclosing quotation marks	Select this option to remove quotation marks that enclose data in the text file. This option is selected by default.
Recognize apostrophe as quotation mark	Select this option to treat apostrophes as quotation marks and omit them. This option is off by default. Note: This option is not recommended unless your data comes from a nonstandard source that places apostrophes around data fields rather than quotation marks.

Table 13.7 Preferences for Import Settings for Text Files (*Continued*)

Preference	Description
Use Regional Settings	Select this option to use the operating system's regional settings when importing a text file. • If the option is deselected (the default setting), files that use a period for a decimal point and a comma for the value separator import correctly. • If the file uses a comma for a decimal point and some other value separator (and the regional settings use a comma for a decimal point), selecting this option imports the text correctly. You must specify the value separator in the Text Data Files import preferences.

Table 13.8 Preferences for Export Settings for Text Files

Preference	Description
Export Table Headers	Select this option to include column names when you save data tables as text files. Selected by default.
Add quotation marks to all column names	Select this option to insert quotation marks around column names. Used to export data to a program that has more stringent requirements than CSV.
Add quotation marks to all character values	Select this option to insert quotation marks around character values. Used to export data to a program that has more stringent requirements than CSV.
Add quotation marks to all numeric values	Select this option to insert quotation marks around numeric values. Used to export data to a program that has more stringent requirements than CSV.
End Of Field	Select one or more characters to use as the delimiter signifying the end of a field when exporting text data. Select the Other option and enter a character to specify a delimiter that is not listed.
End Of Line	Select one or more characters to use as the delimiter that signifies the end of a line (row). Select the Other option and enter a character to specify a delimiter that is not listed.

Windows Specific

These preferences customize settings for Windows computers, including auto-hiding menus and toolbars and selecting the default graphics format.

Figure 13.9 Windows Specific Preferences




Table 13.9 Windows Specific Preferences

Preference	Description
Display Language	Select the language in which you want to run JMP. The locale settings for your operating system normally determine settings for number, date, and currency formats. Select the option below the language menu to use that language to determine these formats instead. Text that appears in windows provided by the operating system (for example, File > Open), do not reflect changes in the language setting. Notes: • After changing the display language, close and restart JMP to have the language settings fully take effect. • The languages that you selected in the JMP installation program determine which languages are available. To make a language available, rerun the JMP installation program, select Modify, and then select the language.
Copy/Drag Graphic Formats	Select one or more graphic formats to use when copying and pasting (or dragging and dropping) graphics from JMP into other applications.
Resolution (DPI) for PNG and JPEG Images	Specify the DPI to be used when you copy a graphic format. Choose from the Default (96) or 300. 300 is better for images that must be stretched, embedded in trade publications, or printed. However, this setting uses more memory and is slower to generate for large images. The following script lets you set the default DPI. Change the number to a different DPI if you want and then run the script. <pre>Pref(Save Image DPI(600));</pre> To verify the default DPI after you run the preceding script, run the following script: <pre>Get Preferences(Save Image DPI);</pre> For details about specifying a higher DPI, see “Setting the Graphic DPI” on page 509 in the “Save and Share Data” chapter.

Table 13.9 Windows Specific Preferences *(Continued)*

Preference	Description
Graphics Formats	Select the format to use for graphics when you save a JMP report as an RTF file or an HTML file. In the Graphic Scale Factor % box, enter the percentage at which you want graphics to appear in other applications. This feature might not work with all versions of your chosen application.
Enable hardware accelerated graphics	Takes better advantage of the computer's graphics processing unit (GPU) for better video performance. Consider selecting this option if your computer is sluggish when drawing JMP windows. This is an experimental feature.
Highlight Outline Headers	Select this option to give title bars in the data table and report windows a light shade of gray. This option is selected by default. Clear this option to give the title bars a darker shade of gray.
JSL Scripts should be run only, not opened, when selected from Recent Files or a file browser	Select this option to force all scripts to run when opened. If this is selected, the script window for the script is not opened. This option is off by default.
Show on the Windows task bar	Select which JMP windows you would like displayed on the Windows task bar. The default selection is All Windows. You can also choose to display the main JMP window and data table windows.
Open the JMP Log window	Select one of the options to open the log only when text (such as error messages) is added to it or every time you start JMP. The default setting displays the log only when you open it.
Auto-hide menu and toolbars	Select the rule used to determine when menus and toolbars are hidden. The default value is Based on window size.
Wrap the main menu in narrow windows	Select this option to wrap the menu to additional lines when the window is narrower is than the menu. This option is on by default.
Show the thumbnail panel in data table windows	Select this option to show the thumbnail panel of reports at the bottom of a data table. This option is on by default.
Dock the Window List in maximized windows	Select this option to automatically dock the Window List if you maximize your JMP windows. This option is off by default.

Table 13.9 Windows Specific Preferences *(Continued)*

Preference	Description
Reset file associations to this application	Click this button to associate all JMP file types with the JMP version that you are running.

Macintosh OS Settings

Macintosh OS Settings preferences customize settings for Macintosh machines, including the graphics formats and file associations.


Figure 13.10 Macintosh OS Settings Preferences

Table 13.10 Macintosh OS Settings

Preference	Description
Alternate Image Formats for Clipboard and Drag & Drop	Select one or more graphic formats to use when copying and pasting (or dragging and dropping) graphics from JMP into other applications.
Clipboard Image Scale Factor	Enter the percentage at which you want graphics to appear in other applications.
Image format for RTF	Select the format to use for graphics when you save a JMP report as an RTF file.
RTF Image Scale Factor	Enter the percentage at which you want graphics to appear in RTF documents.
Image format for HTML	Select the format to use for graphics when you save a JMP report as an HTML file.

Fonts

Font preferences customize the appearance of reports, data tables, and scripts, including fonts, text size, and font style.

Figure 13.11 Fonts Preferences




Table 13.11 Preferences for Customizing Fonts

Preference	Description
Text	Sets the font for the text portion of a JMP analysis report.
Heading	Sets the font for the heading of columns in an analysis report and a data table.

Table 13.11 Preferences for Customizing Fonts (*Continued*)

Preference	Description
Title	Sets the font for the title shown in all title bars.
Small	Sets the font for small text, which is used in the upper left corner of the data grid to show the number of columns and rows.
Mono	Sets the font used in the JMP Scripting Language (JSL) editor for script commands.
Formula Editor	Sets the font for the expressions entered into the Formula Editor.
Annotation	Sets the default font used in annotations.
Axis	Sets the font used for the axis tick labels.
Marker	Sets the font used for alphanumeric markers.
Axis Title	Sets the font for axis titles.
Data Table	Sets the font for displaying data in the data table.
Font Family	Select a proportional font. The font that you select is immediately applied to all settings except for Mono, which is used for scripts.
Use Greek letters	Select this option to use Greek letters instead of spelling out Greek letters. (For example, π instead of pi.) This option is selected by default.
Use math symbols	Select this option to use math symbols instead of simple text representations of math symbols. (For example, $\pm$ instead of +/-) This option is selected by default.

Communications

(Windows only) Communications preferences customize settings for reading data from an external source. These settings need to be specified only if you are using an instrument to do so.

Figure 13.12 Communications Preferences





Table 13.12 Preferences on the Communications Page

Preference	Description
Port	Select the port that your data source uses.
Baud Rate	Set the baud rate for your data source.
Data Bits	Set the number of data bits (7 or 8).
Parity	Set the parity bit. None is the default value.
Stop Bits	Set the stop bits (1 or 2).
Flow Control	Set the flow control. XON/XOFF is the default value.

File Locations

(Windows only) File Locations preferences set the default locations of JMP system files. Usually, the files can stay where JMP installs them, and you do not have to change anything here. However, if you do move files, such as Help files, elsewhere, you should update the location here.

Figure 13.13 File Locations Preferences**Table 13.13** Preferences on the File Locations Page

Preference	Description
Data Files directory	Change the folder in which JMP looks for data files (for example, data tables).
Help Files directory	Change the folder in which JMP looks for Help files.

Table 13.13 Preferences on the File Locations Page *(Continued)*

Preference	Description
Installation directory	Change the JMP installation folder.
License file path	Change the folder in which JMP looks for your JMP License file.
Preferences file directory	Change the folder in which JMP looks for preference information.
Save As directory	Change the folder in which JMP saves data files when you select File > Save As.
Always go to this directory when the File Open window is displayed	Select to have JMP always use the selected path when you select File > Open.

Script Editor

Script Editor preferences customize the appearance of the JSL Script Editor, such as tab width, syntax coloring, and tooltips.

Figure 13.14 Script Editor Preferences




Table 13.14 Preferences on the Script Editor Page

Preference	Description
Use tabs	Select this option to enable tabs in your scripts. This option is selected by default. Clear this option to replace any tab that you type with spaces.
Tab width	Enter how many spaces a tab should indent. If you have disabled tabs, any tab you type is replaced with the number of spaces specified. The default value is 4.
Extra space at bottom of document	Select this option to enable scrolling up from the last blank lines of a script. This option is selected by default on Windows and deselected on Macintosh.
Auto-complete parentheses and braces	Select this option to enable the script editor to automatically add closing parentheses, square brackets, and curly braces when you type an opening one. This option is selected by default.
Show line numbers	Select this option to show the line numbers on the left side of the script editor. This option is off by default.
Show indentation guides	Select this option to see faint vertical lines that mark indentation. This option is selected by default.
Show operator tips	Select this option to see tooltips for JSL operators. This option is selected by default.
Show variable value tips	Select this option to see tooltips for variable values. This option is selected by default.
Wrap text	Select this option to always wrap text in the script editor. This option is off by default.
Show embedded log on script window open	Select this option to have an embedded log window appear in the scripting window when editing or running scripts. This option is off default.
Save and restore document state information	Saves the state of collapsed and expanded code, and restores that state when the script is reopened.
Auto Save Before Run	Automatically saves the script before you run it. This option is off by default.

Table 13.14 Preferences on the Script Editor Page *(Continued)*

Preference	Description
Multiple Selection	Enables you to select lines of code that are not adjacent. Hold down the Ctrl key on Windows or Command key on Macintosh and drag your cursor over the text. Continue this action for any other text that you want to select. This option is on by default.
Code folding	Select this option to use code folding markers in the script editor, which mark the opening and closing of user defined functions and Expr() blocks. You can expand and collapse these marked blocks of code. This option is off by default. You can also choose the appearance of the marker using the JSL code folding marker menu. See the Scripting Tools chapter in the <i>Scripting Guide</i> for details.
Allow additional code folding keywords	Select this option to enable using additional keywords for folding markers in the script editor. See the Scripting Tools chapter in the <i>Scripting Guide</i> for details.
Spaces inside parentheses	Select this option to cause the script editor to add spaces between parentheses, brackets, and braces and their contents for automatically formatted scripts. This is on by default.
Spaces in operator names	Select this option to cause the script editor to add spaces between words within operator names. For example, turning on this option results in New Window instead of NewWindow. This option is selected by default.
Color unknown object messages	Select this option to always show unknown object messages in color. Unknown object messages will appear in the color specified by "Message unknown color". This option is off by default.
Customize Styles	Select colors and fonts for code elements shown in JSL scripts, SAS scripts, the Text Explorer customization window, text files, and so. Reset All Styles to Defaults restores the original colors for all items in the list. Reset Style to Defaults restores the original colors and font for the selected item on the right. Note that resetting the Fonts preferences does not affect the fonts selected on this page.

SAS Integration

SAS Integration preferences customize the default settings for working with SAS servers. For details about using the SAS Integration capabilities, see [“Import Data from SAS”](#) on page 88 in the “Import Your Data” chapter.

Note: The SAS Environment options appear after you select SAS 9.3 or 9.4 from the SAS Server Version list.

Figure 13.15 SAS Integration Preferences

Filter

Preference Group

- General
- Reports
- Graphs
- Styles
- Tables
- Platforms
- Print
- Text Data Files
- Windows Specific
- Fonts
- Communications
- File Locations
- Script Editor
- SAS Integration**
- JMP Updates
- JSL Debugger
- Menu
- Query Builder

SAS Server Version: 9.4

SAS Environment

- ☐ I want to connect to a SAS Environment [Configure...](#)
- ☒ I want to connect directly to a SAS Metadata Server
- ☐ I will manually connect to SAS workspace servers

☒ Automatically connect metadata-defined SAS libraries

SAS Submit Options

- ☐ Automatically generate ODS results
- ODS Result Format: HTML
- ODS Style: Statistical
- ODS Style sheet:
- Prompt if results are larger than 5 MB
- Graphics Format: ActiveX Image
- ☐ Generate ODS statistical graphics
- ☐ Import generated SAS data sets into JMP
- Prompt if data set has more than 100000 rows

SAS Data Import

- ☐ Use SAS variable labels for column names during data import
- ☒ Convert SAS custom formats to JMP value labels
- ☒ Warn before closing unsaved imported data

SAS 9.4 Extended Attributes

- ☐ On export, store table and column properties in extended attributes
- ☐ On import, apply table and column properties from extended attributes

Stored Process Results

Format

- ☒ HTML
- ☐ RTF
- ☐ PDF

Graph Format

- ☒ ActiveX Image
- ☐ Java Image
- ☐ PNG
- ☐ JPEG
- ☐ GIF

Show SAS Log

- ☐ Always
- ☐ Never
- ☒ On Error

Location

- ☒ JMP Log
- ☐ Separate Window

OK Cancel Apply Reset to Defaults Help

Table 13.15 Preferences on the SAS Integration Page

Preference	Description
SAS Server Version	Select the default version for the SAS Server. This can also be changed in the Server Connections window. (See “Connect to a SAS Metadata Server” on page 93 in the “Import Your Data” chapter.) This option does not apply when connecting to local SAS on Windows.
I want to connect to a SAS Environment	Select this option to always connect to a SAS Environment and click Configure to configure the URL of the location.
I want to connect to a SAS Metadata Server	Select this option to always connect to a SAS Metadata Server. This option is selected by default. Clear this option if you do not have a SAS Metadata Server available, and you connect directly to SAS Workspace Servers instead.
I will manually connect to SAS workspace servers	Select this option to manually connect to a SAS workspace server.
Automatically connect metadata-defined SAS libraries	Select this option to connect to metadata-defined SAS libraries automatically across all JMP sessions when you connect to a SAS Workspace Server. Selected by default. When the Workspace Server contains a large number of metadata-defined SAS libraries, deselect this option to speed up your connection to the server.
Automatically generate ODS results	Select this option to generate output delivery system (ODS) results. This option is cleared by default.
ODS Result Format	Select the format for ODS reports. The default value is HTML.
ODS Style	Enter the style name for ODS reports. The default value is Statistical.
ODS Style sheet	Enter the style sheet name for ODS reports.
Prompt if results are larger than __ MB	Enter the number of MB that triggers a prompt for you to continue or cancel the operation. The default value is 5.
Graphics Format	Select the format for graphics for ODS reports.

Table 13.15 Preferences on the SAS Integration Page *(Continued)*

Preference	Description
Generate ODS statistical graphics	Select this option to include statistical graphics in the ODS reports.
Import generated SAS data sets into JMP	Select this option to import any generated data sets into JMP automatically.
Prompt if data set has more than __ rows	Enter the number of rows that triggers a prompt for you to continue or cancel the operation. The default value is 100,000.
Use SAS variable labels for column names during data import	Select this option to use the column labels in the SAS data set as the JMP data table column names when importing a SAS data set into a JMP data table.
Convert SAS custom formats to JMP value labels	Select this option to use the information in the SAS column formats to set JMP value labels when importing a SAS data set into a JMP data table.
Warn before closing unsaved imported data	Select this option to trigger a prompt to save any SAS data sets that you imported into JMP and have not saved before closing.
On export, store table and column properties in extended attributes	Select to allow extended attribute support during SAS 9.4 data export. This option is not selected by default.
On import, apply table and column properties from extended attributes	Select to allow extended attribute support during SAS 9.4 data import. This option is not selected by default.
Stored Process Results: Format	Select a report format: HTML , RTF , or PDF .
Stored Process Results: Graph Format	Select a graph format: ActiveX Image (available only on a SAS server that runs on Windows), Java Image , PNG , JPEG , or GIF .
Show SAS Log	Select Always , Never , or On Error to set when the SAS log is displayed
Location	Select the location for SAS log information: within the JMP log window, or in a separate SAS log window.

JMP Updates

The JMP Update preferences show you what version of JMP you currently have, the last time it was updated, and whether and how often JMP checks automatically for updates.

Figure 13.16 JMP Updates Preferences




Table 13.16 Preferences on the JMP Updates Page

Preference	Description
Check for Updates	Select this option to have JMP automatically check for updates. If this option is selected, specify how often the check is performed: Daily , Weekly , or Monthly .
Current Version	What version of JMP you are currently running.
Last Check	The last time you checked for an update.
Check Now	Click this button to perform an update check immediately.

JSL Debugger

The JSL Debugger preferences let you show or hide line numbers, create breaks in scripts, and show warnings.

Figure 13.17 JSL Debugger Preferences





Table 13.17 Preferences on the JSL Debugger Page

Preference	Description
Show Line Numbers	Shows or hides the line numbers for the script in the debugger. The default value is selected.
Break on Multiple Statements Per Line	Stops executing the script between each expression in a single line. The default value is deselected.
Break On Throw	Breaks when an exception error occurs in a Try() function. For example, the exception error in the Try() function is thrown by a Throw() function. The Debugger breaks on the Throw() instead of continuing through the rest of the codes. This lets you identify where the problem occurred in the script and then return to debugging. The default value is deselected.
Break On Execution Error	Stops executing the script when the error occurs rather than closing the Debugger. The default value is selected.
Warn On Assignment In Condition	Select to show a warning when you enter an assignment expression for the breakpoint condition. For example, if you specify <code>x = 1</code> instead of <code>x == 1</code> in the breakpoint condition, you are prompted to verify the specification. The default value is selected.
Enter Debugger Upon Termination	Select to enter the Debugger when JMP terminates. The default value is selected.
Break for Compatibility Warnings	Stops executing the script when a JSL compatibility issue is encountered. The default value is selected.

Menu Preferences

The Menu preferences show and hide menus based on how you use JMP. This gives you fewer menu items to browse through and streamlines the JMP interface. For example, if you never design experiments, deselect **Design of Experiments**. Other menus are grouped by area of interest, such as quality engineering, advanced modeling, reliability and survival, SAS options and Excel Modeling.

Figure 13.18 Menu Preferences



Query Builder

The Query Builder preferences customize SQL queries that you perform in Query Builder.

Figure 13.19 Query Builder Preferences




Table 13.18 Preferences on the Query Builder Page

Preference	Description
Automatically join tables added to a query	Automatically joins database tables in Query Builder based on keys and common column names. This option is selected by default. Deselect this option to prevent memory issues with large databases.
Refresh the preview when a change occurs	Updates the data view on the Query Preview tab when a change occurs. This option is selected by default.
Maximum number of rows for previews	Limits the number of rows that appear on the Query Preview tab. The default number is 5000.
Keep queries compatible with JMP 12 by default	Maintains query compatibility with JMP 12. When you open a query that is marked JMP 12 compatible in JMP 13 or later, features that create compatibility problems are hidden regardless of how the preference is set.
Maximum number of levels for a Check Box List filter	Determines whether the filter for a categorical variable is added as a Check Box List filter. By default, when you add a categorical variable that has more than 1,000 levels, the filter is added as a Contains filter.
Maximum rows in table for which category levels will be automatically retrieved	Specifies the maximum numbers of rows for which unique category levels in the filtered column are retrieved. The minimum value is -1 (no limit). The maximum value is 1 billion. By default, if the categorical column has more than 1 million rows, JMP does not automatically retrieve the unique category levels.
Retrieve category levels for tables whose size cannot be determined	Determines whether category levels are retrieved for a filtered column when the number of rows cannot be determined. Selected by default. If this option is not selected, the filter is added as a Contains filter.
Default filter type for categorical columns	Specifies a List Box as the default filter type for categorical columns.
Fallback filter type for categorical columns	Specifies a Contains filter as the default filter type for categorical columns when the number of rows cannot be determined or the query is canceled.

Table 13.18 Preferences on the Query Builder Page *(Continued)*

Preference	Description
Run the preview update in the background	Updates the data view Query Preview tab without displaying the status so that you can continue to work while the queries run. This option is selected by default.
Run queries in the background when possible	Runs database queries without displaying the status so that you that can continue to work Query Builder while the queries run. This option is selected by default.

Appendix **A**

Formula Functions Reference


Descriptions of Functions in the Formula Editor

You can add functions to a formula. All of these functions are available in the Functions list of the Formula Editor. This chapter gives a description of functions in the Formula Editor.

More information about functions is available in the following resources:

- The Scripting Index describes all functions and their arguments, demonstrates how the functions work, and links to online Help. In JMP, select **Help > Scripting Index** to view this interactive resource.
- The *JSL Syntax Reference* also provides the arguments for JMP functions, not just those available in the Formula Editor. In JMP, select **Help > JMP Help** and find *JSL Syntax Reference* in the left column.

Figure A.1 Functions in the Formula Editor



For instructions on how to create a formula that contains a function, see [“Create a Formula”](#) on page 352 in the “Formula Editor” chapter.

Contents

Row Functions	633
Numeric Functions	635
Transcendental Functions	636
Trigonometric Functions	639
Character Functions	640
Character Pattern Functions	646
Comparison Functions	650
Conditional Functions	651
Probability Functions	656
Discrete Probability Functions	669
Statistical Functions	672
Random Functions	676
Date Time Functions	681
Row State Functions	684
Assignment Functions	690
Parametric Model Functions	690
Finance Functions	691

Row Functions

Adding a row function to a formula lets you reference specific rows or cells within specific rows. You can also insert values based on an arithmetic sequence. See the JSL Functions chapter in the *Scripting Guide* for details about syntax.

Col Stored Value

Returns the column value that does not have column properties applied to it. If the row is not specified, the current row is used.

Suppose that the Missing Value Codes column property is assigned to the x1 column to treat “999” as a missing value. Another column includes a formula that calculates the mean. To use the value “999” instead of a missing value to calculate the mean, use Col Stored Value in the formula:

```
Mean( Col Stored Value( :x1 ), :x2, :x3 )
```

Count

Creates a list of values beginning with the **from** value and ending with the **to** value. The number of **steps** specifies the number of values in the list between and including the **from** and **to** values. Each value determined by the first three arguments of the count function occurs consecutively the number of times that you specify with the **times** argument. When the **to** value is reached, **Count** starts over at the **from** value.

Also, you can add the **times** argument with the insert button  on the keyboard. This argument is one by default, but repeats the count process as many times as you specify, as illustrated by the Count4 column in the data table in Figure A.2. To add any argument to the **Count** function, highlight the argument preceding the one that you want to enter. Either type a comma or use the insert button  on the Formula Editor keypad.

The columns in the data table below result from the following formulas:

- **Count (1, 9, 2)** gives Count 1
- **Count (1, 9, 3)** gives Count 2
- **Count (1, 9, 9)** gives Count 3
- **Count (1, 9, 3, 3)** gives Count 4

Figure A.2 Example of the Count Function

	count1	count2	count3	count4
1	1	1	1	1
2	9	5	2	1
3	1	9	3	1
4	9	1	4	5
5	1	5	5	5

The **Count** function is useful for generating a column of grid values. For example, the following formulas create a square grid of increment **NRow()**. **NRow()** is the **Row** function that gives the total number of rows in the data table) and axes that range from -5 to 5:

```
Count(-5, 5, Root( NRow() ) );  
Count(-5, 5, Root( NRow() ), Root( NRow() ) );
```

Dif

Returns the difference between the value of the first argument in the current row and its value in the row defined by the current row less the second argument. The default **Dif** is one, which you can change to any number. Note that **Dif(X, n)** gives the same result as $X_{Row()}-X_{Row()-n}$ or as $X_{Row()}-Lag(X, n)$.

Lag

Returns the value of the first argument in the row defined by the current row less the second argument. The default **Lag** is one, which you can change to any number. The value returned for any lag that identifies a row number less than one is missing. Note that **Lag(X, n)** gives the same result as the subscripted notation, $X_{Row()-n}$.

NRow

Returns the total number of rows in the active data table.

Row

Returns the current row number when an expression is evaluated for that row. You can use **Row()** in any expression, including column name subscripts. The default subscript of a column name is **Row()** unless otherwise specified.

Subscript

Enables you to use a column’s value from a row other than the current row. After choosing **Subscript** from the list, enter a numeric expression into the subscript argument. Subscripts that evaluate to nonexistent row numbers produce missing values. Column names with no subscript refers to the current row. To remove a subscript, select the subscript and delete it. Then delete the missing box.

The formula $\text{Count}_{\text{Row}()} - \text{Count}_{\text{Row}()-1}$, where **Row()** is the row number as described below, uses subscripts to calculate the difference between each pair of values from the column named **Count**. This result is the same as that given by the **Dif()** function. When **Row()** is 1, the computation produces a missing value.

The formula below calculates a column called **Fib**, which contains the terms of the *Fibonacci* series (each value is the sum of the two preceding values in the calculated column).

$$\text{If} \left[\begin{array}{l} \text{Row}() \leq 2 \Rightarrow 1 \\ \text{else} \quad \Rightarrow \text{Fib}_{\text{Row}()-1} + \text{Fib}_{\text{Row}()-2} \end{array} \right]$$

It shows the use of subscripts to do recursive calculations. A recursive formula includes the name of the calculated column, subscripted such that it references only previously evaluated rows (rows 1 through $(i-1)$). The calculation of the Fibonacci series shown includes a conditional expression and a comparison. See the sections “[Conditional Functions](#)” on page 651, and “[Comparison Functions](#)” on page 650, for details.

Sequence

Produces an arithmetic sequence of numbers across the rows in a data table, where the start value, ending limit, and increment are specified as arguments.

Numeric Functions

You can create a formula that contains arithmetic operators that are commonly used in formulas. See the JSL Functions chapter in the *Scripting Guide* for details about syntax.

Abs

Returns a positive number of the same magnitude as the value of its argument. For example, **Abs(5)** and **Abs(-5)** both result in 5.

Ceiling

Returns the smallest integer greater than or equal to its argument. For example, **Ceiling(2.3)** results in 3, while **Ceiling(-2.3)** results in -2.

Floor

Returns the largest integer less than or equal to its argument. For example, **Floor(2.7)** results in 2, but **Floor(-0.5)** results in -1.

Integrate

Integrates an expression with respect to a scalar value, using the adaptive quadrature method from Gander and Gautschi (2000). For example, **Integrate(Exp(-x), x, 0, .)** results in 0.99999999986846.

Modulo

Returns the remainder when the second argument is divided into the first. For example, **Modulo(6, 5)** results in 1.

Round

Rounds the first argument to the number of decimal places given by the second argument. For example, **Round(3.554, 2)** rounds to 3.55 and **Round(3.555, 2)** rounds to 3.56.

Transcendental Functions

You can create a formula that supports transcendental functions, such as logarithmic functions for any base, functions for combinatorial calculations, the **Beta** function, and several gamma functions. See the JSL Functions chapter in the *Scripting Guide* for details about syntax.

Exp

Raises e to the power that you specify. Thus, **Exp(1)** = e .

ExpM1

Returns a more accurate calculation of **Exp(x) - 1** when x is very small.

Ln and LnZ

Calculates the natural logarithm of x , except returns 0 when x is 0; for use with derivatives.

Log and Log10

Calculates the natural logarithm (base e). To change the default base, highlight the argument and type a comma or click the insert key on the keypad. The base appears and is editable. The **Log** argument can be any numeric expressions. The expression **Log(e)** evaluates as 1, and **Log(32,2)** is 5. The **Log10** function calculates the logarithm of base 10 only.

Log1P

Returns a more accurate calculation of **Log(1+x)** when x is very small.

Squash

Computes the function $1 / (1 + e^x)$, where x is any numeric column, variable, or expression.

Logist

Also known as Squish or Logistic, is an efficient computation of the function $1 / (1 + e^{-x})$, where x is any numeric column, variable, or expression.

Root or Square Root

Calculates the root of its argument as specified by the index. **Root** initially shows with an index of 2. To change the index, highlight the index argument and enter the value that you want.

Factorial

Returns the product of all numbers 1 through the argument that you specify. For example, **Factorial(5)** evaluates as 120.

NChooseK

Returns the number of n things taken k at a time (n select k) and is computed in the standard way using factorials, as $n! / (k!(n - k)!)$. For example, **NChooseK(5,2)** evaluates as 10.

Beta

Adds the two parameter **Beta** function and is written terms of the Gamma function as:

$$B(m, n) = \frac{\Gamma(m)\Gamma(n)}{\Gamma(m + n)}$$

Gamma

Adds the **Gamma** function, denoted $\Gamma(i)$, and is defined as:

$$\Gamma(i) = \int_0^{\infty} (x^{i-1})(e^{-x})dx$$

Gamma with a single argument is the same as **Gamma(x, infinity)**. The optional second argument changes the upper integer from infinity to the value that you enter. Other interesting gamma function relationships are

- for any $\alpha > 1$, $\Gamma(\alpha) = (\alpha-1) \cdot \Gamma(\alpha-1)$
- for any positive integer, n , $\Gamma(n) = (n-1)!$
- $\Gamma(0.5) = \text{the square root of } \pi$

LGamma

Is the natural log of the result of the gamma function evaluation. You get the same result using the **Log** (natural log) function with the **Gamma** function. However, the **LGamma** function computes more efficiently than do the **Log** (natural log) and the **Gamma** functions together. **NChooseK** is implemented using **LGamma** functions. The result is not always an exact integer. If the result is close to an integer, it is rounded up using the **Floor** function.

Digamma

The logarithmic derivative of the **Gamma** function.

Trigamma

The derivative of the **Digamma** function, or the logarithmic second derivative of the **Gamma** function.

Arrhenius

Calculates the non-specific component of the Arrhenius relationship that is then multiplied by the activation energy in the Arrhenius equation.

$$\frac{11605}{T + 273.15}$$

Arrhenius Inv

The inverse of the Arrhenius function:

$$\left(\frac{11605}{y} \right) - 273.15$$

Logit

Applies the logit transformation to the argument using:

$$\text{logit}(p) = \log\left(\frac{p}{1-p}\right)$$

Logit Percent

Calculates the logit as a percent for the argument.

$$\text{LogitPct}(pct) = \log\left(\frac{\left(\frac{pct}{100}\right)}{1 - \left(\frac{pct}{100}\right)}\right)$$

Logist Percent

Calculates the logistic as a percent for the argument.

$$\text{LogisticPct}(x) = \frac{100}{(1 + e^{-x})}$$

Scheffe Cubic

Is used in fitting certain models. **Scheffe Cubic (X1, X2)** is equivalent to **X1*X2*(X1-X2)**.

Trigonometric Functions

You can create a formula that supports trigonometric functions, such as sine and cosine. JMP's trigonometric functions expect all angle arguments in radians. See the JSL Functions chapter in the *Scripting Guide* for details about syntax.

Sine, Cosine, Tangent

The **Sine** and **Cosine** functions calculate the sine and cosine of their respective arguments given in radians. For example, the expression **Sine(0)** evaluates as 0, and **Cosine(0)** evaluates as 1. The tangent function calculates the tangent of an argument given in radians. The expression **Tan(Pi()/4)** evaluates as 1.

ArcSine, ArcCosine, ArcTangent

The **ArcSine** and **ArcCosine** functions return the inverse sine and inverse cosine of their respective arguments. The returned value is measured in radians. For example, both expressions **ArcSine(1)** and **ArcCosine(0)** evaluate as 1.57080. The **ArcTangent** function returns the inverse tangent of its argument. The returned value is measured in radians. The expression **ArcTangent(1)** evaluates as 0.78540 (=3.14159/4).

SinH, CosH, TanH

The **SinH** and **CosH** functions return the hyperbolic sine and hyperbolic cosine of their respective arguments. The expression **SinH(1)** evaluates as 1.175201, and **CosH(0)** evaluates as 1.0. The **TanH** function returns the hyperbolic tangent of its argument. The expression **TanH(1)** evaluates as 0.761594.

ArcSinH, ArcCosH, ArcTanH

The **ArcSinH** and **ArcCosH** functions return the inverse hyperbolic sine and inverse hyperbolic cosine of their respective arguments. The expression **ArcSinH(1)** evaluates as 0.881374, and

ArcCosH(1) is 0. The **ArcTanH** function returns the inverse hyperbolic tangent of its argument. The expression **ArcTanH(0.5)** evaluates as 0.549306.

Character Functions

You can create a formula that accepts character arguments or returns character strings and converts the data type of a value from numeric to character, or character to numeric. When you create these formulas, note that:

- Character functions can result in either character or numeric data. If you calculate a data type different from the one specified, the data type of the computed column is automatically changed to match the result.
- Arguments that are literal character strings must be enclosed in quotation marks.

See the JSL Functions chapter in the *Scripting Guide* for details about syntax.

Char

Produces a character string that corresponds to the digits in its numeric argument. For example, **Char(1.123)** evaluates as 1.123. See the Types of Data chapter in the *Scripting Guide* for details.

Collapse Whitespace

Trims leading and trailing whitespace and replaces interior whitespace with single space. That is, if more than one white space character is present, the **Collapse Whitespace** command replaces the two spaces with one space.

Concat ||

Concatenates character strings to produce a new string with the function's second character argument appended to the first. For example, **"Dr." || " " || name** produces a new string consisting of the title **Dr.** followed by a space and the contents of the *name* string. (See also ["Concat Items"](#) on page 645.)

Contains

Returns the numeric position within the first argument of the first instance of the second argument, if it exists. The second argument can contain one or more characters. If the second argument does not exist, **Contains** returns a zero. For example, **Contains("Veronica Layman", "ay")** evaluates as 11. **Contains("Lillie Layman", "L")** evaluates as 1. The third argument is optional and is a numeric value that specifies the starting position. If *offset* is negative, **Contains** searches backward from *offset* from the end of the string.

Munger

Computes new character strings from existing strings by inserting or deleting characters. It can also produce substrings, calculate indices, and perform other tasks depending on how you specify its arguments. The **Munger** function treats uppercase and lowercase letters as different characters.

Text is a character expression. **Munger** applies the other three arguments to this string to compute a result.

Offset is a numeric expression indicating the starting position to search in the string. If **Offset** is greater than the position of the first instance of the find argument, the first instance is disregarded.

Find/Length is a character or numeric expression. Use a character string as search criterion, or use a positive integer to return that number of consecutive characters starting from the **Offset** position. If you specify a negative integer as the **Length** value, **Munger** returns all characters from the **Offset** through to the end of the string.

Replace (optional argument) can be a string or unspecified. If it is a string and the **Find/Offset** value is numeric, **Munger** replaces the search criterion with the **Replace string** to form the result. If the **Find/Offset** value is numeric and no string is specified, **Munger** calculates a substring. If the **Find/Length** value is a character string, **Munger** always returns the numeric offset, disregarding the **Replace** value if it exists. To insert the **Replace** argument, click any argument in the **Munger** function and then click the insert button. Use the delete key on your keyboard or the delete button () on the Formula Editor keypad to remove the **Replace** argument.

Lowercase, Uppercase

The **Lowercase** function converts any uppercase character found in its argument to the equivalent lowercase character. For example, **Lowercase**("VERONICA LAYMAN") evaluates as veronica layman. The **Uppercase** function converts any lowercase character found in its argument to the equivalent uppercase character. For example, **Uppercase**("Veronica Layman") evaluates as VERONICA LAYMAN.

Length

Calculates the length of its argument. For example, **Length**("Veronica") evaluates as 8. If the argument is

- a string, length returns the number of characters;
- a list, length returns the number of items in the list;
- a blob (binary object), the number of bytes.

Num

Produces a numeric value that corresponds to its character string argument when the character string consists of numbers only. If a character string contains a non-numeric value, the result is a missing value. For example, **Num**("1.123") evaluates as 1.123.

Substr

Extracts the characters that are the portion of the first argument. Begins at the position given by the second argument, and ends based on the number of characters specified in the third argument. The first argument can be either a character column or a literal value. The starting argument and the length argument can be numbers of expressions that evaluate to numbers. For example, to show the first name only, **Substr**("Veronica Layman", 10, 6) starts at position 10 and reads through position 15, which yields **Layman**.

If *start* is negative, **Substr** searches backward from *start* from the end of the string. If *length* is negative or absent, **Substr** returns a string that begins with *start* and continues to the end of the text string.

Substr can also be used with lists.

Titlecase

Converts the string to title case, that is, an initial uppercase character and subsequent lowercase characters. For example, **Titlecase**("Veronica layman") results in **Veronica Layman**.

Trim

Produces a new character string from its argument, removing any leading and trailing whitespace. The second argument determines if whitespace is removed from the **left**, the **right**, or **both** ends of the string. If no second argument is used, whitespace is removed from both ends. For example, **Trim**("john ") evaluates as **john**. **Trim**(" john ", **both**) also evaluates as **john**.

Word

Extracts the n^{th} word from a character string. One or more spaces define where each word begins and ends unless the optional **delimiters** argument is specified. For example, **Word**(2, "Veronica Layman") returns the word **Layman**.

To insert the **delimiters** argument, click on any argument in the **Word** function and then click the insert button  on the Formula Editor keypad. Use the delete key on your keyboard or the delete button  on the Formula Editor keypad to remove the **delimiters** argument. If you do not specify a delimiter, space is used as the delimiter. If you define the delimiter as an empty string, each character is treated as a separate word.

Most special characters act as single delimiters. You can enter any character or set of characters to act as a word delimiter. For example, to extract the last name in the following

example, use a comma and blank together as the delimiting characters and ask for the first word. **Word**(1, "Layman, Veronica", ", ") returns the word **Layman**.

Words

Extracts the words from *text* according to the delimiters listed in the optional second argument. The default delimiter is space. For example, **Words**("the quick brown fox") returns {"the", "quick", "brown", "fox"}.

If you include a second argument, any and all characters in that argument are taken to be delimiters. For example, **Words**("Doe, Jane P.", ", .") returns {"Doe", "Jane", "P"}.

To insert the **delimiters** argument, click on any argument in the **Words** function and then click the insert button  on the Formula Editor keypad. Use the delete key on your keyboard or the delete button  on the Formula Editor keypad to remove the **delimiters** argument. If you do not specify a delimiter, white space is used as the delimiter. If you define the delimiter as an empty string, each character is treated as a separate word.

Left, Right

Returns a substring of the left-most or right-most *n* characters of the string *text*, respectively. Both functions also work with lists.

Starts With, Ends With

Returns 1 if *whole* begins or ends with *part*, respectively. Returns 0 otherwise. Both functions also work with lists.

Item

Is different than the **Word** function because of the way it treats word delimiters. If a delimiter is found multiple times, or you enter a delimiter with multiple characters, the **Word** function treats them as a single delimiter. The **Item** function uses each delimiter to define a new word position. To compare, suppose a name is of the form lastname, firstname. The delimiter is a comma followed by a blank, such as:

Item(2, "Layman, Veronica", ", ")

Word(2, "Layman, Veronica", ", ")

The **Item** function returns a missing value because it treats the comma and blank separately and finds nothing between them. The **Word** function treats the comma and blank as a single delimiter and finds **Veronica** as the second word.

If you do not specify a delimiter, white space (blank space) is used as the delimiter. If you define the delimiter as an empty string, each character is treated as a separate item.

Char to Hex, Hex, Hex to Char, Hex to Number

Converts between Hex and other formats.

Hex returns the hexadecimal representation of its argument. If the argument is character (in quotes), then the result is a character string twice as long containing the hexadecimal codes for the character values. For example, **Hex("A")** returns the string 41.

If the argument is numeric and “integer” is specified, the Hex function returns an 8-hexadecimal-character representation of the integer returned. For example, **Hex(12, “integer”)** returns the string 0000000C.

Hex to Char converts hexadecimals to characters. The resulting character string might not be valid display characters. All the characters must be in pairs, in the ranges 0-9, A-Z, and a-z. Blanks and commas are allowed and skipped.

Char to Hex converts characters to hexadecimals.

Hex to Number converts hexadecimals to numbers.

For details, see the Types of Data chapter in the *Scripting Guide* book.

Repeat

Creates a string that is the first argument repeated the number of times specified by the second argument. The first argument can be either a character literal, a character variable, or a character expression. For example, **Repeat(“Katie”, 3)** creates **KatieKatieKatie**.

A third argument applies when **Repeat** is used in a JSL script to repeat a matrix. When the first argument is a matrix, the second argument is the rowwise repeat and the third argument is the columnwise repeat.

Insert, Insert Into

Insert inserts a new item into the *list* or *expression* at the given position. If position is not given, it is inserted at the end.

Insert Into is the same as insert, but it inserts in place.

Remove, Remove From

Remove the character(s) at the indicated *position*. If *n* is omitted, the item at *position* is deleted. If position and *n* are omitted, the item at the end is removed. There are three possible arguments: the string, followed by the position, followed by the number of characters to be removed.

Remove From returns items removed in place. The function returns the removed item(s), but you do not have to assign them to anything. The first argument is a variable name, followed by the position, followed by the number of characters to be removed.

Shift, Shift Into

Shift shifts an item or *n* items from the front to the back of the *list* or *expression*. Shifts items from back to front if *n* is negative. **Shift Into** shifts items in place.

Reverse, Reverse Into

Reverse reverses the characters in the string. **Reverse Into** reverses the characters in place.

Concat Items

Concat Items converts a list of string expressions into one string, with each item separated by a delimiter. The delimiter is a blank, if unspecified.

Substitute, Substitute Into

The first argument is a string, the second is a pattern, and the third is a replacement string. **Substitute** finds all matches to the pattern in the string, and replaces them with the replacement string. **Substitute Into** does the same substitution in place.

Regex

The first argument is the source string that Regex searches for a match to the pattern. The second argument is the pattern, in the form of a regular expression. The Formula Editor prompts you for these two required arguments.

Tip: For more information about using regular expressions, search the Internet for *regular expression tutorial*.

By default, Regex performs a case-sensitive search and returns the parts of the source string that match the pattern that you specified (or returns MISSING if the match fails). There are two optional arguments that you can add. You can type a third argument—the *format*—that specifies the string to return. If you choose, you can use regular expressions to specify replacement text in the returned string. If you specify the third argument, you can also specify **IGNORECASE** so that Regex ignores capitalization when searching the source string for a match.

Table A.1 Regex Examples

Sample Regex function	String that is returned
Regex("@ q3 #", "[a-z]([0-9])")	q3 The function is case sensitive, so q3 matches but Q3 would not.

Table A.1 Regex Examples (*Continued*)

Sample Regex function	String that is returned
Regex("@ Q3 #", "[a-z]([0-9])", "\0", IGNORECASE)	Q3 Although \0 is the default argument, it is required in this example so that IGNORECASE can be specified.
Regex("@ Q3 #", "[a-z]([0-9])", "\2\1", IGNORECASE)	3Q

For more information and an example that you can run, select **Help > Scripting Index** and do a search for **Regex**.

XPath Query

XPath Query parses a valid XML document for the expression that you specify. For an example, select **Help > Scripting Index** and search for the function.

Hex to Blob, Char to Blob, Blob to Char

- Hex to Blob** converts the hexadecimal to a blob (Binary Large Object).
- Char to Blob** converts the string to a blob. You can specify the encoding in an optional second argument. The default encoding for the blob is utf-8. utf-16le, utf-16be, us-ascii, iso-8859-1, shift-jis, euc-jp, and ascii~hex are also supported.
- Blob to Char** converts the blob to a string. You can specify the encoding in an optional second argument. The default encoding for the character string is utf-8. utf-16le, utf-16be, us-ascii, iso-8859-1, shift-jis, euc-jp, and ascii~hex are also supported.

Character Pattern Functions

These functions provide powerful pattern matching abilities. Pattern matching is a flexible method for searching and manipulating strings, and regular expressions are also supported. When you create these formulas, note that:

- First, you define a pattern with one more of the character patterns.
- Then, you use **Pat Match** to compare a string to the pattern.
- **Pat Match** returns True (1) if the pattern is found in the string, or it returns False (0) if the pattern was not found in the string.
- To use regular expressions instead of patterns, use **Regex Match**.

For examples, see the Types of Data chapter in the *Scripting Guide*.

Pat Any

Constructs a pattern that matches a single character in the argument.

Pat Not Any

Constructs a pattern that matches a single character that is not in the argument.

Pat Break

Constructs a pattern that matches zero or more characters that are not in its argument; it stops or breaks on a character in its argument. It fails if a character in its argument is not found. In particular, it fails to match if it finds the end of the source string without finding a break character.

Pat Span

Constructs a pattern that matches one or more (not zero) occurrences of characters in its argument. It is greedy; it always matches the longest possible string. It fails rather than matching zero characters.

Pat String

Constructs a pattern that matches its string argument.

Pat Len

Constructs a pattern that matches *n* characters.

Pat Pos

Constructs patterns that match the null string if the current position is *int* from the left end of the string, and fail otherwise.

Pat R Pos

Constructs patterns that match the null string if the current position is *int* from the right end of the string, and fails otherwise.

Pat Tab

Constructs a pattern that matches forward to position *int* in the source string. It can match 0 or more characters. It fails if it would have to move backwards or beyond the end of the string.

Pat R Tab

Constructs a pattern that matches up to position *n* from the end of the string. It can match 0 or more characters. It fails if it would have to move backwards or beyond the end of the string.

Pat Test

Constructs a pattern that succeeds and matches the null string if *expr* is not zero and fails otherwise.

Pat At

Constructs a pattern that matches the null string and stores the current position in the source string into the specified JSL variable (*varName*). The assignment is immediate, and the variable can be used with `expr()` to affect the remainder of the match.

Pat Rem

Constructs a pattern that matches the remainder of the string. It is equivalent to `patRTab(0)`.

Pat Arb

Constructs a pattern that matches an arbitrary string. Initially it matches the null string. It matches one additional character each time the pattern matcher backs into it.

Pat Succeed

Constructs a pattern that always succeeds, even when the matcher backs into it. It matches the null string.

Pat Fail

Constructs a pattern that fails whenever the matcher attempts to move forward through it. The matcher backs up and tries different alternatives. If and when there are no alternatives left, the match fails and `Pat Match` returns 0.

Pat Abort

Constructs a pattern that immediately cancels the pattern match. The matcher does not back up and retry any alternatives. Conditional assignments are not made. Immediate assignments that were already made are kept.

Pat Fence

Constructs a pattern that succeeds and matches the null string when the matcher moves forward through it, but fails when the matcher tries to back up through it. It is a one-way trap door that can be used to optimize some matches.

Pat Arb No

Constructs a pattern that matches zero or more copies of pattern.

Pat Repeat

Matches pattern between minimum and maximum times.

Pat Conditional

Saves the result of the pattern match, if it succeeds, to a variable named as the second argument (type) after the match is finished.

Pat Immediate

Saves the result of the pattern match to a variable named as the second argument (*varName*) immediately.

Pat Altern

Constructs a pattern that matches any one of the pattern arguments.

Pat Concat

Constructs a pattern that matches each pattern argument in turn.

Pat Regex

Constructs a pattern that matches the regular expression in the quoted string argument.

Pat Match

Pat Match executes a pattern match using the source in the first argument and the pattern in the second argument. The pattern must be constructed first, either inline or by assigning it to a JSL variable elsewhere. A third argument, if present, is the replacement text for the matched characters in the source argument (if the source argument is a variable). Pat Match returns true if the match succeeds. Additional arguments, in any order, are ANCHOR (match must begin at start of source), FULLSCAN (turn off some optimizations for special situations), and MATCHCASE (by default, A == a).

Pat Match returns true or false rather than a string, so Pat Match is somewhat difficult to use in a formula. You might find the Regex function ("[Regex](#)" on page 645) easier to use when you are adding pattern-matching formulas in the Formula Editor.

Regex Match

Regex Match is similar to Pat Match. Regex Match executes a pattern match using the source in the first argument and the pattern in the second argument. Regex Match uses a regular

expression for the second argument and returns a list of information about the result of the match.

A simpler function, `Regex` ("[Regex](#)" on page 645), is also available. `Regex` returns a string value rather than a list, so `Regex` is usually easier to use in the Formula Editor than `RegEx Match`.

Comparison Functions

You can create a formula that compare the values of two arguments by using the comparison function. Each comparison relationship evaluates as *true* or *false* based on numeric magnitudes or character rankings. A true relationship evaluates as one, and false evaluates as zero.

Comparisons are useful when you include them in conditional expressions, but they can also stand alone as numeric expressions if neither term in comparison is missing. A relational symbol's arguments can be any two expressions. However, both arguments in a comparison function must be of the same data type. Also note that:

- JMP displays an error if you use a single "=" in a conditional where "==" is expected.
- The Formula Editor uses the International Utilities package when comparing character strings. This package contains different rankings for each international character set and takes diacritical marks into consideration.
- You should not use comparison operators to specifically compare to a missing value. Instead, use the **Is Missing** function to detect a missing value.

See the JSL Functions chapter in the *JSL Syntax Reference* for details about syntax.

< Less than

> Greater than

<= Less than or equal to

>= Greater than or equal to

== Equal to

!= Not equal to

a<b<=c *b* is greater than *a* and less than or equal to *c*

a<=b<c *b* is greater than or equal to *a* and less than *c*

Is Missing Returns a one (1) if the value of the argument for the current row is missing, and a zero if the value is not missing.

Conditional Functions

You can include conditional expressions (called *conditionals* for short) in your formulas. These expressions let you build a sequence of clauses paired with result expressions. Constructing a sequence of clauses is the way you conditionally assign values to cells in a calculated column. Conditionals follow these rules:

- When no clause is true, the Formula Editor evaluates the result expression that accompanies the else clause.
- All result expressions in a conditional expression must evaluate to the same data type.
- A missing term matches any data type.
- By definition, expressions that evaluate as zero are false.
- If an expression evaluates as missing, no clauses are executed and missing is returned. All other numeric expressions are true.

See the Building Blocks chapter in the *Scripting Guide* and the JSL Functions chapter in the *JSL Syntax Reference* for details about syntax.


Use the insert and delete clause buttons on the Formula Editor panel to expand the expression. For maximum efficiency, list the most frequently evaluated clause and result pairs first in the sequence.

Note: **Interpolate**, **Step**, **For**, and **While** are most often used in conjunction with other commands to build a JSL script. You can use the Formula Editor to create and execute a script in that column, but this is not recommended because of dependencies and ambiguities that can result. Most often, scripts are stored as .jsl files, and can be saved with a data table as a table property. For details about table properties, see “[Table Panel](#)” on page 42 in the “Get Started” chapter. For documentation of scripting commands, see the *JSL Syntax Reference*.

If

Shows a single **If** condition with a missing expression and a missing **then clause**. Highlight either **expr** or **then clause** and enter a value. For example, to calculate count as a percentage of total when total is not 0, enter the conditional expression (using columns called **count** and **total**) in Figure A.3.

Figure A.3 A Conditional Expression



To add a new condition to the **If** conditional, highlight **then clause** and click the insert button () on the Formula Editor keypad. Initially, this changes the existing **else** condition to an **expr** clause. Click the insert button again to add an **else clause**. Highlighting **then** or **else** and repetitively clicking the insert button changes the **else** to **expr** or adds a new **expr** clause.

To delete a clause, select the **then clause** above it and press the delete key on your keyboard or click the delete button () on the Formula Editor keypad.

By definition, expressions that evaluate as zero are false. If an expression evaluates as missing, no clauses are executed and missing is returned. All other numeric expressions are true.

Match


Compares an expression to a list of clauses and returns the value of the resulting expression for the first matching clause encountered. You provide the matching expression only once and then give a match value for each clause.

After you select **Match** in the Formula Editor, a list appears with two options:

- Select **Add Match Arguments from Data**, and clauses that correspond to all of the levels in your data are added automatically. Alternatively, hold down the Shift key, select **Conditional**, and then select **Match**. In Figure A.4, the example on the left shows clauses that were added automatically.
- Select **Don't Add** so that you can add each clause individually. In Figure A.4, the example on the right shows an empty clause, which you fill with the missing expressions.

Figure A.4 Examples of Using the Match Function

automatically added Match arguments



empty Match argument



In an automatically filled argument, you should highlight **then clause**, and then enter an expression. In an empty argument, you highlight either **expr**, **value**, or **then clause**, and then enter an expression. (Or, if you highlight an expression and click **Match**, the Formula Editor creates a new **Match** conditional, with the original highlighted expression as **expr** and nothing for the **value** and **else clause**.) Also, keep in mind that:

- **Match** evaluates faster and uses less memory than an equivalent **If** because the variable is evaluated only once for each row in the data table. The **If** condition must evaluate the variable at each **If** clause for each row until a clause evaluates as true. See [“Comparison Functions”](#) on page 650, for a comparison of **Match** and **If** conditionals.

- With **If** and **Match**, the Formula Editor searches down from the top of the sequence for the first true clause and evaluates the corresponding result expression. Subsequent true clauses are ignored.

In the following example, each value is assigned depending on the value of the *age* variable.

Figure A.5 An Example of Using the Match Function

12	⇒	0
13	⇒	2.1
14	⇒	6.2
15	⇒	6.4
16	⇒	6.2
17	⇒	8.5
else	⇒	

Note: **Match** ignores trailing spaces and **If** does not.

Although **Match** returns missing for any missing values, you can also specifically match missing values.

Choose

Choose is a special case of **Match** in which the arguments of the condition are a sequence of integers starting at one. The value of **clause** replaces the match condition. An example of a **Choose** condition is shown in Figure A.6. With **Choose**, the Formula Editor goes directly to the correct choice clause and evaluates the result expression.

Figure A.6 Example of a Choose Condition

Choose(*expr*)(else ⇒ *clause*)

Choose(*expr*)(1 ⇒ *clause*)

Choose(*expr*)(1 ⇒ *clause*, 2 ⇒ , else ⇒)

When you highlight an expression and click **Choose**, the Formula Editor creates a new conditional expression with one **clause**. Use the insert () and delete () buttons on the keypad to add new clauses or remove unwanted clauses, as described previously for the **If** conditional.

Choose evaluates the **Choose** expression and goes immediately to the corresponding result expression to generate the returned value. With **Choose**, you provide a choosing expression that yields sequential integers starting at 1 only once, and then you give a choice for each integer in the sequence.

IfMax


Evaluates the first of each pair of arguments and returns the evaluation of the result expression (the second of each pair) associated with the maximum of the expressions. If more than one expression is the maximum, the first maximum is returned. If all expressions are missing and a final result is not specified, missing is returned. If all expressions are missing and a final result is specified, that final result is returned. The test expressions must evaluate to numeric values, but the result expressions can be anything.

IfMin


Evaluates the first of each pair of arguments and returns the evaluation of the result expression (the second of each pair) associated with the minimum of the expressions. If more than one expression is the minimum, the first minimum is returned. If all expressions are missing and a final result is not specified, missing is returned. If all expressions are missing and a final result is specified, that final result is returned. The test expressions must evaluate to numeric values, but the result expressions can be anything.

And &

Evaluates as 1 when both of its arguments are true. Otherwise, it evaluates as 0. (See Figure A.9.) The formula in Figure A.7 labels Group 1 as drivers only if both comparisons are true.

Figure A.7 Creating an And Function**Or |**

Evaluates as 1 when either of its arguments is true. If both of its arguments are false, then the Or expression evaluates as 0. (See Figure A.9.) The formula in Figure A.8 assigns males and all participants who are more than 13 years old to Group 1.

Figure A.8 Creating an Or Function

The truth tables on the left in Figure A.9 illustrate the results of the **And (&)** and **Or (|)** functions when both arguments have nonmissing values that evaluate to true or false. The table on the right illustrates the result when either the left or right expression (call them **a** and **b**) or both have missing values.

Figure A.9 Evaluations of And and Or Expressions

and &				or			
True		False		True		False	
True	1	0		True	1	1	
	0	0			1	0	

a	b	a b	a & b
false	•	•	false
true	•	true	•
•	false	•	false
•	true	true	•
•	•	•	•

Not !

Evaluates as 1 when its argument is false. Otherwise, **Not** evaluates as 0. When you apply the **Not** function, use parentheses where necessary to avoid ambiguity. For example, `!(weight==64)` can be either true or false (either 1 or 0), but `(!weight)==64` is always false (0) because **Not** can return only 0 or 1. Expressions such as `!(weight==64)` can also be entered as `weight != 64`.

Interpolate

Linearly interpolates the y -value between two points, x_1 , y_1 and x_2 , y_2 that corresponds to the arguments that you give. You can insert additional pairs of x , y arguments with the insert key. **Interpolate** finds the pair of x , y points that correspond to the x -value and completes the interpolation.

Figure A.10 Examples of Interpolate

Interpolate(x)($x_1 \Rightarrow y_1$);
Interpolate(x)($x_1 \Rightarrow y_1$);
Interpolate(x)($x_2 \Rightarrow y_2$);

Step

Step is like **Interpolate** except that it returns the y -value corresponding to the greatest x -value less than or equal to the x and y arguments. That is, it finds the corresponding y for a given x from a step function rather than a linear fit between points. Like **Interpolate**, you can have as many x and y argument pairs as you want.

Figure A.11 Examples of Step

Step(x)($x_n \Rightarrow y_n$);
Step(x)($x_n \Rightarrow y_n$);
Step(x)($\square \Rightarrow \square$);

For

Repeats the statements in the **body** argument as long as the **while** condition is true. The **init** and **next** control the iterations.

While

Repeatedly tests the **expr** condition and executes the **body** until **expr** is no longer true.

Break, Continue

Break stops execution of a loop completely and continues to the statement following the loop. **Continue** ends the current iteration of a loop and begins the loop at the next iteration.

Both are used in **For**, **While**, and **For Each Row** loops.

Stop

Immediately stops a script that is running.

Probability Functions

You can create a formula that calculates probabilities and quantiles for statistical distributions like beta, Chi-square, F, gamma, normal, Student's t, Weibull distributions, Tukey HSD, and so on. See the JSL Functions chapter in the *JSL Syntax Reference* for details about syntax.

Normal Density

Accepts an argument from the range of values for the standard normal distribution, which is all real numbers. It returns the value of the standard normal probability density function (pdf) for the argument. For example, you can create a column of values (X) with the formula **count(-3, 3, nrow())**. In a second column, insert the formula **Normal Density(X)** to generate density values. Then select **Graph > Graph Builder** to plot the normal density by X.

Normal Distribution

Accepts an argument x from the range of values for the standard normal distribution, which is all real numbers. It returns the probability that an observation from the standard normal distribution is less than or equal to x . For example, the expression **Normal Distribution(1.96)** returns 0.975, the probability that an observation from the standard normal distribution is less than or equal to the quantile 1.96. Also, you can specify mean and standard deviation parameters to obtain probabilities from nonstandard normal distributions. The **Normal Distribution** function is the inverse of the **Normal Quantile** function.

Normal Quantile (Probit)

Accepts a probability argument p , and returns the p^{th} quantile from the standard normal distribution. For example, the expression **Normal Quantile(0.975)** returns the 97.5% quantile from the standard normal distribution, which evaluates as 1.96. Also, you can specify parameter values for the mean and standard deviation to obtain quantiles from nonstandard normal distributions. The **Normal Quantile** function is the inverse of the **Normal Distribution** function.

Beta Density

Requires three arguments: quantile argument and the shape parameters alpha and beta. A threshold parameter (θ) and a scale parameter ($\sigma > 0$) are additional arguments. It returns the value of the beta probability density function (pdf) for the given arguments. The beta density is useful for modeling the probabilistic behavior of random variables such as proportions constrained to fall in the interval $[0, 1]$.

Beta Distribution

The beta distribution has two shape parameters: $\alpha > 0$ and $\beta > 0$. A threshold parameter (θ) and a scale parameter (σ) are additional arguments, where $\theta \leq x \leq \theta + \sigma$. The default value for θ is 0. The default value for σ is 1.

The beta distribution function is the inverse of the beta quantile function.

Beta Quantile

Accepts a probability argument, p , and shape and scale parameters, $\alpha > 0$ and $\beta > 0$. It returns the p^{th} quantile from the standard beta distribution. The beta quantile function is the inverse of the beta distribution function.

Cauchy Density

Accepts an argument x , which can be any real number, and optional arguments *center* and *scale*. If you do not specify values for the optional arguments, the function returns the value at x of the Cauchy probability density function (pdf) for a distribution with median 0 and third quartile 1.

If you specify values for center and scale, the function returns the value at x of the Cauchy probability function, characterized as follows:

- The optional parameter *center* is the median of the distribution.
- The optional parameter *scale* is half of the interquartile range, namely, half of the difference between the 0.75 and 0.25 quantiles.

Cauchy Distribution

Accepts an argument x , which can be any real number, and optional arguments *center* and *scale*. If you do not specify values for the optional arguments, the function returns the value at x of the Cauchy cumulative distribution function (cdf) for a distribution with median 0 and third quartile 1. If you specify values for center and scale, the function returns the value at x of the cumulative distribution function for the Cauchy distribution with median given by center and interquartile range given by twice the scale.

Cauchy Quantile

Accepts an argument *prob*, which can be any number between 0 and 1, and optional arguments *center* and *scale*. If you do not specify values for the optional arguments, the function returns the p^{th} quantile, where $p = \text{prob}$, of a Cauchy distribution with median 0 and third quartile 1. If you specify values for center and scale, the function returns the p^{th} quantile of a Cauchy distribution with median given by center and interquartile range given by twice the scale.

ChiSquare Density

Accepts a quantile argument from the range of values for the Chi-squared distribution, a degrees of freedom argument, and an optional noncentrality parameter. It returns the value of the Chi-squared density function (pdf) for the arguments.

ChiSquare Distribution

Accepts a response argument (range of x values) and three parameter arguments: a quantile, a degrees of freedom, and a noncentrality parameter. It returns the probability that an observation from the Chi-squared distribution with the specified noncentrality parameter and degrees of freedom is less than or equal to the given quantile. For example, the expression **ChiSquare Distribution(11.264, 5)** returns the probability that an observation from the Chi-squared distribution centered at 0 with 5 degrees of freedom is less than or equal to 11.264. The expression evaluates as 0.95361.

Furthermore, the **ChiSquare Distribution** function accepts integer and noninteger degrees of freedom. It is centered at 0 by default. The **ChiSquare Distribution** function is the inverse of the **ChiSquare Quantile** function.

ChiSquare Log CDistribution

Returns $1 - \log(\text{value})$ of the Chi-square distribution.

ChiSquare Log Density

Returns the log of the value of the Chi-square probability density.

ChiSquare Log Distribution

Returns the log of the value of the Chi-square distribution.

ChiSquare Noncentrality

Returns the noncentrality parameter nc such that probability is equal to the probability that a Chi-square distributed random variable with df degrees of freedom is less than x .

ChiSquare Quantile

Accepts three arguments: a probability p , a degrees of freedom, and a noncentrality parameter. It returns the p^{th} quantile from the Chi-squared distribution with the specified noncentrality parameter and degrees of freedom. For example, the expression **ChiSquare Quantile(95, 3.5, 4.5)** returns the 95% quantile from the Chi-squared distribution centered at 4.5 with 3.5 degrees of freedom. The expression evaluates as 17.50458.

The **ChiSquare Quantile** function accepts integer and noninteger degrees of freedom. It is centered at 0 by default. The **ChiSquare Quantile** function is the inverse of the **ChiSquare Distribution** function.

Dunnett P Value

Returns the p -value from Dunnett's multiple comparison test.

Dunnett Quantile

Returns the quantile needed in Dunnett's multiple comparison tests.

F Density

Accepts a quantile argument from the range of values for the F -distribution, numerator and denominator degrees of freedom arguments, and an optional noncentrality parameter. It returns the value of the F -density function (pdf) for the arguments.

F Distribution

Accepts four arguments: a quantile, a numerator and denominator degrees of freedom, and a noncentrality parameter. It returns the probability that an observation from the F -distribution with the specified noncentrality parameter and degrees of freedom is less than or equal to the given quantile. For example, the expression **F Distribution(3.32, 2, 3)** returns the probability that an observation from the central F -distribution with 2 degrees of freedom in the numerator and 3 degrees of freedom in the denominator is less than or equal to 3.32. The expression evaluates as 0.82639.

The F -distribution function accepts integer and noninteger degrees of freedom. By default, the non-central parameter is set to 0. The F -distribution function is the inverse of the **F Quantile** function.

F Log CDistribution

Returns the log of 1 - F -distribution.

F Log Density

Returns the log of the F probability density.

F Log Distribution

Returns the log of the F -distribution.

F Noncentrality

Solves the noncentrality such that $\text{prob} = F\text{-distribution}(x, \text{ndf}, \text{ddf}, \text{nc})$.

F Power and F Sample Size

The **F Power** function calculates the power from a given situation that involves an F -test or t -test, and the **F Sample Size** function computes the sample size. The arguments are the values that you specify for computation of a prospective power analysis. (These functions perform the same computations as if you selected **DOE > Sample Size and Power**. See the Prospective Power and Sample Size chapter in the *Design of Experiments Guide* for a discussion of power and sample size.) The arguments include:

- **alpha** The significance level that you are willing to tolerate (often 0.05).
- **dfh** The hypothesis degrees of freedom. It is one (1) for a t -test.
- **dfm** The model degrees of freedom (such that $dfe = n - dfm$).
- **SquaredSize** The squared effect size scaled by the error variance, which is used for making the noncentrality argument for the F -distribution. For this argument, use squared size = Δ^2/σ^2 where σ^2 is the error variance. That is, use:

$$\Delta^2 = (\bar{x} - \mu)^2 \text{ for a one-sample } t\text{-test}$$

$$\Delta^2 = \frac{(\bar{x}_1 - \bar{x}_2)^2}{4} \text{ for a two-sample } t\text{-test}$$

$$\Delta^2 = \sqrt{\sum_{i=1}^k \frac{(\bar{x}_i - \bar{x})^2}{k}} \text{ for a } k\text{-sample } F\text{-test}$$

- **n** (found only in the **F Power** function) The total number of observations (runs, experimental units, or samples) you expect to have. Power (in the **F Sample Size** function) is the probability that you want to have of declaring a significant result.

F Quantile

Accepts four arguments: a probability p , a numerator and denominator degrees of freedom, and a noncentrality parameter. It returns the p^{th} quantile from the F -distribution with the specified noncentrality parameter and degrees of freedom. For example, the expression **F Quantile(0.95, 2, 10, 0)** returns the 95% quantile from the F -distribution centered at 0 with 2 degrees of freedom in the numerator and 10 degrees of freedom in the denominator. The expression evaluates as 4.1028.

The **F Quantile** function accepts integer and noninteger degrees of freedom. By default, the non-central parameter is set to 0. The **F Quantile** function is the inverse of the **F Distribution** function.

Frechet Density

Returns the density at x of a Fréchet distribution with location μ and scale σ .

Frechet Distribution

Returns the probability that a Fréchet distribution with location μ and scale σ is less than x .


Frechet Quantile

Returns the quantile associated with a cumulative probability p for a Fréchet distribution with location μ and scale σ .

Gamma Density

Requires a quantile argument. Also accepts an optional alpha shape parameter, which must be greater than zero and defaults to 1. A scale parameter b , which must be greater than zero and defaults to 1, is optional. A threshold parameter, which must be in the range $-\infty < \theta < +\infty$ and defaults to zero, is optional.

Figure A.12 shows the shape of gamma probability density functions for **shape** parameters of 1, 3, and 5. The standard gamma density function is strictly decreasing when α (**shape**) ≤ 1 . When $\alpha > 1$ the density function begins at zero when x is θ , increases to a maximum, and then decreases.

Figure A.12 Gamma Density Example**Gamma Distribution**

Is based on the standard gamma function, and accepts a single argument with a quantile value. The shape, scale, and threshold parameters are optional, with defaults as described previously in the discussion of the **Gamma Density** function. It returns the probability that an observation from a standard gamma distribution is less than or equal to the specified x . The **Gamma Distribution** function is the inverse of **Gamma Quantile** function.

Gamma Log CDistribution

Returns the log of 1 - Gamma distribution.

Gamma Log Density

Returns the log of the Gamma probability density.

Gamma Log Distribution

Returns the log of the Gamma distribution.

Gamma Quantile

Accepts a probability argument p , and returns the p^{th} quantile from the standard gamma distribution with the shape parameter that you specify. The **Gamma Quantile** function is the inverse of the **Gamma Distribution** function.

GenGamma Density

Returns the density at x of a GenGamma probability distribution with parameters μ , σ , and λ .

GenGamma Distribution

Returns the probability that a GenGamma distributed random variable (with parameters μ , σ , and λ) is less than x .

GenGamma Quantile

Returns the quantile from a GenGamma distribution, the value for which the probability is p that a random value would be lower. μ , σ , and λ are parameters, respectively.

GLog Density

Returns the density or pdf at a particular quantile q of a generalized logarithm distribution with location μ , scale σ , and shape λ . When the shape parameter is equal to zero, the distribution reduces to a Lognormal(μ , σ).

GLog Distribution

Returns the probability or cdf that a generalized logarithm distributed random variable is less than q . When the shape parameter is equal to zero, the distribution reduces to a Lognormal(μ , σ).

GLog Quantile

Returns the quantile, the value for which the probability is p that a random value would be lower. When the shape parameter is equal to zero, the distribution reduces to a Lognormal(μ , σ).

Johnson Sb Distribution

Returns the probability that a Johnson Sb-distributed random variable is less than x . There are four optional arguments: γ , δ , θ , and σ . For a description of the Johnson Sb distribution and these parameters, see the JSL Functions chapter in the *JSL Syntax Reference* book.

Johnson Sb Quantile

Returns the p^{th} quantile of the Johnson Sb distribution. There are four optional arguments: *gamma*, *delta*, *theta*, and *sigma*. For a description of the Johnson Sb distribution and these parameters, see the JSL Functions chapter in the *JSL Syntax Reference* book.

Johnson Sb Density

Returns the density at x of a Johnson Sb distribution. There are four optional arguments: *gamma*, *delta*, *theta*, and *sigma*. For a description of the Johnson Sb distribution and these parameters, see the JSL Functions chapter in the *JSL Syntax Reference* book.

Johnson Sl Distribution

Returns the probability that a Johnson Sl-distributed random variable is less than x . There are four optional arguments: *gamma*, *delta*, *theta*, and *sigma*. For a description of the Johnson Sl distribution and these parameters, see the JSL Functions chapter in the *JSL Syntax Reference* book.

Johnson Sl Quantile

Returns the p^{th} quantile of the Johnson Sl distribution. There are four optional arguments: *gamma*, *delta*, *theta*, and *sigma*. For a description of the Johnson Sl distribution and these parameters, see the JSL Functions chapter in the *JSL Syntax Reference* book.

Johnson Sl Density

Returns the density at x of a Johnson Sl distribution. There are four optional arguments: *gamma*, *delta*, *theta*, and *sigma*. For a description of the Johnson Sl distribution and these parameters, see the JSL Functions chapter in the *JSL Syntax Reference* book.

Johnson Su Distribution

Returns the probability that a Johnson Su-distributed random variable is less than x . There are four optional arguments: *gamma*, *delta*, *theta*, and *sigma*. For a description of the Johnson Su distribution and these parameters, see the JSL Functions chapter in the *JSL Syntax Reference* book.

Johnson Su Quantile

Returns the p^{th} quantile of the Johnson Su distribution. There are four optional arguments: *gamma*, *delta*, *theta*, and *sigma*. For a description of the Johnson Su distribution and these parameters, see the JSL Functions chapter in the *JSL Syntax Reference* book.

Johnson Su Density

Returns the density at x of a Johnson Su distribution. There are four optional arguments: *gamma*, *delta*, *theta*, and *sigma*. For a description of the Johnson Su distribution and these parameters, see the JSL Functions chapter in the *JSL Syntax Reference* book.

LEV Density

Returns the density at x of the largest extreme value distribution with location *mu* and scale *sigma*.

LEV Distribution

Returns the probability that the largest extreme value distribution with location *mu* and scale *sigma* is less than x .

LEV Quantile

Returns the quantile associated with a cumulative probability p of the largest extreme value distribution with location *mu* and scale *sigma*.

LogGenGamma Density

Returns the density at x of a LogGenGamma probability distribution with parameters *mu*, *sigma*, and *lambda*.

LogGenGamma Distribution

Returns the probability that a LogGenGamma distributed random variable (with parameters *mu*, *sigma*, and *lambda*) is less than x .

LogGenGammaQuantile

Returns the quantile from a LogGenGamma distribution, the value for which the probability is p that a random value would be lower. *mu*, *sigma*, and *lambda* are parameters, respectively.

Logistic Density

Returns the density at x of a logistic distribution with location *mu* and scale *sigma*.

Logistic Distribution

Returns the probability that the logistic distribution with location *mu* and scale *sigma* is less than x .

Logistic Quantile

Returns the quantile associated with a cumulative probability p of the logistic distribution with location *mu* and scale *sigma*.

Loglogistic Density

Returns the density at x of the loglogistic distribution with location μ and scale σ .

Loglogistic Distribution

Returns the probability that the loglogistic distribution with location μ and scale σ is less than x .

Loglogistic Quantile

Returns the quantile associated with a cumulative probability p of the loglogistic distribution with location μ and scale σ .

Lognormal Density

Returns the density at x of the lognormal distribution with location μ and scale σ .

Lognormal Distribution

Returns the probability that the lognormal distribution with location μ and scale σ is less than x .

Lognormal Quantile

Returns the quantile associated with a cumulative probability p of a lognormal distribution with location μ and scale σ .

Normal Biv Distribution

Computes the probability that an observation is less than or equal to (x,y) with correlation coefficient r where the observation is marginally normally distributed. You can specify the mean and standard deviation for the X and Y coordinates of the observation. The default values are 0 for both means and 1 for both standard deviations.

Normal Log CDistribution

Returns the log of 1 - Normal distribution.

Normal Log Density

Returns the log of the Normal probability density.

Normal Log Distribution

Returns the log of the Normal distribution.

Normal Mixture Density

Returns the density at q of a normal mixture distribution with group means *mean*, group standard deviations *stdev*, and group probabilities *probability*. The *mean*, *stdev*, and *probability* arguments are all vectors of the same size.

Normal Mixture Distribution

Returns the probability that a normal mixture distributed variable with group means *mean*, group standard deviations *stdev*, and group probabilities *probability* is less than q . The *mean*, *stdev*, and *probability* arguments are all vectors of the same size.

Normal Mixture Quantile

Returns the quantile, the values for which the probability is p that a random value would be lower. The *mean*, *stdev*, and *probability* arguments are all vectors of the same size.

SEV Density

Returns the density at x of the smallest extreme distribution with location *mu* and scale *sigma*.

SEV Distribution

Returns the probability that the smallest extreme distribution with location *mu* and scale *sigma* is less than x .

SEV Quantile

Returns the quantile associated with a cumulative probability p of the smallest extreme distribution with location *mu* and scale *sigma*.

SHASH Density

Returns the density at x of the sinh-arcsinh (SHASH) distribution.

SHASH Distribution

Returns the probability that the sinh-arcsinh (SHASH) distribution is less than x .

SHASH Quantile

Returns the quantile associated with a cumulative probability p of the sinh-arcsinh (SHASH) distribution.

t Density

Accepts a quantile argument from the range of values for the t -distribution, a degrees of freedom argument, and an optional noncentrality parameter. It returns the value of the t -density function (pdf) for the arguments. To compare a t -density with 5 df with a standard

normal distribution, you can create a column of quantile values (X) with the formula **count(-3, 3, nrow())**. In a second column, insert the formula **t Density(X, 5)**. In a third column, insert the formula **Normal Density(X)**. Then select **Graph > Graph Builder** to plot the *t*-density and the normal density by X. You will see that the *t*-density has slightly more spread than the normal.

t Distribution

Accepts three arguments: a quantile, a degrees of freedom, and a noncentrality parameter. It returns the probability that an observation from the Student's *t*-distribution with the specified noncentrality parameter and degrees of freedom is less than or equal to the given quantile. For example, the expression **t Distribution(.9, 5)** returns the probability that an observation from the Student's *t*-distribution centered at 0 with 5 degrees of freedom is less than or equal to 0.9. The expression is evaluated as 0.79531. *t*-distribution accepts integer and noninteger degrees of freedom. It is centered at 0 by default, but you can enter a value for the noncentrality parameter. The **t Quantile** function is the inverse of the **t Distribution** function.

t Log CDistribution

Returns $1 - \log(\text{value})$ of the normal distribution function at quantile x for the *t* distribution.

t Log Density

Returns the log of the value of the density function at quantile x for the *t* distribution.

t Log Distribution

Returns the log of the value of the distribution function at quantile x for the *t* distribution.

t Log Noncentrality

Solves the noncentrality such that $prob = T \text{ Distribution}(x, df, nc)$.

t Quantile

Accepts three arguments: a probability p , a degrees of freedom, and a noncentrality parameter. It returns the p^{th} quantile from the Student's *t*-distribution with the specified noncentrality parameter and degrees of freedom. For example, the expression **Student's t Quantile(.95, 2.5)** returns the 95% quantile from the Student's *t*-distribution centered at 0 with 2.5 degrees of freedom. The expression evaluates as 2.558219. The **t Quantile** function is the inverse of the **t Distribution** function. This function also accepts integer and noninteger degrees of freedom. It is centered at 0 by default, but you have the option to enter a value for the noncentrality parameter. The **t Distribution** function is the inverse of the **t Quantile** function.

Tukey HSD Quantile

Accepts a probability argument $1 - \alpha$, and returns the $1 - \alpha$ quantile from Tukey's HSD test for the parameters that you specify. The α argument is the significance level that you

want. $nGroups$ is the number of groups in a study. dfe is the error degrees of freedom (based on the total study sample). This is the quantile used to calculate least significant difference in Tukey's multiple comparisons test.

Tukey HSD P Quantile

Returns the p -value from Tukey's HSD multiple comparisons test.

Weibull Density

Accepts a quantile argument from the range of values for the Weibull distribution, and optional shape, scale, and threshold arguments. The density function for a Weibull distribution with shape parameter β , scale parameter α , and threshold parameter θ is given in the Distributions chapter in the *Basic Analysis* book. The Weibull Density function returns the value of the probability density function (pdf) for the corresponding Weibull distribution.

Weibull Distribution

Accepts a quantile argument x from the range of values for the Weibull distribution, and optional shape, scale, and threshold arguments. The distribution function for a Weibull distribution with shape parameter β , scale parameter α , and threshold parameter θ is given in the *Basic Analysis* book. The Weibull Distribution function returns the probability that an observation is less than or equal to the specified x for the Weibull distribution with the shape, scale, and threshold parameters that you specified. The **Weibull Distribution** function is the inverse of **Weibull Quantile** function.

The Weibull distribution has different shapes depending on the values of α (a scale parameter that affects the x direction) and β (a shape parameter). It often provides a good model for estimating the length of life, especially for mechanical devices and in biology. The two-parameter Weibull is the same as the three-parameter Weibull with a threshold of zero.

Weibull Quantile

Accepts a probability argument p , and returns the p^{th} quantile from the Weibull distribution with the shape, scale, and threshold parameters that you specify. The **Weibull Quantile** function is the inverse of the **Weibull Distribution** function.

Discrete Probability Functions

Gamma Poisson Probability

Returns the probability or pmf that a gamma-Poisson distributed random variable is equal to x . In general, the gamma Poisson functions accept arguments that are the mean parameter

λ , the overdispersion parameter σ , and the count of interest x . When the overdispersion is equal to one, the Gamma Poisson reduces to a Poisson(λ) distribution.

Gamma Poisson Distribution

Returns the probability that a gamma-Poisson distributed random variable is less than or equal to x . In general, the gamma Poisson functions accept arguments that are the mean parameter λ , the overdispersion parameter σ , and the count of interest x .

Gamma Poisson Quantile

Returns the smallest integer quantile for which the cumulative probability of the Gamma Poisson (λ , σ) distribution is larger than or equal to p .

Binomial Distribution

Returns the probability that an observation from a binomial distribution with parameters p and n is less than or equal to k . In general, the binomial functions accept arguments that are the probability of success p (the event of interest), the number of trials n , and the number of successes k .

Binomial Probability

Computes the probability that a random variable from a binomial distribution is equal to k . In general, the binomial functions accept arguments that are the probability of success p (the event of interest), the number of trials n , and the number of successes k .

Binomial Quantile

Returns the smallest integer quantile for which the cumulative probability of the Binomial (p , n) distribution is larger than or equal to the specified probability.

Neg Binomial Distribution

Returns the probability that a negative binomially distributed random variable is less than or equal to k , where the probability of success is p , and the number of successes is n .

Neg Binomial Probability

Returns the probability that a negative binomially distributed random variable is equal to k , where the probability of success is p , and the number of successes is n .

Beta Binomial Distribution

Returns the probability or pmf that a beta binomially distributed random variable is less than or equal to x . In general, the beta binomial functions accept arguments that are the probability of success p (the event of interest), the overdispersion parameter δ , and the number of trials

n . When the overdispersion parameter for the beta binomial is zero, the distribution reduces to a binomial(p, n).

Beta Binomial Probability

Returns the probability or cmf that a beta binomially distributed random variable is equal to x . When the overdispersion parameter for the beta binomial is zero, the distribution reduces to a binomial(p, n).

Beta Binomial Quantile

Returns the smallest integer quantile for which the cumulative probability of the Beta Binomial (p, n, delta) distribution is larger than or equal to the specified probability. When the overdispersion parameter for the beta binomial is zero, the distribution reduces to a binomial (p, n).

Hypergeometric Distribution

Computes the probability that a random variable from a hypergeometric distribution is less than or equal to x . The hypergeometric distribution models the total number of successes in a fixed sample drawn without replacement from a finite population. The hypergeometric functions accept as arguments the size of the population N , the total number of items with the desired characteristic in the population, K , the number of samples drawn n , and the number of successes in the sample x .

Hypergeometric Probability

Computes the probability that a random variable from a hypergeometric distribution is equal to x .

Poisson Distribution

Computes the probability that a random variable from a Poisson distribution with mean λ is less than or equal to the count of interest. In general, Poisson functions accept an argument that is the count of interest, and λ , the mean parameter.

Poisson Probability

Computes the probability that a random variable from a Poisson distribution with mean λ is equal to the count of interest.

Poisson Quantile

Returns the smallest integer quantile for which the cumulative probability of the Poisson (λ) distribution is larger than or equal to p .

Statistical Functions

There are two types of **Statistical** functions you can use in a formula:

- The functions with names that have the prefix **Col**. These functions compute statistics for a column of numbers or expressions involving columns.
- The **Mean**, **Std Dev**, **Number**, **Sum**, **Quantile**, **Maximum**, **Minimum**, and **N Missing** functions. These functions evaluate across columns or arguments. The statistic is computed for each row across the series of arguments. You can use the insert key () on the on-screen keypad, or type a comma to add arguments to the functions that accept multiple arguments. When there are multiple contiguous arguments, select the function and the first argument, and then Shift-click the last argument in the group. These functions then automatically show with the complete list.

Note: Missing values are ignored in statistical functions.

See the JSL Functions chapter in the *JSL Syntax Reference* for details about syntax.

Col Mean

Calculates the mean (or arithmetic average) of the numeric values identified by its argument. The formula **Col Mean**(age) calculates the average of all nonmissing values in the **age** column.

Col Moving Average

Returns the moving average over a given interval based at the current row. Missing values are ignored

Col Std Dev

Measures the spread around the mean of the distribution identified by its argument. In the normal distribution, about 68% of the distribution is within one standard deviation of the mean. 95% of the distribution is within two standard deviations of the mean. 99% of the distribution is within three standard deviations of the mean.

Col Number

Counts the number of nonmissing values in the column that you specify. A missing numeric value occurs when a cell has no assigned value or is the result of an invalid operation (such as division by zero). Missing values show on the spreadsheet as a missing value mark (•). Missing character values are null character strings. In formulas for row state columns, an excluded row state characteristic is treated as a missing value.

Col N Missing

Counts the number of missing values in the column that you specify. A missing numeric value occurs when a cell has no assigned value or is the result of an invalid operation (such as division by zero). Missing values show in the data grid with a missing value character (•). Missing character values are null character strings.

Col Sum

Computes the sum of the values in its numeric argument. Missing values are ignored.

Col Minimum and Col Maximum

Takes the minimum of its numeric arguments. **Col Minimum** ignores missing values. **Col Maximum** takes the maximum of a numeric column argument and ignores missing values.

Col Quantile

Computes the value at which a specific percentage of the values is less than or equal to that value. For example, the value calculated as the 50% quantile, also called the median, is greater than or equal to 50% of the data. Half of the data values are less than the 50th quantile.

The **Col Quantile** function's quantile argument represents the quantile percentage divided by 100. The 25% quantile, also called the lower quartile, corresponds to $p = 0.25$, and the 75% quantile, called the upper quartile, corresponds to $p = 0.75$.

The Formula Editor computes a quantile for a column of n nonmissing values by arranging the values in ascending order. The subscripts of the sorted column values, $y_1, y_2, \dots, y_n$ represent the ranks in ascending order.

The p th quantile value is calculated using the formula $p(n + 1)$, where p is the percent value and n is the total number of nonmissing values. If $p(n+1)$ is an integer, then the quantile value is $y_{p(n+1)}$. If $p(n + 1)$ is not an integer, then the value is interpolated by assigning the integer part of the result to i , assigning the fractional part to f , and applying the formula $(1 - f)y_i + (f)y_{i+1}$.

For example, suppose a column has values 2, 4, 6, 8, 10, 12, 14, 16, 18, and 20. The 50% quantile is calculated as $0.5(10 + 1) = 5.5$.

Because the result is fractional, the 50% quantile value is interpolated as

$$(1 - 0.5) \times 10 + (0.5) \times 12 = (0.5)10 + (0.5)12 = 6 + 5 = 11$$

The following are example **ColQuantile** formulas:

- **ColQuantile(age, 1)** Calculates the maximum age.
- **ColQuantile(age, 0.75)** Calculates the upper quartile age.
- **ColQuantile(age, 0.5)** Calculates the median age.
- **ColQuantile(age, 0.25)** Calculates the lower quartile age.

- **ColQuantile(age, 0)** Calculates the minimum age.

The **ColQuantile** argument can be any expression that evaluates to a value between (and including) 0 and 1. For example, the first formula in Figure A.13 calculates quantile values of age in ascending order for each row. The column then contains the interpolated values of **age** in ascending order in the calculated column. The second formula lists the interpolated values of age in descending order.

Figure A.13 Examples of the Quantile Function



Col Rank

Ranks each row's value, from 1 for the lowest value to the number of non-missing columns for the highest value. Ties can be broken by reporting the average of the possible rankings, assigning the ranks in the order that they originally appear, giving both values the lowest possible rank, or arbitrarily. (JMP 12 used arbitrary tie breaking.) Distribution's Normal Quantile output uses average tie breaking.

Col Standardize

Performs the usual standardization on its numeric expression. For each row i , **Col Standardize(height)** is $(\text{Height}_{\text{Row } i} - \text{Col Mean}(\text{Height})) / \text{Col Std Dev}(\text{Height})$.

Mean

Calculates the arithmetic average of the nonmissing values in the list of arguments that you specify. The arguments can be constants, numbers, or expressions. The **Mean** function initially shows with a single argument. You add arguments with the insert button () on the Formula Editor keypad or by typing a comma.

Std Dev

Computes standard deviation of the nonmissing values in the list of arguments that you specify. The arguments can be constants, numbers, or expressions. The **Std Dev** function initially shows with a single argument. You add arguments by clicking the insert button () on the Formula Editor keypad or by typing a comma.

Number

Counts the number of nonmissing values in the list of arguments that you specify.

Sum

Returns the sum of the nonmissing values in the list of arguments that you specify.

Quantile


Calculates the quantile specified by the first argument for all the nonmissing values in the remaining list of arguments that you specify.

Summation (Σ)

Evaluates for an explicit range of values in a column, as given by the summation indices. This behavior is different from all other statistical functions (except **Product**), which *always* evaluate *on every row*. The **Summation** function uses the summation notation shown in Figure A.14. To calculate a sum, replace the missing *body* term with an expression containing the index variable i , or an index variable that you assign. **Summation** repeatedly evaluates the expression for $i = 1$, $i = 2$, through $i = \text{NRow}()$ and then adds the nonmissing results together to determine the final result.

You can replace **NRow()**, the number of rows in the active spreadsheet, and the index constant, i , with any expression appropriate for your formula. For example, the summation formula in Figure A.14 computes the total for each row of all revenue values for rows 1 through the current row number, filling the calculated column with the cumulative totals of the revenue column.

Figure A.14 Example of the **Summation** function




Product (Π)

Evaluates for an explicit range of values in a column, as given by the summation indices, as opposed to all other statistical functions (except **Summation**), which *always* evaluate *on every row*. **Product** uses the notation shown in the formula in Figure A.15. To calculate a product, replace the missing body term with an expression containing the index variable j . **Product** repeatedly evaluates the expression for $i = 1$, $i = 2$, through $i = n$ and multiplies the nonmissing results together to determine the final result.

You can replace **NRow()**, the number of rows in the active spreadsheet and the index constant, i , with any expression appropriate for your formula.

For example, the product example in Figure A.15 calculates $i!$ (each row number's factorial).

Figure A.15 Examples of the **Product** Function**Minimum and Maximum**

Return the minimum and maximum value, respectively, from the list of nonmissing arguments that you specify.

N Missing

Counts the number of missing values in the list of arguments that you specify.

Desirability

Are smooth piecewise functions that are crafted to fit the control points. The minimize and maximize functions are three-part piecewise smooth functions that have exponential tails and a cubic middle.

The target function is a piecewise function. It is a scale multiple of a normal density on either side of the target (with different curves on each side), which is also piecewise smooth and fit to the control points.

SSQ

Returns the sum of squares of all elements.

Random Functions

You can create formulas that generate real numbers by effectively “rolling the dice” within the constraints of the specified distribution. Each time you click **Apply** in the Formula Editor window, these functions produce a new set of random numbers.

Note: Random numbers are generated using the Mersenne-Twister technique. This technique has a period length of $2^{19937}-1$. For details about the generators, see Matsumoto and Nishimura (1998). The new generators are verified to pass all the DIEHARD tests as documented in Marshall (1996).

See the JSL Functions chapter in the *JSL Syntax Reference* for details about syntax.

Random Uniform

Generates random numbers uniformly between 0 and 1. This means that any number between 0 and 1 is as likely to be generated as any other. The result is an approximately even distribution. You can shift the distribution and change its range with constants. For example, `5 + Random Uniform()*20` generates uniform random numbers between 5 and 25.

Random Normal

Generates random numbers that approximate a normal distribution with a mean of 0 and standard deviation of 1 if no arguments are used, or with the mean and standard deviation entered as arguments. The normal distribution is bell shaped and symmetrical. You can also modify the `Random Normal` function with constants if no arguments are entered to give a normal distribution with specific mean and standard deviation. For example, the formula `Random Normal()*5 + 30` generates a random normal variable with a mean of 30 and a standard deviation of 5.

Random Exp

Generates a single parameter exponential distribution for the distribution parameter $\lambda=1$. You can modify the exponential function to use a different λ .

For example, `Random Exp()*0.1` generates an exponential distribution for $\lambda=0.1$. The exponential distribution is often used to model simple failure time data, where λ is the failure rate.

Random Gamma

Gives a gamma distribution for the parameter, **alpha**, you enter as the function argument. The gamma distribution describes the time until the k^{th} occurrence of an event. The gamma distribution can also have a scale parameter, **beta**. A gamma variate with shape parameter α and scale β can be generated with the formula `beta*Random Gamma(alpha)`. If $2*\alpha$ is an integer, a Chi-squared variate with $2*\alpha$ degrees of freedom is generated with the formula `2*Random Gamma(alpha)`.

Random Beta

Generates a pseudo-random number distributed `Beta(alpha, beta)`.

Random Cauchy

Generates a Cauchy distribution with location parameter 0 and scale parameter 1. The Cauchy distribution is bell shaped and symmetric but has heavier tails than the normal distribution. A Cauchy variate with location parameter α and scale parameter β can be generated with the formula `alpha+beta*Random Cauchy()`.

Random Category

Generates a random category given an alternation of probability and result expressions (for example, `Random Category(.2, "A", .3, "B", .4, "C", "D");`).

Random Johnson Su

Returns a random number from the Johnson Su distribution.

Random Johnson Sb

Returns a random number from the Johnson Sb distribution.

Random Johnson Sl

Returns a random number from the Johnson Sl distribution.

Random Triangular

Generates a triangular distribution of numbers between 0 and 1, with the midpoint that you enter as the function argument. You can add a constant to the function to shift the distribution and multiply to change its span.

Random Integer

Generates a uniform distribution of integers between 1 and the argument that you enter as **n1**, if nothing is entered for **n2**. If you enter both **n1** and **n2** ($n1 < n2$), **Random Integer** generates a uniform distribution of the integers between and including **n1** and **n2**.

Random Binomial

Generates random numbers from a binomial distribution with parameters that you enter as function arguments. The first argument is n , the number of trials in a binomial experiment. The second argument is p , the probability that the event of interest occurs. When n is 1, the binomial function generates a distribution of Bernoulli trials. For example, $n = 1$ and $p = 0.5$, give the distribution of tossing a fair coin. The mean of the binomial distribution is np , and variance is $np(1 - p)$.

Random Negative Binomial

Generates a negative binomial distribution for the parameters that you enter as function arguments. The first parameter is the number of successes of interest (r) and the second argument is the probability of success (p). The random variable of interest is the number of failures that precede the r^{th} success. In contrast to the binomial variate, where the number of trials is fixed and the number of successes is variable, the negative binomial variate is for a fixed number of successes and a random number of trials. The mean of the negative binomial distribution is $(r(1 - p))/p$ and the variance is $(r(1 - p))/p^2$.

Random Beta Binomial

Returns random numbers from the beta binomial distribution for n trials with probability p and correlation or overdispersion δ .

Random Frechet

Returns a random number from a Fréchet distribution with the location μ and scale σ .

Random Geometric

Returns random numbers from the geometric distribution with the parameter that you enter as the function argument. The parameter, p , is the probability that a specific event occurs at any one trial. The number of trials until a specific event occurs for the first time is described by the geometric distribution. The mean of the geometric distribution is $(1-p)/p$, and the variance is $(1-p)/p^2$.

Random Poisson

Generates a Poisson variate based on the value of the parameter, λ , you enter as the function argument. λ is often the expected number of events occurring per unit time or unit of area. λ is both the mean and the variance of the Poisson distribution.

Random Gamma Poisson

Returns random numbers from the gamma Poisson distribution with parameters λ and σ .

Random Weibull

Returns a random number from a Weibull distribution.

Random Logistic

Returns a random number from a logistic distribution with the location μ and scale σ .

Random Loglogistic

Returns a random number from a loglogistic distribution with the location μ and scale σ .

Random Lognormal

Returns a Lognormal-distributed random number with location parameter μ and scale σ .

Random GLog

Returns random numbers from the generalized logarithm distribution with parameters μ , σ , and λ . When λ is equal to zero, the function returns a lognormal(μ , σ).

Random Reset

Restarts the random number sequences with a seed that you specify.

Random LEV

Returns a random number from an LEV distribution with the specified location *mu* and scale *sigma*.

Random SEV

Returns a random number from the smallest extreme distribution with the specified location *mu* and scale *sigma*.

Random SHASH


Returns a random number from the sinh-arcsinh (SHASH) distribution.

Col Shuffle

Selects a row number at random from the current data table. Each row number is selected only once. When **Col Shuffle** is used as a subscript, it returns a value selected at random from the column that serves as its argument. Each value from the original column is assigned only once as **Col Shuffle**'s result.

For example, to identify a 50% random sample without replacement, use the formula in Figure A.16.

Figure A.16 Formula Identifying 50% Random Sample



The formula in Figure A.16 selects half the values ($n/2$) from the column *x* and assigns them to the first half of the rows in the computed column. The remaining rows of the computed column fill with missing values.

Resample Freq

Generates a random selection with replacement frequency counts, suitable for use in bootstrapping. For example, it supports a second **Freq Column** argument, enabling it to do bootstrap samples relating to a pre-existing frequency column specified in the second argument. **Resample Freq()** generates a 100% resample. **ResampleFreq(rate)** generates a *rate* frequency sample. **Resample(rate, column)** generates a sample that is calculated by the *rate* multiplied by the sum of the specified column.

Date Time Functions

JMP stores dates and times in numeric columns using the Macintosh standard of the *number of seconds since January 1, 1904*. When a column has date values, you can assign a date format to that column by double-clicking a column name and selecting **Date** or **Time** from the **Format** menu. See [“Numeric Format Options”](#) on page 261 in the “The Column Info Window” chapter.

See the JSL Functions chapter in the *JSL Syntax Reference* for details about syntax.

In Minutes, In Hours, In Days, In Weeks, In Years

Converts from the units of the function name to the equivalent number of seconds for the argument. The argument must be a number or numeric expression. For example, **In Minutes(2)** yields **120**, and **In Years(1)** yields **31,557,600** (60 seconds * 60 minutes * 24 hours * 365.25 days).

Date DMY, Date MDY

Accepts numeric expressions for day, month, and year and return the associated JMP date. For example, **Date DMY(20, 3, 1991)** and **Date MDY(3, 20, 1991)** evaluate to **2,752,272,000**.

Today

Returns the number of seconds between January 1, 1904 and the current date. For example, at midnight on March 20, 1991 (a Wednesday), the **Today** function returns **2752272000** (2,752,272,000 seconds) and continues counting. If you evaluate the **Today** function later in the day, it reflects the additional seconds.

Day, Month, Year

Returns the day of the month, the month (as a number from 1 to 12), a four-digit year, respectively. The argument for these functions is interpreted as a JMP date. For example, on March 20, 1991:

- **Day(2752272000)** returns the number **20**.
- **Month(2752272000)** returns the number **3**.
- **Year(2752272000)** returns the number **1991**.

Quarter

Returns the annual quarter of a *datetime* value as an integer 1-4.

Hour, Minute, Second

Returns the hour, the minute, and the seconds of a date-time value, respectively. The argument for these functions is interpreted as a JMP date. For example, on March 20, 1991:

- **Hour(2752572649)** returns the number 11.
- **Minute(2752572649)** returns the number 30.
- **Second(2752572649)** returns the number 49.

Day of Week, Day of Year, Week of Year, Time of Day

The argument for these functions is a JMP date. **Day Of Week** returns a number from 1 to 7, where 1 represents Sunday. **Day Of Year** returns the number of days from the beginning of the year. **Week Of Year** returns a number from 1 to 52 based on the rule specified. Rule 1 (default) has weeks start on Sunday with the first Sunday being week 2 and week 1 is a partial week or empty; rule 2 has the first Sunday begins week 1 with any previous days being week 0; rule 3 returns the ISO week number where the week starts on Monday and week 1 is the first week of the year with four days in that year. With ISO weeks, it is possible for the first or last three days of the year to belong to the neighboring year's week number. **Time Of Day** returns a number from 0 to 86399 (time of day in seconds). For example, on Wednesday, March 20, 1991:

- **Day Of Week(2752272000)** returns the number 4.
- **Day Of Year(2752272000)** returns the number 79.
- **Week Of Year(2752272000)** returns the number 12.
- **Time Of Day(2752272000)** returns the number 0.

Informat

The argument for the **Informat** function is a date character string. For example, **Informat("03/20/1991")** returns the appropriate JMP date value, 2752272000. JMP can read all the date formats except for **Abbrev Date** and **Long Date**.

Abbrev Date, Long Date, Short Date

The argument for these date functions is a JMP date. They return character strings that are the formatted representation of the argument. For example:

- **Abbrev Date(2752272000)** returns **Wed, Mar 20,1991**.
- **Long Date(2752272000)** returns **Wednesday, March 20, 1991**.
- **Short Date(2752272000)** returns **3/20/91**.

Format

The first argument in the **Format** function is a JMP date. This function returns the character string representation of the date by the date format that you specify in the second argument, which is a quoted string. If you apply this formula to a numeric column, JMP automatically changes the column's data type to character.

You can also supply a column for the first argument and leave the rest blank. The result is the formatted value of the column reference. This can be used to extract value labels of a column when the value labels are turned off.

MDYHMS

The argument of **MDYHMS** is a JMP date. This function shows all date and time fields, appending zeros as time fields if no time information is present. This is useful if a date column is formulated such that not all date information is displayed. The **MDYHMS** function can be used to see all available date and time information.

Date Increment

Adds 1 or more intervals to a starting datetime value. For example, **Date Increment(Today(), "Day", 3)** adds three days to the current date. **Date Increment(Today(), "Year", 3)** adds 3 years to the current date.

Date Difference

Returns the difference of two datetime values. The interval argument can be Second, Minute, Hour, Day, Week, Month, Quarter, Year. The alignment arguments are described here:

Start is used to count the number of times an interval starts.

Actual is used to count whole intervals.

Fractional is used to count fractional intervals.

For example, the following formula returns **207.890243055556**, the number of days between the dates:

```
Date Difference(  
    01Jan2010:00:00:00,  
    27Jul2010:21:21:57,  
    "Day",  
    "fractional"  
);
```

The following formula returns **207**, the number of completed days between the dates:

```
Date Difference(  
    01Jan2010:00:00:00,  
    27Jul2010:21:21:57,  
    "Day",  
    "actual"  
);
```

The following formula returns **9**, the number of completed hours between the times:

```
Date Difference(  
    01Jan2010:00:00:00,  
    01Jan2010:09:00:00,  
    "Hour",  
    "actual"  
);
```

```
01Jan2010:00:00:00,  
01Jan2010:09:22:57,  
"Hour",  
"actual"  
);
```

The following formula returns 1, the number of times a new hour started between the times:

```
Date Difference(  
31Dec2010:23:59:59,  
01Jan2011:00:59:59,  
"Hour",  
"start"  
);
```

Row State Functions

There are six characteristics that rows in a data table can have: selected, hidden, excluded, labeled, colored, and marked. If you give rows one or more of these characteristics and then create row state data table columns, you can then create a formula that computes and saves row state conditions. (See [“Column Properties”](#) on page 268 in the “The Column Info Window” chapter, and [“Row State Columns”](#) on page 265 in the “The Column Info Window” chapter.) This formula processes row state data just as it would process character and numeric data.

See the JSL Functions chapter in the *JSL Syntax Reference* for details about syntax.

Note: A row can be assigned any combination of row states; a row state column can have multiple row states as a value.

Table A.2 describes the type of argument each Row State function requires and what each returns.

Table A.2 Row State Functions

Function Name	Argument Type Required	What the Function Returns (Your Column Data Type Should be This Type)
Row State	none	row state of current row
As Row State	numeric	all row states of current row
Combine States	multiple row state arguments	multiple row state assignments
Excluded State	positive integer or zero	row state-excluded or not excluded


Table A.2 Row State Functions (*Continued*)

Function Name	Argument Type Required	What the Function Returns (Your Column Data Type Should be This Type)
Hidden State	positive integer or zero	row state-hidden or not hidden
Labeled State	positive integer or zero	row state-labeled or not labeled
Color State	integer or color name or {red, green, blue}	row state color
Marker State	integer or character	row state marker
Selected State	positive integer or zero	row state-selected or not selected
Hue State	integer	row state hue
Shade State	integer 1-5	row state intensity
Excluded	Row State() or row state column	integer 0 (not excluded) or 1 (excluded)
Hidden	Row State() or row state column	integer 0 (not hidden) or 1 (hidden)
Labeled	Row State() or row state column	integer 0 (not labeled) or 1 (labeled)
Color Of	Row State() or row state column	color map integer
Marker Of	Row State() or row state column	marker map integer
Selected	Row State() or row state column	integer 0 (not selected) or 1 (selected)

Row State

Returns the active row state condition of the current row as true or false. You can use this function to conveniently write conditional clauses that depend on the status of the current row. For example, Figure A.17 assigns a 1 to rows that are currently selected and labeled and 0 otherwise.

Figure A.17 Row State



As Row State

Converts a numeric argument to a row state or set of row state conditions. Row states are stored internally in JMP as a 16-bit number, with each bit assigned to represent one of the possible row states as illustrated in Figure A.3. For example, the binary representation of **1327** is **0000010100101111**. **As Row State(1327)** would therefore set the row state as selected, excluded, hidden, labeled, with marker 2 and color 10.

Table A.3 Row States Stored as 16-Bit Numbers: Each Bit Represents a Row State

Bit	Row State
0	Not selected (0) or Selected (1)
1	Unexcluded (0) or Excluded (1)
2	Unhidden (0) or Hidden (1)
3	Unlabeled (0) or Labeled (1)
4-7	Marker
8-14	Color

Combine States

Generates a row state combination with two or more arguments. Use the insert button () on the Formula Editor keypad or type a comma to add arguments to the **Combine States** function. The currently selected expression becomes the first argument when you select **Combine States**. **Replace** each argument with an expression that evaluates to a row state. This formula:

```
Combine States(  
  Selected State( Modulo( Row(), 2 ) ),  
  Labeled State( Modulo( Row() + 1, 2 ) ) );
```

alternately labels or selects each row in the calculated row state column. The **Selected State** and **Labeled State** functions are defined later in this section. Use the insert () and delete

() buttons on the Formula Editor keypad to add more arguments or remove unwanted arguments.

If you include conflicting row states in a combination, the results are unpredictable.

Excluded State

Interprets a numeric argument as true or false. When an argument evaluates as true, the **Excluded State** function assigns the excluded condition as the value of the column for that row. For example, **Excluded State(Modulo(Row(),2))** assigns the excluded row state as the value of the row state column for each odd numbered row.

Hidden State

Assigns the hidden row state condition when its argument is greater than zero. If the argument is zero, the value in the column for that row is not hidden.

Labeled State

Gives the labeled row state condition when its argument is greater than zero. If the argument is zero the row value in the column for that row is not labeled.

Color State

Returns the color from the JMP color map that corresponds to its integer argument. JMP colors are numbered 0 through 84. Zero maps to black.

Marker State

Returns markers from the JMP marker map that correspond to its integer argument. JMP markers are numbered 0 through 16. The formula **Marker State(Row())** assigns all the row state markers in a repeating sequence determined by the current row number to the calculated row state column. A row state column can have multiple row states as a value.

Selected State

Gives the selected row state condition when its argument is greater than zero. If the argument is zero, the value in the column for that row is not selected.

Hue State

Returns the color from the JMP hue map that corresponds to its integer argument. JMP hues are numbered 0 through 11 but larger integers are treated as *modulo* 12. The **Hue State** function does not map to black, gray, or white. A hue of zero maps to red and hue of 11 maps to magenta. The formula on the left in Figure A.19 assigns row state colors in a chromatic spread based on the value of z. The **Hue State** function used with a row state data type column.

Figure A.18 Example of Hue State Function

$$\text{Hue State} \left(\frac{\left(z - \text{Col Quantile}(z, 0) \right)}{\left(\text{Col Quantile}(z, 1) - \text{Col Quantile}(z, 0) \right)} \right) \cdot 12$$

Shade State

Assigns five shade levels to a color or hue. A shade of -2 is darkest and shade of +2 is lightest. A shade of zero is a pure color. The formula on the right in Figure A.19 assigns shade values based on the value of z.

Figure A.19 Example of Shade State Function

$$\text{Shade State} \left(\frac{\left(z - \text{Col Quantile}(z, 0) \right)}{\left(\text{Col Quantile}(z, 1) - \text{Col Quantile}(z, 0) \right)} \right) \cdot (5 - 2)$$

To assign all shades of all the colors in the colors palette, you need to use the **Hue State** and **Shade State** assignments together. The formula in Figure A.20 uses the **Combine States** function described at the beginning of this section. The first argument in the **Combine States** function is the **Hue State** formula shown previously, and the second argument is the **Shade State** formula. In addition, the **Marker State** function with an argument of 2 assigns the X marker to each row, and the **Selected State** function with an argument of 1 selects each row.


Figure A.20 Combine States Example For Using Both Hue State and Row State

$$\text{Combine States} \left(\begin{array}{l} \text{Hue State} \left(\frac{\left(z - \text{Col Quantile}(z, 0) \right)}{\left(\text{Col Quantile}(z, 1) - \text{Col Quantile}(z, 0) \right)} \right) \cdot 12, \\ \text{Shade State} \left(\frac{\left(z - \text{Col Quantile}(z, 0) \right)}{\left(\text{Col Quantile}(z, 1) - \text{Col Quantile}(z, 0) \right)} \right) \cdot (5 - 2), \\ \text{Marker State}(2), \\ \text{Selected State}(1) \end{array} \right)$$

Excluded, Hidden, Labeled, and Selected


Accepts a row state expression argument (row state column or row state constant) that evaluates as either 1 or 0 (true or false). These characteristics are inactive by default. Often, the **Row()** function is the argument, which detects the active row state condition of each row. For example, in Figure A.21, the formula assigns 99 whenever a row is actively selected, and 0 otherwise. Note that this formula is used in a column that has a numeric data type.

Figure A.21 Example of a Formula Using the **Selected** Function



The example in Figure A.22 assigns row state conditions to a row state column. The formula for the row state column (in the column called **x**) checks to determine whether the active row state is either **Hidden** or **Excluded**, and if so, assigns the **Labeled** row state.

Figure A.22 Calculate Row State Information in a Row State Column



Color Of

Accepts any row state expression or column, or the **Row State()** function as its argument. Returns a number from the JMP color map that corresponds to the active color state, or zero if there is no assigned color.

Marker Of

Accepts any row state expression or column, or the **Row State()** function as its argument. Returns a number from the JMP marker map that corresponds to the active marker or zero if there is no assigned marker.

Assignment Functions

Assignment functions work in place. That is, the result returned by the operation (on the right of the operator) is stored in the argument on the left of the operator and replaces its current value.

Assignment statements are most often used in conjunction with other commands to build a JSL script. You can use the Formula Editor to create and execute a script in that column, but this is not recommended because of dependencies and ambiguities that can result. Most often, scripts are stored as .jsl files, and can be saved with a data table. See [“Create and Save Scripts”](#) on page 249 in the “Enter and Edit Data” chapter. For details about syntax, see the JSL Functions chapter in the *JSL Syntax Reference*.

Note: The first argument of an **assignment** function must be capable of being assigned. This means you cannot have an assignment such as $3+=4$, because 3 is a constant value that cannot be reassigned. You must first create a variable (a table variable or local variable) whose value is 3. (For details about table variables, see [“Use Table Variables”](#) on page 248 in the “Enter and Edit Data” chapter. For details about local variables, see [“Refer to Values in Columns and Table Variables”](#) on page 354 in the “Formula Editor” chapter). Then use that variable as the left-hand argument of the assignment function.

= (assign) Puts the value of b into a . For example $(a=b)$.

+= (add to) Adds the value of b to a and puts the result back into a . For example, $a+=b$.

-= (subtract to) Subtracts the value of b and puts the result back into a . For example, $a-=b$.

***= (multiply to)** Multiplies b with a and puts the result back into a . For example, $a*=b$.

/= (divide to) Divides b into a and puts the result back into a . For example, $a/=b$.

++ (post increment) Adds one (1) to a , in place, so that $a++$. For example, if the initial value of a is 4, the expression $a++$ changes a to 5.

-- (post decrement) Subtracts one (1) from a , in place, so that $a--$. For example, if the initial value of a is 4, the expression $a--$ changes a to 3.

Parametric Model Functions

This category is a short cut to create three parametric models that are linear functions of set of window-selected columns.

Linear Model, Interactions Model, Full Quadratic Model

Selecting each of these opens a column selection box that lets you select one or more columns to be included in the model. The function then creates and populates the chosen model.

Finance Functions

Lets you create formulas to calculate principal payments, interest rate, rate of return, and so on.

Double Declining Balance

Returns the depreciation of an asset for a specified period of time. The function uses the double-declining balance method or some other depreciation factor.

Future Value

Returns the future value of an investment that is based on periodic, constant payments and a constant interest rate.

Interest Payment

Returns the interest payment for a given period for an investment that is based on periodic, constant payments and a constant interest rate.

Interest Rate

Returns the interest rate per period of an annuity.

Internal Rate of Return

Returns the internal rate of return for a series of cash flows in the *values* argument.

Modified Internal Rate of Return

Returns the modified internal rate of return for a series of periodic cash flows. The cost of investment and the interest received on reinvested cash is included.

Net Present Value

Returns the net present value of an investment by using a discount rate and a series of future payments (negative values) and income (positive values).

Number of Periods

Returns the number of periods for an investment that is based on periodic, constant payments and a constant interest rate.

Payment

Returns the payment for a loan that is based on constant payments and a constant interest rate.

Present Value

Returns the present value of an investment.

Principal Payment

Returns the payment on the principal for a given period for an investment that is based on periodic, constant payments and a constant interest rate.

Straight Line Depreciation

Returns the straight-line depreciation of an asset for one period.

Sum Of Years Digits Depreciation

Returns the sum-of-years' digits depreciation of an asset for a specified period.

Appendix **B**

JMP Technical Details

This chapter contains technical details that apply to multiple platforms in JMP and to SAS integration.

Contents

[Features That Support Multithreading](#) 695

[Conventions for Mapping JMP Attributes to SAS Extended Attributes](#) 696

Features That Support Multithreading

Some features in JMP are coded to take advantage of multiple central processing units (CPUs) on a machine, allowing these features to run significantly faster. This process is called multithreading.

The following features support multithreading:

-  Boosted Trees
-  Bootstrap Forest
- Choice
-  Covering Arrays
- Distribution
- Factor Analysis
- Fit Life by X
- Fit Model: Parametric Survival,  Mixed Model,  Generalized Regression, and  Response Screening
- Functional Data Explorer
- Gaussian ( Fast GASP and the use of Categorical variables are only in JMP Pro.)
- Latent Class Analysis
- Life Distribution
- Multivariate
- Neural ( Some features are only in JMP Pro.)
- Nominal Logistic
- Nonlinear and Nonlinear Curve
- Normal Mixtures in Cluster Analysis
- Partial Least Squares ( Some features are only in JMP Pro.)
- Partition
- Predictor Screening
- Principal Components
- Process Screening
- Profiler (Does not apply to Profilers launched from within other platforms.)
- Reliability Forecast
-  Repairable Systems Simulation
- Response Screening

-  Sparse Principal Components
- SVD Imputation in the Missing Values Screening
- Text Explorer ( SVD and Latent Class Analysis are only in JMP Pro.)
-  Uplift
- Variable Clustering

Conventions for Mapping JMP Attributes to SAS Extended Attributes

SAS extended attributes are metadata that you define in SAS code to import information such as table scripts, labels, length, and type. You associate the extended attributes with a data set or variable and define them in name-value pairs, such as `_JMP_TABLESCRIPTNAME_2="OnOpen"`.

This section provides information about SAS extended attributes and their corresponding JMP attributes.

Table B.1 Table Attributes

JMP Table Attribute	SAS Attribute Name	SAS Attribute Type and Default Value	Description
Table Variable Count	<code>_JMP_TABLEVARCOUNT</code>	Numeric, 0	Count of table variables
Table Variable Name 1	<code>_JMP_TABLEVARNAME_1</code>	String	Name of the first table variable
Table Variable Value 1	<code>_JMP_TABLEVARVALUE_1</code>	String	Value of the first table variable
Table Variable Name 2	<code>_JMP_TABLEVARNAME_2</code>	String	Name of the second table variable
Table Variable Value 2	<code>_JMP_TABLEVARVALUE_2</code>	String	Value of the second table variable
Table Variable Name <i>n</i>	<code>_JMP_TABLEVARNAME_<i>n</i></code>	String	Name of the <i>n</i> th table variable

Table B.1 Table Attributes (*Continued*)

JMP Table Attribute	SAS Attribute Name	SAS Attribute Type and Default Value	Description
Table Variable Value n	<code>_JMP_TABLEVARVALUE_n</code>	String	Value of the n th table variable
Table Script Count	<code>_JMP_TABLESCRIPTCOUNT</code>	Numeric	Count of table scripts
Table Script Name 1	<code>_JMP_TABLESCRIPTNAME_1</code>	String	Name of the first table scripts
Table Script Value 1	<code>_JMP_TABLESCRIPTVALUE_1</code>	String	Value of the first table scripts
Table Script Name 2	<code>_JMP_TABLESCRIPTNAME_2</code>	String	Name of the second table script
Table Script Value 2	<code>_JMP_TABLESCRIPTVALUE_2</code>	String	Value of the second table script
Table Script Name n	<code>_JMP_TABLESCRIPTNAME_n</code>	String	Name of the table script n
Table Script Value n	<code>_JMP_TABLESCRIPTVALUE_n</code>	String	Value of table script n
Lock Data Table	<code>_JMP_ISLOCKED</code>	Boolean, 0	Locked table
Suppress Formula Eval	<code>_JMP_SUPPRESSEDVAL</code>	Boolean, 0	Suppressed formula evaluation
Column Group Count	<code>_JMP_COLGRPCOUNT</code>	Numeric, 0	Number of column groups
Column Group Name 1	<code>_JMP_COLGRPNAME_1</code>	String	Name of column group 1
Column Group Start Col 1	<code>_JMP_COLGRPSTARTCOL_1</code>	String	Name of first column in group 1
Column Group NCols 1	<code>_JMP_COLGRPNCOLS_1</code>	Numeric	Number of columns in group 1

Table B.1 Table Attributes (*Continued*)

JMP Table Attribute	SAS Attribute Name	SAS Attribute Type and Default Value	Description
Column Group Name 2	_JMP_COLGRPNAME_2	String	Name of column group 2
Column Group Start Col 2	_JMP_COLGRPSTARTCOL_2	String	Name of first column in group 2
Column Group NCols 2	_JMP_COLGRPNCOLS_2	Numeric	Number of columns in group 2
Column Group Name <i>n</i>	_JMP_COLGRPNAME_ <i>n</i>	String	Name of column group <i>n</i>
Column Group Start Col <i>n</i>	_JMP_COLGRPSTARTCOL_ <i>n</i>	String	Name of first column in group <i>n</i>
Column Group NCols <i>n</i>	_JMP_COLGRPNCOLS_ <i>n</i>	Numeric	Number of columns in group <i>n</i>

Table B.2 Column Attributes

JMP Column Attribute	SAS Attribute Name	SAS Attribute Type and Default Value	Description
Column Name	_JMP_COLNAME	String	Original column name in JMP
Data Length	_JMP_DATALENGTH	Numeric, 0	Length of the data. For numeric types, the value can be 1, 2, 4, or 8. For character types, 0 (or negative) means variable length, positive values mean fixed-length.
Row State column	_JMP_ISROWSTATE	Numeric, 0	0 = not row state, 1 = default row state for table, 2 = row state column

Table B.2 Column Attributes (*Continued*)

JMP Column Attribute	SAS Attribute Name	SAS Attribute Type and Default Value	Description
Label	_JMP_ISLABEL	Boolean, 0	Label column. 1 for yes. 0 for no.
Scroll Lock	_JMP_ISSCROLLLOCK	Boolean, 0	Scroll locked column. 1 for yes. 0 for no.
Hidden	_JMP_ISHIDDEN	Boolean, 0	Hidden column. 1 for yes. 0 for no
Excluded	_JMP_ISEXCLUDED	Boolean, 0	Excluded column. 1 for yes. 0 for no
Notes	_SAS_NOTES	String	Notes about the column
Modeling Type	_SAS_LEVEL	String	Valid values are Binary, Interval, Ordinal, Nominal, Unary. JMP maps Binary and Unary to Nominal and Interval to Continuous.
Preselect Role	_SAS_MININGROLE	String	Valid values are Assessment, Censor, Classification, Cost, Cross ID, Decision, Frequency, ID, Input, Key, Label, Prediction, Referrer, Rejected, Residual, Segment, Sequence, Target, Text, Text Location, Time ID, Treatment, Web Address, Weight. JMP maps Y to Target, X to Input, Freq to Frequency, and Weight to Weight.
Distribution	_SAS_DISTRIBUTION	String	Distribution type to fit for this column
Format Name	_JMP_FORMATNAME	String	Format of the column (such as Fixed Dec or Percent)

Table B.2 Column Attributes (*Continued*)

JMP Column Attribute	SAS Attribute Name	SAS Attribute Type and Default Value	Description
Format Width	_JMP_FORMATWIDTH	Numeric	Width of the column
Format Decimals	_JMP_FORMATDECIMALS	Numeric	Number of decimal places
Format Code	_JMP_FORMATCODE	String	Typically the currency code for currency formats
Use Thousands Separator	_JMP_USETHOUSANDSSEP	Boolean, 0	Include thousands separator. 1 for yes. 0 for no.
Input Format	_JMP_INFORMAT	String	Input format (for date, time, or duration-formatted columns)
Formula	_JMP_FORMULA	String	Column formula
Suppress Formula Eval	_JMP_SUPPRESSEVAL	Boolean, 0	Suppressed formula evaluation. 1 for yes. 0 for no.
Lock	_JMP_ISLOCKED	Boolean, 0	Locked column. 1 for yes. 0 for no.
Range Check Code	_JMP_RANGECHECK_CODE	String	A code that identifies the type of range check. Examples are LE, LT, LTLT, !LT, and !LELE.
Range Check Low	_JMP_RANGECHECK_LOW	Numeric	First argument to range check
Range Check High	_JMP_RANGECHECK_HIGH	Numeric	Second optional argument to range check
List Check	_JMP_LISTCHECK	String	List check
Missing Value Codes	_JMP_MISSINGCODES	String	Values to be treated as missing

Table B.2 Column Attributes (*Continued*)

JMP Column Attribute	SAS Attribute Name	SAS Attribute Type and Default Value	Description
Value Label Count	_JMP_VALUELABEL_COUNT	Numeric	Count of value labels
Value Label Code	_JMP_VALUELABELCODE_1	String	Code for the value label (such as EQ, LT, LE, LTLT, and LET.). Always EQ for character variables.
Value Label Lower Bound	_JMP_VALUELABELLOW_1	Varies	The lower bound of a numeric range, or the only bound if the ranges is unbounded on one side. A string for character columns. Numeric for numeric columns.
Value Label Upper Bound	_JMP_VALUELABELHIGH_1	Numeric	The upper bound of a numeric range. Not used for character value labels.
Value Label Display	_JMP_VALUELABELDISPLAY_1	String	The display string for this value label
Use Value Labels	_JMP_USEVALUELABELS	Boolean, 0	Uses value labels when displaying this column. 1 for yes. 0 for no.
Value Scores	_JMP_VALUESCORES	String	Associates data values with numerical scores
Value Ordering	_JMP_VALUEORDER	String	The order of values for the column
Value Colors	_JMP_VALUECOLORS	String	Maps values to colors.
Color Gradient	_JMP_COLORGRADIENT	String	Maps values to a color gradient.

Table B.2 Column Attributes (*Continued*)

JMP Column Attribute	SAS Attribute Name	SAS Attribute Type and Default Value	Description
Color Cells	_JMP_COLORCELLS	Boolean, 0	Color cells of this column using the specified value colors or color gradient. 1 for yes. 0 for no.
Axis	_JMP_AXIS	String	Axis definition
Coding	_JMP_CODING	String	Code a range of values to -1, 1 for modeling purposes
Mixture	_JMP_MIXTURE	String	Participation in a mixture of columns adding up to a value. The Mixture column property has numeric values (limits) and string values (L Pseudo Component and U Pseudo Component).
Row Order Levels	_JMP_ROWORDER	Boolean, 0	Sort the column by occurrence rather than value. 1 for yes. 0 for no.
Spec Limits	_JMP_SPECLIMITS	String	Target value and upper and lower spec limits
Control Limits	_JMP_CONTROLLIMITS	String	Control limits for control chart type
Response Limits	_JMP_RESPONSELIMITS	String	Bounds on response's acceptable range, used by profilers
Design Role	_JMP_DESIGNROLE	String	Role in a designed experiment
Factor Changes	_JMP_FACTORCHANGES	String	Difficulty of changing a factor, for DOE. Value values: Easy, Hard, Very Hard
Sigma	_JMP_SIGMA	String	Sigma for Control Charts

Table B.2 Column Attributes (Continued)

JMP Column Attribute	SAS Attribute Name	SAS Attribute Type and Default Value	Description
Units	_JMP_UNITS	String	Units for this variable; can be any string
Time Frequency	_JMP_TIMEFREQ	String	Numeric, Annual, Quarterly, Monthly, Weekly, Daily, Hourly, By Minutes, By Seconds
Map Role	_JMP_MAPROLE	String	Role in a map data set
Multiple Response Separator	_JMP_MRSEP	String, ","	Separator for a multiple-response column.
Label Column	_JMP_LABELCOLUMN	Boolean, 0	Is this column a label column? 1 for yes. 0 for no.
Expression Column	_JMP_ISEXPRESSIONCOLUMN	Boolean, 0	Is this column an expression column? 1 for yes. 0 for no.

Table B.3 Custom Column Properties

JMP Column Attribute	SAS Attribute Name	SAS Attribute Type and Default Value	Description
Custom Property Count	_JMP_CUSTCOLPROPCOUNT	Numeric, 0	Count of custom column property
Custom Property Name 1	_JMP_CUSTCOLPROPNAME_1	String	Name of the custom column property 1
Custom Property Value 1	_JMP_CUSTCOLPROPVALUE_1	String	Value of the custom column property 1

Table B.3 Custom Column Properties *(Continued)*

JMP Column Attribute	SAS Attribute Name	SAS Attribute Type and Default Value	Description
Custom Property Name 2	_JMP_CUSTCOLPROPNAME_2	String	Name of the custom column property 2
Custom Property Value 2	_JMP_CUSTCOLPROPVALUE_2	String	Value of the custom column property 2
Custom Property Name <i>n</i>	_JMP_CUSTCOLPROPNAME_ <i>n</i>	String	Name of the custom column property <i>n</i>
Custom Property Value <i>n</i>	_JMP_CUSTCOLPROPVALUE_ <i>n</i>	String	Value of the custom column property <i>n</i>

Symbols

! (Not) function 655
!= (not equal to) function 650
.emf 509
.eps 509
.gif 509
.pdf 509
*= (Multiply To) function 690
/= (Divide To) function 690
& (And) function 654
& (And) function and conditional clauses 654
^, *See* insert button on keypad
+= (Add to) function 690
< (less than) function 650
<= (less than or equal to) function 650
= (Assign) function 690
== (equal to) function 650
> (greater than) function 650
>= (greater than or equal to) function 650
| (Or) function 654

Numerics

1-, 2-, and 4-byte integers 261

A

A tool. *See* annotate tool
Abbrev Date function 682
Abs function 635
Absolute Value transformation 229
Add files opened by scripts to the Recent Files list 583
add ranges, missing values 272
Add to (+) function 690
adding
 columns 175
 graphics and graphics scripts 471

 maps and boundaries 477
 rows 175
 statistics columns 395
add-ins, opening as text 153
Aggregate functions (SQL) 144
Aggregate menu options, launch window 232
Allow Unquoted Strings in JSL 581
allowing short numeric formats 261, 595
analysis roles 297
And (&) function and conditional clauses 654
Annotate error lines in log 581
annotations
 creating 478
 setting the default font 612
anonymizing data 346
apostrophes in imported data 152
appending horizontally. *See* joining
appending tables. *See* concatenating tables
ArcCosH function 639
ArcCosine function 639
ArcSine function 639
ArcSinH function 639
ArcTangent function 639
ArcTanH function 639
arguments, formula 378
arithmetic buttons, formula editor 361
arranging windows 65
Arrhenius function 638
Arrhenius Inv function 638
Arrhenius Inverse transformation 230
Arrhenius transformation 230
arrow
 cursor tool 52
 double arrow tool 52
arrow tool 52
As Row State function 684, 686
Assign (=) function 690
Assignment functions 690

assignment table property 430
 asterisk icon 45
 attaching tables. *See* concatenating tables
 Auto Scroll 536
 Auto-complete parentheses and braces, in
 script editor 618
 Auto-hide menu and toolbars 608
 automatic recalc option 413
 Automatically generate ODS results 621
 Automatically join tables added to a query 629
 Auto-save the report to option 585
 autosaving
 documents 583
 scripts 618
 Average function, transforming columns 231–
 232
 axis
 adjusting 405, 455
 copying and pasting settings 466
 customizing 455
 divider lines and frames 464
 gridlines 461
 increments 454, 458
 labels 465
 minimum and maximum values 457
 numeric format 456
 scale 456
 scrolling 454
 specifications for columns 276
 Axis column property 276

B

background colors 453
 background image, pasting 474
 backwards compatibility, Unicode 581
 bars, histogram colors 453
 base e 636
 See also natural logarithm
 Bernoulli trials 678
 Best numeric formats 261
 Beta Binomial Distribution function 670
 Beta Binomial Probability function 671
 Beta Binomial Quantile function 671
 Beta Density function 657
 Beta Distribution function 657
 Beta function 637

Beta Quantile function 657
 BETWEEN statement (SQL) 143
 Bezier curve 481
 binning formula 224
 Binomial Distribution function 670
 Binomial Probability function 670
 Binomial Quantile function 670
 Blink button in row editor 206
 Blob to Char function 646
 boxes around formulas 377
 braces in script editor, auto-complete 618
 Break function 656
 brush tool 437
 buttons
 copying 563
 creating 559
 show and hide 567
 By Matching Columns option. *See* joining

C

Cartesian join. *See* joining
 Categorical Color Theme 591
 Cauchy distribution 677
 Ceiling function 635
 cell formulas 179
 cells, selecting 190
 Change Alias 121
 Char function 640
 Char to Blob function 646
 Char to Hex function 644
 character data types 258
 Character functions 640–646
 Character menu options, launch window 234
 Character Pattern functions 646–650
 character sets
 save text as Unicode 581
 select during text import 151
 ChiSquare Density function 658
 ChiSquare Distribution function 658
 ChiSquare Quantile function 659
 Choose function 653
 circle with strikethrough icon 196, 198–199
 cleaning data 200, 237
 closing
 JMP Starter window 68
 levels in a report 405

- several files 65
- coding column property 277
- Coefficient of Variation 397
- Col functions 673, 680
- Col Maximum function 673
- Col Mean function 672
- Col Minimum function 673
- Col N Missing function 673
- Col Number function 672
- Col Quantile function 673
- Col Rank function 674
- Col Shuffle function 680
- Col Standardize function 674
- Col Std Dev function 672
- Col Stored Value function 633
- Col Sum function 673
- Collapse Whitespace function 640
- Color function 685
- Color Of function 689
- Color Presets 592
- Color State function 685, 687
- Color Theme 274
- color themes 216
- Color unknown object messages, in script editor 619
- coloring cells 196
- colors
 - background in graph 453
 - by row state 213
 - histogram bars 453
 - markers 440
 - rows and columns 212
 - shapes added to reports 480–482
- column header text import option 603
- column switcher 412
- columns
 - add properties 268
 - adding 175
 - adjusting widths 41
 - axis specifications 273
 - characteristics 210
 - combining 221
 - compressing 222
 - computed 121
 - creating a formula 227
 - deleting 175
 - design roles 277
 - duplicating 195
 - excluding 199
 - filtering 57
 - find selected 190
 - fonts used in headings 611
 - formulas 269, 352
 - hiding 200
 - indicator 221
 - invert selection 184
 - joining 321
 - labeling 211
 - lock in place 220
 - locking 220, 257
 - measuring units 277
 - moving 195
 - names 41, 196
 - notes 270
 - numeric, changing format 429
 - order of data in reports 274
 - panel 44
 - preselected analysis roles 297
 - properties 255–297
 - rearranging 193
 - reordering 193
 - resizing 192
 - row state 265–266
 - selecting 183
 - Sigma values 279
 - sorting 193
 - source column 319
 - splitting 311
 - stacking 306
 - standardizing properties 294
 - transposing 314
 - validating data 270
 - value labels 272
- Columns Viewer 185
- columnwise statistics functions 672
- Combine menu options, launch window 231
- combine reports 408
- Combine States function 684, 686
- combining columns 221
- commas as decimal points 152
- Communications preferences 613
- Compare column 191

- comparing data tables 206
 - Comparison functions 650
 - Compress file when saved option 43
 - Compress Selected Columns 222
 - compressing
 - columns 222
 - data tables 43, 247
 - Compuserve Graphics Interchange Format. *See* GIF
 - computed column in Query Builder 121
 - Concat function 640
 - Concat Items function 645
 - concatenating tables 318
 - conditional data filter 420
 - conditional formatting, reports 430
 - Conditional functions 651–656
 - confidential data 346
 - connect to a SAS Environment preference 621
 - connect to a SAS Metadata Server
 - preference 621
 - Connections, database. *See* database connection
 - ConstraintState column property 293
 - Contains function 640
 - Continue function 656
 - Continuous Color Theme 591
 - Continuous modeling type 258
 - control chart column properties 278
 - Convert SAS custom formats 622
 - Copy As SAS Formula 377
 - Copy Formula
 - creating a subset 302
 - joining tables 323
 - copy menu and toolbar items 563
 - Copy Table Script 43
 - Copy/Drag Graphic Formats 607
 - copying
 - axis frame settings 466
 - column properties 50
 - graph contents 466
 - row states 266
 - text 511
 - toolbars 555
 - CosH function 639
 - Cosine function 639
 - Count 232
 - Count (in a formula) 635
 - Count column 202
 - Count function 633
 - creating
 - data tables 169
 - menu items and buttons 559
 - menus 558
 - source columns (when concatenating tables) 319
 - crosshairs tool 453
 - CSV, saving data table as 488
 - Cube Root transformation 229
 - Cube transformation 229
 - Cumulative Sum 235
 - currency formats, in columns 262
 - cursors 52
 - custom expression, Query Builder 130
 - customization sets
 - changing 554
 - importing 568
 - Customize Styles, in script editor 619
 - customizing
 - axes 455
 - graph elements 468
 - toolbars (Macintosh) 570
 - toolbars and menus (Windows) 553
- ## D
- dashboards, creating 533
 - data
 - grid 40
 - missing 200
 - recoding 200
 - data filter 415–428
 - Data Filter Auto Clear 596
 - Data Filter Check Box Display 597
 - Data Filter Include Check 596
 - Data Filter Select Check 596
 - Data Filter Show Check 596
 - Data Table Background Color 597
 - Data Table Grid Color 597
 - Data Table Header Grid Color 597
 - data tables
 - compare 206–210
 - compressing 43, 247
 - concatenating 318
 - creating 169

- data grid 40–53
- disable undo 43
- joining 321
- locking 43, 246
- memory issues 43
- names and notes, placing on reports 585
- names, changing 246
- opening 53
- organizing 192
- panels 41
- preferences 593
- replace database with 493
- saving 486
- saving as Excel file 487
- sorting 304
- splitting 311
- stacking 306
- subsetting 301
- summarizing 391
- transposing 314
- updating 343
- data types
 - character formats 258
 - date and time formats 261
 - numeric formats 261
 - row states 258
 - specifying 257
- database
 - connection 136
 - replace with data table 493
- datafeed. *See* communications settings
- Date Difference function 683
- Date DMY function 681
- Date Increment function 683
- Date MDY function 681
- Date Time functions 681–684
- Date Time menu options, launch window 233
- dates and times
 - formats 261–262
 - inserting on report window 584
- Day function 681
- Day of Week function 682
- Day of Year function 682
- decimal point as comma, text file 605
- Default Field Width 596
- delete button, formula editor 361
- deleting
 - columns 175
 - functions 376
 - menus 566
 - rows 175
 - toolbars 566
- derivatives, calculating in formula 371
- descriptive statistics. *See* statistics columns
- deselecting parts of a report 406
- design roles 277, 297
- Design, table variable 248
- Desirability function 676
- DF column property 293
- diamond icon, on a report 407
- Dif function 634
- Difference 231, 235
- Difference (reverse order) 231
- Digamma function 638
- Disable undo in data table 43
- disclosure icon. *See* diamond icon
- discontiguous selection 180, 184
- Discrete Probability functions 669–671
- Display Language 607
- Distribution column property 280
- Distributional menu options, launch window 232
- Divide To (/=) function 690
- Dock the Window List 608
- DOE (Design of Experiments)
 - coding 277
 - column properties 277
- Double Declining Balance function 691
- DPI, exporting report graphics 509
- dragging and dropping
 - in data table 195
 - into formulas 376
 - into other programs 511
- drawing tools 480–482
- dropping
 - columns when splitting tables 312
 - columns when stacking tables 308
 - duplicates when joining tables 323
- Dunnett P Value function 659
- Dunnett Quantile function 659
- duplicate rows, selecting 182
- duplicating cells and columns 195

E

editing

- column names 196
- formulas 375
- names of data tables 246
- names of report tables 430
- reports 406
- tables 192
- WHERE clauses 145

efficient evaluations 370

empty box in formula 386

EMS 495

Encapsulated PostScript File 495

End of Field and End of Line options 151

End of Field and End of Line options 151

end of field text import option 603

end of line text import option 603

Ends With function 643

end-to-end merging. *See* concatenating tables

Enhanced Metafile 495

EPS support in reports 495

equal to (==) function 650

equation editor. *See* formula editor

errors, ignoring in formulas 374

evaluating columns' formulas

- viewing evaluations in formulas 374
- when creating subsets 302
- when joining tables 323
- when splitting columns 312
- when stacking columns 308

Excel files

- advanced import options 81
- hierarchical headings 82
- import options 79
- labels as headings 580
- opening 75
- opening method 580
- password-protected 75
- previewing the data 76
- saving data table as 487
- selecting worksheets when opening 580
- supported versions 74

Excel Import Wizard 76

Excluded function 689

Excluded functions 684–685, 687

excluding

columns when splitting tables 312

columns when stacking tables 308

duplicates when joining tables 323

rows and columns from analyses 197

excluding markers 443

Exp function 636

Exp transformation 229

Expand Formula column property 292

ExpM1 function 636

exponent button, formula editor 361

exporting

data tables 486

reports 494

expression columns 445, 450

Expression data type 289

Expression Role column property 289

extended attributes

importing from SAS 91

mapping to JMP attributes 696

preferences 622

Extra space at bottom of document, in script

editor 618

extracting data from image 477

F

F Density function 659

F Distribution function 659

F Power function 669

F Quantile function 661

F Sample Size function 660

factor, for mixture experiments 278

Factorial function 637

fast marker

drawing speed 441

threshold 590

Fibonacci series 635

file formats, supported 74

File Locations preferences 614

fill hollow markers 441

fill pattern 467

Fill Selection Mode 590

filling columns with data 267

Filter image 476

filtering data 415

Finance Functions 691

Find/Length expression 641

finding and replacing values

See searching for values

Flip image 476

Floor function 635

font size in reports 408

fonts

 changing in data tables 41

 changing size in data tables 408

Fonts preferences 610

For function 656

For quantile statistics option, summarizing
 tables 394

Format function 682

format, changing in report 428

formula column, creating 269

formula editor 352–384

formulas

 arguments, opening and closing 378

 boxes, hiding and showing 377

 cell expressions 179

 constants, adding 359

 copy relative to the right 367

 creating 352

 creating a column 227

 data table elements, adding 354

 displaying derivatives 371

 editing 375

 entering into cells 179

 evaluating 369, 373, 597

 examples 379

 expressions 375

 fonts 378, 612

 functions, adding 362, 633

 glossary of terms 385

 JSL view 374

 keyboard shortcuts 384

 opening and closing arguments 378

 operators, adding 361

 orientation in formula editor 378

 re-evaluating 43

 shortcuts, keyboard 384

 simplifying complex 372

 tutorials 379

 viewing 374, 377

Frame Border 593

Frame Color 592

frame sizes of plots or graphs 449

freeze columns 220

Freq (Frequency). *See* preselected role

Full Quadratic Model function 691

function types

 Add to (+=) 690

 And 654

 Assign (=) 690

 Assignment 690

 Beta 637

 Character 640

 Character Pattern 646

 Col 673, 680

 Color 685

 Color State 685

 Combine States 684

 Comparison 650

 Conditional 651

 Date Time 681

 Discrete Probability 669

 Divide To 690

 Excluded 684–685

 Hidden 685

 Hidden State 685

 Hue State 685

 Is Missing 650

 Marker 685

 Match 382

 Multiply To (*=) 690

 Numeric 635

 Parametric Model 690–691

 Post Decrement (--) and Increment (++) 690

 Probability 656

 Random 676

 Row 633

 Row State 684

 Shade State 685

 Statistical 672

 Transcendental 636

 trigonometric 639–640

functions

 adding 362

 aggregate (SQL) 144

 columnwise statistics 672

 deleting 376

 peeling 376

Row States 684
Future Value function 691

G

Gamma Density function 661
Gamma Distribution function 662
Gamma function 637
Gamma Poisson Distribution function 670
Gamma Poisson Probability function 669
Gamma Poisson Quantile function 670
Gamma Quantile function 663
General preferences 575, 577
Generate ODS statistical graphics 622
GIF 495
global variables, storing a report table 430
GLog Density function 663
GLog Distribution function 663
GLog Quantile function 663
glossary of formula terms 385
Go To command 184
Go To Row command 180
grabber tool. *See* hand (grabber) tool
gradients 275
Graph Background Color 593
Graph Border 588
Graph Format 622
Graph Height 589
graph marker theme, default 589
graphics
 adding to buttons 561
 reordering 473
 saving reports as graphics 509
 scripts 471
 See also images
Graphics Format, ODS reports 621
Graphics Formats, Windows preference 608
graphs
 copying and pasting contents 466
 copying to data table 467
 customizing elements 468
Graphs preferences 587
greater than (>) function 650
greater than or equal to (>=) function 650
grid. *See* data grid
gridlines 461
GROUP BY command (SQL) 145

Group By, Query Builder 123
grouping variables
 using when sorting tables 306
 using when splitting tables 311

H

hand (grabber) tool
 using in reports 405
 using to scroll axes 454
HAVING command (SQL) 145
Hex function 644
Hex to Blob function 646
Hex to Char function 644
Hex to Number function 644
Hidden functions 685, 687, 689
Hidden State function 685
Hide Overlapping Labels 588
hiding
 columns 198
 JMP Starter window 579
 menu tips 581
 rows 198
 thumbnails of reports 608
 toolbars 553
hiding markers 443
hiding results 407
hierarchical data filter 420
Highlight Outline Headers option 608
high-resolution graphics 509
histogram bars, color 453
histograms, bar colors 453
Home Window 59
horizontal
 alignment in reports 405
 formula display 378
Hour function 681
Hover Help 585
hover labels
 displaying images on 450
 pinning 451
HTML 5, save output as 496
Hue State function 685, 687
Hypergeometric Distribution function 671
Hypergeometric Probability function 671

I

I-beam cursors 52

icons

- asterisk 45
- circle with strikethrough 196, 198–199
- column characteristics 45
- column properties 45
- compress 247
- diamond (disclosure) 407
- list check 45
- lock 45, 246
- mask 45, 198, 200
- modeling types 45
- next to column names 45
- plus 45, 270
- preselected roles 297
- range check 45
- red triangle 409
- yellow tag 45, 211

If function 651

IfMax function 654

IfMin function 654

ignoring

- errors 374
- missing values (when updating tables) 344

image format

- Macintosh preference 610
- Windows preference 608

Image Format for PowerPoint 580

images

- adding to maps 477
- dragging into graph 475
- extracting data 477
- filters 476
- pasting in background 474

Import generated SAS data sets into JMP 622

import preferences 603

importing

- data from database 136
- Excel files 75–88
- from a database 137
- HDF5 data 165
- HTML 161
- ODBC 492
- SAS files 89–91
- SPSS files 163

text files 147–156

text from the Script window 155

toolbar and menu customizations 568

Triple-S files 164

using SQL statements 135, 139

In Days function 681

In Hours function 681

In Minutes function 681

IN statement (SQL) 143

In Weeks function 681

In Years function 681

Include Column 126

Include marginal statistics option 393

Include Non Matches option 324

Include Responses Not in Data 597

increasing font sizes 408

indent guides, showing in script editor 618

indenting text in scripts 619

indicator columns 221

Individual Worksheet Settings 79

Informat function 682

Informative Missing Terms column
property 293

initial data values 267

initializing data 267

input formats 261

insert button, formula editor 361

Insert function 644

Insert Into function 644

insertion points 52

Integrate function 636

Interactions Model function 691

interactive HTML, save output as 496

Interest Payment function 691

Interest Rate function 691

internal name, toolbar button 558, 560

Internal Rate of Return function 691

international numeric formats 265

Internet

file formats 495

opening data 161

Interpolate function 655

Interquartile Range (summary statistics) 398

inverting the selected rows 51

Is Missing function 650

ISO date formats, SAS import 89

Item function 643

J

JMP Query Builder 332

JMP.PFS 577

Johnson Sb Density function 664

Johnson Sb Distribution function 663

Johnson Sb Quantile function 664

Johnson SI Density function 664

Johnson SI Distribution function 664

Johnson SI Quantile function 664

Johnson Su Density function 665

Johnson Su Distribution function 664

Johnson Su Quantile function 664

joining

by matching columns 323, 328

by row number 324

tables, methods 321

using Cartesian join 324, 326

virtually 335

Joint Photographics Expert Group (JPEG, JPG) 495, 509

journals, creating 512

JPEG, JPG 495, 509

JRE version 88

JSL Debugger preferences 625

JSL scripts

adding 249

autosaving 618

code folding 619

copying 252

creating from a report 509

deleting 44, 252

editing 44, 252

evaluate automatic execution 595

fonts 612

formula editor 374

graphics 471

new 43

preferences 617

running 252

running when a data table is opened 251

saving in data tables 43, 249–253

saving in English 582

viewing in formula editor 374

JSL Scripts should be run only 608

K

Keep All option 312

keypad, formula editor 146

L

Label column name 309

Labeled and Labeled State functions 685

Labeled function 689

Labeled State function 687

labels

axis 465

copying to other graphs 436

displaying images on 450

icon 211, 444–445

markers 444

pinning 451

rows and columns 211

Lag function 634

language preference, JMP indexes 582

large plus tool 52

laser pointer 586

lasso tool 438

launch windows 55

Left function 643

legends

adding 446

removing 448

Length function 641

LEV Density function 665

LEV Distribution function 665

LEV Quantile function 665

LGamma function 638

library. *See* SAS transport files

license file, specify location 616

LIKE statement (SQL) 143

line numbers, in script editor 618

line tool 480

Line Width 589

linear axis scale 456

Linear Model function 691

lines

changing width 453

dotted or dashed reference lines 463

Link Reference and Link ID column

properties 50

- linked data table 302, 437
- List Check property 223
- list checking 270
 - cursor 53
 - sorting data 304
- Ln and LnZ functions 636
- loading, SQL queries 145
- local variables
 - formula editor 362
 - using in formula 357, 380
- Location preference 622
- locking
 - columns 257
 - data tables 43, 246
- log
 - opening by default 608
 - saving 530
 - saving a report to 585
 - showing DisplayBox messages 582
- Log function 636
- Log transformation 229
- Log window, saving reports to 585
- Log, axis scale type 456
- Log10 function 636
- Log1P function 636
- logarithm, natural 636
- Logist function 230, 637
- Logistic Density function 665
- Logistic Distribution function 665
- Logistic function 637
- Logistic Percent 230
- Logistic Percent transformation 230
- Logistic Quantile function 665
- Logistic transformation 230
- Logit function 638
- Logit Percent 230
- Logit Percent transformation 230
- Logit transformation 230
- Loglogistic Density function 666
- Loglogistic Distribution function 666
- Loglogistic Quantile function 666
- Lognormal Density function 666
- Lognormal Distribution function 666
- Lognormal Quantile function 666
- Long Date function 682
- Lowercase function 641

M

- Macintosh OS Settings preferences 609
- magnifier tool 450
- Major Grid Line Color preference 592
- Major Grid Lines 593
- Make Window with Legend 447
- making indicator columns 221
- Manage Rules 587
- manually connect to SAS workspace servers
 - preference 621
- Map Role column property 281
- marginal statistics 393
- Marker functions 685
- Marker Label Color Style preference 590
- Marker Label Fixed Color preference 590
- Marker Of function 689
- Marker Selection Color 589
- Marker Selection Fade 589
- marker selection mode 589
- Marker State function 687
- markers
 - adding 212
 - changing shape 446
 - changing sizes 440
 - colors 440
 - default shape 589
 - default size 589
 - drawing speed 441
 - excluding 443
 - hiding 443
 - highlighting 442
 - labels 444
 - legends 446
 - opaque 441
 - outlines 441
 - point values 447
 - shapes 212, 440
 - specify images for 445
 - speed 590
 - transparency 443
- mask icon 198, 200
- Match flag 323
- Match function 382, 652
- matching
 - cases while searching 202
 - columns when joining tables 328

- values of two data tables. *See* joining
- whole words in search 202
- Matching Specification in Join 322
- matrices in columns 289
- matrix, convert report table into 430
- Max (summary statistics) 397
- Maximum function 676
- Maximum number of levels for a Check Box
 - List filter preference 629
- MDYHMS function 683
- Mean (summary statistics) 396
- Mean function 674
- measuring units, columns 277
- Median 232
- Median (summary statistics) 397
- members, importing from SAS 91
- memory issues 43
- Menu preferences 626
- menu tips 581
- menus
 - copying 563
 - creating 558
 - deleting 566
 - merging from old version 569
 - rearranging 565
- merge horizontally. *See* joining
- merge old menus 569
- merge vertically. *See* concatenating
- Mersenne-Twister technique 676
- Min (summary statistics) 397
- minimum and maximum axis values 457
- Minimum function 676
- Minor Grid Line Color preference 592
- Minor Grid Lines preference 593
- Minute function 681
- missing data patterns 200
- missing SPSS value code 163
- missing value codes 271
- missing values
 - add ranges 272
 - assign a label to 272
 - coding system 287
 - comparing 650
 - replace with previous value 178
 - updating tables 344
- modeling types

- Continuous 258
- continuous 258
- icons 45
- Multiple Response 259
- Nominal 259
- None 259
- Ordinal 258
- specifying 260
- Unstructured Text 259
- Vector 259
- Modified Internal Rate of Return function 691
- Modulo function 636
- Month function 681
- Month Year 234
- moving
 - cells and columns 195
 - rows 195
 - selection in data table 597
- Multiple Response column property 283
- Multiple Response modeling type 259
- multiple selection 619
- Multiply To (=) function 690
- multithreading 695
- Munger function 381, 641

N

- N and N Missing (summary statistics) 396–397
- N Categories (summary statistics) 397
- N Missing function 676
- naming
 - data tables 246
 - report tables 430
 - reports 408
- natural logarithm 636
- NChooseK function 637
- Neg Binomial Distribution function 670
- Neg Binomial Probability function 670
- Negation transformation 229
- nested variables 395
- nesting boxes, formula editor 379
- Net Present Value function 691
- Nominal modeling type 259
- Non matches, include when joining tables 324
- noncentrality 658–659, 661, 667–668
- None modeling type 259
- Normal Biv Distribution function 666

- Normal Density function 656
- Normal Distribution function 656
- Normal Quantile function 657
- Not (!) function 655
- not equal to (!=) function 650
- notes
 - as table variables 248
 - displaying in report windows 585
 - saving in a column 270
- NRow function 634
- Num function 642
- Number function 674
- Number of Periods function 692
- Number of Series option 307
- numeric
 - allowing short numeric 595
 - Best format 261
 - formats 261–265
 - in axes 456
 - short 261
 - international formats 265
- numeric columns, changing format 429
- Numeric functions 635–636

O

- ODBC 138, 492
- ODBC drivers for importing data 75
- ODBC Hide Connection String 597
- ODS Result Format 621
- ODS results 110
- ODS Style 621
- ODS Style sheet 621
- Offset expression 641
- OnOpen scripts 251, 595
- Open All Below 405
- Open All Like This 405
- Open as Template, Query Builder 134
- Open Database Connectivity 492
- Open Text File Charset 581
- opening
 - add-ins as text 153
 - data in text editors 153
 - databases 138
 - Excel files 75
 - JMP files 53
 - JMP Starter window 68

- journals 53
- SAS data sets 89
- SAS files 89
- SAS stored process report as data table 162
- text files 147
- operator
 - showing tips in script editor 618
- operators
 - adding 361
 - in assignment functions 690
- Or (!) function 654
- ORACLE synonyms 139
- order of operations 369
- ordering
 - columns 193
 - row order levels 274
 - values 273
- Ordinal modeling type 258
- orientation of formulas 378
- Original color preference 593
- outlines
 - adding to markers 441
 - structure of reports 407
- Output Table option
 - joining tables 322
 - sorting tables 305
- oval tool (simple shape tool) 480, 482

P

- page breaks, inserting 407, 511
- panels. *See* data table panels
- Parametric Model Functions 690–691
- parentheses
 - script editor, adding spaces inside 619
 - script editor, auto-complete 618
- password-protected
 - Excel files 75
 - SAS data sets 106
- Paste Special command 511
- Pat Abort function 648
- Pat Altern function 649
- Pat Any function 647
- Pat Arb function 648
- Pat Arb No function 649
- Pat At function 648
- Pat Break function 647

- Pat Concat function 649
- Pat Conditional function 649
- Pat Fail function 648
- Pat Fence function 648
- Pat Immediate function 649
- Pat Len function 647
- Pat Match function 649
- Pat Not Any function 647
- Pat Pos function 647
- Pat R Pos function 647
- Pat R Tab function 648
- Pat Regex function 649
- Pat Rem function 648
- Pat Repeat function 649
- Pat Span function 647
- Pat String function 647
- Pat Succeed function 648
- Pat Tab function 647
- Pat Test function 648
- patterns of missing data 200
- Payment function 692
- PDF file, headers and footers 520
- peel (delete expression), formula editor 362
- percent of total (summary statistics) 397
- pictures in columns 289
- Pin File 61
- platforms
 - common features 55
 - launch windows 56
- Platforms preferences 598
- plots and graphs
 - annotations, adding 478
 - appearances, altering 448
 - markers, changing 439
 - resizing 449
 - shapes, adding 480
 - statistics, adding 392
- PNG 495, 509
- points. *See* markers
- Poisson Distribution function 671
- Poisson Probability function 671
- Poisson Quantile function 671
- polygon (spline) tool 481–482
- Portable Network Graphics. *See* PNG
- Post Decrement (--) and Increment (++) functions 690
- Post-Query Script 133
- Pow10 transformation 229
- power. *See* Sample Size and Power
- PowerPoint
 - image format 580
- precedence in formulas 369
- Predicting column property 293
- preferences 575
 - Communications 613
 - file location 577
 - File Locations 614
 - Fonts 610
 - General 577
 - Graphs 587
 - JSL Debugger 625
 - Macintosh OS Settings 609
 - Menu 626
 - Platforms 598
 - Print 600
 - Query Builder 628
 - Reports 583
 - reset 577
 - SAS Integration 620
 - Script Editor 617
 - Styles 591
 - Tables 593
 - Text Data Files 601
 - Windows Specific 606
- preselected analysis roles 297
- Present Value function 692
- presentations, journal 513
- Preserve SAS formats 492
- Preserve SAS formats when exporting to SAS 595
- Preserve SAS variable names 492
- Preserve SAS variable names when exporting to SAS 595
- previewing
 - JMP files 67
 - text on import 149
- Principal Payment function 692
- Print Data Grid as is 595
- Print preferences 600
- printing page breaks 511
- Probability functions 656–660
- Probit function 657

Product function 675
Profit Matrix column property 283
projects 521

Q

QC Alarm Script column property 279
Quantile function 675
quantile statistics 394
Quarter function 681
queries, SQL 145
Query Builder 113–136
 Aggregation function 123
 build the query 119
 building the query 119
 compatibility with JMP 12 121, 629
 computed column 121
 connecting to database 114
 custom expression 130
 editing join conditions 118
 filtering the data 126
 Group By 123
 Open query as a template 134
 preferences 628
 red triangle options 134
 run script after query 133
 sampling the data 125
 SAS 97
 saving query as a template 134
 selecting columns 119
 selecting tables 115
 sorting the data 131
 update from database 134
 view running queries 133
 writing custom SQL 130
quotation marks in imported data 152

R

Random Beta Binomial function 679
Random Beta function 677
Random Binomial function 678
Random Cauchy function 677
random data, adding 267
Random Exp function 677
Random Frechet function 679
Random functions 676–680

Random Gamma function 677
Random Gamma Poisson function 679
Random Geometric function 679
Random GLog function 679
Random Integer function 678
Random Johnson Sb function 678
Random Johnson SI function 678
Random Johnson Su function 678
Random LEV 680
Random Logistic function 679
Random Loglogistic function 679
Random Lognormal function 679
Random Negative Binomial function 678
Random Normal function 677
Random Poisson function 679
Random Reset function 680
random sample (subset) 302
Random SHASH function 680
Random Triangular function 678
Random Uniform function 677
Random Weibull function 679
range checking 53, 270
range comparison function 650
ranges, summary statistics 397
Ratio 231–232
Ratio (reverse order) 231–232
read-only data 247
rearranging
 cells and columns 195
rearranging toolbars 563
Recent Files (Macintosh) 64
Recent Files (Windows) 61
Reciprocal transformation 229
recoding data 237
rectangle tool (simple shape tool) 480
red triangle icon 409
re-evaluate formulas 43
Refresh the preview when a change occurs 629
Regex function 645
Regex Match function 649
Remove From function 644
Remove function 644
renaming
 data tables 246
 reports 408
reopening the initial JMP window on

- startup 579
- reordering columns 193
- reordering graphics 473
- Repeat function 644
- Replace argument 641
- replacing
 - tables (when sorting) 306
 - values in a data table 202
- Report Invalid Display Box Messages 582
- report windows
 - dates and times, adding 584
 - disclosure icon 407
 - formatting 405
 - options 409
 - order of data 273–274
 - red triangle icon 409
 - renaming 408
 - saving 494
 - tables 428
- reports
 - changing format 428
 - preferences 583
- rerun formulas 43
- Resample Freq function 680
- Reset file associations 609
- reset preferences 577
- resizing
 - columns and rows 192
 - graphs 449
 - windows 408
- restricting search to selected rows or
 - columns 203
- Reverse function 645
- Reverse Into function 645
- reverting columns to original order 194
- rich text format. *See* RTF
- Right function 643
- roles
 - design roles 277
 - preselected analysis roles 297
- root button, formula editor 362
- Root function 637
- Rotate image 476
- Round function 636
- row editor 204
- Row functions 633–634

- Row menu options, launch window 235
- row state
 - clearing 220
 - coloring rows by column values 213
 - columns 265–266
 - data types 258, 266
- Row State functions 684–686

- rows
 - adding 175
 - characteristics 210
 - coloring 212
 - deleting 175
 - excluding 197
 - excluding and hiding 196
 - hiding 198
 - inverting selected 51
 - joining 321
 - labeling 211, 444
 - legends 446
 - markers 212
 - menu items 52
 - moving 195
 - order of data in reports 274
 - resizing 41, 192
 - selecting 180
 - selecting duplicate 182
 - sorting in data tables 304
 - subsetting 301
 - summarizing 391
 - transposing 314

- rows panel 47
- RTF (Rich Text Format) files 496
- Run on Open 133
- Run queries in the background when
 - possible 630
- Run the preview update in the background 630
- RunsPerBlock column property 293

S

- sample the data, Query Builder 125
- Sampling in databases 139
- SAS
 - adding SQL table variable to imported
 - table 102
 - browsing data sets 98
 - connecting

- local machine 97
- Metadata Server 93
- SAS mid-tier environment 96
- Workspace Server 95
- creating transport files 91
- exporting data tables 111
- extended attributes 91, 106, 492, 696
- generating ODS results 110
- importing data sets 89, 101
- importing password-protected data sets 106
- importing variable labels 622
- ISO date formats 89
- Query Builder 97
- restoring JMP metadata from SAS extended attributes 102
- running stored processes 108
- saving data table as transport file 490
- saving in SAS format 491
- submitting code 108
- transport files 490
- using labels for imported column names 102
- variable names 89
- SAS 9.3 preferences 620
- SAS column properties 287
- SAS Integration preferences 620
- SAS metadata server, automatically connect 621
- SAS metadata server, supported version 92
- SAS server version 96
- SAS Server Version preference 621
- Save and restore document state information, in script editor 618
- Save and Save As menu items 486
- Save Data Table Columns GZ Compressed 582
- Save Data Table Columns GZ Compressed preference 43
- Save Journals GZ Compressed 582
- Save Session Script 530
- Save the session when exiting 583
- saving
 - column property 276
 - data table as CSV file 488
 - data table as SAS data set 491
 - data table as text file 489
 - data table to database 492
 - data tables 486
 - log windows 530
 - report as Adobe Flash file 508
 - report as interactive HTML 496
 - report as PowerPoint file 507
 - reports 494
 - reports as graphics 509
 - results to a database 492
 - scripts 509
 - scripts in English 582
 - scripts to a data table 249
 - SQL queries 145
 - Unicode 581
- saving and evaluating formulas (when concatenating tables) 319
- Scalable Vector Graphic format 509
- scaling a graph 449
- scaling axes 454
- Scheffe Cubic function 639
- Script All By-Groups menu 413
- script editor
 - auto-complete parentheses and braces 618
 - extra space at bottom of document 618
 - indent guides, showing 618
 - line numbers, showing 618
 - operator tips, showing 618
 - preferences 617
 - spaces in operator names 619
 - spaces inside parentheses 619
 - tab width 618
 - use tabs 618
 - variable value tips, showing 618
- scripts. *See* JSL scripts
- scroll lock/unlock 220
- scrolling axes 454
- searching for values 202
- Second function 681
- Select Dominant 181
- Select Individual Excel Worksheets preference 580
- Select Randomly 181
- SELECT statement (SQL) 141
- Selected function 685, 689
- Selected State function 685, 687
- selecting

- cells 180, 184, 190–191
- duplicate rows 182
- irregular area of points 438
- marker types 447
- parts of a report 406
- points in plots 437
- rectangular area of points 437
- rows and columns in data tables 183–190
- rows and columns in plots 437
- selecting JSL in editor 619
- selection (large plus) cursor 52
- sequence data, adding 267
- Sequence function 635
- sessions, saving 529
- SEV Density function 667
- SEV Distribution function 667
- SEV Quantile function 667
- Shade Alternate Table Rows 593
- Shade State function 685, 688
- Shade Table Cells 593
- Shade Table Headings 593
- SHASH Density function 667
- SHASH Distribution function 667
- SHASH Quantile function 667
- Shift function 645
- Shift Into function 645
- Short Date function 682
- short, allowing short numeric 260, 595
- shortcuts, keyboard 384
- short-integer format 595
- Show Alternate Column Name 596
- Show conditional formatting 587
- Show embedded log on script window open, in script editor 618
- Show indent guides, in script editor 618
- Show line numbers, in script editor 618
- Show log warnings for JSL compatibility changes 581
- Show menu tips 581
- Show on the Windows task bar 608
- Show operator tips, in script editor 618
- Show SAS Log 622
- Show the thumbnail panel 608
- Show Tree Structure 407
- Show variable value tips, in script editor 618
- showing the toolbar 563
- Sigma, assigning values 279
- simple shape tool (oval or rectangle) 480
- simplify formulas 372
- Sine function 639
- SinH function 639
- sizing a graph 449
- sizing/scaling 454
- slope computation 381
- sorting
 - data tables 304
 - list check 304
 - order 306
 - results by fields in a database (SQL) 142
 - value labels 304
 - value ordering 304
- Source Flag column 323
- Source Label Column 309
- Spaces in operator names, in script editor 619
- Spaces inside parentheses, in script editor 619
- speed, marker 590
- splash window 579
- Split By column 313
- Split Label Col 311
- splitting columns 311
- SPSS files, importing 163
- SQL database
 - build a query 113
 - syntax in queries 141
 - write a query 135
- SQL statements 139
- Square 229
- Square Root transformation 229
- Squash function 637
- Squish function 230, 637
- SSS import 164
- stacking columns 306
- Standard Deviation 396
- Standard Deviation function 674
- Standard Error 397
- standardizing attributes 295, 367
- Starter window 68
- Starts With function 643
- Statistical functions 672–676
- Statistics button 392, 396
- statistics column 392, 395–396
- Status Bars 63

- Std Dev and Std Err (summary statistics) 396
- Std Dev function 674
- Step function 655
- Stop function 656
- Store extended attributes 492
- Stored Process Results 622
- stored process, copy metadata path 108
- Straight Line Depreciation function 692
- stripping enclosing quotes on imported data 152
- Styles preferences 591
- subgroups, summary statistics 395
- submit SAS code 108
- Subqueries (SQL) 145
- Subscript function 634
- subsetting
 - from a data table 301
 - from a histogram 303
- Substitute function 645
- Substitute Into function 645
- Substr function 642
- Subtract To (—) function 690
- Sum function 674
- Sum Of Years Digits Depreciation function 692
- Sum Wgt (summary statistics) 397
- summary table, creating 391
- Summation function 675
- supported version of SAS metadata server 92
- suppressing formula evaluation 43, 373
 - on open 597
 - when creating a subset 302
 - when joining tables 323
- SVG 496
- switch terms button, formula editor 362
- synonyms (ORACLE) 139
- syntax colors in scripts 619
- system tables (ORACLE) 139

T

- t Density function 667
- t Distribution function 668
- t Quantile function 668
- Tab width, in script editor 618
- Table Column Borders 593
- Table Heading Column Borders 593
- Table Row Borders 593
- table variables
 - adding 248–321
 - creating 42, 249
 - editing 249
 - in formulas 248, 354
 - notes 248
- Tables preferences 593
- tables, in report 428, 430
- tabs in script editor 618
- Tangent function 639
- TanH function 639
- terms, switching in a formula 362
- text
 - editing 153
 - importing 148
 - mode for formulas 374
 - opening add-ins as text 153
 - opening text files 147
 - saving data table as 489
- Text Data Files preferences 601
- text export preferences 605
- text files, saving without Unicode 581
- text import preferences 601
- Text to Columns 220
- threshold of markers 590
- Tick Marks Inside Graph Frame 593
- Time Frequency column property 280
- Time of Day function 682
- time, adding to reports 584
- Tip of the Day window, hiding 579
- title bar fonts 612
- Titlecase function 642
- Today function 681
- toolbars
 - adding buttons 555
 - copy 555
 - copying 563
 - create 555
 - deleting 566
 - File_Edit toolbar 556
 - hidden 563
 - personalizing (Macintosh) 570–571
 - rearranging 563
 - show and hide 567
 - showing by default 608
- toolbars and menus, personalizing

- (Windows) 553–569
- Transcendental functions 636–639
- Transform menu options, launch window 229
- transforming columns 229
- translating toolbar and button captions 558
- transparency, markers 443
- transport files, creating 91
- transposing rows and columns 314
- treat empty columns as numeric 604
- Trigamma function 638
- trigonometric function types 639
- Trim function 642
- Triple-S import 164
- truth tables 655
- Tukey HSD P Quantile function 669
- Tukey HSD Quantile function 668
- two-digit year rule
 - importing data 152
 - preference in text import 604
- two-way table of summary statistics 395

U

- unary sign function button, formula editor 362
- Underline Table Headings 593
- Unicode, save text files preference 581
- units, specifying in column 277
- univariate statistics 392
- Unstructured Text modeling type 259
- Update From Database 134
- Update from database, Query Builder 134
- updating data tables 343
- Uppercase function 641
- Use a Floating Window for Data Filters 596
- Use an Asterisk with the PValue Format 587
- Use for Marker 445
- Use Regional Settings 152
- Use SPSS Labels for column names during import 581
- Use tabs, in script editor 618
- Use Thousands Separator 596
- Use Triple-S Labels as Headings 581
- User Tables, database connections 139

V

- validating data 270

- value labels, sorting 304
- value ordering, sorting data 304
- values
 - high and low for columns (in DOE) 277
 - minimum and maximum 457
 - ordering 273
- variable names 89
- variable value tooltips in script editor 618
- variables
 - local to a formula 357
 - table. *See* table variables
- Variance (summary statistics) 397
- Vector modeling type 259
- vertical, formula display 378
- Views, database 139
- virtually joining data tables 335

W-Z

- Week 234
- Week of Year function 682
- Weibull Density function 669
- Weibull Distribution function 669
- Weibull Quantile function 669
- weight, preselected roles 297
- WHERE clause editor 145
- WHERE statement (SQL) 142
- While function 656
- wildtrack.org 477
- Window Background Color 593
- Window List (Macintosh) 65
- Window List (Windows) 62
- Windows Specific preferences 606
- windows, hide splash 579
- Word and PowerPoint, copy reports into 511
- Word function 642
- Word. *See* Microsoft Word
- Words function 643
- worksheets, selecting 580
- Wrap Text, in script editor 618
- Wrap the main menu in narrow windows 608
- WWW. *See* Internet
- Y-Axis Title Above Graph 588
- Year function 681
- Year Quarter 234
- yellow tag icon 211, 444–445
- zooming 450